

(19) World Intellectual Property Organization  
International Bureau



(43) International Publication Date  
9 August 2007 (09.08.2007)

PCT

(10) International Publication Number  
**WO 2007/089603 A2**

(51) International Patent Classification:  
**A61B 17/04** (2006.01)

(74) Agent: **POLLACK, Brian, R.**; EDWARDS ANGELL  
PALMER & DODGE LLP, P.o.box 55874, Boston, MA  
02205 (US).

(21) International Application Number:  
PCT/US2007/002204

(81) Designated States (unless otherwise indicated, for every  
kind of national protection available): AE, AG, AL, AM,  
AT, AU, AZ, BA, BB, BG, BR, BW, BY, BZ, CA, CH, CN,  
CO, CR, CU, CZ, DE, DK, DM, DZ, EC, EE, EG, ES, FI,  
GB, GD, GE, GH, GM, GT, HN, HR, HU, ID, IL, IN, IS,  
JP, KE, KG, KM, KN, KP, KR, KZ, LA, LC, LK, LR, LS,  
LT, LU, LV, LY, MA, MD, MG, MK, MN, MW, MX, MY,  
MZ, NA, NG, NI, NO, NZ, OM, PG, PH, PL, PT, RO, RS,  
RU, SC, SD, SE, SG, SK, SL, SM, SV, SY, TJ, TM, TN,  
TR, TT, TZ, UA, UG, US, UZ, VC, VN, ZA, ZM, ZW.

(22) International Filing Date: 29 January 2007 (29.01.2007)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:  
60/763,038 27 January 2006 (27.01.2006) US

(71) Applicant (for all designated States except US): **SU-  
TURTEK INCORPORATED** [US/US]; 51 Middlesex  
Street, North Chelmsford, MA 01863 (US).

(84) Designated States (unless otherwise indicated, for every  
kind of regional protection available): ARIPO (BW, GH,  
GM, KE, LS, MW, MZ, NA, SD, SL, SZ, TZ, UG, ZM,  
ZW), Eurasian (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM),  
European (AT, BE, BG, CH, CY, CZ, DE, DK, EE, ES, FI,  
FR, GB, GR, HU, IE, IS, IT, LT, LU, LV, MC, NL, PL, PT,  
RO, SE, SI, SK, TR), OAPI (BF, BJ, CF, CG, CI, CM, GA,  
GN, GQ, GW, ML, MR, NE, SN, TD, TG).

(72) Inventors; and

(75) Inventors/Applicants (for US only): **MEADE, John,**  
**C.** [US/US]; 85 Millville Road, Mendon, MA 01756  
(US). **MACARTHUR, Douglas, M.** [US/US]; 18 Olde  
Surrey Drive, Acton, MA 01720 (US). **BLINN, Stephen,**  
**M.** [US/US]; 14 Upham Road, Amherst, NH 03031  
(US). **SAULINER, Christopher** [US/US]; 12 B Street,  
Brunswick, ME 04011 (US). **EDWARDS, Brian, R.**  
[US/US]; 85 Mill Street, Raymond, ME 04071 (US).  
**BRECHER, Gerald, I.** [US/US]; 488 Pleasant Street,  
North Andover, MA 01845 (US).

Published:

— without international search report and to be republished  
upon receipt of that report

For two-letter codes and other abbreviations, refer to the "Guid-  
ance Notes on Codes and Abbreviations" appearing at the begin-  
ning of each regular issue of the PCT Gazette.

(54) Title: APPARATUS AND METHOD FOR TISSUE CLOSURE

(57) Abstract: A tissue closure device includes a pusher assembly having a drive arm extending from a drive shaft and a drive mechanism at a distal end of the drive arm, wherein the drive mechanism is capable of releasably engaging and rotating a suturing needle having a pointed end and a blunt end about a rotational axis and a cartridge having a protective housing and the suturing needle, the cartridge extending from a distal end of a cartridge holder assembly and releasably attached to the cartridge holder assembly. A pointed end of the suturing needle may be positioned within the protective housing before and after a complete rotation of the suturing needle about the rotational axis. A removable electronic module may be provided controlled by an actuator that mechanically engages the drive shaft to rotate the drive shaft and the drive mechanism, thereby rotating the suturing needle about the rotational axis.



WO 2007/089603 A2

## **APPARATUS AND METHOD FOR TISSUE CLOSURE**

### **RELATED APPLICATIONS**

[001] This application claims the benefit of priority to U.S. Provisional Patent Application No. 60/763,038 filed January 27, 2006, which is incorporated herein by reference.

### **FIELD**

[002] The embodiments disclosed herein relate to a medical device for performing a procedure on tissue, such as bony tissue. Embodiments disclosed herein are appropriate for sternotomy closure, among other procedures. More particularly, embodiments disclosed herein are useful for the manipulation and control of a suture needle during sternotomy closure, and methods for using such a device.

### **BACKGROUND**

[003] Surgical procedures present many challenges which can compromise the health of the patient as well as the health of the medical professional. For some surgical procedures, such as cardiac surgery and pneumonectomy, access to the organ is generally gained by a sternotomy, a surgical procedure in which the sternum is divided with a device such as a saw or other suitable cutting instrument. After performing the sternotomy, the sternum must be re-approximated. The medical professional typically closes the sternum using a stainless steel needle with a sharp cutting point onto which is attached a suture comprising a length of relatively inflexible stainless steel wire, or alternatively, a combination of stiff stainless steel wire and flexible stainless steel cable. The wire (or combination cable and wire) suture is manually drawn through both sides of the sternum so that sufficient length of the wire is protruding from both sides of the sternum and there is no longer any slack wire below the sternum. After removing the needle from the wire, the medical professional must manually wrap an end of one wire around the other wire either with their hands or forceps, repeatedly twisting the two ends of the wires around each other in a helical or spiral manner. The medical professional then cuts the twisted wires to a desired length and uses surgical tools to bury the sharp, cut, twisted ends of the wires into the space

between the re-approximated edges of the sternum so that the sharp, cut, twisted ends of the wire do not poke into the underside of the patient's skin. Typically, between six and eight wire sutures are placed in the sternum in order to close the sternum along its length.

[004] The prior art sternotomy closure procedures present many problems to the medical professional and the patient. Manual suturing is often difficult because the suturing needle must be forced through tough, dense bone. Manual suturing also involves the handling and manipulation of a sharp suturing needle with an instrument such as a needle forceps, which can result in inadvertent, accidental needle pricks through a surgeon's or nurse's gloves, posing a potential risk of infection for the surgeon, nurse, staff, and patient. Manipulating an inflexible wire within the chest cavity underneath the sternum and ribcage is often difficult and awkward. For example, traditionally, the surgeon must manually lift the divided sternum upward when placing a suture through the bone, placing his or her hand in significant danger of needle puncture because of the force required to penetrate the bone. In addition, medical professionals are often stuck by the sharp, cut, twisted ends of the wires, and are thus subjected to the risk of potentially fatal bloodborne infections such as HIV/AIDS and Hepatitis B and C. Furthermore, the direct handling of the needle can cause the needle to become contaminated with pathogenic bacteria that can cause onset of infection at the site of the sutures. There is also a risk of the needle penetrating the heart and adjacent vessels and structures and causing a serious and often fatal infection.

[005] Prior art sternotomy sutures for use by medical professionals are described, for example, in U.S. Patent No. 4,074,732 entitled "Wire Cutting, Stripping and Twisting Tool;" U.S. Patent No. 5,089,012 entitled "Surgical Suture, in Particular for Sternotomy Closure;" U.S. Patent No. 5,318,566 entitled "Sternotomy Cable and Method;" and U.S. Patent No. 5,830,234 entitled "Method for Double Wire Sternotomy Suture," all of which are hereby incorporated by reference herein in their entireties. Prior art sternotomy sutures require the medical professional to use their fingers or manual tools to manipulate the sutures and to provide an appropriate amount of tension to the sutures. In addition, U.S. Patent No. 6,923,819 discloses an apparatus and method for surgical suturing with thread management, the entirety of which is hereby incorporated by reference herein.

[006] Thus, it is evident that there is a need in the art for an apparatus and method for sternotomy closure that is safe, reliable, user friendly, and effective. The present invention provides a solution for this and other problems.

### SUMMARY

[007] The purpose and advantages of the present invention will be set forth in and become apparent from the description that follows. Additional advantages of the invention will be realized and attained by the methods and systems particularly pointed out in the written description and claims hereof, as well as from the appended drawings.

[008] To achieve these and other advantages and in accordance with the purpose of the invention, as embodied herein, the invention includes an apparatus and method for joining tissue, such as bony tissue. According to aspects illustrated herein, there is provided a device for joining tissue that may be used, for example, for sternotomy re-approximation including a pusher assembly, and a cartridge. The pusher assembly has a drive arm extending from a drive shaft and a drive mechanism at a distal end of the drive arm. The drive mechanism is capable of releasably engaging and rotating a suturing needle having a pointed end and a blunt end about a rotational axis. The cartridge includes a protective housing and the suturing needle. The cartridge extends from a distal end of a cartridge holder assembly and is releasably attached to the cartridge holder assembly.

[009] In accordance with a further aspect of the invention, a pointed end of the suturing needle is preferably positioned within the protective housing before and after a complete rotation of the suturing needle about the rotational axis. Moreover, if desired, a removable electronic module may be provided in the device that is controlled by an actuator that mechanically engages the drive shaft to rotate the drive shaft and the drive mechanism, thereby rotating the suturing needle about the rotational axis.

[0010] In accordance with a further aspect the invention also provides a cartridge for housing a suturing needle that can be used, if desire, for example, in sternum re-approximation. The cartridge includes a housing having a curved shape, an inner wall and an outer wall. The housing also includes a track in the inner wall of the housing whereby the suturing needle follows a curved path along the track during a revolution of the suturing

needle. The cartridge further includes an aperture defined in the housing that intercepts the track, wherein the housing shields the pointed end of the suturing needle during at least a portion of the revolution of the suturing needle.

[0011] In accordance with another aspect, the invention further provides a suturing needle for use, for example, in sternum re-approximation. The needle includes a curved body having a pointed end that is protected at an end of a rotation cycle and a blunt end that engages a suturing material. The suturing material preferably includes a flexible leader engaged to a wire suture.

[0012] In accordance with still another aspect, the invention provides a method for joining tissue, such as sternum re-approximation. The method includes releasably engaging a cartridge having a protective housing and a suturing needle to a cartridge holder assembly of a tissue closure device. The method further includes, placing the tissue closure device having the cartridge and the suturing needle to cause an aperture in the cartridge to be disposed between a first side and a second side of a segment of tissue to be closed, such as a split sternum, wherein a pointed end of the suturing needle is positioned within the protective housing before and after a complete rotation of the suturing needle about a rotational axis. The method also includes activating an electronic module coupled to a pusher assembly that releasably engages the suturing needle to cause rotational movement of the suturing needle across the aperture in the cartridge and advance the suturing needle through the first side of the tissue segment and pulling a suturing material attached to the suturing needle through the first side of the tissue segment. The method further includes using the device to complete a stitch through the second side of the tissue segment.

[0013] It is to be understood that both the foregoing general description and the following detailed description are exemplary and are intended to provide further explanation of the invention claimed.

[0014] The accompanying drawings, which are incorporated in and constitute part of this specification, are included to illustrate and provide a further understanding of the method and devices of the invention. Together with the description, the drawings serve to explain the principles of the invention.

### BRIEF DESCRIPTION OF THE DRAWINGS

- [0015] The presently disclosed embodiments will be further explained with reference to the attached drawings, wherein like structures are referred to by like numerals throughout the several views. The drawings shown are not necessarily to scale, with emphasis instead generally being placed upon illustrating the principles of the presently disclosed embodiments.
- [0016] **FIG. 1** is a pictorial view of the main components of a tissue closure device provided in accordance with the invention.
- [0017] **FIG. 2A** and **FIG. 2B** are perspective views of a front end assembly of the tissue closure device of **FIG. 1**.
- [0018] **FIG. 3A** shows an expanded view of a pawl. **FIG. 3B** and **FIG. 3C** show an expanded view of a pusher assembly with the pawl in place.
- [0019] **FIG. 4** shows an expanded view of a curved tissue closure needle.
- [0020] **FIG. 5A** is a perspective view of the relative configuration of a tissue closure needle with respect to the pusher assembly. **FIG. 5B** and **FIG. 5C** are sectional views of the tissue closure needle and the pusher assembly.
- [0021] **FIG. 6** is a perspective view of a cartridge holder assembly of the tissue closure device of **FIG. 1**.
- [0022] **FIG. 7** shows an expanded view of a needle cartridge.
- [0023] **FIG. 8A** shows an expanded view of an anti-rotate and locking bar. **FIG. 8B** shows an expanded view of the relative configuration of the anti-rotate and locking bar with respect to a suturing needle housed in a needle cartridge.
- [0024] **FIG. 9** shows close-up view of an alternative cartridge locking mechanism utilizing a retractable pin incorporated into the cartridge holder assembly instead of a locking bar.

- [0025] **FIG. 10** shows an isolated view of the cartridge locking pin of **FIG. 9**.
- [0026] **FIG. 11** shows a cutaway view of the cartridge locking pin of **FIG. 9** engaged with the locking pin recess of the cartridge.
- [0027] **FIG. 12** shows the locking pin recess of **FIG. 11** on the proximal surface of the needle cartridge.
- [0028] **FIG. 13** shows an anti-rotate bar without the locking bar feature, which can be used when the locking pin feature of **FIG. 9** is incorporated into the cartridge holder assembly.
- [0029] **FIG. 14A** shows a perspective view of the relative configuration of the needle cartridge with respect to the cartridge holder assembly and the anti-rotate and locking bar before the needle cartridge has been locked into place. **FIG. 14B** shows a perspective view of the relative configuration of the needle cartridge with respect to the cartridge holder assembly and the anti-rotate and locking bar after the needle cartridge has been locked into place.
- [0030] **FIG. 15** shows a suture retainer on the top side of the cartridge, used to hold the suture material away from the needle, drive arm and pawl of the needle pusher assembly.
- [0031] **FIG. 16** shows a rearward-leaning perspective view of the front of the cartridge, revealing the recess of the suture retainer of **FIG. 15** into which the suture can be placed.
- [0032] **FIG. 17** shows the suture material in cross-section, placed within the recess of the suture retainer of **FIG. 15**.
- [0033] **FIG. 18** shows a top view of the needle cartridge and suture retainer of **FIG. 15**, revealing the detents of the suture retainer projections that hold the suture material within the recess.
- [0034] **FIG. 19** shows a needle brace that can be installed on the needle cartridge from the outside/distal surface of the cartridge.

[0035] FIG. 20 shows the needle brace of FIG. 19 installed against the needle cartridge.

[0036] FIG. 21 shows a rear perspective view of the needle brace of FIG. 19 installed in the cartridge, revealing its positioning adjacent to the blunt and pointed ends of the suturing needle.

[0037] FIG. 22 shows an alternative design of the needle brace of FIG. 19, in which the stop at the pointed end of the needle comprises a flexible tab, which can aid in securing the brace onto the cartridge.

[0038] FIG. 23 shows the needle brace of FIG. 22 installed onto the cartridge, showing the flexible tab snapped onto the point of the needle.

[0039] FIG. 24 shows an electronic module of the tissue closure device of FIG. 1.

[0040] FIGS. 25 A – H show various perspective views of the electronic module of the tissue closure device of FIG. 1, including a left front perspective (A), front perspective (B), right front perspective (C), left rear perspective (D), rear perspective (E), right rear perspective (F), top perspective (G) and bottom perspective (H).

[0041] FIG. 26A, FIG. 26B and FIG. 26C show views of a tissue closure device wherein the electronic module has been encased in a housing.

[0042] FIGS. 27 A – F show the installation of the funnel into the back end of the handle of the suturing device, with the funnel aligned with the barrel of the handle (A and D), the funnel in position within the handle (B and E), and the electronic module of FIG. 24 aligned with the installed funnel (C and F).

[0043] FIGS. 28 A – F show various perspective views of the funnel of FIG. 27 in isolation, showing the rear (A), front (B), right side (C), left side (D), top (E) and bottom (F) of the funnel.

[0044] FIG. 29 shows the electronic module of FIG. 25 showing an alternative arrangement of the power and actuation buttons and indicator LED's.



[0045] FIG. 30 shows an enlarged view of a drive wheel and a stop plate. A drive pin penetrates the stop plate and rides in a “U-shaped” track.

[0046] FIG. 31A, FIG. 31B, and FIG. 31C show segmented sectional views of the main components of the tissue closure device.

[0047] FIG. 32A shows an embodiment of a tissue closure needle having the tissue closing suture material attached thereto. FIG. 32B shows an expanded view of a crimp that houses the ends of the two materials that form a tissue closure suture material.

[0048] FIGS. 33 A-C show details of the construction of the pointed end of the tissue closure needle of FIG. 4, with the distribution of the facets (A), the angle of the outer curvature facet (B), and the resulting shape of the needle point (C).

[0049] FIG. 34 shows a disposable paper and plastic film package enclosing the sterile needle cartridge of FIG. 7, and the suturing needle and attached suture material of FIG. 32A.

[0050] FIG. 35 shows an embodiment of a tissue closure device of the presently disclosed embodiments.

[0051] FIGS. 36 A – C show front perspective views of an embodiment of the suturing device of FIG. 1, with needle cartridge attached, including left front (A), front (B), and right front (C) perspectives.

[0052] FIGS. 37 A - D show other perspective views of the suturing device of FIG. 36, without an attached cartridge, including left rear (A), right rear (B), bottom (C) and top (D) perspectives.

[0053] FIG. 38 shows a further embodiment of a tissue closure device provided in accordance with the invention.

[0054] FIGS. 39A-39D shows the operation of the driver arm in the cartridge holder assembly operating in a rear drive mode.

[0055] **FIG. 40** shows an embodiment of a tissue closure device placed at a sternotomy site such that the device is between a first side and a second side of a split sternum.

[0056] While the above-identified drawings set forth presently disclosed embodiments, other embodiments are also contemplated, as noted in the discussion. This disclosure presents illustrative embodiments by way of representation and not limitation. Numerous other modifications and embodiments can be devised by those skilled in the art which fall within the scope and spirit of the principles of the presently disclosed embodiments.

### DETAILED DESCRIPTION

[0057] Reference will now be made in detail to the present preferred embodiments of the invention, examples of which are illustrated in the accompanying drawings. The method and corresponding steps of the invention will be described in conjunction with the detailed description of the system.

[0058] The devices and methods presented herein may be used for tissue closure. The present invention is particularly well suited for procedures involving bony tissue, such as sternotomy closures. As depicted, the disclosed tissue closure device, or suturing device, is a motorized, electrically powered apparatus. The power source can be battery or standard wall electrical power. The tissue closure devices disclosed herein advantageously prevent accidental needle punctures to the medical professional and readily and easily drive needles through bony tissue, eliminating the need to manually force the needles through the bone. Within the context of sternotomy closure, the disclosed devices protect the heart and adjacent vessels and structures from inadvertent needle punctures during closure and replicates the standard sternotomy closure technique. In so doing, the disclosed embodiments provide easier and more fluent manipulation of the wire or wire/cable combination within the chest cavity or other anatomy, and produce tissue closure in a time efficient manner so the patient is not subjected to health risks associated with having a tissue segment, such as the sternum, open for more time than necessary.

[0059] The main components of a tissue closure device of the presently disclosed embodiments are shown generally at **50** in **FIG. 1**. The tissue closure device **50** can be used

to produce a continuous, or more commonly, an interrupted suture so as to enable closure of the sternal halves after a sternotomy procedure, for example. As depicted, device 50 is a motorized, battery-powered apparatus designed to prevent needle punctures during sternotomy closure or other similar procedures. Device 50 delivers reliable closure using standard needles and wires and replicates standard tissue (e.g., sternotomy) closure techniques. Device 50 easily drives needles through bone as well as other tissue, thus eliminating the need to manually force the needles through the bone; and protects the heart and adjacent vessels and structures from inadvertent needle punctures during closure.

[0060] Referring to **FIG. 1**, the tissue closure device 50 includes a removable electronic module 60 including a battery pack 62, an electric motor 61, and a gear box 59, as well as electronic circuits. The gear box 59 further includes a shaft that runs through a stop plate 66, a bearing surface 68, and a drive wheel 67. A drive pin 63 engages the drive wheel 67 and when in use, mates with a hole in a drive plate 80 that is part of a front end assembly 70. The bearing surface 68 acts as a lubricating surface between the stop plate 66 and the drive wheel 67. The bearing surface 68 may be any lubricious material having a low coefficient of friction, for example fluoropolymer compounds such as those including polytetrafluoroethylene (PTFE).

[0061] The electric motor 61 preferably is compact yet powerful. In one embodiment, a DC motor can be selected from the Maxon RE-max 29 series, for example, commercially available from Maxon Precision Motors, Inc. of Fall River, MA. Model no. 226784 can be used, which weighs 159 grams, is 29 mm in size, operates on 9 volts, can generate 22 watts, and has a no-load speed rating of 7630 RPM. The gear box 59 can be selected from, for example, the Maxon Gearhead GP32C series, which is 32 mm in size. Model no. 166943 can be used, which has 3 stages, weighs 194 grams, and has a 103:1 gear reduction ratio.

[0062] As depicted, the front end assembly 70 includes a pusher assembly (not visible) and a cartridge holder assembly 72. The pusher assembly has a drive arm that houses a drive mechanism ("pawl") and a drive shaft that runs throughout the length of the front end assembly 70 and enters the drive plate 80. A needle cartridge 90 carrying a tissue closure needle 110 may be removably attached to a distal end 81 of the cartridge holder assembly 72.

[0063] **FIG. 2A** and **FIG. 2B** show the front end assembly 70 including a pusher assembly 71 and the cartridge holder assembly 72 with the attached disposable needle

cartridge 90 which houses the tissue closure needle 110. The pusher assembly 71 includes a drive shaft 73 and a drive arm 75 that is in intimate contact with the needle 110 via a pawl. The drive shaft 73 engages a spline in the drive plate 80 so the drive shaft 73 is rotationally attached to the drive plate 80. When the electronic module is attached to the front end assembly the drive shaft 73 engages a bushing located in the drive wheel 67. The cartridge holder assembly 72 (shown in FIG. 2B) includes a shaft barrel 74 and a support arm assembly 76 that is comprised of a pair of "skeletalized" arms extending along mutually divergent axes so as to provide an opening 78 to view the device 50 during its operation. The open configuration of the support arms 76 are minimal in bulk and provide a relatively wide opening 78 that allows the medical professional to directly view the aperture in the needle cartridge 90 and cartridge holder assembly 72, the space, for example, between a first side and a second side of a split sternum and needle advancement through the space during operation of the tissue closure device 50. Although the embodiment shown in FIG. 2 has a plurality of support arms 76, other variants include a support arm assembly comprising a single support arm. The improved viewing ability offered by the shape and configuration of the support arm assembly 76 enables precise device placement over the sternum in the case of a sternotomy closure procedure, and uniform advancement of the tissue closure device 50 after every stitch to provide a uniform and symmetric suture, thereby protecting the heart and adjacent vessels and structures from inadvertent needle punctures during closure.

[0064] The distal end 81 of the cartridge holder assembly 72 is where the needle cartridge 90 is disposably attached. The needle cartridge 90 comprises a circular housing that may be formed of a suitable rigid medical grade sterilizable metal or plastic material. Preferably, the material forming the cartridge 90 possesses both rigidity and a low coefficient of friction to reduce the power required to move the needle disposed within it. One such material, for example, is Lubricomp DFP22H, produced by GE Plastics, a polycarbonate containing 10% glass fill, 8% PTFE (Teflon), and 2% silicone. Constructing the cartridge from this material can provide for up to 20% more driving power at the point of the needle. The housing may be releasably retained by the distal end 81 of the cartridge holder assembly 72 by known means, such as a plurality of grooves located along on the edge of an inner lip in diametrically opposite positions that are capable of engaging the same plurality of slots correspondingly located in the distal end 81 of the cartridge holder assembly 72. The grooves when engaged enable the needle cartridge 90 to be retained by the distal end 81 of the

cartridge holder assembly 72. A torsion return spring 77 engages the shaft barrel 74 and the drive plate 80 and is responsible for returning the drive shaft 73 back to a "start" position such that when the electronic module 60 is attached to the front end assembly 70 the drive pin 63 will properly engage the drive plate 80 of the front end assembly 70.

[0065] As best shown in FIG. 31A and FIG. 31B, O-rings 57 between the pusher assembly 71 and the cartridge holder assembly 72 create a separation barrier to ensure the device 50 stays sterile during operation. The first O-ring 57 seals the rotating shaft against the front end assembly. The second O-ring 57 seals closer to the housing and seals the front end assembly against the nose collar 157. The plurality of O-rings 57 provide a sterile barrier to seal the device exterior from the interior of the handle. Alternatively, as shown in FIG. 31C, a Teflon seal 57A can be used, which provides for a more durable barrier to the entry and exit of fluids and other possible contaminants. The barrier seal eliminates means of exiting of any non-sterile germs, debris, particles, etc., from the inside of the device to the sterile outside of the device front end.

[0066] FIG. 3B and FIG. 3C show expanded views of the pusher assembly including a pawl 95 (as shown in FIG. 3A) located at the tip, which resides in a slot in the drive arm 75 of the pusher assembly, and is connected to the drive arm 75 by a pivot pin 99. The needle (not shown) is driven in a circular path by the pawl 95.

[0067] FIG. 4 shows an embodiment of the curved tissue closure needle 110 of the presently disclosed embodiments, which is particularly suitable for penetration through bony material. The needle 110 is formed as a circular split ring defining an aperture (or gap) 111, a sharp, pointed end 112 and an opposite blunt end 113. A cylindrical bore 114 aligned axially with respect to the needle 110, is located at the blunt end 113. The leading end of the suturing material for tissue closure is inserted into the bore 114 and restrained by mechanically crimping. Alternatively, the opening for accommodating the suture material can be in the form of an "eye" wherein the leading end of the suturing material may be passed through for attaching it to the needle 110. To enable the needle 110 to penetrate to the required depth, the needle 110 preferably has an arcuate extent between about 250° and about 330°.

[0068] The needle 110 further includes two symmetric notches 115a and 115b along the radially rear edge, i.e. the edge proximal to the cartridge holder assembly. The notch 115b is positioned toward the sharp pointed end 112 of the needle 110. The notch 115a is positioned toward the blunt end 113 of the needle 110. The notches 115a and 115b are

located opposite to one another, each having a perpendicular (about 90°) segment and an angular segment that makes an angle of about 60° with the perpendicular segment. The notches 115a and 115b are engaged by the drive mechanism (pawl) in the cartridge holder assembly 72 and enable the needle 110 to undergo a rotational movement upon actuation of the drive mechanism, thereby causing it to penetrate and advance through the space spanning the tissue segment, such as a split sternum. A notch 116 is located on the radially outer edge ("outer notch") of the needle 110 proximally to the notch 115b that is closer to the sharp, pointed end 112. The outer notch 116 engages with an anti-rotate bar located in the cartridge holder assembly 72, whereby rotation of the needle 110 in a direction opposite to the advancing direction or "needle backing-up" is prevented. The positive engagement of the needle outer notch 116 during operation prevents the needle 110 from straying out of sequence during the suturing process.

[0069] The needle 110 is enclosed within a cartridge, so the sharp pointed end 112 is not exposed. This needle position, as loaded, is referred to as the "home" position. In the home position, the needle 110 is fully contained within the cartridge housing to eliminate needle-pricks during handling of the cartridge or the loaded device. The width of the aperture in the needle cartridge is comparable to and corresponds with the width of the gap in the needle 110 so that when the needle 110 is in the home position the needle 110 does not project materially into the aperture 111. Such an alignment causes the needle 110 to reside entirely within the needle cartridge, thereby preventing inadvertent contact of the sharp pointed end 112 with the user's fingers during handling of the disposable needle cartridge for placement on the cartridge holder assembly or disposal after use, and while operating the tissue closure device 50. Such protection of the needle 110 in the tissue closure device 50 prevents accidental "needle-pricks" from occurring, thereby substantially reducing the risk of infection caused by pathogenic bacteria or viruses that may contaminate the needle 110 during or after use prior to disposal. The needle 110 may be rotated in a curved track of the needle cartridge about the longitudinal axis of the suturing device 50 to advance the pointed needle end 112 so that the needle 110 first spans the aperture 111 and then returns to the home position. The suturing material is attached to the needle 110, and therefore follows the path of the needle 110. The suturing material may then be cut and twist tied and secured by an appropriate method. Every stitch, whether a single, interrupted stitch, or one of a series of continuous, running stitches may be placed in like manner. The tissue closure, or suturing

device 50, therefore, may be used to insert either a single stitch, or to insert a suture comprising a plurality of continuous stitches as a replacement method for a more tedious and time-consuming manual suturing process.

[0070] **FIG. 5A** provides a detailed view of the pusher assembly 71 with relation to the suturing needle 110. The pawl at the tip of the drive arm 75 is capable of interfitting with wedge shaped notches located along the radially inner edge of the needle 110. The drive arm 75 is capable of sweeping back and forth in an arc spanning about 190°. The drive arm rotates more than 180°, and the overdrive accounts for any design irregularities and tolerances on the needle 110 and the moving parts and ensures that the pawl will always pick up the needle notch 116.

[0071] The advancing movement of the needle 110 during operation causes triangular slots along the radially inner edge of the needle 110 to align with the wedge-shaped pawl in the drive arm 75, thereby causing the pawl to engage the slots due to a positive pressure exerted on the pin 99, and to "lock" into the slots. The rotatory advancing movement of the needle 110 is therefore controlled to occur sequentially through about 190° each time the tissue closure device 50 is actuated. For each suture stitch, the needle 110 rotates through an arc of about 360°, while the drive arm 75 rotates back and forth for a total of about 760° degrees per stitch.

[0072] **FIG. 5B** and **FIG. 5C** are sectional views of the tissue closure needle and the pusher assembly. As shown in **FIG. 5B**, a flat spring 96 asserts tension on the pawl 95 to push the pawl 95 distally into the needle 110 and into the notch 115b. When the pawl 95 is rotated, the pawl 95 picks up that notch 115b and drives the needle 110.

[0073] **FIG. 5C** shows the pawl 95 not engaged in the notch 115b and engaging the surface of the needle 110. As the pawl 95 moves along the outer surface of the needle 110, the pawl 95 encounters the notch 115b. The pawl tip engages the ramp for the notch 115b and the flat spring 96 pushes the pawl 95 into the needle notch 115b.

[0074] **FIG. 5C** shows a pawl stop 98 that permits the pawl tip to only extend a certain amount into the needle 110 to not bind the needle 110 and cause the needle 110 to stop. The pawl 95 has an angled surface that angles away from the pawl stop 98. When the pawl 95 rotates clockwise, the pawl 95 can only turn until the angled surface contacts the pawl stop 98. The pawl 95 contacting the pawl stop 98 is shown in **FIG. 5B**. The pawl stop

98 prevents further rotation of the pawl 95 and prevents the pawl 95 from binding the needle 110 in the cartridge 90.

[0075] FIG. 6 shows a close-up view of the distal end 81 of the cartridge holder assembly 72. The cartridge holder assembly 72 is composed of a sterilizable medical grade material which can either be a metallic material such as stainless steel to enable its reuse subsequent to sterilization following a prior use, or a sterilizable medical grade plastic material, in which case, it may be discarded and disposed after a single use. The cartridge holder assembly 72 has a cylindrical configuration with a distal edge 87 and a proximal edge 89 with respect to the device actuator handle (not shown), with an aperture 85 that corresponds in dimension and location to coincide with a substantially similar aperture located in the disposable needle cartridge. The cartridge holder assembly 72 additionally comprises a plurality of slots 82 located along on the distal edge 87 that are located opposite to one another, and are capable of engaging the same plurality of retaining clips correspondingly located in the needle cartridge housing (not shown). The cartridge holder assembly 72 further comprises a cylindrical slot (not visible) located on the distal edge 87 that is capable of engaging a pivoting pin of identical diameter correspondingly located on a gate assembly 105. The proximal edge 89 of the cartridge holder assembly 72 is attached to the shaft segment 74 by the support arm assembly 76. The gate assembly 105 prevents the needle from leaving the track and falling out into the back of the cartridge holder assembly 72. The gate assembly 105 pivots on a pivot pin 107 like a rocker switch during each actuation of the tissue closure device 50 to permit a circular movement of the drive mechanism that engages the needle. Stop pins 106 located on the cartridge holder assembly cause the gate assembly 105 to stop and reverse direction, like a "see-saw," "up-down" motion. The gate assembly 105 precludes the lateral movement and dislocation of the needle within the cartridge holder assembly 72. The gate assembly 105 is able to pivot on the pivot pin 107 so that the drive arm 75 which engages with the needle via the pawl can pass by the gate assembly 105. An anti-rotate bar 100 is capable of engaging with the needle cartridge 90 to lock it in place on the cartridge holder assembly 72 as well as to engage the needle, whereby rotation of the needle in a direction opposite to the advancing direction or "needle backing-up" is prevented.

[0076] FIG. 7 shows a close-up view of a disposable needle cartridge 90 of the presently disclosed embodiments, which is preferably offered in a sterilized sealed package.



The needle cartridge **90** comprises a circular housing **91** that may be formed of a suitable rigid medical grade sterilizable metal or plastic material. The material forming the cartridge **90** preferably has both rigidity and a low coefficient of friction to reduce the power required to move the needle disposed within it. One such material, for example, is Lubricomp DFP22H, produced by GE Plastics, a polycarbonate containing 10% glass fill, 8% PTFE (Teflon), and 2% silicone. Constructing the cartridge from this material can provide for up to 20% more needle driving power at the point of the needle. The housing **91** may be releasably retained by the cartridge holder assembly at the distal end of suturing device **50** by known means, such as a plurality of grooves **94** in diametrically opposite positions that are capable of engaging with the plurality of slots on the distal edge of the cartridge holder assembly. The needle cartridge **90** further comprises a groove **93** that is capable of engaging the anti-rotate and locking bar **100** correspondingly located on the cartridge holder assembly.

[0077] While the grooves **94** when engaged enable the needle cartridge **90** to be retained by the cartridge holder assembly, the groove **93** when engaged with the anti-rotate and locking bar **100** causes an aperture **97** defined in the needle cartridge **90** to be aligned with the corresponding aperture in the cartridge holder assembly. The needle cartridge **90** further comprises a circular groove or "track" **92** that is inscribed in the inside surface of the housing **91**, which lies in a plane that is perpendicular to the longitudinal axis of both the housing **91** and that of the suturing device **50**. The aperture **97** interrupts the track **92**.

[0078] The arcuate suturing needle **110** composed of medical grade stainless steel or similar material is slidably positioned in the track **92**. The radius of the arc defining the arcuate needle **110** is approximately equal to the circumference to the needle cartridge **90** at the aperture **97** therein. The needle **110** normally resides in a "home" position in the track **92** such that the gap in the arcuate needle **110** is in alignment with the aperture **97** in the cartridge **90**. The sharp, pointed end of the needle **110** is situated on one side and entirely within the confines of the housing aperture **97**; the pointed end of the needle **110** is, therefore, shielded by the cartridge housing **91**. The blunt end of the needle **110** that is attached to a suturing material is located at the opposite side of the aperture **97**. The sharp, pointed end of the needle **110** is, therefore, wholly contained within the cartridge **90** and does not protrude beyond the housing of the cartridge **90**. Thus, the sharp pointed end of the needle **110** is not exposed to the user.

[0079] FIG. 8A shows a close-up view of the anti-rotate and locking bar 100. As shown in FIG. 8B, the anti-rotate and locking bar 100 includes a cartridge locking surface 101, which makes contact with the needle cartridge 90 and locks it into place, and an anti-rotate surface 102, which contacts the needle 110. A coil spring 104 engages the cartridge holder assembly 72 and allows the anti-rotate and locking bar 100 to move up and down so as to lock or un-lock the needle cartridge 90 into place on the cartridge holder assembly 72.

[0080] FIGS. 14A and 14B show an enlarged view of the distal end 81 of the cartridge holder assembly 72. In FIG. 14A, the needle cartridge 90 is in a non-locked position. In order to lock the needle cartridge 90, the needle cartridge 90 needs to be rotated counter clockwise. To unlock the needle cartridge 90 from the distal end 81 of the cartridge holder assembly 72, the anti-rotate and locking bar 100 may be pressed down to engage the coil spring and this will allow the anti-rotate and locking bar 100 to pivot at pivot pin 103.

[0081] FIG 9 shows an alternative cartridge locking mechanism. A locking pin 200 is slidably disposed within the cartridge holder assembly 72. A handle and button 203 connected to the locking pin 200 allows the operator to slide the pin 200 proximally along the slot 204 from a position that protrudes from the distal edge 87 of the cartridge holder assembly 72 to a fully retracted position (not shown). As shown in the cross-sectional view of FIG. 11, the locking pin 200 is biased to protrude from the distal edge 87 of the cartridge holder assembly 72 by virtue of the spring 201 situated on the proximal end of the locking pin 200. When the needle cartridge 90 is secured to the cartridge holder assembly 72, whereby the grooves 94 are fully engaged with the slots 82, a locking pin recess 202 on the mating surface of the cartridge 90 aligns with the pin 200, allowing the pin 200 to protrude and engage the recess 202, thereby locking the needle cartridge 90 rotationally onto the cartridge holder assembly 72. The locking pin recess 202 is formed to be slightly larger but with a similar cross-sectional shape as the locking pin 200. In one embodiment, the cross-sectional shape of the locking pin 200 and the shape of the locking pin recess 202 are circular. To release the cartridge from the cartridge holder assembly, a user can engage the handle and button 203 attached to the pin 200 and slide the pin 200 proximally to retract it from the locking pin recess 202. Upon retracting the locking pin 200, the user can rotate the needle cartridge 90 to disengage the grooves 94 from the slots 82, and thereby remove the cartridge from the cartridge holder assembly 72. The locking pin recess 202 is more clearly

seen in **FIG. 12**, a perspective view of a portion of the mating or proximal surface of the needle cartridge **90**.

[0082] The anti-rotate and locking bar **100** engages the outer notch of the needle **110** to prevent rotation of the needle **110** and prevent "needle backing-up" and thereby precluding the needle **110** from straying out of sequence. **FIG. 14B** shows the needle cartridge **90** locked into position both rotationally and axially.

[0083] The construction of the anti-rotate and locking bar **100** can be simplified if the cartridge locking function is achieved with a locking pin **200**. The arm leading to the locking surface **101** of the anti-rotate and locking bar **100**, can be eliminated, resulting in a purely anti-rotate bar **300**, as shown in **FIG. 13**. The anti-rotate bar **300** can comprise an anti-rotate surface **302** that makes contact with the needle **110**. The anti-rotate bar **300** is biased by spring **304** to engage the anti-rotate surface **302** with the outer notch **116** of needle **110** to prevent reverse rotation of the needle **110**.

[0084] As shown in **FIG. 15**, the cartridge **90** can be equipped with a suture retainer **400** to keep the suture material **138** from interfering with the rotation of the needle **110** during operation of the suturing device **50**. The suture retainer **400** helps to keep the suture material **138** away from the needle track **92** of the cartridge **90**. A front perspective view of the needle retainer **400** is shown in **FIG. 16**. The projections **401** help the operator to guide the suture material **138** into the needle retainer recess **402** of the cartridge **90**. As shown in **FIG. 17**, the detents **403** of the needle retainer **400** cause the passageway to the needle retainer recess **402** to be slightly smaller than the diameter of the suture material **138**, allowing the operator to press-fit the suture material **138** into the needle retainer recess **402**. This is also shown in **FIG. 18**, illustrating how the detents **403** provide a slightly narrower passageway for the suture material into and out of the needle retainer recess **402**. This feature prevents the suture material **138** from unintentionally slipping out of the needle retainer **400**.

[0085] The needle cartridge **90** can also be equipped with a needle brace **500**, as shown in **FIG. 19**. Positioning a needle brace **500** against the cartridge **90** can prevent inadvertent movement of the needle **110** within the cartridge **90** during handling of the cartridge **90** and suture material **138** prior to loading the cartridge **90** onto the cartridge holder assembly **72**. This keeps the needle **110** from straying within the track to a position placing it out of proper sequence for initiation of the first actuation cycle of the suturing device **50**. The

needle brace 500 has a flange 501 that contacts the outside (distal) surface of the needle cartridge 90 holding the brace in position, as shown in FIG. 20. The needle brace 500 has a body 502 whose outside radial dimension conforms to the inside radial dimension of the cartridge 90, allowing a shoulder feature 503 of needle brace 500 to be situated near the inside (proximal) surface of cartridge 90 and adjacent to the hub or blunt end of needle 110 seated within the cartridge 90, as shown in FIG. 21. The needle 110 is thus prevented from rotating within its track in a reverse direction. Similarly, the pointed end of needle 110 is prevented from moving forward in its track by the presence of the vertical segment 504 of body 502 of needle brace 500, which closely conforms to the inside radial dimension of cartridge 90 and blocks the forward movement of needle 110 in its track. With the needle brace 500 in position, an individual can manipulate the cartridge/needle/suture assembly without fear of inadvertently moving the needle within the track of cartridge 90. Such movement could potentially position the needle out of proper sequence for activation after it is placed on the cartridge holder assembly 72. The needle brace 500 may be formed of a suitable rigid medical grade disposable metal or plastic material.

[0086] The needle brace 500 can be secured within the inner circumference of the cartridge 90, either through a frictional 'press' fit, or through tabs placed along the periphery of the needle brace 500, which can cooperate with corresponding depressions (not shown) along the inner circumference of the cartridge 90. In a further refinement of the needle brace 500, the vertical segment 504 can be constructed so that it forms a tab 504A as shown in FIG. 22. The tab 504A is constructed of material with sufficient elastic properties to be somewhat bendable. The Lubricomp plastic material referenced earlier, for example, possesses this characteristic. With the pointed end of needle 110 positioned at the end of the track of cartridge 90, installing needle brace 500 causes the tab 504A to bend slightly and snap into position over the tip of the needle 112, thereby locking the needle brace 500 into position, as shown in FIG. 23. A user can remove the needle brace 500 by applying sufficient force to overcome the elastic resistance of the tab 504a.

[0087] FIG. 24 is an exploded perspective view of the removable electronic module 60 which is a battery-operated electro-mechanical assembly. The electronic module 60 includes the battery pack 62 and the electric motor 61 which includes the gear box 59 and an output shaft 58, as well as electronic circuits. The battery 62 is preferably re-chargeable and provides the power for the electronic module 60. The battery 62 should have a minimum

battery life of about 400 discharge cycles and be able to perform 18 sutures (or 36 total cycles) through a tissue segment such as the sternum. The motor 61 provides the rotational force necessary for the tissue closure device 50 to function. An electronics board controls the operation of the electronic module 60 based on user controlled power and actuation buttons. Indicators are provided to provide feedback to the user of the current status of the electronic module 60. A microprocessor and firmware control the starting, stopping, and torque of the electric motor 61. The electronics also includes the recharging circuit for the battery pack 62. The electronic module 60 may be provided as non-sterile and may be attached to the front end assembly prior to surgery by an aseptic technique. The electronic module 60 may be removed from the front end assembly following a procedure for cleaning, battery charging and storage. Additional views of the electronic module 60 are shown in FIG. 25(A) to 25(H).

[0088] FIGS. 26A and 26B show the tissue closure device 50 wherein the removable electronic module 60 has been enclosed in a thermoplastic enclosure 150 and a thermoplastic housing 151. A door 152, locked by a clamp latch 153, provides entry and exit for the removable electronic module 60. The handle 160 of the device has the door 152 at the proximal end where the removable electronic module 60 is inserted. When the non-sterile battery pack is installed, the door 152 needs to be closed and sealed. The door 152 is sealed using an O-ring or Teflon seal similar to the front end of the device to prevent the egress of any non-sterile germs from the inside the device into the sterile operating field.

[0089] In order to facilitate the placement of a non-sterile electronic module 60 into a sterile handle 160, a funnel 600 can be provided, which is temporarily placed within the opening of the proximal end of the handle 160, as shown in FIGS. 27(A-F). The funnel 600 operates as a physical barrier between the person (e.g. circulating nurse) who handles the non-sterile electronic module 60 and the person (e.g. surgical scrub nurse) who handles the sterile components of the suturing device 50. The sterile components include the handle 160, the door 152, the latch 153, the nose collar 157, the shaft segment 74, cartridge holder assembly 72, and cartridge 90. The funnel 600 is initially sterile when inserted into the handle 160. As shown in FIGS. 28(A-F), the funnel 600 has a proximal barrel 601 and a distal barrel 602, each shaped in cross-section to conform to the cross-sectional shape of the handle 160 and corresponding electronic module 60. The proximal 601 and distal 602 barrels of the funnel 600 are separated by a flange 603 broad enough to form a barrier between the

hand of the person inserting the electronic module 60 and the rest of the suturing device 50. An arrow 604 can be printed or engraved on the surface of the flange to direct the user in installing the funnel 600 in the proper vertical orientation. The arrow 604 or other suitable printing 605 on the flange 603 can also help the user distinguish the proximal 601 from the distal 602 barrels of the funnel 600. The distal barrel 602 can fit within the handle 160, as shown in FIG. 27B and 27E. The electronic module 60 can be passed through the cavity of the funnel 600, as shown in FIG. 27C and 27F. Once the electronic module has passed through the funnel 600, and has been inserted into the handle 160, the funnel 600 is no longer considered to be sterile and can be removed. The door 152 can then be closed in a sterile manner and secured with the latch 153, also securing the proximal end of the electronic module 60 in place. The outer surfaces of the suturing device 50 remain sterile, a condition facilitated by the use of the funnel 600. In an alternative embodiment, the funnel 600 can have a sterile drape (preferably disposable) attached to the periphery of the flange 603 in order to extend the barrier separating the sterile from the non-sterile components and personnel. The mode of attachment of the drape to the flange 603 can include, for example, a high strength adhesive that resists breakdown by heat, moisture and sterilizing gas.

[0090] As shown in FIGS. 26A through 26C, a silicone keypad is encapsulated into the enclosure 150 and provides two buttons, one for power 154, and one for actuation 155. An alternative electronic module 60 with a different arrangement of the keypad buttons is shown in FIG. 29, in which the Power-on/Power-off button 154A is separated from the actuation button 155A by the LED indicator 156. The electronic keypad 154A and 155A, and LED indicator 156 are integral to the battery/motor/gear box unit, and form the electronic module 60, as shown in FIG. 29. The Power-on / Power-off button 154 enables the electronic module to either be turned on or off. The actuation button 155 may be depressed which would run the electronic module through one cycle. One cycle consists of a 360° needle 110 rotation accomplished through two 190° rotations of the output shaft 58. The electronic module 60 interfaces with the enclosure 150 through the stop plate 66 mounted to the front of the electronic module 60. The stop plate 66 has flat faces and a taper to engage into the enclosure 150. This provides the connection to capture the torque applied within the unit so that the operator does not have to oppose the torque of the suturing operation (anti-rotation feature). The stop plate 66 also limits the rotation travel of the output shaft 58 to about 190°. A drive wheel is attached to the output shaft of the electronic module 60. The

drive wheel contains a drive pin which engages with the drive plate of the front end assembly 70. The drive pin supplies the torque to the front end assembly 70 to drive the needle 110 through the tissue. The drive wheel also contains two permanent magnets. These magnets are preferably used in conjunction with a Hall effect sensor 162 to detect the rotational extents of travel. A nose collar 157 attaches the front end assembly 70 to the housing 151 via screws 158 or some other means for mechanical engagement.

[0091] Three indicators (LEDs) 156 show the status of the unit: Power (Green), Error (Red) & Low Battery (Yellow). The housing 151 and keypad provide an exterior surface that is capable of sustaining hospital wipe-down procedures, but is not sterilizable in an autoclave. The electronic module software and operating features cause the needle driver arm to automatically move to its home position (reverse motion limit) when the Power-on /Power-off button 154 is initially activated (depressed). The unit will turn itself off after 10 minutes of inactivity in the event it is stored with the power on. Depressing the Power-on /Power-off button 154 during an actuation cycle will be ignored by the software. When the electronic module is switched On, the On LED indicator will illuminate and remain illuminated until switched Off. In one embodiment, triggering an actuation cycle to drive the needle through tissue by depressing the actuation button 155 will cause the device 50 to automatically power off at the end of the cycle. Once switched On or Off, the electronic module will stay in that condition until deliberately switched to the opposite condition, unless there is an error mode, the electronic module times-out from inactivity, or an actuation cycle has occurred. The electronic module has an Error LED (color red) to indicate an Error Mode. The electronic module also has a Low Battery LED (color Yellow) which indicates the internal battery needs to be charged. The actuation button 155 must be depressed for the device 50 to drive the tissue closure needle 110. The actuation cycle begins when the actuation button 155 is depressed. The actuation button 155 does not have to remain depressed (i.e. the actuation cycle will complete if the button is released). The actuation button 155 only requires one depression to rotate the needle 110 360° (the needle driver arm will automatically rotate 190° twice to accomplish rotating the needle 110 the full 360°) The actuation button 155 is operable so long as the device 50 is On and not already in a suturing sequence. The actuation button 155 must be released and the Power-on button 154 re-depressed before depression of the Actuation button 155 will again begin the next suturing cycle. The electronic Hall effect sensor 162 combined with the firmware sense the extent of the about 190 degree rotations

utilizing the permanent magnets in the drive wheel. Once the end of motion is detected the firmware modifies the torque applied to the motor to create a soft-stop. Some of the Error Modes that may occur during operation are listed in Table 1.

LED:	Power Green	Error Red	Low Battery Yellow	REM Status:
Off Mode	OFF	OFF	OFF	Unit is off and will not actuate
On Mode	ON	OFF	OFF	Unit is ready for use
Actuating	ON	OFF	OFF	Unit is actuating through a cycle.
Error Mode	ON	ON	OFF	Indicates an error occurred. Mechanism will return to home position and not actuate if actuation button is depressed.
Recharge Required	ON	OFF	ON	Battery needs to be recharged upon completion of surgery. i.e. unit can do 6 more complete sutures.
Battery drained	ON	ON	ON	Battery is drained. Unit will not actuate. Needs to be recharged.
Charging Battery	OFF	OFF	Blinking	Charging cycle. Device will not turn on or actuate while in this mode. Blinking rate TBD.
Battery Fully Charged	OFF	OFF	ON	Battery charging cycle is completed

**Table 1**

[0092] **FIG. 30** is a close-up view of the stop plate 66 and drive wheel 67 (shown as transparent), permanent magnets 65, the drive pin 63 and the gear 59 shaft. At the center of the stop plate 66 there is a hole which provides the entry point for the gear 59 shaft. The stop plate 66 is attached to the gear box 59 by screws 69. The stop plate 66 comprises a “U-shaped” track 64 in which the drive pin 63 rides. As the device is actuated, such that the electronic module causes rotation, the drive pin 63 will ride along the track 64 until the drive pin 63 reaches a stopping point. The track 64 provides the mechanical stops that limit the rotation of the device 50. The permanent magnets 65 are used in conjunction with the Hall effect sensor 162 located at a distal end of an electronics board 161 located inside the removable electronic module 60 to detect the rotational extents of travel. The electronic Hall effect sensor 162 combined with the firmware sense the extent of the about 190 degree rotations utilizing the magnets 65 in the drive wheel 67. Once the end of motion is detected the firmware modifies the torque applied to the motor 61 to create a soft-stop.



[0093] FIG. 26C shows the Hall effect sensor 162 located on the electronics board 161 that is used to detect the rotational position of the drive wheel 67. When the rotation is nearing the stopping point, the magnets 65 pass adjacent to the Hall effect sensor 162, sending a signal to the control electronics that the needle 110 will soon be stopping. At that point the motor torque is reduced. The motor continues to drive to the mechanical stopping point at the reduced torque level. When the drive pin 63 hits the mechanical stopping point, the control electronics sense the current spike that is caused by the motor not turning any more and shut off the power to the motor. At least two magnets 65 are positioned in the drive wheel 67 to sense the approach to stopping points at both ends of the arc traveled by the drive wheel 67.

[0094] FIGS. 31A and 31B show the main components of the suturing device 50. In FIG. 31A the electronic module 60 has been drawn disengaged from the front end assembly 70. During the disengaged stage, the torsion return spring 77 is extended to allow the pusher assembly 71 to return to a "home" position. In the home position, the drive plate 80 returns to a start position, such that a hole 84 in the drive plate 80 is ready to accept the drive pin 63. As shown in FIG. 31B the electronic module 60 has been attached to the front end assembly 70. When the electronic module 60 is connected, the drive shaft 73 engages a bushing 67a located in the drive wheel 67; the drive pin 63 engages the hole 84 in the drive plate 80 and the device 50 is ready.

[0095] FIG. 32A shows the curved suturing needle 110 having a tissue closing material attached. The needle 110 is formed as a circular split ring with the aperture (or gap) 111, the sharp, pointed end 112 and the opposite blunt end 113. The cylindrical bore 114 aligned axially with respect to the needle 110, is located at the blunt end 113. A flexible leader 136 of the tissue closing suture material is inserted into the blunt end 113 and can be restrained by mechanical engagement, for example mechanical crimping. Those skilled in the art will recognize that the flexible leader 136 may engage the needle 110 by any type of mechanical engagement including, but not limited to, welding, soldering, or laser welding. For example, the assembly comprising the flexible leader 136 inserted into the bore 114 of the needle can be immobilized in a clamp, and the junction circumferentially welded with a YAG laser welder or other suitable laser welder. The junction between the flexible leader and wire monofilament suture similarly can be welded or laser-welded. A suture-needle assembly welded in this manner can provide a smoother transition between the needle and

flexible leader, and between the flexible leader and the monofilament suture than mechanical crimping, which facilitates drawing the suture material through the tissue. Thus it is easier to pass the suture through the first side of the divided sternum, for example, while maneuvering the device 50 in preparation for placing a suture in the second side of the divided sternum. To enable the needle 110 to penetrate to the required depth, the needle 110 preferably has an arcuate extent between about 250° and about 330°.

[0096] For suturing through bone, it may be preferable to have a triple-faceted (or 'cutting-edge') needle point as shown in FIG. 33A, each facet occupying approximately 120° of the circumference of the needle shaft. As shown in FIG. 33B, One of the facets can be oriented to face the outside curvature of the needle, in which case the outside-facing facet can be cut at a shallower angle than the other two facets, preferably at an angle of approximately 21° with respect to the long axis of the needle shaft. The resulting cutting surface of the needle point as shown in FIG. 33C will have a shorter cutting height, leading to more efficient penetration of bony or other dense tissue. Alternatively, when placing the sutures around the outer or lateral edge of the sternum, the needle tip can be configured with a 'blunt taper-point' or 'ball-point'. The rounded tip and conical shape of the leading component of the needle shaft permits less traumatic penetration through softer tissues. Other applications may require sharper tipped 'taper-point' needles, or even 'reverse-cutting edge' needles.

[0097] The needle 110 has two symmetric notches 115a and 115b along the radially rear edge, i.e. the edge proximal to the cartridge holder assembly. The notch 115b is positioned toward the sharp pointed end 112 of the needle 110. The notch 115a is positioned toward the blunt end 113 of the needle 110. The notches 115a and 115b are located opposite to one another, each having a perpendicular (about 90°) segment and an angular segment that makes an angle of about 60° with the perpendicular segment. The notches 115a and 115b are engaged by the drive mechanism (pawl) in the cartridge holder assembly 72 and enable the needle 110 to undergo a rotational movement upon actuation of the drive mechanism, causing the needle 110 to penetrate and advance through the space spanning the split sternum, or other tissue location. A notch 116 is located on the radially outer edge ("outer notch") of the needle 110 proximally to the notch 115b that is closer to the sharp pointed end 112. The outer notch 116 engages with an anti-rotate and locking bar located in the cartridge holder assembly 72, whereby rotation of the needle 110 in a direction opposite to the advancing

direction or "needle backing-up" is prevented. The positive engagement of the needle outer notch 116 during operation prevents the needle 110 from straying out of sequence during the suturing process. In addition, the blunt end or hub 113 of the needle 110 can also engage the anti-rotate bar 100 (or 300, if the device has a separate locking pin), as seen in FIG. 39C, to prevent the needle 110 from reversing direction after it has traversed the aperture in the needle cartridge 90.

[0098] The needle 110 is enclosed within a cartridge, so the sharp pointed end 112 is not exposed. This needle position, as loaded, is referred to as the "home" position. In the home position, the needle 110 is fully contained within the cartridge housing to eliminate needle-pricks during handling of the cartridge or the loaded device. The width of the aperture in the needle cartridge is comparable to and corresponds with the width of the gap in the needle 110 so that when the needle 110 is in the home position the needle 110 does not project materially into the aperture 111. Such an alignment causes the needle 110 to reside entirely within the needle cartridge, thereby preventing inadvertent contact of the sharp pointed end 112 with the user's fingers during handling of the disposable needle cartridge for placement on the cartridge holder assembly or disposal after use, and while operating the suturing device 50. Such protection of the needle 110 in the suturing device 50 prevents accidental "needle-pricks" from occurring, thereby substantially reducing the risk of infection caused by pathogenic bacteria or viruses that may contaminate the needle 110 during or after use prior to disposal. The needle 110 may be rotated in a curved track of the needle cartridge about the longitudinal axis of the suturing device 50 to advance the pointed needle end 112 so that the needle 110 first spans the aperture 111 and then returns to the home position.

[0099] FIG. 32B shows an expanded view of a crimp 137 that houses the ends of the two materials that form a tissue closure suture material. The tissue closing material includes the flexible leader 136 attached to a wire suture 138 by means of the crimp 137. The crimp has an opening on each end, a first opening 137a accepts the flexible leader 136 and a second opening 137b accepts the wire suture 138. The flexible leader 136 is placed into the first opening 137a and then the crimp 137 is mechanically crimped to engage the flexible leader 136. The wire suture 138 is placed into the second opening 137b and then the crimp 137 is mechanically crimped to engage the wire suture 138. Those skilled in the art will recognize that the crimp 137 may engage the flexible leader 136 and the wire suture 138 by any type of mechanical engagement including, but not limited to, welding, soldering, or laser welding.

The crimp **137** has a curved shape to make it easier to slide through the holes. The crimp **137** is streamlined and low profile to travel through tissue, cartilage or bone.

[00100] The flexible leader **136** has a diameter (gauge) that is larger or equal to the diameter of the wire suture **138**. The flexible leader **136** may be formed from a stainless steel material or by some other braided or monofilament material. In an embodiment, the flexible leader **136** is formed from wire cable. In an embodiment, the length of the flexible leader **136** is between about 8 inches to about 18 inches. The flexible leader **136** may be longer than 18 inches. The flexible leader **136** acts to improve ease of suture manipulation within the thorax, for example (under the sternum) during placement of each of the series of wire sternum closure sutures and thus make sternum closure faster and easier. The wire cable **138** may be formed from wire suture, such as stainless steel, made available in varying wire sizes, such as, for example, 5, 6, and 7. In an embodiment, the length of the wire suture **138** is at least 18 inches and may be longer than 18 inches. As shown in FIG. 34, the cartridge **90**, needle **110** and suture material **138** can form the components of a sterile kit, packaged in appropriate plastic/reinforced paper material **700**, which preferably can be peeled open to lay out the components onto a sterile field. The bottom web of the package can be thermoformable transparent plastic film, such as polyamide/polyethylene or polypropylene/polyethylene. This allows the contents of the sealed package to be visible. The top web can be sterilizable paper, such as Tyvek®, with a basic weight of about 60 gm/m<sup>2</sup> or more, allowing it to be permeable to sterilizing gas, so that the cartridge **90**, needle **110** and suture material **138** can be sterilized from within the package. The top and bottom webs are sealed along the periphery of the package using a suitable adhesive. The package preferably can be opened by hand, using peel-open corners and peelable seams.

[00101] The suturing device **50** is designed to be held in the dominant hand of the medical professional. FIG. 35 shows an embodiment of a suturing device having a ergonomic handle **160**. FIGS. 36A-C show aspects of the front side of the device **50** with cartridge **90** attached. FIGS. 37A-D show aspects of the rear sides (FIG. 37A and 37B), the bottom side (FIG. 37C) and the top side (FIG. 37D) of suturing device **50** without the cartridge **90**. FIG. 38 shows an embodiment of a suturing device having a pistol-like handle **160**. The handle **160** is supplied non-sterile to the medical professional. The hospital or office is responsible for sterilizing the device **50** by techniques known in the art, such as gravity steam sterilization, Steris and ETO. In an embodiment shown in FIG. 35, the

electronic module 60 has been surrounded by a hollow handle/body that includes an activator button and may also include flush ports along the handle/body in order to provide a port of entry for cleaning fluids or suction such that the device 50 can be cleaned prior to or after use. In an embodiment shown in FIG. 38, the electronic module 60 has been surrounded by a different hollow handle that includes an activator button and may also include flush ports along the handle/body in order to provide a port of entry for cleaning fluids or suction such that the device 50 can be cleaned prior to or after use. Those skilled in the art will recognize that the battery pack 62 and electric motor 61 can be placed anywhere in the handle and be within the scope and spirit of the presently disclosed embodiments.

[00102] FIGS. 39A, 39B, 39C and 39D show serial views of the "rear-drive" needle operating drive mechanism operating within the distal end of the cartridge holder assembly. The "rear-drive" mechanism comprises the drive arm 75 connected to a drive shaft that is capable of circular motion so as to "sweep" along the circular inner edge of the cartridge holder assembly. FIG. 39A shows the needle 110 in the "home" position. Initially, the pawl 95 has not made contact with the needle 110. The drive arm 75 moves to engage a notch 115a in the needle 110 (referred to as rest position). As shown in FIG. 39B, the gate assembly 105 is resting at stop pin 106. Actuation of the device causes the drive shaft to rotate about 190° in a counterclockwise direction (referred to as position # 1), thereby causing the drive arm 75 to move circularly from its "home" rest position and move up to and past the gate assembly 105, causing the gate assembly to pivot clockwise in the process so that the gate assembly 105 is now resting at the other stop pin 106. The needle 110 is prevented from moving backwards by the anti-rotate and locking bar 100. The needle 110, in this position, is referred to as in a "penetrating-state" of the needle 110 cycle. As shown in FIG. 39C, the pawl 95 has been disengaged from the notch 115a and the drive arm 75 continues to move circularly until it comes to rest once again in the "home" position, about 190° clockwise from position # 1 (this new position is referred to as position # 2). The pawl 95 then engages the notch 115b. The gate assembly 105 has pivoted counterclockwise to rest again at the other stop pin 106. FIG. 39D shows the pawl 95 engaged in the notch 115b and the drive arm 75 continuing to move circularly until it is about 190° clockwise from position # 2 (this new position is referred to as position #3). The gate assembly 105 has pivoted clockwise again to rest at stop pin 106. The needle 110 is pulled through the space between the tissue gap (e.g.,

split sternum) and the closing material follows. The drive arm 75 then returns back to the start home position by rotating 190° clockwise to the position shown in **FIG. 39A**.

[00103] In an embodiment, the handle of the suturing device 50 does not contain batteries, but is powered by electric power provided from outside the sterile field of the operating room (OR). In this external electric power embodiment, the device is configured with an autoclavable motor in the handle and a sterilizable power cord attached to the handle. The device would be connected with the sterilizable cord to a power supply unit that is located outside the sterile field in the operating room. That power unit would be plugged into wall power, and be able to convert the wall power (i.e., 120 volts or 240 volts) to voltage levels appropriate for the motor. The sterilizable cord transmits power to the hand-held unit which contains the motor and the needle driving mechanics. In addition, the control electronics could also be located in the external power unit rather than inside the handle. This change in configuration would reduce the size of the handle.

[00104] The suturing device 50 of the presently disclosed embodiments can be used for any procedure in which bony tissue or dense soft tissue closure is required. The tissue chosen should be sufficiently compliant to permit penetration by one of the variety of needle tips that can be used with the device. Other possible uses could include, for example, repair of injuries or incisions involving the attachment points of the rotator cuff, quadriceps tendon, patellar tendon or Achilles tendon, and rib reapproximation after lateral thoracotomy. In some of these cases, it may be advantageous to use non-metallic suture material attached to a needle that is compatible with the cartridge 90, cartridge holder assembly 72, and pusher assembly 71 of the device 50. The non-metallic suture material can include, for example, braided or monofilament nylon, prolene or dacron, natural material such as silk or catgut, and synthetic absorbable material such as polyglycolic acid, polyglactin, polyglyconate or polydioxone.

[00105] Using a sternotomy procedure as an example, prior to the procedure, the handle of device 50 is sterilized in a hospital autoclave and delivered to the operating room in the same manner as any other piece of sterile surgical equipment. The battery pack 62 of the electronic module 60 has been charged using a charger and is brought into the non-sterile area of the operating room. As part of the routine set up of the surgical field in the operating room, a surgical scrub nurse will open the sterile package containing the sterilized handle of device 50. The scrub nurse will then open the rear portal of the handle and will use standard

practice aseptic technique to present the open portal of the handle to a circulating nurse who is located outside of the sterile operating field. At this time, the scrub nurse can grasp a sterile funnel 600 by the flange 603 and insert it into the handle 160 of the device 50. The circulating nurse will take the fully charged electronic module 60 and install the module 60 into the open rear portal of the handle 160 using standard aseptic technique. The circulating nurse can then grasp the flange 603 of the funnel 600 and withdraw it from the handle 160, being careful not to make contact with any other component of the device 50. To assist in this procedure, the circulating nurse can withdraw the funnel 600 by using a sterile forceps or clamp to grasp the flange 603. The scrub nurse will close the portal, securing and sealing the electronic module 60 into the handle. The reusable device 50 is now ready for the loading of the disposable suture cartridge 90.

[00106] When it is time to close the sternum, the scrub nurse will open the sterile disposable suture cartridges 90 that will be used in the case (a typical package will be a 6-pack). One suture cartridge 90 is loaded onto the cartridge holder assembly 72 of the device 50. The device 50 is checked to make sure that the power light 154 is OFF, none of the LED lights 156 should be illuminated. The 10 o'clock and 2 o'clock slots on the needle cartridge 90 are aligned with the 10 o'clock and 2 o'clock tabs on the cartridge holder assembly 72. The needle cartridge 90 is aligned with the cartridge holder assembly 72, pushed onto the cartridge holder assembly 72, and then rotated counterclockwise to lock the needle cartridge 90 in place. The locking pin 200 comes into alignment with the locking pin recess 202 of the cartridge 90, at which point the locking pin 200 can engage the locking pin recess 202. The needle brace 500, if present, can be removed from the cartridge 90 after it has been secured to the cartridge holder assembly 72. The Power On button 154 is then turned on. The green LED will come on, indicating the device 50 is ready. The actuation button 155 is then pressed to cycle the needle 110 once, prior to placing the device 50 in the surgeon's hand. The device 50 should cycle twice, causing the needle 110 to rotate one revolution. The device 50 is now ready to be used to place the first suture. The scrub nurse will hand the device 50 to the surgeon who will perform the suture placement process. Sutures are placed at the surgeon's discretion from top to bottom of the sternum. Typically about six to eight sutures are used to close the sternum. As an additional measure to enhance its operational safety, the device 50 can be programmed to have each actuation cycle require the operator to press the Power-on button 154 before pressing the actuation button 155.

[00107] To commence the sternotomy closure, any embodiment of the sternotomy closure device 50 is placed at the site of the sternotomy such that the device 50 is between a first side and a second side of a split sternum, the typical starting point is around the manubrium 170 (or head) of the sternum as shown in FIG. 40. The surgeon will elevate one side of the divided sternum with his or her left hand. The surgeon places and aligns the opening (aperture) of the needle cartridge 90 over the cut edge of the sternum locating the penetration point he desires for the suture under the top of the cartridge opening. The surgeon can also use the lower edge of the cartridge holder assembly 72 to elevate the divided sternum during the suturing, obviating the need to place his or her hand under the sternum. The needle will enter the sternum from the exterior (outside) of the patient. The surgeon presses the Power-on button 154 prior to positioning the device 50, and then presses the actuation button 155 while holding the device 50 in the desired location. When the button 155 is pressed, the following actions occur: The electronic controller starts the motor and gearbox rotating clockwise. This motion is transferred from the inside of the electronic module to the drive shaft by the following chain of components: Gearbox shaft to drive wheel to drive plate to the drive shaft to the drive arm. The drive arm holds the pawl. The pawl engages the rear drive notch of the needle. As the drive arm rotates through a first half circular arc, the pawl pushes the needle through a first half of one rotation. This is the stroke that penetrates the sternum. When the drive arm reaches the end of a stroke, the drive arm stops. The drive arm will then reverse direction and return to a start position. As soon as the drive arm reaches the start position, the drive arm stops again. The drive arm now starts to rotate clockwise again. The pawl picks up the front needle notch and pulls the needle through the completion of a stroke. When the drive arm reaches the end of this stroke, the drive arm stops. The drive arm will then reverse direction and return to a start position. As soon as the drive arm reaches a start position, it stops again, and the device 50 automatically powers down. The needle is now completely driven through the one side of the sternum. The flexible leader has been pulled into and through the hole created by the needle. The surgeon will now rotate the device 50 handle clockwise pulling the leader through the one side of the sternum. The surgeon's left hand may be used to assist pulling the flexible leader through the sternum. The surgeon will now elevate the other side of the sternum. The surgeon places and aligns the opening of the needle cartridge 90 over the sternum bone locating the penetration point he desires for the suture under the bottom of the needle



cartridge opening. After the surgeon presses the Power-on button **154**, followed by the actuation button **155**, the needle will enter the sternum from the interior (inside) of the patient. The steps are repeated. At this point, the flexible leader has passed through this side of the sternum. The surgeon may press the cartridge locking surface **101** located on the anti-rotate and locking bar and rotate the needle cartridge **90** clockwise to remove the needle cartridge **90** from the device **50**.

[00108] The device **50** may be passed to the scrub nurse for loading of a second needle cartridge **90**. The surgeon will now use both hands to pull the flexible leader and suture through both sides of the sternum following standard practice for any sternum closure suture. The needle, flexible leader and crimp ferrule are removed from the monofilament suture using standard practices. The surgeon now moves on to place a second suture. The process continues for all remaining sutures that the surgeon chooses to place, typically to an area near the xiphoid process **172**. After all desired sutures are placed, the sternum closure is completed using standard surgical techniques. The device **50** may be prepared for cleaning, sterilization and charging. A typical procedure may include: The clean up personnel will wipe down the outside of the device **50** with a disinfectant. The rear portal will be opened and the electronic module will be removed. The electronic module goes to non-sterile equipment storage for charging on the dedicated charger. The device handle will be cleaned according to a validated cleaning protocol. The device handle will be sterilized according to a validated sterilization protocol.

[00109] A Teflon seal **57A** or an O-ring seal **57** between the pusher assembly and the cartridge holder assembly **72** provide a sterility barrier so that when the pusher assembly is driving the needle, the drive shaft will rotate within the Teflon seal **57A** or O-ring **57** which will prevent anything from migrating down the drive shaft and finding its way inside the handle of the tissue closure device **50**.

[00110] A method for sternum re-approximation is provided herein. The method includes (a) releasably engaging a cartridge having a protective housing and a suturing needle to a cartridge holder assembly of a sternotomy closure device; (b) placing the sternotomy closure device having the cartridge and the suturing needle to cause an aperture in the cartridge to be between a first side and a second side of a split sternum, wherein a pointed end of the suturing needle is positioned within the protective housing before and after a complete rotation of the suturing needle about a rotational axis; (c) activating an electronic

module coupled to a pusher assembly that releasably engages the suturing needle to cause rotational movement of the suturing needle across the aperture in the cartridge and advance the suturing needle through the first side of the split sternum; (d) pulling a suturing material attached to the suturing needle through the first side of the split sternum; and (e) repeating steps (c) and (d) for the second side of the split sternum forming a stitch through the first side and the second side of the split sternum. Steps (b) through (e) are repeated until a length of the first side and the second side of the split sternum have been re-approximated.

[00111] All patents, patent applications, and published references cited herein are hereby incorporated by reference in their entirety. It will be appreciated that various of the above-disclosed and other features and functions, or alternatives thereof, may be desirably combined into many other different systems or applications. Various presently unforeseen or unanticipated alternatives, modifications, variations, or improvements therein may be subsequently made by those skilled in the art which are also intended to be encompassed by the following claims. Thus, it is intended that the present invention include modifications and variations that are within the scope of the appended claims and their equivalents.

## CLAIMS

What is claimed is:

1. A tissue closure device comprising:  
  
a pusher assembly having a drive arm extending from a drive shaft and a drive mechanism at a distal end of the drive arm, wherein the drive mechanism is capable of releasably engaging and rotating a suturing needle having a pointed end and a blunt end about a rotational axis;  
  
a cartridge having a protective housing and the suturing needle, the cartridge extending from a distal end of a cartridge holder assembly and releasably attached to the cartridge holder assembly, wherein a pointed end of the suturing needle is positioned within the protective housing before and after a complete rotation of the suturing needle about the rotational axis; and  
  
a removable electronic module controlled by an actuator that mechanically engages the drive shaft to rotate the drive shaft and the drive mechanism, thereby rotating the suturing needle about the rotational axis.
2. The tissue closure device of claim 1 wherein the suturing needle is arcuate having a radius commensurate with a rotational radius of the drive mechanism of the pusher assembly, the drive mechanism releasably engaging the suturing needle to orient the suturing needle around the longitudinal axis of the drive shaft.
3. The tissue closure device of claim 1 wherein the cartridge further comprises:  
  
a curved lip covering an arc greater than about 180° and less than about 330°;  
  
at least one groove for engaging an anti-rotate and locking bar on the cartridge holder assembly;  
  
a track in a wall whereby the suturing needle follows a curved path along the track during needle rotation; and

an aperture in the curved lip which intercepts the track whereby the pointed end of the suturing needle traverses the aperture during each revolution of the suturing needle along the path.

4. The tissue closure device of claim 3 wherein the engagement of the anti-rotate and locking bar with the cartridge causes the aperture in the cartridge to be aligned with an aperture in the cartridge holder assembly.
5. The tissue closure device of claim 1 wherein the suturing needle covers an arc greater than about 180° and less than about 330° having an aperture located adjacent to the blunt end for engaging a suturing material.
6. The tissue closure device of claim 5 wherein the suturing material includes a flexible leader engaged to a wire suture.
7. The tissue closure device of claim 6 wherein the flexible leader has a diameter larger than a diameter of the wire suture.
8. The tissue closure device of claim 6 wherein a diameter of the flexible leader is equal to a diameter of the wire suture.
9. The tissue closure device of claim 6 wherein a mechanical crimp engages an end of the flexible leader and an end of the wire suture.
10. The tissue closure device of claim 6 wherein the flexible leader is a wire cable.
11. The tissue closure device of claim 6 wherein the wire suture is composed of stainless steel.
12. The tissue closure device of claim 1 wherein the cartridge holder assembly further includes a gate assembly to maintain the suturing needle within the protective housing of the cartridge, wherein the gate assembly pivots to permit a circular movement of the drive mechanism that engages the suturing needle.
13. The tissue closure device of claim 1 wherein the actuator is a manually operable trigger, button or switch.

14. The tissue closure device of claim 1 wherein the actuator is activated by automation using an electric power source.
15. The tissue closure device of claim 1 wherein the actuator is activated by automation using an electromagnetic power source.
16. The tissue closure device of claim 1 wherein the electronic module further comprises:
  - a power source for providing power to the electronic module;
  - a motor and a gear box that provide a rotational force to rotate the drive shaft and the drive mechanism to rotate the suturing needle;
  - an electronics board that controls operation of the electronic module;
  - a stop plate that limits the rotation of the drive shaft and the drive mechanism; and
  - a drive wheel having a drive pin that engages a drive plate on the pusher assembly and supplies a torque to drive the suturing needle, and at least two magnets and a Hall effect sensor used to detect the rotational travel of the drive shaft.
17. The tissue closure device of claim 16 wherein the power source includes a battery pack.
18. The tissue closure device of claim 16 wherein the power source includes an external power supply connected to a handle by a sterilizable cable.
19. A cartridge for housing a suturing needle for use in tissue re-approximation comprising:
  - a housing having a curved shape, an inner wall and an outer wall;
  - a track in the inner wall of the housing whereby the suturing needle follows a curved path along the track during a revolution of the suturing needle; and

an aperture in the housing that intercepts the track, wherein the housing shields the pointed end of the suturing needle during at least a portion of the revolution of the suturing needle.

20. A suturing needle for use in tissue re-approximation comprising:

a curved body having a pointed end that is protected at an end of a rotation cycle and a blunt end that engages a suturing material, wherein the suturing material comprises a flexible leader engaged to a wire suture.

21. The suturing needle of claim 20 wherein the flexible leader has a diameter larger than a diameter of the wire suture.

22. The suturing needle of claim 20 wherein a diameter of the flexible leader is equal to a diameter of the wire suture.

23. The suturing needle of claim 20 wherein a mechanical crimp engages an end of the flexible leader and an end of the wire suture.

24. The suturing needle of claim 20 further comprising an aperture between the pointed end and the blunt end.

25. The suturing needle of claim 20 wherein the flexible leader is a wire cable, and is welded to the wire suture.

26. The suturing needle of claim 20 wherein the wire suture is composed of stainless steel.

27. The suturing needle of claim 20 further comprising at least one notch along a radial edge of the suturing needle, wherein the notch is capable of releasably engaging and rotating the suturing needle about a rotational axis.

28. A method for tissue re-approximation comprising:
- (a) releasably engaging a cartridge having a protective housing and a suturing needle to a cartridge holder assembly of a tissue closure device;
  - (b) placing the tissue closure device having the cartridge and the suturing needle to cause an aperture in the cartridge to be between a first side and a second side of a tissue segment, wherein a pointed end of the suturing needle is positioned within the protective housing before and after a complete rotation of the suturing needle about a rotational axis;
  - (c) activating an electronic module coupled to a pusher assembly that releasably engages the suturing needle to cause rotational movement of the suturing needle across the aperture in the cartridge and advance the suturing needle through the first side of the split tissue segment;
  - (d) pulling a suturing material attached to the suturing needle through the first side of the split tissue segment; and
  - (e) repeating steps (c) and (d) for the second side of the split tissue segment forming a stitch through the first side and the second side of the split tissue segment.
29. The method of claim 28 wherein steps (b) through (e) are repeated until a length of the first side and the second side of the split tissue segment have been re-approximated.
30. The method of claim 28, wherein the tissue segment includes bony material.
31. The method of claim 28 wherein the tissue segment is a split sternum requiring reapproximation.
32. The method of claim 28 wherein the tissue closure device comprises:
- a pusher assembly having a drive arm extending from a drive shaft and a drive mechanism at a distal end of the drive arm, wherein the drive mechanism is capable of releasably engaging and rotating a suturing needle having a pointed end and a blunt end about a rotational axis; and

a cartridge holder assembly to which the cartridge having the protective housing and the suturing needle is releasably attached.

33. The method of claim 28 wherein the suturing needle is arcuate having a radius commensurate with a rotational radius of the drive mechanism of the pusher assembly, the drive mechanism releasably engaging the suturing needle to orient the suturing needle about the longitudinal axis of the drive shaft.

34. The method of claim 28 wherein the cartridge further comprises:

a curved lip covering an arc greater than about 180° and less than about 330°;

at least one groove for engaging an anti-rotate and locking bar on the cartridge holder assembly;

a track in a wall whereby the suturing needle follows a curved path along the track during needle rotation; and

an aperture in the curved lip which intercepts the track whereby the pointed end of the suturing needle traverses the aperture during each revolution of the suturing needle along the path.

35. The method of claim 28 wherein the suturing needle covers an arc greater than about 180° and less than about 330° having an aperture located adjacent to the blunt end for engaging a suturing material.

36. The method of claim 35 wherein the suturing material includes a flexible leader engaged to a wire suture.

37. The method of claim 28 wherein the electronic module is activated by a manually operable trigger, button or switch.

38. The method of claim 28 wherein the electronic module is activated by automation using an electric power source.



39. The method of claim 28 wherein the electronic module is activated by automation using an electromagnetic power source.
40. The method of claim 28 wherein the electronic module is removable from the sternotomy closure device.
41. The method of claim 28 wherein the electronic module further comprises:
- a power source for providing power to the electronic module;
  - a motor and a gear box that provide a rotational force to rotate the drive shaft and the drive mechanism to rotate the suturing needle;
  - an electronics board that controls operation of the electronic module;
  - a stop plate that limits the rotation of the drive shaft and the drive mechanism; and
  - a drive wheel having a drive pin that engages a drive plate on the pusher assembly and supplies a torque to drive the suturing needle, and at least two magnets and a Hall effect sensor used to detect the rotational travel of the drive shaft.
42. The method of claim 41 wherein the power source comprises a battery pack.
43. The method of claim 41 wherein the power source comprises an external power supply connected to a handle by a sterilizable cable.







FIG. 1




**FIG. 2B**



**FIG. 3A**



**FIG. 3B**



**FIG. 3C**




FIG. 4




FIG. 5A

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

7/53




FIG. 5B

01/29/2007



Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

8/53




FIG. 5C

01/29/2007

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

9/53





FIG. 6

Printed: 04/02/2007

DRW

PCT/US2007/002204 PCT/US0702204

**10/53**



**FIG. 7**

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

11/53




FIG. 8A

01/29/2007

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

12/53




FIG. 8B

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

13/53




FIG. 9

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

14/53




FIG. 10

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

15/53




FIG. 11



Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

16/53




FIG. 12

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

17/53




FIG. 13

Printed: 04/02/2007

DRAW

PCT/US2007/002204

PCT/US0702204

18/53




FIG. 14A

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

19/53




FIG. 14B

Printed: 04/02/2007

DRAW

PCT/US2007/002204

PCT/US0702204

20/53




FIG. 15

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

21/53




FIG. 16

01/29/2007

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

22/53




FIG. 17

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

23/53




FIG. 18



Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

24/53




FIG. 19

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

25/53




FIG. 20

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

26/53




FIG. 21

01/29/2007

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

27/53




FIG. 22

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

28/53




FIG. 23

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

29/53




FIG. 24

01/29/2007

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

30/53




FIG. 25A




FIG. 25B




FIG. 25C

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

31/53




FIG. 25D




FIG. 25E




FIG. 25F



Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

32/53




FIG. 25G




FIG. 25H

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

33/53




FIG. 26A




FIG. 26B

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

34/53




FIG. 26C

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

35/53




FIG. 27A




FIG. 27B




FIG. 27C

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

36/53




FIG. 27D




FIG. 27E




FIG. 27F

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

37/53




FIG. 28A




FIG. 28B




FIG. 28C




FIG. 28D




FIG. 28E




FIG. 28F

01/29/2007

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

38/53




FIG. 29

01/29/2007

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

39/53




FIG. 30



Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

40/53




FIG. 31A




FIG. 31B

01/29/2007

Printed: 04/02/2007

DRAW

PCT/US2007/002204

PCT/US0702204

41/53




FIG. 31C

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

42/53




FIG. 32A




FIG. 32B

01/29/2007

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

43/53




FIG. 33A




FIG. 33B




FIG. 33C

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

44/53




FIG. 34

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

45/53

50




FIG. 35

Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

46/53




FIG. 36A




FIG. 36B




FIG. 36C

Printed: 04/02/2007

DRW

PCT/US2007/002204 PCT/US0702204

47/53




FIG. 37A




FIG. 37C




FIG. 37B




FIG. 37D



Printed: 04/02/2007

DRW

PCT/US2007/002204

PCT/US0702204

48/53




FIG. 38

Printed: 04/02/2007

DRW

PCT/US2007/002204 PCT/US0702204

49/53




FIG. 39A

Printed: 04/02/2007

DRW

PCT/US2007/002204 PCT/US0702204

50/53




FIG. 39B

Printed: 04/08/2007

DRW

PCT/US2007/002204 PCTUS0702204

52/53




FIG. 39D

Printed: 04/03/2007

DRW

PCT/US2007/002204 PCTUS0702204

53/53




FIG. 40

NOT FURNISHED UPON FILING

NO PRESENTADO(A) EN EL MOMENTO DE LA PRESENTACIÓN

NON SOUMIS(E) AU MOMENT DU DÉPÔT