(12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(19) World Intellectual Property Organization
International Bureau

(43) International Publication Date
26 July 2012 (26.07.2012)

WIPO | PCT

(10) International Publication Number
WO 2012/100094 A2

(51) International Patent Classification:
F01B 21/02 (2006.01) *B05B 1/02* (2006.01)
F03C 1/00 (2006.01) *F01K 27/00* (2006.01)
F01B 23/10 (2006.01) *F02C 1/02* (2006.01)
F01B 29/04 (2006.01) *F04B 39/06* (2006.01)

(21) International Application Number:
PCT/US2012/021923

(22) International Filing Date:
19 January 2012 (19.01.2012)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:
13/010,683 20 January 2011 (20.01.2011) US

(71) Applicant *(for all designated States except US)*: **LIGHTSAIL ENERGY, INC.** [US/US]; 815 Alice St., Oakland, California 94607 (US).

(72) Inventors; and

(75) Inventors/Applicants *(for US only)*: **STAHLKOPF, Karl E.** [US/US]; 2350 Pacific Heights Rd., Honolulu, Hawaii 96813 (US). **FONG, Danielle A.** [CA/US]; 2327 Prince St. #3, Berkeley, California 94705 (US). **CRANE, Stephen E.** [US/US]; 3970 Piner Rd., Santa Rosa, California 95401 (US). **BERLIN, Edwin P., Jr.** [US/US]; 6426 Ascot Dr., Oakland, California 94611 (US). **POURMOUSA ABKENAR, AmirHossein** [CA/US]; 2221 Verano Place, Irvine, California 92617 (US).

(74) Agent: **CHO, Steve**; AMPACC Law Group, PLLC, 6100 219th Street SW, STE 580, Mountlake Terrace, Washington 98043 (US).

(81) Designated States *(unless otherwise indicated, for every kind of national protection available)*: AE, AG, AL, AM, AO, AT, AU, AZ, BA, BB, BG, BH, BR, BW, BY, BZ, CA, CH, CL, CN, CO, CR, CU, CZ, DE, DK, DM, DO, DZ, EC, EE, EG, ES, FI, GB, GD, GE, GH, GM, GT, HN, HR, HU, ID, IL, IN, IS, JP, KE, KG, KM, KN, KP, KR, KZ, LA, LC, LK, LR, LS, LT, LU, LY, MA, MD, ME, MG, MK, MN, MW, MX, MY, MZ, NA, NG, NI, NO, NZ, OM, PE, PG, PH, PL, PT, QA, RO, RS, RU, RW, SC, SD, SE, SG, SK, SL, SM, ST, SV, SY, TH, TJ, TM, TN, TR, TT, TZ, UA, UG, US, UZ, VC, VN, ZA, ZM, ZW.

(84) Designated States *(unless otherwise indicated, for every kind of regional protection available)*: ARIPO (BW, GH, GM, KE, LR, LS, MW, MZ, NA, RW, SD, SL, SZ, TZ, UG, ZM, ZW), Eurasian (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European (AL, AT, BE, BG, CH, CY, CZ, DE, DK, EE, ES, FI, FR, GB, GR, HR, HU, IE, IS, IT, LT, LU, LV, MC, MK, MT, NL, NO, PL, PT, RO, RS, SE, SI, SK, SM, TR), OAPI (BF, BJ, CF, CG, CI, CM, GA, GN, GQ, GW, ML, MR, NE, SN, TD, TG).

[Continued on next page]

(54) Title: COMPRESSED AIR ENERGY STORAGE SYSTEM UTILIZING TWO-PHASE FLOW TO FACILITATE HEAT EXCHANGE



(57) Abstract: A compressed-air energy storage system according to embodiments of the present invention comprises a reversible mechanism to compress and expand air, one or more compressed air storage tanks, a control system, one or more heat exchangers, and, in certain embodiments of the invention, a motor-generator. The reversible air compressor-expander uses mechanical power to compress air (when acting as a compressor) and converts the energy stored in compressed air to mechanical power (when acting as an expander). In certain embodiments, the compressor-expander comprises one or more stages, each stage consisting of pressure vessel (the pressure cell) partially filled with water or other liquid. In some embodiments, the pressure vessel communicates with one or more cylinder devices to exchange air and liquid with the cylinder chamber(s) thereof. Suitable valving allows air to enter and leave the pressure cell and cylinder device, if present, under electronic control.

WO 2012/100094 A2

Published:

— *without international search report and to be republished upon receipt of that report (Rule 48.2(g))*

COMPRESSED AIR ENERGY STORAGE SYSTEM UTILIZING TWO-PHASE FLOW TO FACILITATE HEAT EXCHANGE

BACKGROUND

[0001] Air compressed to 300 bar has energy density comparable to that of lead-acid batteries and other energy storage technologies. However, the process of compressing and decompressing the air typically is inefficient due to thermal and mechanical losses. Such inefficiency limits the economic viability of compressed air for energy storage applications, despite its obvious advantages.

[0002] It is well known that a compressor will be more efficient if the compression process occurs isothermally, which requires cooling of the air before or during compression. Patents for isothermal gas compressors have been issued on a regular basis since 1930 (e.g., U.S. Patent No. 1,751,537 and No. 1,929,350). One approach to compressing air efficiently is to effect the compression in several stages, each stage comprising a reciprocating piston in a cylinder device with an intercooler between stages (e.g., U.S. Patent No. 5,195,874). Cooling of the air can also be achieved by injecting a liquid, such as mineral oil, refrigerant, or water into the compression chamber or into the airstream between stages (e.g., U.S. Patent No. 5,076,067).

[0003] Several patents exist for energy storage systems that mix compressed air with natural gas and feed the mixture to a combustion turbine, thereby increasing the power output of the turbine (e.g., U.S. Patent No. 5,634,340). The air is compressed by an electrically-driven air compressor that operates at periods of low electricity demand. The compressed-air enhanced combustion turbine runs a generator at times of peak demand. Two such systems have been built, and others proposed, that use underground caverns to store the compressed air.

[0004] Patents have been issued for improved versions of this energy storage scheme that apply a saturator upstream of the combustion turbine to warm and humidify the incoming air, thereby improving the efficiency of the system (e.g., U.S. Patent No. 5,491,969). Other patents have been issued that mention the possibility of using low-grade heat (such as waste heat from some other process) to warm the air prior to expansion, also improving efficiency (e.g., U.S. Patent No. 5,537,822).

SUMMARY

[0005] Embodiments of the present invention relate generally to energy storage systems, and more particularly, relates to energy storage systems that utilize compressed air as the energy storage medium, comprising an air compression/expansion mechanism, a heat exchanger, and one or more air storage tanks.

[0006] According to embodiments of the present invention, a compressed-air energy storage system is provided comprising a reversible mechanism to compress and expand air, one or more compressed air storage tanks, a control system, one or more heat exchangers, and, in certain embodiments of the invention, a motor-generator.

[0007] The reversible air compressor-expander uses mechanical power to compress air (when it is acting as a compressor) and converts the energy stored in compressed air to mechanical power (when it is acting as an expander). The compressor-expander comprises one or more stages, each stage consisting of pressure vessel (the "pressure cell") partially filled with water or other liquid. In some embodiments, the pressure vessel communicates with one or more cylinder devices to exchange air and liquid with the cylinder chamber(s) thereof. Suitable valving allows air to enter and leave the pressure cell and cylinder device, if present, under electronic control.

[0008] The cylinder device referred to above may be constructed in one of several ways. In one specific embodiment, it can have a piston connected to a piston rod, so that mechanical power coming in or out of the cylinder device is transmitted by this piston rod. In another configuration, the cylinder device can contain hydraulic liquid, in which case the liquid is driven by the pressure of the expanding air, transmitting power out of the cylinder device in that way. In such a configuration, the hydraulic liquid can interact with the air directly, or a diaphragm across the diameter of the cylinder device can separate the air from the liquid.

[0009] In low-pressure stages, liquid is pumped through an atomizing nozzle into the pressure cell or, in certain embodiments, the cylinder device during the expansion or compression stroke to facilitate heat exchange. The amount of liquid entering the chamber is sufficient to absorb (during compression) or release (during expansion) all the heat associated with the compression or expansion process, allowing those processes to proceed near-isothermally. This liquid is then returned to the pressure cell during the non-power phase of the stroke, where it can exchange heat with the external environment via a conventional heat exchanger. This allows the compression or expansion to occur at high efficiency.

[0010] Operation of embodiments according the present invention may be characterized by a magnitude of temperature change of the gas being compressed or expanded. According to one embodiment, during a compression cycle the gas may experience an increase in temperate of 100 degrees Celsius or less, or a temperature increase of 60 degrees Celsius or less. In some embodiments, during an expansion cycle, the gas may experience a decrease in temperature of 100 degrees Celsius or less, 15 degrees Celsius or less, or 11 degrees Celsius or less –nearing the freezing point of water from an initial point of room temperature.

[0011] Instead of injecting liquid via a nozzle, as described above, air may be bubbled though a quantity of liquid in one or more of the cylinder devices in order to facilitate heat exchange. This approach is preferred at high pressures.

[0012] During expansion, the valve timing is controlled electronically so that only so much air as is required to expand by the desired expansion ratio is admitted to the cylinder device. This volume changes as the storage tank depletes, so that the valve timing must be adjusted dynamically.

[0013] The volume of the cylinder chambers (if present) and pressure cells increases from the high to low pressure stages. In other specific embodiments of the invention, rather than having cylinder chambers of different volumes, a plurality of cylinder devices is provided with chambers of the same volume are used, their total volume equating to the required larger volume.

[0014] During compression, a motor or other source of shaft torque drives the pistons or creates the hydraulic pressure via a pump which compresses the air in the cylinder device. During expansion, the reverse is true. Expanding air drives the piston or hydraulic liquid, sending mechanical power out of the system. This mechanical power can be converted to or from electrical power using a conventional motor-generator.

BRIEF DESCRIPTION OF THE DRAWINGS

[0015] Figure 1 is a schematic representation of the first embodiment of a compressed air energy storage system in accordance with the present invention, that is a single-stage, single-acting energy storage system using liquid mist to effect heat exchange.

[0016] Figure 2 is a block diagram of a second embodiment of a compressed air energy storage system showing how multiple stages are incorporated into a complete system in accordance with the present invention.

[0017] Figure 3 is a schematic representation of a third embodiment of a compressed air energy storage system, that is a single-stage, single-acting energy storage system that uses both liquid mist and air bubbling through a body of liquid to effect heat exchange.

[0018] Figure 4 is a schematic representation of a one single-acting stage that uses liquid mist to effect heat exchange in a multi-stage compressed air energy storage system in accordance with the present invention.

[0019] Figure 5 is a schematic representation of one double-acting stage in a multi-stage compressed air energy storage system in accordance with the present invention.

[0020] Figure 6 is a schematic representation of one single-acting stage in a multi-stage compressed air energy storage system, in accordance with the present invention, that uses air bubbling through a body of liquid to effect heat exchange.

[0021] Figure 7 is a schematic representation of a single-acting stage in a multi-stage compressed air energy storage system, in accordance with the present invention, using multiple cylinder devices.

[0022] Figure 8 is a schematic representation of four methods for conveying power into or out of the system.

[0023] Figure 9 is a block diagram of a multi-stage compressed air energy system that utilizes a hydraulic motor as its mechanism for conveying and receiving mechanical power.

[0024] Figure 10 shows an alternative embodiment of an apparatus in accordance with the present invention.

[0025] Figures 11A-11F show operation of the controller to control the timing of various valves.

[0026] Figures 12A-C show the configuration of an apparatus during steps of a compression cycle according to an embodiment of the present invention.

[0027] Figures 13A-C show the configuration of an apparatus during steps of an expansion cycle according to an embodiment of the present invention.

[0028] Figures 14A-C show the configuration of an apparatus during steps of a compression cycle according to an embodiment of the present invention.

[0029] Figures 15A-C show the configuration of an apparatus during steps of an expansion cycle according to an embodiment of the present invention.

[0030] Figures 16A-D show the configuration of an apparatus during steps of a compression cycle according to an embodiment of the present invention.

[0031] Figures 17A-D show the configuration of an apparatus during steps of an expansion cycle according to an embodiment of the present invention.

[0032] Figures 18A-D show the configuration of an apparatus during steps of a compression cycle according to an embodiment of the present invention.

[0033] Figures 19A-D show the configuration of an apparatus during steps of an expansion cycle according to an embodiment of the present invention.

[0034] Figure 20 shows a simplified view of a computer system suitable for use in connection with the methods and systems of the embodiments of the present invention.

[0035] Figure 20A is an illustration of basic subsystems in the computer system of Figure 20.

[0036] Figure 21 is an embodiment of a block diagram showing inputs and outputs to a controller responsible for controlling operation of various elements of an apparatus according to the present invention.

[0037] Figure 22 is a simplified diagram showing an embodiment of an apparatus according to the present invention. Figures 22A-B show the apparatus of Figure 22 operating in different modes.

[0038] Figure 23 is a simplified diagram showing flows of air within an embodiment of a compressor-expander.

[0039] Figure 24A is a simplified diagram showing an alternative embodiment of an apparatus according to the present invention.

[0040] Figure 24B is a simplified diagram showing an alternative embodiment of an apparatus according to the present invention.

[0041] Figure 24C is a simplified diagram showing an alternative embodiment of an apparatus according to the present invention.

[0042] Figure 24D is a simplified diagram showing a further alternative embodiment of an apparatus according to the present invention.

[0043] Figure 25 is a simplified schematic view showing an embodiment of a compressor-expander.

[0044] Figure 26 shows a simplified view of an embodiment of a multi-stage apparatus.

[0045] Figure 26A shows a simplified view of an alternative embodiment of a multi-stage apparatus.

[0046] Figure 26B shows a simplified view of an alternative embodiment of a multi-stage apparatus.

[0047] Figure 27 shows a simplified schematic view of an embodiment of a compressor mechanism.

[0048] Figures 28-28A are simplified schematic views of embodiments of aerosol refrigeration cycles.

[0049] Figure 29 shows a velocity field for a hollow-cone nozzle design.

[0050] Figure 30 shows a simulation of a fan nozzle.

[0051] Figure 31 shows a system diagram for an embodiment of an aerosol refrigeration cycle.

[0052] Figure 32 plots temperature versus entropy for an embodiment of an aerosol refrigeration cycle.

[0053] Figure 32A is a power flow graph illustrating work and heat flowing through an embodiment of an aerosol refrigeration cycle.

[0054] Figure 33 is a simplified schematic representation of an embodiment of a system in accordance with the present invention.

[0055] Figure 33A shows a simplified top view of one embodiment of a planetary gear system which could be used in embodiments of the present invention. Figure 33AA shows a simplified cross-sectional view of the planetary gear system of Figure 33A taken along line 33A-33A'.

[0056] Figure 34 is a simplified schematic representation of an alternative embodiment of a system in accordance with the present invention.

[0057] Figure 35 is a simplified schematic representation of an alternative embodiment of a system in accordance with the present invention.

[0058] Figure 35A is a simplified schematic representation of an alternative embodiment of a system in accordance with the present invention.

[0059] Figure 36 is a simplified schematic representation of an alternative embodiment of a system in accordance with the present invention.

[0060] Figure 37 is a simplified schematic representation of an alternative embodiment of a system in accordance with the present invention.

[0061] Figure 38 is a schematic view of an air storage and recovery system employing a mixing chamber in accordance with an embodiment of the present invention.

[0062] Figure 39 is a schematic view of a single stage apparatus including a mixing chamber and a compression chamber in accordance with one embodiment of the present invention.

[0063] Figures 39A-39B are simplified schematic representations of the embodiment of Figure 39 in operation.

[0064] Figures 39CA-39CB are simplified schematic representations of possible trajectories of injected liquids.

[0065] Figure 40 is a schematic view of a single stage apparatus including a mixing chamber and an expansion chamber in accordance with one embodiment of the present invention.

[0066] Figures 40A-40B are simplified schematic representations of the embodiment of Figure 40 in operation.

[0067] Figure 41 is a schematic view of an embodiment of an apparatus for performing both compression and expansion according to an embodiment of the present invention.

[0068] Figures 41A-D are simplified schematic representations of the embodiment of Figure 41 in operation.

[0069] Figures 41EA-EE are simplified schematic representations showing operation of a valve and cylinder configuration.

[0070] Figures 41FA-FC are simplified schematic representations showing operation of one embodiment.

[0071] Figure 41G is a simplified schematic view of one embodiment of a valve structure.

[0072] Figure 41H is a simplified schematic view of a cam-based valve design which may be used in accordance with embodiments of the present invention.

[0073] Figure 42A is a simplified diagram of an embodiment of a multistage apparatus for gas compression according to the present invention.

[0074] Figure 42B is a simplified block diagram of one embodiment of a multistage dedicated compressor according to the present invention.

[0075] Figures 42BA-42BC show simplified views of embodiments of the various modular elements of the system of Figure 42B.

[0076] Figure 42C is a simplified diagram showing an alternative embodiment of a multistage dedicated compressor according to the present invention.

[0077] Figure 43 is a simplified block diagram of one embodiment of a multistage dedicated expander according to the present invention.

[0078] Figure 43A shows a simplified view of an embodiment of one modular element of the system of Figure 43.

[0079] Figure 43B is a simplified diagram showing an alternative embodiment of a multistage dedicated expander according to the present invention.

[0080] Figure 44 is a simplified diagram showing one embodiment of a multistage compressor/expander apparatus according to the present invention.

[0081] Figure 45 is a simplified diagram showing an alternative embodiment of a multistage compressor/expander apparatus according to the present invention.

[0082] Figure 46A is a simplified view of an embodiment of the present invention wherein output of a mixing chamber is selectively output to three compression/expansion cylinders.

[0083] Figure 46B is a simplified view of an embodiment of the present invention wherein output of a mixing chamber may be shunted to a dump.

[0084] Figure 47 is a block diagram showing inputs and outputs to a controller responsible for controlling operation of various elements of an apparatus according to embodiments of the present invention.

[0085] Figures 48A-C show operation of the controller to control the timing of various valves in the system.

[0086] Figures 49A-C plot pressure versus volume in chambers experiencing compression and expansion modes.

[0087] Figure 50A is a simplified schematic view of an compressed gas energy storage system employing liquid injection according to an embodiment of the present invention.

[0088] Figure 50B is a simplified schematic view of an compressed gas energy recovery system employing liquid injection according to an embodiment of the present invention.

[0089] Figures 51 is a simplified schematic view of an compressed gas energy storage and recovery system employing liquid injection according to an embodiment of the present invention.

[0090] Figure 52 is a block diagram showing inputs and outputs to a controller responsible for controlling operation of various elements of an apparatus according to embodiments of the present invention.

[0091] Figure 53A is a simplified diagram of an embodiment of a multistage apparatus for gas compression according to the present invention.

[0092] Figure 53B is a simplified block diagram of one embodiment of a multistage dedicated compressor according to the present invention.

[0093] Figures 53BA-53BC show simplified views of embodiments of the various modular elements of the system of Figure 53B.

[0094] Figure 53C is a simplified diagram showing an alternative embodiment of a multistage dedicated compressor according to the present invention.

[0095] Figure 54 is a simplified block diagram of one embodiment of a multistage dedicated expander according to the present invention.

[0096] Figure 54A shows a simplified view of an embodiment of one modular element of the system of Figure 54.

[0097] Figure 55 is a simplified diagram showing an alternative embodiment of a multistage dedicated expander according to the present invention.

[0098] Figure 56 is a simplified diagram showing an embodiment of a multistage apparatus according to the present invention that is configurable to perform compression or expansion.

[0099] Figure 57 is a simplified diagram showing an alternative embodiment of a multistage apparatus according to the present invention that is configurable to perform compression or expansion.

[0100] Figures 58 is a simplified schematic representation of an embodiment of a single stage compressed air storage and recovery system.

[0101] Figures 58A-C are simplified schematic representations of embodiments of multi-stage compressed air storage systems according to the present invention.

[0102] Figures 59-59B show views of an embodiment of a stage comprising a cylinder having a moveable piston disposed therein.

[0103] Figure 60 is a table listing heating and cooling functions for an energy storage system according to an embodiment of the present invention.

[0104] Figures 61A-C show views of a stage operating as an expander.

[0105] Figure 62 is a table listing possible functions for an energy storage system according to the present invention incorporated within a power supply network.

[0106] Figures 63A-C show views of a stage operating as a compressor.

[0107] Figure 64A shows a multi-stage system where each of the stages is expected to exhibit a different change in temperature. Figure 64B shows a multi-stage system where each stage is expected to exhibit a substantially equivalent temperature change.

[0108] Figure 65 generically depicts interaction between a compressed gas system and external elements.

[0109] Figure 66 is a simplified schematic view of a network configured to supply electrical power to end users.

[0110] Figure 67 shows a simplified view of the levelizing function that may be performed by a compressed gas energy storage and recovery system according to an embodiment of the present invention.

[0111] Figure 68 shows a simplified view of an embodiment of a compressed gas energy storage and recovery system according to the present invention, which is co-situated with a power generation asset.

[0112] Figure 68A shows a simplified view of an embodiment of a compressed gas energy storage and recovery system utilizing a combined motor/generator and a combined compressor/expander.

[0113] Figure 68B shows a simplified view of an embodiment of a compressed gas energy storage and recovery system utilizing dedicated motor, generator, compressor, and expander elements.

[0114] Figure 68C shows a simplified view of an embodiment of a compressed gas energy storage and recovery system in accordance with the present invention utilizing a multi-node gearing system.

[0115] Figure 69 shows a simplified view of an embodiment of a compressed gas energy storage and recovery system according to the present invention, which is co-situated with an end user behind a meter.

[0116] Figures 69A-D show examples of thermal interfaces between an energy storage system and an end user.

[0117] Figure 70 shows a simplified view of an embodiment of a compressed gas energy storage and recovery system according to the present invention, which is co-situated with an end user and a local power source behind a meter.

[0118] Figure 71 is a table summarizing various operational modes of a compressed gas energy storage and recovery system that is co-situated behind a meter with an end user.

[0119] Figure 72 is a table summarizing various operational modes of a compressed gas energy storage and recovery system that is co-situated behind a meter with an end user and with a local power source.

[0120] Fig. 73 represents a simplified view according to certain embodiments.

[0121] Fig. 74 is a graph of mass weighted average temperature over two compression cycles with a compression ratio of 32.

[0122] Fig. 74A is a false color representation of temperature in Kelvin at top dead center from a CFD simulation of gas compression at a high compression ratio.

[0123] Fig. 75 shows a thermodynamic cycle.

[0124] Fig. 76A plots efficiency versus water volume fraction.

[0125] Fig. 76B shows a temperature of the exhaust air with increase in water volume fraction.

[0126] Fig. 77 shows the temperature at top dead center at a location close to the cylinder head.

[0127] Fig. 78 shows the temperature variation with and without spraying water.

[0128] Fig. 79 shows a multiphase flow simulation of jet breakup in two-dimensions.

[0129] Fig. 80 is a CFD simulation of water spray emitted from an embodiment of a pyramid nozzle.

[0130] Figure 81a shows an experimental picture of the drops taken using a Particle Image Velocimetry (PIV) system.

[0131] Figure 81b plots measured droplet size distribution.

[0132] Figure 82 is a simplified view of a cooling system according to an embodiment of the present invention which utilizes a phase change of a refrigerant.

[0133] Figure 83 indicates the mass-average air temperature in cylinder (K) versus crank rotation from CFD simulations with and without splash model.

[0134] Figure 84 shows a simplified cross-sectional view of an embodiment of an apparatus which utilizes a piston as a gas flow valve.

[0135] Figure 85 shows an embodiment of an apparatus utilizing the flow of liquid into a chamber.

[0136] Figures 86A-C show views of a compression apparatus in accordance with an embodiment of the present invention.

[0137] Figure 87 show a simplified view of an embodiment of an apparatus in accordance with the present invention including a liquid flow valve network.

[0138] Figure 88 show a simplified view of an embodiment of an apparatus in accordance with the present invention.

[0139] Figure 89 shows a simplified cross-sectional view of the space defining a liquid injection sprayer according to an embodiment of the present invention.

[0140] Figures 90A-90C show simplified views of an embodiment of a spray nozzle fabricated from a single piece.

[0141] Figures 91A-91D show simplified views of another embodiment of a spray nozzle fabricated from a single piece.

[0142] Figures 92A-92D show simplified views of another embodiment of a spray nozzle fabricated from a single piece.

[0143] Figure 93 is a perspective view of one plate of a multi-piece nozzle design, showing one of the opposing surfaces defining one-half of the sprayer structure.

[0144] Figure 93A shows a top view of the plate of Figure 93.

[0145] Figure 93B shows a side view of the plate of Figure 93.

[0146] Figure 94 is a perspective view of the second plate showing the surface defining the recess forming the other half of the sprayer structure.

[0147] Figure 95 shows a view of an embodiment of an assembled sprayer structure taken from the perspective of a chamber that is configured to receive liquid from the sprayer.

[0148] Figure 96 shows a view of the embodiment of the assembled sprayer structure of Figure 95, taken from the perspective of a source of liquid to the sprayer.

[0149] Figure 97 shows relative distances of different portions of the nozzle design of Fig. 89.

[0150] Figure 98 shows the fan spray expected from the nozzle design of Fig. 89.

[0151] Figures 99A-D show views of another embodiment of a multi-piece nozzle structure.

[0152] Figures 100A-J show various views of another embodiment of a multi-piece nozzle structure.

[0153] Figures 101A-C show an experimental setup for evaluating nozzle performance.

[0154] Figure 102 shows the global flow structure at 100 PSIG water pressure from two instantaneous shadowgraphy images.

[0155] Figure 103 shows mean velocity vectors from run 1 and run 4.

[0156] Figure 104 shows RMS velocity vectors from run 1 and run 4.

[0157] Figure 105 shows one instantaneous image with recognized droplets from run 1.

[0158] Figure 106 showing the histogram of the droplet size of run 1.

[0159] Figure 107 shows one instantaneous image with recognized droplets from run 4.

[0160] Figure 108 shows the corresponding histogram of droplet size.

[0161] Figure 109A shows one instantaneous image with recognized droplets of run 12. Figure 109B shows one instantaneous image with recognized droplets of run 14.

[0162] Figure 110A shows the histogram of the droplet size of run 12. Figure 110B shows the histogram of run 14.

[0163] Figure 111A shows the droplet size distribution along z axis of runs 5 to 15 and runs 25 to 27. Figure 111B shows the same data in terms of sheet angle.

[0164] Figure 112A shows the number of droplets recognized at each z location of runs 5 to 15 and runs 25 to 27. Figure 112B shows the same data in terms of sheet angle.

[0165] Figure 113 shows the global flow structure at 50 PSIG water pressure from two instantaneous shadowgraphy images.

[0166] Figure 114 shows the mean velocity vector fields from runs 2 and 3.

[0167] Figure 115 shows the RMS velocity vector fields from runs 2 and 3.

[0168] Figure 116 shows one instantaneous image with recognized droplets from run 2.

[0169] Figure 117 shows the corresponding histogram of the droplet size.

[0170] Figure 118 shows one instantaneous image with recognized droplets from run 3.

[0171] Figure 119 shows a corresponding histogram of the droplet size from run 3.

[0172] Figure 120 shows one instantaneous image with recognized droplets of run 20.

[0173] Figure 121 shows a histogram of the corresponding droplet size from run 20.

[0174] Figure 122A plots droplet size distribution along the z axis for runs 16-21 and 22-24 in terms of mm. Figure 122B plots this data in terms of sheet angle.

[0175] Figure 123A shows the number of droplets recognized at each z location of runs 16 to 24. Figure 123B shows the same data in terms of sheet angle.

[0176] Figure 124 is a simplified schematic view of an compressed gas energy storage and recovery system employing liquid injection according to an embodiment of the present invention.

[0177] Figure 124A shows a view of a chamber wall having a valve and sprayers according to an embodiment of the present invention.

[0178] Figure 125 is a simplified schematic view of an compressed gas energy storage and recovery system employing liquid injection according to an embodiment of the present invention.

[0179] Figure 126 is a simplified enlarged view of a compression or expansion chamber having sprayers for direct injection of liquid according to an embodiment of the present invention.

[0180] Figure 127 is a simplified enlarged view of a compression or expansion chamber having sprayers for direct injection of liquid according to an embodiment of the present invention.

[0181] Figure 128 is a simplified enlarged view of a compression or expansion chamber having sprayers for direct injection of liquid according to an embodiment of the present invention.

[0182] Figure 129 is a simplified enlarged view of a compression or expansion chamber having sprayers for direct injection of liquid according to an embodiment of the present invention.

[0183] Figure 130A shows an embodiment of a spray nozzle positioned in a cylinder head according to the present invention.

[0184] Figure 130B shows an alternative embodiment of a spray nozzle positioned in a cylinder head according to the present invention.

[0185] Figure 131 shows an embodiment of an apparatus utilizing liquid injection having a complex chamber profile.

[0186] Figure 132 shows another embodiment of an apparatus utilizing liquid injection having a complex chamber profile.

[0187] Figures 133A-G show views of an alternative embodiment of a nozzle design.

[0188] Figures 134A-C show views of various embodiments of nozzle designs.

[0189] Figure 135A-E show the design of a compression or expansion apparatus having tuned resonance characteristics.

[0190] Figure 136 shows an embodiment of an active regulator apparatus to extract power.

[0191] Figure 137 shows an embodiment of an apparatus having an internal spray generation mechanism.

[0192] Figure 138 shows an embodiment of an apparatus using an internal high pressure to pump liquid through a spray nozzle.

[0193] Figure 139 shows an embodiment of an apparatus using a passive port valve with a piston actuator.

[0194] Figure 140 shows features of an embodiment of an apparatus utilizing condensation of water to replenish the spray water supply.

[0195] Figure 141 shows features of an embodiment of an apparatus wherein energy from expansion is used to maintain near-constant pressure in a gas storage unit.

[0196] Figure 142 is a simplified schematic view of a network configured to supply electrical power to end users.

[0197] Figure 143 shows a simplified view of an embodiment of a system according to the present invention, co-situated with a power generation asset.

[0198] Figures 144A-B show different views of an embodiment of a system according to the present invention, configured to receive various inputs and to produce various outputs.

[0199] Figure 145A shows a simplified view of an embodiment of an apparatus according to the present invention.

[0200] Figure 145BA is a table showing different configurations of the apparatus of Figure 145A

[0201] Figures 145BB-BG are highly simplified depictions of the flow of gases through the apparatus of Figure 145A in various configurations.

[0202] Figures 145C-EB are tables showing different energy pathways of an embodiment of a system in various configurations.

[0203] Figure 146 shows a flowchart of apportioning inputs and outputs of an embodiment of a system.

[0204] Figure 147 plots power over time showing an example of a transition of grid capacity from a renewable energy source to a long-term generation asset.

[0205] Figure 147A is a simplified schematic view of a system including a processor configured to coordinate operation of an energy system with a power supply network.

[0206] Figures 148AA-148D show simplified schematic views depicting a swirl flow nozzle design according to an embodiment of the present invention.

[0207] Figures 149A-149DB show simplified schematic views depicting the architecture of swirl flow nozzle designs according to embodiments of the present invention.

[0208] Figures 150A-B show an experimental setup to evaluate performance of an embodiment 1 of a swirl nozzle. Figure 150C shows a simplified sketch of the coordinate system and the field of view.

[0209] Figure 151 shows a structure of the spray from the embodiment 1 at a higher pressure.

[0210] Figure 152A shows mean velocity vectors of certain runs of the embodiment 1. Figure 152B shows RMS velocity vectors from these runs.

[0211] Figure 153 shows profiles of velocity magnitude taken along one line of a run of the embodiment 1.

[0212] Figure 154A shows one instantaneous image with recognized droplets from the run. Figure 154B shows the histogram of droplet size.

[0213] Figure 155A shows one instantaneous image with recognized droplets from another run. Figure 155B shows the histogram of the droplet size.

[0214] Figure 156A shows one instantaneous image with recognized droplets of another run. Figure 156B shows the histogram of the droplet size.

[0215] Figure 157 plots shows droplet size distribution along the z axis in terms of sheet angle.

[0216] Figure 158 shows flow structure of a lower pressure run of the embodiment 1 nozzle from two instantaneous shadowography images.

[0217] Figure 159A shows mean and RMS velocity fields from lower pressure runs of the embodiment 1 nozzle. Figure 159B shows the RMS velocity vectors from these runs.

[0218] Figure 160 plots profiles of velocity magnitude taken along one line in a lower pressure run.

[0219] Figure 161A shows one instantaneous image with recognized droplets from a run of the nozzle. Figure 161B shows a histogram of droplet size.

[0220] Figure 162A shows one instantaneous image with recognized droplets from another run of the nozzle. Figure 162B shows a histogram of droplet size.

[0221] Figure 163A shows one instantaneous image with recognized droplets of a run from a nozzle. Figure 163B shows the histogram of the droplet size of this run.

[0222] Figure 164 shows droplets size distribution along the z axis (in terms of sheet angle) of several runs of the nozzle.

[0223] Figure 165 plots exit velocity versus water pressure for the embodiment 1 nozzle.

[0224] Figures 166A-B show an experiment setup to evaluate performance of a nozzle embodiment 2. Figure 166C shows a simplified sketch of the coordinate system and the field of view, and is not drawn to scale.

[0225] Figure 167 shows a structure of the spray from the embodiment 2 at a high pressure.

[0226] Figure 168A shows the mean velocity vectors from some high pressure runs of the embodiment 2 nozzle. Figure 168B shows the RMS velocity vectors from those runs.

[0227] Figure 169 shows profiles of velocity magnitude along one line of a run.

[0228] Figure 170A shows one instantaneous image with recognized droplets of a run of the nozzle design of embodiment 2. Figure 170B shows the histogram of the droplet size of this run.

[0229] Figure 171A shows one instantaneous image with recognized droplets of another run of the nozzle design of embodiment 2. Figure 171B shows the histogram of the droplet size of this run.

[0230] Figure 172 plots droplet size distribution along z axis (in terms of sheet angle) of certain higher pressure runs of the embodiment 2 nozzle design.

[0231] Figure 173 shows the flow structure of a lower pressure run of the nozzle embodiment 2 design.

[0232] Figure 174A shows mean velocity vectors of lower pressure runs of the nozzle design of embodiment 2. Figure 174B shows the RMS velocity vectors of those runs.

[0233] Figure 175 shows profiles of velocity magnitude along one line of a run.

[0234] Figure 176A shows one instantaneous image with recognized droplets of a run of the nozzle embodiment 2. Figure 176B shows a histogram of the droplet size of the run.

[0235] Figure 177A shows one instantaneous image with recognized droplets of another run of the nozzle embodiment 2. Figure 177B shows a histogram of droplet size.

[0236] Figure 178 plots droplets size distribution along the z axis (in terms of sheet angle), of lower pressure runs of the embodiment 2 nozzle design.

[0237] Figures 179A-179C show an experimental setup to test another embodiment of a swirl nozzle design.

[0238] Figures 179D-E plot droplet size distribution along the z axis (in terms of sheet angle), of runs of the nozzle design of Figures 179A-C.

[0239] Figure 179F are results of modeling showing contours of velocity magnitude of an embodiment of a nozzle according to the present invention.

[0240] Figures 180A-180C show an experimental setup to test still another embodiment of a swirl nozzle design.

[0241] Figures 180D-E plot droplet size distribution along the z axis (in terms of sheet angle), of runs of the nozzle design of Figures 180A-C.

[0242] Figure 181 shows an embodiment of a heat exchanger.

[0243] Figure 181A presents a table of configurations of the apparatus of Figure 181.

[0244] Figures 182A-182C show an experimental setup to test another embodiment of a swirl nozzle design.

[0245] Figures 183A-B plot droplet size distribution along the z axis (in terms of sheet angle), of runs of the nozzle design of Figures 182A-C.

[0246] Figures 184A-184C show an experimental setup to test another embodiment of a swirl nozzle design.

[0247] Figures 185A-B plot droplet size distribution along the z axis (in terms of sheet angle), of runs of the nozzle design of Figures 184A-C.

[0248] Figures 186A-186C show an experimental setup to test another embodiment of a swirl nozzle design.

[0249] Figure 187 plots droplet size distribution along the z axis (in terms of sheet angle), of runs of the nozzle design of Figures 184A-C.

[0250] Figures 188A-188C show an experimental setup to test another embodiment of a swirl nozzle design.

[0251] Figures 189A-B plot droplet size distribution along the z axis (in terms of sheet angle), of runs of the nozzle design of Figures 188A-C.

[0252] Figures 190A-C compare performance of the nozzle designs of Figures 186A-C and Figures 188A-C.

[0253] Figures 191A-191C show an experimental setup to test an embodiment of a swirl nozzle design with different liquids.

[0254] Figures 192A-C plot three measures of droplet size distribution for different liquid sprays.

[0255] Figures 193A-C plot three measures of droplet size distribution for liquid sprays at different pressures.

[0256] Figures 194A-C compare droplet size distribution for different liquid sprays at different pressures.

[0257] Figures 195A-B show droplet size for liquid sprays including a surfactant.

[0258] Figure 196 shows an embodiment of a cylinder according to the present invention having a gas flow valve positioned proximate to liquid spray nozzles.

[0259] Figure 197 shows an embodiment of a system according to the present invention, as incorporated with power conditioning electronics behind a meter.

[0260] Figure 198 shows an alternative approach to incorporating an embodiment of a present invention with power conditioning electronics behind an interface with a power grid.

[0261] Figure 199 is a simplified schematic diagram showing use of an embodiment of the present invention for load balancing behind a meter.

[0262] Figure 200 plots nozzle flow rate versus pressure, for different liquids flowed through a swirl nozzle design according to an embodiment of the present invention.

[0263] Figures 201A-KB show features of an alternative swirl nozzle design.

[0264] While certain drawings and systems depicted herein may be configured using standard symbols, the drawings have been prepared in a more general manner to reflect the variety of implementations that may be realized from different embodiments.

DETAILED DESCRIPTION

[0265] While the present invention will be described with reference to a few specific embodiments, the description is illustrative of the invention and is not to be construed as limiting the invention. Various modifications to the present invention can be made to the preferred embodiments by those skilled in the art without departing from the true spirit and scope of the invention. It will be noted here that for a better understanding, like components are designated by like reference numerals throughout the various figures.

[0266] ***Single-Stage System***

[0267] Figure 1 depicts the simplest embodiment of the compressed air energy storage system 20 of the present invention, and illustrates many of the important principles. Briefly, some of these principles which improve upon current compressed air energy storage system designs include mixing a liquid with the air to facilitate heat exchange during compression and expansion, thereby improving the efficiency of the process, and applying the same mechanism for both compressing and expanding air. Lastly, by controlling the valve timing electronically, the highest possible work output from a given volume of compressed air can be obtained.

[0268] As best shown in Figure 1, the energy storage system 20 includes a cylinder device 21 defining a chamber 22 formed for reciprocating receipt of a piston device 23 or the like therein. The compressed air energy storage system 20 also includes a pressure cell 25 which when taken together with the cylinder device 21, as a unit, form a one stage reversible compression/expansion mechanism (i.e., a one-stage 24). There is an air filter 26, a liquid-air separator 27, and a liquid tank 28, containing a liquid 49d fluidly connected to the compression/expansion mechanism 24 on the low pressure side via pipes 30 and 31, respectively. On the high pressure side, an air storage tank or tanks 32 is connected to the pressure cell 25 via input pipe 33 and output pipe 34. A plurality of two-way, two position valves 35-43 are provided, along with two output nozzles 11 and 44. This particular embodiment also includes liquid pumps 46 and

47. It will be appreciated, however, that if the elevation of the liquid tank 28 is higher than that of the cylinder device 21, water will feed into the cylinder device by gravity, eliminating the need for pump 46.

[0269] Briefly, atmospheric air enters the system via pipe 10, passes through the filter 26 and enters the cylinder chamber 22 of cylinder device 21, via pipe 30, where it is compressed by the action of piston 23, by hydraulic pressure, or by other mechanical approaches (see Figure 8). Before compression begins, a liquid mist is introduced into the chamber 22 of the cylinder device 21 using an atomizing nozzle 44, via pipe 48 from the pressure cell 25. This liquid may be water, oil, or any appropriate liquid 49f from the pressure cell having sufficient high heat capacity properties. The system preferably operates at substantially ambient temperature, so that liquids capable of withstanding high temperatures are not required. The primary function of the liquid mist is to absorb the heat generated during compression of the air in the cylinder chamber. The predetermined quantity of mist injected into the chamber during each compression stroke, thus, is that required to absorb all the heat generated during that stroke. As the mist condenses, it collects as a body of liquid 49e in the cylinder chamber 22.

[0270] The compressed air/liquid mixture is then transferred into the pressure cell 25 through outlet nozzle 11, via pipe 51. In the pressure cell 25, the transferred mixture exchanges the captured heat generated by compression to a body of liquid 49f contained in the cell. The air bubbles up through the liquid and on to the top of the pressure cell, and then proceeds to the air storage tank 32, via pipe 33.

[0271] The expansion cycle is essentially the reverse process of the compression cycle. Air leaves the air storage tank 32, via pipe 34, bubbling up through the liquid 49f in the pressure cell 25, enters the chamber 22 of cylinder device 21, via pipe 55, where it drives piston 23 or other mechanical linkage. Once again, liquid mist is introduced into the cylinder chamber 22, via outlet nozzle 44 and pipe 48, during expansion to keep a substantially constant temperature in the cylinder chamber during the expansion process. When the air expansion is complete, the spent air and mist pass through an air-liquid separator 27 so that the separated liquid can be reused. Finally, the air is exhausted to the atmosphere via pipe 10.

[0272] The liquid 49f contained in the pressure cell 25 is continually circulated through the heat exchanger 52 to remove the heat generated during compression or to add the heat to the chamber to be absorbed during expansion. This circulating liquid in turn exchanges heat with a thermal reservoir external to the system (e.g. the atmosphere, a pond, etc.) via a conventional air or water-cooled heat exchanger (not shown in this figure, but shown as 12 in Figure 3). The circulating liquid is conveyed to and from that external heat exchanger via pipes 53 and 54 communicating with internal heat exchanger 52.

[0273] The apparatus of Figure 1 further includes a controller/processor 1004 in electronic communication with a computer-readable storage device 1002, which may be of any design, including but not limited to those based on semiconductor principles, or magnetic or optical storage principles. Controller 1004 is shown as being in electronic communication with a universe of active elements in the system, including but not limited to valves, pumps, chambers, nozzles, and sensors. Specific examples of sensors utilized by the system include but are not limited to pressure sensors (P) 1008, 1014, and 1024,

temperature sensors (T) 1010, 1018, 1016, and 1026, humidity sensor (H) 1006, volume sensors (V) 1012 and 1022, and flow rate sensor 1020.

[0274] As described in detail below, based upon input received from one or more system elements, and also possibly values calculated from those inputs, controller/processor 4 may dynamically control operation of the system to achieve one or more objectives, including but not limited to maximized or controlled efficiency of conversion of stored energy into useful work; maximized, minimized, or controlled power output; an expected power output; an expected output speed of a rotating shaft in communication with the piston; an expected output torque of a rotating shaft in communication with the piston; an expected input speed of a rotating shaft in communication with the piston; an expected input torque of a rotating shaft in communication with the piston; a maximum output speed of a rotating shaft in communication with the piston; a maximum output torque of a rotating shaft in communication with the piston; a minimum output speed of a rotating shaft in communication with the piston; a minimum output torque of a rotating shaft in communication with the piston; a maximum input speed of a rotating shaft in communication with the piston; a maximum input torque of a rotating shaft in communication with the piston; a minimum input speed of a rotating shaft in communication with the piston; a minimum input torque of a rotating shaft in communication with the piston; or a maximum expected temperature difference of air at each stage.

[0275] The compression cycle for this single-stage system proceeds as follows:

Step	1	2	3	4	5
Description	Add liquid to cylinder device	Add mist to cylinder device	Compress	Move compressed air to pressure cell	Refill cylinder device
Valve 35	Open	Closed	Closed	Closed	Closed
Valve 36	Open	Closed	Closed	Closed	Open
Valve 37	Closed	Closed	Closed	Closed	Closed
Valve 38	Closed	Closed	Closed	Open	Closed
Valve 39	Closed	Open	Closed	Closed	Closed
Valve 40	Closed	Closed	Closed	Closed	Closed
Valve 41	Closed	Closed	Closed	Open	Closed
Valve 42	Open	Closed	Closed	Closed	Closed
Valve 43	Closed	Closed	Closed	Closed	Open
Pump 46	On	Off	Off	Off	Off
Pump 47	Off	On	Off	Off	Off
Piston 23	Near bottom dead center (BDC)	Near BDC	At BDC at start of step	Between BDC and TDC	At TDC at start of step

[0276] During step 1 of the compression cycle, liquid 49d is added to the chamber 22 of the cylinder device 21 from the liquid tank 28 (collecting as body of liquid 49e) such that, when the piston 23 reaches top dead center (TDC), the dead volume in the cylinder device is zero. This will only have to be done occasionally, so that this step is omitted on the great majority of cycles.

[0277] During step 2 of the compression cycle, liquid mist from pressure cell 25 is pumped, via pump 47, into the cylinder chamber 22, via pipe 48 and nozzle 44. The selected quantity of mist is sufficient to absorb the heat generated during the compression step (step 3). The volume fraction of liquid must

sufficiently low enough that the droplets will not substantially fuse together, thus reducing the effective surface area available for heat exchange (that is, the interface between air and liquid). Typically, the pressure differential between the pressure cell 25 and the chamber 22 of the cylinder device 21 is sufficiently high so that the operation of pump 47 is not required.

[0278] During step 3 of the compression cycle, the piston 23 is driven upward by a crankshaft (not shown) coupled to a piston rod 19, by hydraulic pressure, or by some other mechanical structure (as shown in Figure 8), compressing the air and mist contained in the cylinder chamber.

[0279] Step 4 of the compression cycle begins when the air pressure inside the cylinder chamber 22 is substantially equal to the pressure inside the pressure cell 25, at which point outlet valve 38 opens, allowing compressed air to flow from the cylinder chamber to the pressure cell. Because of the liquid added to the cylinder device during step 1 of the compression cycle, substantially all the air in the cylinder chamber can be pushed out during this step. The compressed air is introduced into the pressure cell 25 through an inlet nozzle 11, along with any entrained mist, creating fine bubbles so that the heat generated during compression will exchange with the liquid 49f in the cell rapidly.

[0280] During step 5 of the compression cycle, the piston 23 is pulled down allowing low-pressure air to refill it, via valve 36 and pipe 30. The above table shows valve 39 as being closed during this step, and shows pump 47 as being off during this step 5. However, this is not required. In other embodiments valve 39 could be open and pump 47 could be on, during the step 5 such that mist is introduced into the cylinder chamber as it is refilled with air.

[0281] The expansion cycle for this single-stage system proceeds as follows:

Step	1	2	3	4
Description	Add liquid to cylinder device	Add compressed air and liquid mist to cylinder device	Expansion	Exhaust spent air
Valve 35	Open	Closed	Closed	Closed
Valve 36	Open	Closed	Closed	Open
Valve 37	Closed	Open	Closed	Closed
Valve 38	Closed	Closed	Closed	Closed
Valve 39	Closed	Open	Closed	Closed
Valve 40	Closed	Open	Closed	Closed
Valve 41	Closed	Closed	Closed	Closed
Valve 42	Closed	Closed	Closed	Open
Valve 43	Closed	Closed	Closed	Closed
Pump 46	On	Off	Off	Off
Pump 47	Off	On	Off	Off
Piston 23	Near TDC	At TDC at start of step	Near TDC at start of step	At BDC at start of step

[0282] During step 1 of the expansion cycle, liquid is added to the cylinder chamber from the liquid tank 28 to eliminate dead volume in the system. This will be required only rarely, as mentioned above. Similar to the compression cycle, the pump 46 can be eliminated if the liquid tank 28 is oriented at an elevation higher than that of the chamber of cylinder device 21.

[0283] During step 2 of the expansion cycle, a pre-determined amount of air, V_0, is added to the chamber of the cylinder device by opening inlet valve 37 for the correct interval, which is dependent on the pressure of the air in the pressure cell and the desired expansion ratio. The V_0 required is the total cylinder device volume divided by the desired expansion ratio. For a single stage system, that ratio is less than or equal to the pressure of air in the air storage tank in atmospheres. At the same time air is being introduced into the cylinder chamber 22, liquid mist from the pressure cell is being pumped (via pump 47) through inlet nozzle 44 into the cylinder chamber. If a sufficient pressure differential exists between the pressure cell 25 and the cylinder device 21, pump 47 is not required. Once the pressure inside of the cylinder chamber is sufficiently high, valve 37 is closed. The piston 23 is urged in the direction of BDC beginning with this step, transmitting power out of the system via a crankshaft, hydraulic pressure, or other mechanical means.

[0284] During step 3 of the expansion cycle, the air introduced in step 2 is allowed to expand in the chamber 22. Liquid mist also continues to be pumped into the chamber 22 through nozzle 44. The predetermined total amount of mist introduced is that required to add enough heat to the system to keep the temperature substantially constant during air expansion. The piston 23 is driven to the bottom of the cylinder device during this step.

[0285] It will be appreciated that this two-step expansion process (a quantity of air V_0 introduced in the first step – step 2 – and then allowed to expand in the second step – step 3) allows the system to extract substantially all the energy available in the compressed air.

[0286] During step 4 of the expansion cycle, the crankshaft or other mechanical linkage moves the piston 19 back up to top dead-center (TDC), exhausting the spent air and liquid mist from the cylinder device. The power required to drive the piston comes from the momentum of the system and/or from the motion of other out-of-phase pistons. The exhausted air passes through an air-liquid separator, and the liquid that is separated out is returned to the liquid tank 28.

[0287] ***Multi-Stage System***

[0288] When a larger compression/expansion ratio is required than can be accommodated by the mechanical or hydraulic approach by which mechanical power is conveyed to and from the system, then multiple stages should be utilized. A multi-stage compressed air energy storage system 20 with three stages (i.e., first stage 24a, second stage 24b and third stage 24c) is illustrated in schematic form in Figure 2. Systems with more or fewer stages are constructed similarly. Note that, in all figures that follow, when the letters a, b, and c are used with a number designation (e.g. 25a), they refer to elements in an individual stage of a multi-stage energy storage system 20.

[0289] In accordance with the present invention, each stage may typically have substantially the same expansion ratio. A stage's expansion ratio, r_1, is the *Nth* root of the overall expansion ratio. That is,

[0290] $r = \sqrt[N]{R}$

[0291] Where R is the overall expansion ratio and N is the number of stages. It will be appreciated, however, that the different stages can have different expansion ratios, so long as the product of the expansion ratios of all of the stages is R. That is, in a three-stage system, for example:

[0292] $r_1 \times r_2 \times r_3 = R.$

[0293] In order for the mass flow rate through each stage to be substantially the, the lower pressure stages will need to have cylinder chambers with greater displacements. In a multi-stage system, the relative displacements of the cylinder chambers are governed by the following equation:

[0294] $$V_i = V_T \frac{r^i}{\sum_{n=1}^{N} r^n}$$

[0295] Where V_i is the volume of the i^{th} cylinder device, and V_T is the total displacement of the system (that is, the sum of the displacements of all of the cylinder devices).

[0296] As an example, suppose that the total displacement of a three-stage system is one liter. If the stroke length of each piston is substantially the same and substantially equal to the bore (diameter) of the final cylinder chamber, then the volumes of the three cylinder chambers are about 19 cm^3, 127 cm^3, and 854 cm^3. The bores are about 1.54 cm, 3.96 cm, and 10.3 cm, with a stroke length of about 10.3 cm for all three. The lowest-pressure cylinder device is the largest and the highest-pressure cylinder device the smallest.

[0297] Figure 9 is a schematic representation of how three stages 24a, 24b and 24c could be coupled to a hydraulic system (e.g., a hydraulic motor 57 and six hydraulic cylinders 61a1 - 61c2) to produce continuous near-uniform power output. Each compressed-air-driven piston 23a1 – 23c2 of each corresponding compressed-air driven cylinder device 21a1 – 21c2 is coupled via a respective piston rod 19a1 – 19c2 to a corresponding piston 60a1 – 60c2 of a respective hydraulic cylinder device 61a1 – 61c2.

[0298] The chambers of the air-driven cylinder devices 21a1 – 21c2 vary in displacement as described above. The chambers of the hydraulic cylinder devices 61a1 – 61c2, however, are substantially identical in displacement. Because the force generated by each air-driven piston is substantially the same across the three stages, each hydraulic cylinder device provides substantially the same pressure to the hydraulic motor 57. Note that, in this configuration, the two air-driven pistons 21a1, 21a2 that comprise a given stage (e.g. the first stage 24a) operate 180 degrees out of phase with each other.

[0299] ***Stages Using Liquid Mist to Effect Heat Exchange in a Multi-Stage System***

[0300] If a stage is single-acting and uses liquid mist to effect heat exchange, it operates according to the scheme described in the section titled *Single-Stage System* above. Each single-acting stage of a multi-stage system 20 (e.g., the second stage 24b of Figure 2) is illustrated schematically in Figure 4. In this configuration, air passes to a cylinder chamber 22b of the second stage 24b illustrated from the pressure cell 25a of the next-lower-pressure stage (e.g., first stage 24a) during compression, and to the

pressure cell of the next-lower-pressure stage during expansion, via pipe 92a/90b. Liquid passes to and from the pressure cell 25a of the next-lower-pressure stage via pipe 93a/91b.

[0301] In contrast, air passes from pressure cell 25b of the stage illustrated (e.g., the second stage 24b) to the chamber of the cylinder device of the next higher-pressure stage (e.g., the third stage 24c) during compression and from the chamber of the cylinder device of the next higher-pressure stage during expansion via pipe 92b/90c. It will be appreciated that the air compression/expansion mechanism (i.e., second stage 24b) illustrated is precisely the same as the central elements (the cylinder device 21 and the pressure cell 25 of the first stage 24) shown in Figure 1, with the exception that, in Figure 4, there is a pipe 93b that conveys liquid from the pressure cell of one stage to the chamber of the cylinder device of the next higher-pressure stage. Pipe 93b is not required for the highest-pressure stage; hence, it doesn't appear in the diagrams, Figures 1 and 3, of single-stage configurations.

[0302] If the stage illustrated is the lowest-pressure-stage (e.g., first stage 24a in the embodiment of Figure 2), then line 90a passes air to an air-liquid separator (e.g., separator 27 in Figure 1) during the expansion cycle and from an air filter (e.g., filter 26 in Figure 1) during the compression cycle. Similarly, if the stage illustrated is the lowest-pressure stage, then line 91a communicates liquid to and from the liquid tank. If the stage illustrated is the highest-pressure-stage (e.g., the third stage 24c), then air is conveyed to and from the air tank (e.g., air tank 32 in Figure 1) via pipe 92c.

[0303] ***Single-Acting Stage Utilizing Bubbles to Effect Heat Exchange***

[0304] Instead of using liquid mist sprayed into the cylinder device or pressure cell in order to cool the air as it compresses or warm it as it expands, one specific embodiment of the present invention utilizes the inverse process. As best illustrated in Figure 6, that is, the air is bubbled up through a body of liquid 49c1 in the chamber 22c of the cylinder device 21c. This process should be used in preference to the mist approach above discussed when the volume fraction of mist required to effect the necessary heat exchange would be sufficiently high enough to cause a high percentage of the droplets to fuse during the compression cycle. Typically, this occurs at higher pressures. Hence, the use of the designator c in Figure 6 (e.g. 25c) indicating a third, or high-pressure stage.

[0305] As described above in connection with Figure 1, the apparatus of Figure 6 further includes a controller/processor 6002 in electronic communication with a computer-readable storage device 6004, which may be of any design, including but not limited to those based on semiconductor principles, or magnetic or optical storage principles. Controller 6002 is shown as being in electronic communication with a universe of active elements in the system, including but not limited to valves, pumps, chambers, nozzles, and sensors. Specific examples of sensors utilized by the system include but are not limited to pressure sensors (P) 6008 and 6014, temperature sensor (T) 6010, 6016, and 6018, and volume sensor (V) 6012.

[0306] Figure 6 illustrates a stage that uses bubbles to facilitate heat exchange. The compression cycle for this single-acting stage system proceeds as follows:

Step	1	2	3	4
Description	Fill cylinder	Compress	Transfer air to	Replenish liquid

	device with air		pressure cell	
Valve 108c	Closed	Closed	Closed	Closed
Valve 109c	Closed	Closed	Open	Closed
Valve 114c	Closed	Closed	Closed	Closed
Valve 41c	Closed	Closed	Open	Closed
Valve 40c	Closed	Closed	Closed	Closed
Valve 106c	Open	Closed	Closed	Closed
Valve 110c	Closed	Closed	Closed	Closed
Valve 111c	Closed	Closed	Closed	Open
Pump 105c	On	Off	Off	Off
Pump 113c	Off	Off	Off	On
Piston 23c	At top of liquid at start of step	At TDC at start of step	Near BDC at start of step	At BDC at start of step

[0307] In contrast, the expansion cycle for this single-acting stage system uses the following process:

Step	1	2	3	4
Description	Replenish liquid in cylinder device	Add compressed air to cylinder device	Expansion	Exhaust spent air
Valve 108c	Closed	Closed	Closed	Open
Valve 109c	Closed	Closed	Closed	Closed
Valve 114c	Closed	Open	Closed	Closed
Valve 41c	Closed	Closed	Closed	Closed
Valve 40c	Closed	Open	Closed	Closed
Valve 106c	Closed	Closed	Closed	Closed
Valve 110c	Open	Closed	Closed	Closed
Valve 111c	Closed	Closed	Closed	Closed
Pump 105c	Off	Off	Off	Off
Pump 113c	On	Off	Off	Off
Piston 23c	At BDC at start	At top of liquid	Near BDC at start	At TDC at start

[0308] An air-liquid mixture from the chamber 22c of cylinder device 21c in this stage (e.g., third stage 24c) is conveyed to the pressure cell 25b of the next lower-pressure stage (e.g., second stage 24b) during the expansion cycle, via valve 108c and pipe 91c/95b. Air is conveyed to the chamber 22c of cylinder device 21c in this third stage 24c, for example, from the next lower-pressure stage 24b during compression via pipe 92b/90c.

[0309] In contrast, air from the pressure cell 25c of this second stage 24c, for instance, is conveyed to and from the cylinder chamber 22d of next higher-pressure stage via pipe 92c/90d together with the operation of in-line valve 41c. Liquid 49c from the pressure cell 25c of this stage is conveyed to the cylinder chamber 22d of the next higher-pressure stage 24d, for example, via pipe 93c/94d. An air-liquid mixture from the cylinder chamber 22d of the next higher-pressure stage (during the expansion cycle thereof) is conveyed to pressure cell 25c of this stage via pipe 91d/95c.

[0310] It will be appreciated that, in some multi-stage systems, some (lower-pressure) stages might employ the liquid mist technique while other (higher-pressure) stages may employ the bubbles technique to store and remove energy therefrom.

[0311] ***Multiple Phases***

[0312] The systems as described so far represent a single phase embodiment. That is, all pistons operate together over the course of one cycle. During expansion, for example, this produces a varying amount of mechanical work output during one half of the cycle and requires some work input during the other half of the cycle. Such work input may be facilitated by the use of a flywheel (not shown).

[0313] To smooth out the power output over the course of one cycle and reduce the flywheel requirements, in one embodiment, multiple systems phases may be employed. *N* sets of pistons thus may be operated 360/*N* degrees apart. For example, four complete sets of pistons may be operated 90 degrees out of phase, smoothing the output power and effecting self-starting and a preferential direction of operation. Note that valves connecting cylinder devices to a pressure cell are only opened during less than one-half of a cycle, so it is possible to share a pressure cell between two phases 180 degrees apart.

[0314] If *N* phases are used, and *N* is even, pairs of phases are 180 degrees apart and may be implemented using double-acting pistons. Figure 5 illustrates a double-acting stage that uses liquid mist to effect heat exchange. Each half of the piston operates according the protocol outlined in the section *Single Stage System,* but 180 degrees out of phase.

[0315] As described above in connection with Figure 1, the apparatus of Figure 5 further includes a controller/processor 5002 in electronic communication with a computer-readable storage device 5004, which may be of any design, including but not limited to those based on semiconductor principles, or magnetic or optical storage principles. Controller 5002 is shown as being in electronic communication with a universe of active elements in the system, including but not limited to valves, pumps, chambers, nozzles, and sensors. Specific examples of sensors utilized by the system include but are not limited to pressure sensors (P), temperature sensors (T), humidity sensor (H), and volume sensors (V).

[0316] The compression cycle for the double-acting stage illustrated in Figure 5 proceeds as follows:

Step	1	2	3	4	5
Description	Add mist to chamber 22b1 and move air to pressure cell from chamber 22b2	Compress air in chamber 22b1 and refill chamber 22b2	Move air to pressure cell from chamber 22b1 and add mist to chamber 22b2	Refill chamber 22b1 and compress air in chamber 22b2	Replenish liquids in cylinder device
Valve 35b1	Closed	Closed	Open	Open	Closed
Valve 36b1	Closed	Closed	Closed	Closed	Open
Valve 37b1	Closed	Closed	Closed	Closed	Closed
Valve 38b1	Closed	Closed	Open	Closed	Closed
Valve 39b1	Open	Closed	Closed	Closed	Closed
Valve 35b2	Open	Open	Closed	Closed	Closed
Valve 36b2	Closed	Closed	Closed	Closed	Open
Valve 37b2	Closed	Closed	Closed	Closed	Closed
Valve 38b2	Open	Closed	Closed	Closed	Closed
Valve 39b2	Closed	Closed	Open	Closed	Closed
Valve 40b	Closed	Closed	Closed	Closed	Closed
Valve 41b	Open	Closed	Open	Closed	Closed
Pump 47b	On	Off	On	Off	Off
Piston 23b	Near TDC at	Between TDC	Near BDC at	Between TDC	Between TDC

	start of step	and BDC, moving down	start of step	and BDC, moving up	and BDC

[0317] Note that step 5 is unnecessary, in some specific embodiments, and can be omitted in the great majority of cycles since the liquid levels in the piston remain substantially the same across long periods of operation.

[0318] In contrast, the expansion cycle for the double-acting stage illustrated in Figure 5 proceeds as follows:

Step	1	2	3	4	5
Description	Add mist and air to chamber 22b1 and exhaust air from chamber 22b2	Allow air in chamber 22b1 to expand and continue exhausting air from chamber 22b2	Add mist and air to chamber 22b2 and exhaust air from chamber 22b1	Allow air in chamber 22b2 to expand and continue exhausting air from chamber 22b1	Replenish liquids in cylinder device
Valve 35b1	Closed	Closed	Open	Open	Closed
Valve 36b1	Closed	Closed	Closed	Closed	Open
Valve 37b1	Open	Closed	Closed	Closed	Closed
Valve 38b1	Closed	Closed	Closed	Closed	Closed
Valve 39b1	Open	Closed	Closed	Closed	Closed
Valve 35b2	Open	Open	Closed	Closed	Closed
Valve 36b2	Closed	Closed	Closed	Closed	Open
Valve 37b2	Closed	Closed	Open	Closed	Closed
Valve 38b2	Closed	Closed	Closed	Closed	Closed
Valve 39b2	Closed	Closed	Open	Closed	Closed
Valve 40b	Open	Closed	Open	Closed	Closed
Valve 41b	Closed	Closed	Closed	Closed	Closed
Pump 47b	On	Off	On	Off	Off
Piston 23b	Near TDC at start of step	Between TDC and BDC, moving down	Near BDC at start of step	Between TDC and BDC, moving up	Between TDC and BDC

[0319] Note that, as with compression, step 5 is rarely necessary and can be omitted in the great majority of cycles.

[0320] ***Stages with Multiple Cylinder devices***

[0321] If it is desirable that all the cylinder devices in a multi-stage system 20 be of substantially similar size, the larger (lower-pressure) cylinder devices may be divided up into two or more smaller cylinder devices communicating in parallel. An example of such a stage is illustrated in Figure 7, which is an alternative embodiment of the stage of embodiment of Figure 4. In this configuration, four substantially similar cylinder devices 21b1-21b4 share a single pressure cell 25b containing body of liquid 49b. However, if it is desirable to operate the cylinder devices out of phase with each other so that the system as a whole may convey power more uniformly, separate pressure cells will be required for each cylinder device. As mentioned above, the exception is cylinder devices that are 180 degrees out of phase, which then may share a common pressure cell.

[0322] Referring back to the embodiment of Figure 7, each cylinder device 21b1-21b4 operates according to the scheme used for the mist-type system described in the *Single-Stage System* section above.

[0323] Multi-cylinder device stages may be single or double-acting, and may use either liquid mist or bubbles to effect heat exchange. A multi-stage system may have some stages with a single cylinder device and others with multiple cylinder devices.

[0324] ***Options for Conveying Mechanical Power to and from the System***

[0325] At least four methods may be applied to convey power to and from a stage in accordance with the present invention. These are described as follows, and illustrated in Figure 8.

[0326] W. A direct-acting hydraulic cylinder device 21w is shown and operates as follows. During the expansion cycle, air entering the chamber 22w of cylinder device 21w, via valve 121w and pipe 122w, urges the hydraulic liquid 49w out through valve 123w. It then flows through pipe 124w. The force thus pneumatically applied against the liquid can be used to operate a hydraulic device (e.g., a hydraulic motor 57, a hydraulic cylinder device or a hydro turbine as shown in Figure 9) to create mechanical power. During the compression cycle, the reverse process occurs. An external source of mechanical power operates a hydraulic pump or cylinder device, which forces hydraulic liquid 49w into the cylinder chamber 22w, through valve 123w, compressing the air in the chamber. When the air has reached the desired pressure, valve 121w is opened, allowing the compressed air to flow from the cylinder chamber 22w to the next higher-pressure stage or to the air tank.

[0327] X. A single-acting piston 23x (also illustrated in Figure 4) may be connected to a conventional crankshaft via a piston rod 19x. Its operation is described in detail in the section titled *Single-Stage System* above.

[0328] Y. A double-acting piston (also illustrated in Figure 5), may similarly be connected to a crankshaft via a piston rod 19y. Its operation is described in detail in the section titled *Multiple Phases* above.

[0329] Z. A hydraulic cylinder device 21 with a diaphragm 125 is illustrated such that when air enters the cylinder chamber 22z, via valve 121z, during the expansion cycle, the diaphragm 125 is forced downwardly. Consequently, the hydraulic liquid 49z is urged or driven through valve 123z and through pipe 124z. Similarly, during compression, the hydraulic liquid 49z is driven through valve 123z and into the cylinder chamber 22z, deflecting the diaphragm 125 upwardly, compressing the air in the upper part of the chamber 22z, which then exits via valve 121z.

[0330] Note that all four of these options can be used with either the liquid mist technique or the bubbles technique to effect heat transfer. The necessary valves and nozzles to supply the mist or bubbles are not shown on Figure 8.

[0331] While the above examples describe the use of pistons, other types of moveable elements may be utilized and still remain within the scope of the present invention. Examples of alternative types of apparatuses which could be utilized include but are not limited to screw compressors, multi-lobe blowers, vane compressors, gerotors, and quasi-turbines.

[0332] ***Single-Stage, Single-Acting Energy Storage System:***

[0333] Referring now to the embodiment of Figure 3, a single-stage, single-acting energy storage system 20 is illustrated that utilizes two pressure cells 25d and 25e configured as direct-acting hydraulic cylinder devices (option A above). The two pressure cells operate substantially 180 degrees out of phase with each other. Liquid mist is used to effect heat exchange during the compression cycle, and both bubbles and mist are used to effect heat exchange during the expansion cycle.

[0334] As described above in connection with Figure 1, the apparatus of Figure 3 further includes a controller/processor 3006 in electronic communication with a computer-readable storage device 3008, which may be of any design, including but not limited to those based on semiconductor principles, or magnetic or optical storage principles. Controller 3006 is shown as being in electronic communication with a universe of active elements in the system, including but not limited to valves, pumps, chambers, nozzles, and sensors. Specific examples of sensors utilized by the system include but are not limited to pressure sensors (P) 3016, 3022, and 3038, temperature sensors (T) 3018, 3024, and 3040, humidity sensor (H) 3010, and volume sensors (V) 3036, 3014, and 3020.

[0335] The compression cycle of the single-stage, single-acting energy storage system 20 proceeds as follows:

Step	1	2	3	4
Description	Compress air in cell 25d while spraying mist, and replenish the air in cell 25e	Move compressed air from cell 25d to air tank	Compress air in cell 25e while spraying mist, and replenish the air in cell 25d	Move compressed air from cell 25e to air tank
Valve 130	Closed	Closed	Open	Open
Valve 131	Open	Open	Closed	Closed
Valve 132	Closed	Open	Closed	Closed
Valve 133	Closed	Closed	Closed	Closed
Valve 134	Open	Open	Closed	Closed
Valve 135	Closed	Closed	Open	Open
Valve 136	Closed	Closed	Closed	Open
Valve 137	Closed	Closed	Closed	Closed
Valve 138	Pump out to cell 25d, pump in from cell 25e	Pump out to cell25d, pump in from cell 25e	Pump out to cell 25e, pump in from cell 25d	Pump out to cell 25e, pump in from cell 25d
Pump 46	On	On	On	On

[0336] During step 1, fluid is pumped from pressure cell 25e using the hydraulic pump-motor 57 into pressure cell 25d, thereby compressing the air inside cell 25d. Fluid mist is sprayed through nozzle 141, which absorbs the heat of compression. When the pressure inside cell 25d has reached the pressure of

the air tank 32, valve 132 is opened to let the compressed air move to the air tank. As these steps have been progressing, air at atmospheric pressure has entered the system via pipe 10 and air filter 26d and thence into cell 25e to replace the fluid pumped out of it.

[0337] When all the air has been driven out of cell 25d, the process reverses, and step 3 commences, with the four-way valve 138 changing state to cause liquid to be pumped out of cell 25d and into cell 25e, causing the air in cell 25e to be compressed. Thus, liquid is pumped back and forth between cells 25d and 25e in a continuous cycle.

[0338] The expansion cycle of the single-stage, single-acting energy storage system proceeds as follows:

[0339] In step 1, compressed air is bubbled into pressure cell 25d via nozzle 11d. As the bubbles rise, they exchange heat with the body of fluid 49d. Air is forced out of cell 25d, passing through pipe 139d, and then driving hydraulic motor 57, thereby delivering mechanical power

[0340] In step 2, the valve 133 admitting the compressed air into cell 25d is closed, allowing the air in cell 25d to expand, continuing to operate motor 57. In step 3, once the air admitted in step 1 has risen to the top of cell 25d and can no longer exchange heat with the body of fluid 49d, fluid mist is sprayed into the cell via nozzle 141 to further warm the expanding air.

[0341] As fluid passes through the hydraulic motor 57 during steps 1, 2, and 3, it continues through pipe 139e and enters pressure cell 25e, urging the air present in that cell through pipe 140 and into the liquid trap-reservoir 13d, and thence into the atmosphere via air filter 26d and finally pipe 10.

[0342] Steps 4, 5, and 6 mirror steps 1, 2, and 3. That is, compressed air is bubbled into pressure cell 25e, forcing fluid through the hydraulic motor 57, and then into pressure cell 25d.

[0343] If reservoir 13e is depleted during operation, excess liquid is pumped from the bottom of reservoir 13d into cells 25d and 25e, using a pump, not shown in the figure, connected to pipe 140.

[0344] Over time, both liquid traps 13d and 13e will change temperature due to the air and entrained droplets transferring heat – a heat exchanger, as shown by coils 52d and 52e, in pressure cells 25d and 25e, and connected to a conventional external heat exchanger 12 that exchanges heat with the environment, will moderate the temperature to near ambient.

[0345] The volume of compressed air bubbled into the cells during steps 1 and 3 depends on the power output desired. If the air can expand fully to one atmosphere without displacing all the liquid in the cell, then the maximum amount of work will be done during the stroke. If the air does not fully expand during the stroke, all else being equal the power output will be higher at the expense of efficiency.

[0346] Note that the pressure cells cannot be of insufficient height so that the air bubbles reach the surface of the liquid during the course of the stroke, since almost all heat exchange with the body of liquid occurs while the bubbles are rising through it. However, they must be sufficiently tall for the column of bubbles to completely separate from the fluid by the time the exhaust stroke completes. If the system must be run slowly, some of the bubbles will reach the top before expansion completes. In this event, liquid mist is sprayed through nozzles 141 (in step 3) or 142 (in step 6) of the expansion cycle.

[0347] Figure 3 is meant to illustrate the basic principles. In a system in which a large expansion ratio is desired will require the use of multiple stages 24.

[0348] ***System Configurations***

[0349] It will be understood that a plurality of energy storage system embodiments, designed in accordance with this invention, are possible. These energy storage system 20 may be single or multi-stage. Stages may be single-cylinder device or multi-cylinder device. Heat exchange may be effected via liquid mist or via bubbles. Power may be conveyed in and out of the system via any of the at least four methods described in the previous section. Each possible configuration has advantages for a specific application or set of design priorities. It would not be practicable to describe every one of these configurations here, but it is intended that the information given should be sufficient for one practiced in the art to configure any of these possible energy storage systems as required.

[0350] Some configurations may have the following elements in common:

[0351] 1. Near-isothermal expansion and compression of air, with the required heat exchange effected by a liquid phase in high-surface-area contact with the air.

[0352] 2. A reversible mechanism capable of both compression and expansion of air.

[0353] 3. Electronic control of valve timing so as to obtain the highest possible work output from a given volume of compressed air.

[0354] 4. If the energy storage system utilizes a hydraulic motor or a hydro turbine, then the shaft of that device connects directly or via a gearbox to the motor-generator. If the energy storage system utilizes reciprocating pistons, then a crankshaft or other mechanical linkage that can convert reciprocating motion to shaft torque is used.

[0355] ***Use of Waste Heat During Expansion***

[0356] In order to operate isothermally, the tendency of air to cool as it expands while doing work (i.e. by pushing a piston or displacing hydraulic liquid) must be counteracted by heat exchange with the ambient air or with a body of water (e.g. a stream or lake). If, however, some other source of heat is available – for example, hot water from a steam condenser – it may be used advantageously during the expansion cycle. In Figure 1, as described in the *Single-Stage System* section above, pipes 53 and 54 lead to an external heat exchanger. If those pipes are routed instead to a heat source, the efficiency of the expansion process can be increased dramatically.

[0357] Because the system operates substantially at or near ambient temperature, the source of heat need only be a few degrees above ambient in order to be useful in this regard. The heat source must, however, have sufficient thermal mass to supply all the heat required to keep the expansion process at or above ambient temperature throughout the cycle.

[0358] As described in detail above, embodiments of systems and methods for storing and recovering energy according to the present invention are particularly suited for implementation in conjunction with a

host computer including a processor and a computer-readable storage medium. Such a processor and computer-readable storage medium may be embedded in the apparatus, and/or may be controlled or monitored through external input/output devices. Figure 20 is a simplified diagram of a computing device for processing information according to an embodiment of the present invention. This diagram is merely an example, which should not limit the scope of the claims herein. One of ordinary skill in the art would recognize many other variations, modifications, and alternatives. Embodiments according to the present invention can be implemented in a single application program such as a browser, or can be implemented as multiple programs in a distributed computing environment, such as a workstation, personal computer or a remote terminal in a client server relationship.

[0359] Figure 20 shows computer system 2010 including display device 2020, display screen 2030, cabinet 2040, keyboard 2050, and mouse 2070. Mouse 2070 and keyboard 2050 are representative "user input devices." Mouse 2070 includes buttons 2080 for selection of buttons on a graphical user interface device. Other examples of user input devices are a touch screen, light pen, track ball, data glove, microphone, and so forth. Figure 20 is representative of but one type of system for embodying the present invention. It will be readily apparent to one of ordinary skill in the art that many system types and configurations are suitable for use in conjunction with the present invention. In a preferred embodiment, computer system 2110 includes a Pentium™ class based computer, running Windows™ XP™ or Windows 7™ operating system by Microsoft Corporation. However, the apparatus is easily adapted to other operating systems and architectures by those of ordinary skill in the art without departing from the scope of the present invention.

[0360] As noted, mouse 2170 can have one or more buttons such as buttons 2180. Cabinet 2140 houses familiar computer components such as disk drives, a processor, storage device, etc. Storage devices include, but are not limited to, disk drives, magnetic tape, solid-state memory, bubble memory, etc. Cabinet 2140 can include additional hardware such as input/output (I/O) interface cards for connecting computer system 2110 to external devices external storage, other computers or additional peripherals, further described below.

[0361] Figure 20A is an illustration of basic subsystems in computer system 2010 of Figure 20. This diagram is merely an illustration and should not limit the scope of the claims herein. One of ordinary skill in the art will recognize other variations, modifications, and alternatives. In certain embodiments, the subsystems are interconnected via a system bus 2075. Additional subsystems such as a printer 2074, keyboard 2078, fixed disk 2079, monitor 2076, which is coupled to display adapter 2082, and others are shown. Peripherals and input/output (I/O) devices, which couple to I/O controller 2071, can be connected to the computer system by any number of approaches known in the art, such as serial port 2077. For example, serial port 2077 can be used to connect the computer system to a modem 2081, which in turn connects to a wide area network such as the Internet, a mouse input device, or a scanner. The interconnection via system bus allows central processor 2073 to communicate with each subsystem and to control the execution of instructions from system memory 2072 or the fixed disk 2079, as well as the exchange of information between subsystems. Other arrangements of subsystems and

interconnections are readily achievable by those of ordinary skill in the art. System memory, and the fixed disk are examples of tangible media for storage of computer programs, other types of tangible media include floppy disks, removable hard disks, optical storage media such as CD-ROMS and bar codes, and semiconductor memories such as flash memory, read-only-memories (ROM), and battery backed memory.

[0362] Figure 21 is a schematic diagram showing the relationship between the processor/controller, and the various inputs received, functions performed, and outputs produced by the processor controller. As indicated, the processor may control various operational properties of the apparatus, based upon one or more inputs.

[0363] An example of such an operational parameter that may be controlled is the timing of opening and closing of a valve allowing the inlet of air to the cylinder during an expansion cycle. Figures 11A-C is a simplified and enlarged view of the cylinder 22 of the single-stage system of Figure 1, undergoing an expansion cycle as described previously.

[0364] Specifically, during step 2 of the expansion cycle, a pre-determined amount of air V_0, is added to the chamber from the pressure cell, by opening valve 37 for a controlled interval of time. This amount of air V_0 is calculated such that when the piston reaches the end of the expansion stroke, a desired pressure within the chamber will be achieved.

[0365] In certain cases, this desired pressure will approximately equal that of the next lower pressure stage, or atmospheric pressure if the stage is the lowest pressure stage or is the only stage. Thus at the end of the expansion stroke, the energy in the initial air volume V_0 has been fully expended, and little or no energy is wasted in moving that expanded air to the next lower pressure stage.

[0366] To achieve this goal, valve 37 is opened only for so long as to allow the desired amount of air (V_0) to enter the chamber, and thereafter in steps 3-4 (Figures 11B-C), valve 37 is maintained closed. In certain embodiments, the desired pressure within the chamber may be within 1 psi, within 5 psi, within 10 psi, or within 20 psi of the pressure of the next lower stage.

[0367] In other embodiments, the controller/processor may control valve 37 to cause it to admit an initial volume of air that is greater than V_0. Such instructions may be given, for example, when greater power is desired from a given expansion cycle, at the expense of efficiency of energy recovery.

[0368] Timing of opening and closing of valves may also be carefully controlled during compression. For example, as shown in Figures 11D-E, in the steps 2 and 3 of the table corresponding to the addition of mist and compression, the valve 38 between the cylinder device and the pressure cell remains closed, and pressure builds up within the cylinder.

[0369] In conventional compressor apparatuses, accumulated compressed air is contained within the vessel by a check valve, that is designed to mechanically open in response to a threshold pressure. Such use of the energy of the compressed air to actuate a check valve, detracts from the efficiency of recovery of energy from the air for performing useful work.

[0370] By contrast, as shown in Figure 11F, embodiments of the present invention may utilize the controller/processor to precisely open valve 38 under the desired conditions, for example where the built-

up pressure in the cylinder exceeds the pressure in the pressure cell by a certain amount. In this manner, energy from the compressed air within the cylinder is not consumed by the valve opening process, and efficiency of energy recovery is enhanced. Embodiments of valve types that may be subject to control to allow compressed air to flow out of a cylinder include but are not limited to pilot valves, cam-operated poppet valves, rotary valves, hydraulically actuated valves, and electronically actuated valves.

[0371] While the timing of operation of valves 37 and 38 of the single stage apparatus may be controlled as described above, it should be appreciated that valves in other embodiments may be similarly controlled. Examples of such valves include but are not limited to valves 130, 132, 133, 134, 136, and 137 of FIG. 3, valves 37b and 38b of FIG. 4, valves 37b1, 38b1, 37b2 and 38b2 of FIG. 5, valves 106c and 114c of FIG. 6, and the valves 37b1-4 and 38b1-4 that are shown in FIG. 7.

[0372] Another example of a system parameter that can be controlled by the processor, is the amount of liquid introduced into the chamber. Based upon one or more values such as pressure, humidity, calculated efficiency, and others, an amount of liquid that is introduced into the chamber during compression or expansion, can be carefully controlled to maintain efficiency of operation. For example, where an amount of air greater than V_0 is inlet into the chamber during an expansion cycle, additional liquid may need to be introduced in order to maintain the temperature of that expanding air within a desired temperature range.

[0373] The present invention is not limited to those particular embodiments described above. Other methods and apparatuses may fall within the scope of the invention. For example, the step of adding liquid to a cylinder device is not required during every cycle. In addition, liquid may be added to the chamber at the same time air is being inlet.

[0374] Accordingly, the following table describes steps in an embodiment of a compression cycle for a single-stage system utilizing liquid mist to effect heat exchange, as shown in connection with Figures 12A-C, where similar elements as in Figure 1 are shown:

Step	1	2	3
Description	Refill cylinder device	Compress	Move compressed air to pressure cell
Valve 35	Closed	Closed	Closed
Valve 36	Open	Closed	Closed
Valve 37	Closed	Closed	Closed
Valve 38	Closed	Closed	Open
Valve 39	Open	Closed	Closed
Valve 40	Closed	Closed	Closed
Valve 41	Open	Open	Open
Valve 42	Closed	Closed	Closed
Valve 43	Open	Closed	Closed
Pump 46	Off	Off	Off
Pump 47	On	Off	Off
Piston 23	At TDC at start of step	At BDC at start of step	Between BDC and TDC

[0375] The corresponding expansion cycle where liquid is introduced at the same time as air, is shown in the table below, in connection with Figures 13A-C:

Step	1	2	3
Description	Add compressed air and liquid mist to cylinder device	Expansion	Exhaust spent air
Valve 35	Closed	Closed	Closed
Valve 36	Closed	Closed	Open
Valve 37	Open	Closed	Closed
Valve 38	Closed	Closed	Closed
Valve 39	Open	Closed	Closed
Valve 40	Open	Open	Open
Valve 41	Closed	Closed	Closed
Valve 42	Closed	Closed	Open
Valve 43	Closed	Closed	Closed
Pump 46	Off	Off	Off
Pump 47	On	Off	Off
Piston 23	At TDC at start of step	Near TDC at start of step	At BDC at start of step

[0376] Moreover, where bubbles are utilized to effect heat exchange, the step of replenishing liquid is not required in every cycle. The following table, in conjunction with Figures 14A-C, describes steps in an embodiment of a compression cycle for a single-stage system utilizing bubbles to effect heat exchange, where elements similar to those in Figure 6 are referenced:

Step	1	2	3
Description	Fill cylinder device with air	Compress	Transfer air to pressure cell
Valve 108c	Closed	Closed	Closed
Valve 109c	Closed	Closed	Open
Valve 114c	Closed	Closed	Closed
Valve 41c	Open	Open	Open
Valve 40c	Closed	Closed	Closed
Valve 106c	Open	Closed	Closed
Valve 110c	Closed	Closed	Closed
Valve 111c	Closed	Closed	Closed
Pump 105c	On	Off	Off
Pump 113c	Off	Off	Off
Piston 23c	At top of liquid at start of step	At TDC at start of step	Near BDC at start of step

[0377] The corresponding expansion cycle for this system is shown in the table below in conjunction with Figures 15A-C:

Step	1	2	3
Description	Add compressed air to cylinder device	Expansion	Exhaust spent air
Valve 108c	Closed	Closed	Open
Valve 109c	Closed	Closed	Closed
Valve 114c	Open	Closed	Closed
Valve 41c	Closed	Closed	Closed
Valve 40c	Open	Open	Open
Valve 106c	Closed	Closed	Closed
Valve 110c	Closed	Closed	Closed
Valve 111c	Closed	Closed	Closed
Pump 105c	Off	Off	Off
Pump 113c	Off	Off	Off
Piston 23c	At top of liquid	Near top of	At TDC at start

		liquid	

[0378] Shown in Figures 16A-D and in the table below, are the steps of an embodiment of a compression cycle for a multi-phase stage, referencing the elements of Figure 5:

Step	1	2	3	4
Description	Add mist and air to chamber 22b1 and compress air in chamber 22b2	Continue, moving air to pressure cell	Add mist and air to chamber 22b2 and compress air in chamber 22b1	Continue, moving air to pressure cell
Valve 35b1	Open	Open	Closed	Closed
Valve 36b1	Closed	Closed	Closed	Closed
Valve 37b1	Closed	Closed	Closed	Closed
Valve 38b1	Closed	Closed	Closed	Open
Valve 39b1	Open	Open	Closed	Closed
Valve 35b2	Closed	Closed	Open	Open
Valve 36b2	Closed	Closed	Closed	Closed
Valve 37b2	Closed	Closed	Closed	Closed
Valve 38b2	Closed	Open	Closed	Closed
Valve 39b2	Closed	Closed	Open	Open
Valve 40b	Closed	Closed	Closed	Closed
Valve 41b	Open	Open	Open	Open
Pump 47b	On	On	On	On
Piston 23b	TDC at start of step	Between TDC and BDC, moving down	BDC at start of step	Between BDC and TDC, moving up

[0379] The corresponding expansion cycle for the double-acting stage is illustrated in Figures 17A-D and in the following table:

Step	1	2	3	4
Description	Add mist and air to chamber 22b1 and exhaust air from chamber 22b2	Allow air in chamber 22b1 to expand and continue exhausting air from chamber 22b2	Add mist and air to chamber 22b2 and exhaust air from chamber 22b1	Allow air in chamber 22b2 to expand and continue exhausting air from chamber 22b1
Valve 35b1	Closed	Closed	Open	Open
Valve 36b1	Closed	Closed	Closed	Closed
Valve 37b1	Open	Closed	Closed	Closed
Valve 38b1	Closed	Closed	Closed	Closed
Valve 39b1	Open	Closed	Closed	Closed
Valve 35b2	Open	Open	Closed	Closed
Valve 36b2	Closed	Closed	Closed	Closed
Valve 37b2	Closed	Closed	Open	Closed
Valve 38b2	Closed	Closed	Closed	Closed
Valve 39b2	Closed	Closed	Open	Closed
Valve 40b	Open	Open	Open	Open
Valve 41b	Closed	Closed	Closed	Closed
Pump 47b	On	Off	On	Off
Piston 23b	TDC at start of step	Between TDC and BDC, moving down	BDC at start of step	Between BDC and TDC, moving up

[0380] A compression cycle for a single-stage, single-acting energy storage system shown in Figures 18A-D, is described in the table below, with mist sprayed at the time of inlet of air into the cylinder, with similar elements as shown in Figure 3:

Step	1	2	3	4
Description	Compress air in cell 25d while spraying mist, and replenish the air in cell 25e	Move compressed air from cell 25d to air tank	Compress air in cell 25e while spraying mist, and replenish the air in cell 25d	Move compressed air from cell 25e to air tank
Valve 130	Closed	Closed	Open	Open
Valve 131	Closed	Closed	Open	Open
Valve 132	Closed	Open	Closed	Closed
Valve 133	Closed	Closed	Closed	Closed
Valve 134	Open	Open	Closed	Closed
Valve 135	Open	Open	Closed	Closed
Valve 136	Closed	Closed	Closed	Open
Valve 137	Closed	Closed	Closed	Closed
Valve 138	Fluid out from cell 25e, in to cell 25d	Fluid out from cell 25e, in to cell 25d	Fluid out from cell 25d, in to cell 25e	Fluid out from cell 25d, in to cell 25e
Pump 46	On	On	On	On

[0381] The corresponding expansion cycle of the single-stage, single-acting energy storage system proceeds as follows as shown in Figures 19A-D:

Step	1	2	3	4
Description	Add air to cell 25d while spraying mist, and move air from cell 25e	Expand air in cell 25d while spraying mist, continue to exhaust cell 25e	Add air to cell 25e while spraying mist, and move air from cell 25d	Expand air in cell 25e while spraying mist, continue to exhaust cell 25d
Valve 130	Closed	Closed	Open	Open
Valve 131	Open	Open	Closed	Closed
Valve 132	Closed	Closed	Closed	Closed
Valve 133	Open	Closed	Closed	Closed
Valve 134	Open	Open	Closed	Closed
Valve 135	Closed	Closed	Open	Open
Valve 136	Closed	Closed	Closed	Closed
Valve 137	Closed	Closed	Open	Closed
Valve 138	Fluid out from cell 25d, in to cell 25e	Fluid out from cell 25d, in to cell 25e	Fluid out from cell 25e, in to cell 25d	Fluid out from cell 25e, in to cell 25d
Pump 46	On	On	On	On

[0382] Variations on the specific embodiments describe above, are possible. For example, in some embodiments, a plurality of pistons may be in communication with a common chamber. In other embodiments, a multistage apparatus may not include a separate pressure cell.

[0383] For example, in the embodiment of Figure 10, the stages are connected directly together through a heat exchanger, rather than through a pressure cell as in the embodiment of Figure 4. The relative phases of the cycles in the two stages must be carefully controlled so that when Stage 1 is performing an exhaust step, Stage 2 is performing an intake step (during compression). When Stage 2 is performing an exhaust step, Stage 1 is performing an intake step (during expansion).

[0384] The timing is controlled so the pressures on either side of heat exchanger 10024 are substantially the same when valves 37 and 10058 are open. Liquid for spray nozzle 44 is supplied from an excess water in cylinder 22 by opening valve 10036 and turning on pump 10032. Similarly, liquid for spray nozzle 10064 is supplied from an excess water in cylinder 10046 by opening valve 10038 and turning on pump 10034. Such precise timing during operation may be achieved with the operation of a controller/processor that is communication with a plurality of the system elements, as has been previously described.

[0385] The present invention is not limited to the embodiments specifically described above. For example, while water has been described as the liquid that is injected into air as a mist, other liquids could be utilized and fall within the scope of the present invention. Examples of liquids that could be used include polypropylene glycol, polyethylene glycol, and alcohols.

[0386] The following claims relate to compression.

[0387] 1. A method for storing energy, the method comprising:

introducing a first quantity of air at a first temperature into a first chamber;

in a compression cycle, subjecting the first quantity of air to compression by a first piston coupled to the first chamber;

injecting a first determined quantity of fluid into the first quantity of air to absorb thermal energy generated by the compression cycle and thereby maintain the first quantity of air in a first temperature range during the compression; and

transferring at least a portion of the first quantity of air to a first pressure cell.

[0388] 2. The method of claim 1 wherein the first determined quantity of fluid is based upon one or more control parameters.

[0389] 3. The method of claim 2 wherein the control parameter is calculated for the compression cycle from a measured physical property.

[0390] 4. The method of claim 2 wherein the control parameter comprises a maximum increase in a temperature of the first quantity of air during compression.

[0391] 5. The method of claim 2 wherein the control parameter comprises an amount of the fluid present in liquid form inside the chamber.

[0392] 6. The method of claim 2 wherein the control parameter comprises an efficiency.

[0393] 7. The method of claim 2 wherein the control parameter comprises a power input to the piston.

[0394] 8. The method of claim 2 wherein the control parameter comprises a speed of the piston.

[0395] 9. The method of claim 2 wherein the control parameter comprises a force on the piston.

[0396] 10. The method of claim 1 wherein the piston is solid, liquid, or a combination of solid and liquid.

[0397] 11. The method of claim 1 wherein the first temperature range is reflected by a change in a temperature of the first quantity of air from a first temperature to a second temperature below a boiling point of the fluid.

[0398] 12. The method of claim 11 wherein the fluid comprises water.

[0399] 13. The method of claim 12 wherein the first temperature range is about 60 degrees Celsius or less.

[0400] 14. The method of claim 1 wherein the first determined quantity of fluid is injected by spraying or misting.

[0401] 15. The method of claim 1 wherein the thermal energy transferred from the first quantity of air to the first determined quantity of fluid is facilitated by bubbling air through a liquid.

[0402] 16. The method of claim 1 further comprising transferring compressed air within the pressure cell to a storage tank.

[0403] The following claims relate to compression and expansion.

[0404] 17. The method of claim 1 further comprising:

in an expansion cycle, transferring a second quantity of air from the first pressure cell to the first chamber;

allowing the second quantity of air to expand and drive the first piston; and

injecting a second determined quantity of fluid into the second quantity of air to provide thermal energy absorbed by the expanding air and thereby maintain the second quantity of air in a second temperature range during the expansion.

[0405] 18. The method of claim 17 further comprising generating electrical power from the driving of the first piston.

[0406] 19. The method of claim 17 wherein the second determined quantity of fluid is based upon a one or more control parameters.

[0407] 20. The method of claim 17 wherein the control parameter is calculated for the expansion cycle from a measured physical property.

[0408] 21. The method of claim 17 wherein the control parameter comprises a maximum decrease in a temperature of the second quantity of air during the expansion.

[0409] 22. The method of claim 17 wherein the control parameter comprises an amount of the fluid present in liquid form inside the chamber.

[0410] 23. The method of claim 17 wherein the control parameter comprises an efficiency.

[0411] 24. The method of claim 17 wherein the control parameter comprises a power output by the first piston.

[0412] 25. The method of claim 17 wherein the control parameter comprises a speed of the piston.

[0413] 26. The method of claim 17 wherein the control parameter comprises a force on the piston.

[0414] 27. The method of claim 17 wherein the first determined quantity of fluid is injected by spraying or misting.

[0415] 28. The method of claim 17 wherein thermal energy is transferred from the second quantity of air to the second determined quantity of fluid facilitated by bubbling air through a liquid.

[0416] 29. The method of claim 17 wherein the fluid comprises water.

[0417] 30. The method of claim 17 further comprising placing the chamber in communication with additional thermal energy during the expansion cycle.

[0418] 31. The method of claim 30 wherein the additional thermal energy is waste heat from another thermal source.

[0419] 32. The method of claim 17 wherein the second temperature range is reflected by a change in a temperature of the second quantity of air from a first temperature to a second temperature above a freezing point of the fluid.

[0420] 33. The method of claim 32 wherein the fluid comprises water.

[0421] 34. The method of claim 33 wherein the second temperature range is about 11 degrees Celsius or less.

[0422] 34a. The method of claim 17 wherein at an end of an expansion stroke of the first piston, the second quantity of air is configured to produce a pressure on the first piston substantially equal to a desired pressure.

[0423] 34b. The method of claim 34a, wherein the desired pressure is an input pressure of the next lowest pressure stage, or is ambient pressure.

[0424] 34c. The method of claim 34a wherein the desired pressure is calculated to maximize an efficiency of expansion.

[0425] 34d. The method of claim 34a wherein the desired pressure is calculated to produce a desired level of power output.

[0426] 34e. The method of claim 34a wherein the desired pressure is within approximately 5 psi of an input pressure of the next lowest pressure stage.

[0427] The following claims relate to multi-stage operation.

[0428] 35. The method of claim 17 further comprising:

providing a second chamber in selective fluid communication with the first pressure cell and with a second pressure cell;

introducing from the first pressure cell, a third quantity of air at a second temperature into the second chamber;

in a compression cycle of the second chamber,

subjecting the third quantity of air to compression by a second piston coupled to the second chamber;

injecting a third determined quantity of fluid into the third quantity of air to absorb thermal energy generated by the compression and thereby maintain the third quantity of air in a third temperature range during the compression; and

transferring at least a portion of the third quantity of air to the second pressure cell.

[0429] 36. The method of claim 35 further comprising:

in an expansion cycle of the second chamber, transferring a fourth quantity of air from the second pressure cell to the second chamber;

allowing the fourth quantity of air to expand and drive the second piston;

injecting a fourth determined quantity of fluid into the fourth quantity of air to provide thermal energy absorbed by the expanding air and thereby maintain the fourth quantity of air in a fourth temperature range during the expansion; and

transferring at least a portion of the fourth quantity of air from the second chamber to the first pressure cell.

[0430] The following claims relate to expansion.

[0431] 37. A method for releasing stored energy, the method comprising:

in an expansion cycle, transferring a quantity of air from a pressure cell to a chamber having a piston disposed therein;

allowing the quantity of air to expand and drive the piston; and

injecting a determined quantity of fluid into the quantity of air to provide thermal energy absorbed by the expanding air and thereby maintain the quantity of air in a first temperature range during the expansion.

[0432] 38. The method of claim 37 wherein the determined quantity of fluid is based upon one or more control parameters.

[0433] 39. The method of claim 38 wherein the control parameter is calculated from a measured physical property.

[0434] 40. The method of claim 38 wherein the control parameter comprises a maximum decrease in a temperature of the quantity of air during the expansion.

[0435] 41. The method of claim 38 wherein the control parameter comprises an amount of the fluid present in liquid form inside the chamber.

[0436] 42. The method of claim 38 wherein the control parameter comprises an efficiency.

[0437] 43. The method of claim 38 wherein the control parameter comprises a power input to the piston.

[0438] 44. The method of claim 38 wherein the control parameter comprises a speed of the piston.

[0439] 45. The method of claim 38 wherein the control parameter comprises a force of the piston.

[0440] 46. The method of claim 38 wherein the piston is solid, liquid, or a combination of solid and liquid.

[0441] 47. The method of claim 38 wherein the fluid comprises water.

[0442] 48. The method of claim 38 wherein the first temperature range is reflected by a change in a temperature of the first quantity of air from a first temperature to a second temperature, the change less than a determined value.

[0443] 49. The method of claim 48 wherein the lower temperature is greater than a freezing point of the fluid.

[0444] 50. The method of claim 48 wherein the higher temperature is less than a boiling point of the fluid.

[0445] 51. The method of claim 38 wherein the first determined quantity of fluid is injected by spraying or misting.

[0446] 52. The method of claim 38 wherein the thermal energy transferred from the quantity of air to the determined quantity of fluid is facilitated by bubbling air through a liquid.

[0447] 52a. The method of claim 37 wherein at an end of an expansion stroke of the piston, the quantity of air is configured to produce a pressure on the piston substantially equal to a desired pressure.

[0448] 52b. The method of claim 37, wherein the desired pressure is an input pressure of the next lowest pressure stage, or is ambient pressure.

[0449] 52c. The method of claim 37 wherein the desired pressure is calculated to maximize an efficiency of expansion.

[0450] 52d. The method of claim 37 wherein the desired pressure is calculated to produce a desired level of power output.

[0451] 53. A method comprising:

providing an energy storage system comprising a pressure cell in selective fluid communication with a chamber having a moveable piston disposed therein;

flowing air into the chamber;

in a compression cycle, storing energy by placing the piston in communication with an energy source to compress the air within the chamber, and then transferring the compressed air to the pressure cell; and then

in an expansion cycle, releasing energy by transferring air from the pressure cell back into the chamber while allowing the piston to move in response to expansion of air inside the chamber;

monitoring an operational parameter of the compression cycle and/or the expansion cycle; and

controlling the operational parameter to maintain a temperature of air in the chamber within a range.

[0452] 54. The method of claim 53 wherein determining an operational parameter comprises controlling an amount of a liquid introduced into the air within the chamber during the compression cycle.

[0453] 55. The method of claim 53 wherein the liquid comprises water.

[0454] 56. The method of claim 53 wherein determining an operational parameter comprises controlling an amount of a liquid introduced into the air within the chamber during the expansion cycle.

[0455] 57. The method of claim 56 wherein the liquid comprises water.

[0456] 58. The method of claim 53 wherein a lower bound of the range is greater than a freezing point of a liquid introduced into the air within the chamber.

[0457] 59. The method of claim 58 wherein the liquid comprises water.

[0458] 60. The method of claim 53 wherein an upper bound of the range is lower than a boiling point of a liquid introduced into the air within the chamber.

[0459] 61. The method of claim 60 wherein the liquid comprises water.

[0460] 62. The method of claim 53 wherein determining an operational parameter comprises controlling a timing of the transfer of air from the pressure cell into the chamber during the expansion cycle.

[0461] 62a. The method of claim 62 wherein the timing is controlled such that at an end of an expansion stroke of the piston, the transferred air is configured to produce a desired pressure on the piston.

[0462] 62b. The method of claim 62a, wherein the desired pressure is an input pressure of the next lowest pressure stage, or is ambient pressure.

[0463] 62c. The method of claim 62a wherein the desired pressure is calculated to maximize an efficiency of expansion.

[0464] 62d. The method of claim 62a wherein the desired pressure is calculated to produce a desired level of power output.

[0465] 62e. The method of claim 62a wherein the desired pressure is within approximately 5 psi of an input pressure of the next lowest pressure stage.

[0466] 63. The method of claim 53 wherein determining an operational parameter comprises monitoring a pressure in the pressure cell.

[0467] 64. The method of claim 53 wherein determining an operational parameter comprises monitoring a pressure in the chamber.

[0468] 65. The method of claim 53 wherein determining an operational parameter comprises monitoring a temperature of the air in the chamber.

[0469] 66. The method of claim 53 wherein determining an operational parameter comprises monitoring a humidity of the air flowed into the chamber.

[0470] 67. The method of claim 53 wherein determining an operational parameter comprises monitoring a humidity of air exhausted from the chamber.

[0471] 68. The method of claim 53 wherein determining an operational parameter comprises monitoring a power released during the expansion cycle.

[0472] 69. The method of claim 53 wherein determining an operational parameter comprises monitoring a position of the piston.

[0473] 70. The method of claim 53 wherein determining an operational parameter comprises monitoring a force on the piston.

[0474] 71. The method of claim 54 wherein determining an operational parameter comprises monitoring a temperature of the liquid.

[0475] 72. The method of claim 56 wherein determining an operational parameter comprises monitoring a temperature of the liquid.

[0476] 73. The method of claim 54 wherein determining an operational parameter comprises monitoring a rate of flow of the liquid.

[0477] 74. The method of claim 56 wherein determining an operational parameter comprises monitoring a rate of flow of the liquid.

[0478] 75. The method of claim 54 wherein determining an operational parameter comprises monitoring a level of the liquid in the chamber.

[0479] 76. The method of claim 56 wherein determining an operational parameter comprises monitoring a level of the liquid in the chamber.

[0480] 77. The method of claim 54 wherein determining an operational parameter comprises monitoring a volume of the liquid in the chamber.

[0481] 78. The method of claim 56 wherein determining an operational parameter comprises monitoring a volume of the liquid in the chamber.

[0482] 79. The method of claim 53 wherein:

the piston is in communication with a rotating shaft; and

determining an operational parameter comprises monitoring a speed of the rotating shaft.

[0483] 80. The method of claim 53 wherein:

the piston is in communication with a rotating shaft; and

determining an operational parameter comprises monitoring a torque of the rotating shaft.

[0484] 81. The method of claim 53 wherein the operational parameter is controlled based upon a derived parameter calculated from the monitored operational parameter.

[0485] 82. The method of claim 81 wherein the derived parameter is selected from the group comprising, an efficiency of power conversion, an expected power output, an expected output speed of a rotating shaft in communication with the piston, an expected output torque of a rotating shaft in communication with the piston, an expected input speed of a rotating shaft in communication with the piston, an expected input torque of a rotating shaft in communication with the piston, a maximum output speed of a rotating shaft in communication with the piston, a maximum output torque of a rotating shaft in communication with the piston, a minimum output speed of a rotating shaft in communication with the piston, a minimum output torque of a rotating shaft in communication with the piston, a maximum input speed of a rotating shaft in communication with the piston, a maximum input torque of a rotating shaft in communication with the piston, a minimum input speed of a rotating shaft in communication with the piston, a minimum input torque of a rotating shaft in communication with the piston, or a maximum expected temperature difference of air at each stage.

[0486] 83. The method of claim 53 wherein controlling the operational parameter comprises controlling a timing of the transfer of air from the chamber to the pressure cell during the compression cycle.

[0487] 84. The method of claim 53 wherein controlling the operational parameter comprises controlling a timing of the transfer of air from the pressure cell to the chamber during the expansion cycle.

[0488] 85. The method of claim 54 wherein controlling the operational parameter comprises controlling a timing of a flow of liquid to the chamber.

[0489] 86. The method of claim 56 wherein controlling the operational parameter comprises controlling a timing of a flow of liquid to the chamber.

[0490] 87. The method of claim 53 wherein:

during the compression cycle, the piston is in communication with a motor or a motor-generator; and

controlling the operational parameter comprises controlling an amount of electrical power applied to the motor or the motor-generator.

[0491] 88. The method of claim 53 wherein:

during the expansion cycle, the piston is in communication with a generator or a motor-generator; and

controlling the operational parameter comprises controlling an electrical load applied to the generator or the motor-generator.

[0492] 89. The method of claim 54 wherein:

the liquid is flowed to the chamber utilizing a pump; and

controlling the operational parameter comprises controlling an amount of electrical power supplied to the pump.

[0493] 90. The method of claim 56 wherein:

the liquid is flowed to the chamber utilizing a pump; and

controlling the operational parameter comprises controlling an amount of electrical power supplied to the pump.

[0494] 91. The method of claim 53 wherein:

liquid in the pressure cell is circulated through a heat exchanger that is in thermal communication with a fan; and

controlling the operational parameter comprises controlling an amount of electrical power supplied to the fan.

[0495] 92. The method of claim 53 further comprising placing the chamber in communication with additional thermal energy during the expansion cycle.

[0496] 93. The method of claim 92 wherein the additional thermal energy is waste heat from another thermal source.

[0497] 94. The method of claim 53 wherein controlling the operational parameter comprises controlling a compression ratio.

[0498] 95. The method of claim 53 further comprising transferring compressed air within the pressure cell to a storage tank.

[0499] The following claims relate to a system.

[0500] 96. An energy storage and recovery system comprising:

a first chamber having a moveable piston disposed therein and in selective communication with an energy source;

a pressure cell in selective fluid communication with the first chamber through a first valve;

an air source in selective fluid communication with the first chamber through a second valve;

a liquid source in selective fluid communication with the first chamber through a third valve; and

a controller in electronic communication with, and configured to operate, system elements in one of the following states:

an intake step wherein the first valve is closed, the second valve is open, and the third valve may be open or closed;

a compression step wherein the piston is in communication with the energy source, the first and second valves are closed, the third valve is open or closed, and then the first valve is opened upon compression of the air in the chamber by the piston,

an expansion step wherein the piston is not in communication with the energy source, the first valve is opened, the second valve is closed, and the third valve may be open or closed, such that the air expands in the chamber to move the piston, and then the first valve is closed as the air continues to expand, and

an exhaust step wherein the piston is not in communication with the energy source, the first valve is closed, the second valve is open, and the third valve may be open or closed; and;

wherein the controller is configured to determine an operational parameter in order to maintain a temperature of the air in the first chamber within a range.

[0501] 97. The energy storage and recovery system of claim 96 wherein the moveable piston comprises a solid piston.

[0502] 98. The energy storage and recovery system of claim 96 wherein the moveable piston comprises a liquid piston.

[0503] 99. The energy storage and recovery system of claim 96 further comprising a sprayer configured to inject the liquid into the air within the chamber.

[0504] 100. The energy storage and recovery system of claim 99 wherein the liquid comprises water.

[0505] 101. The energy storage and recovery system of claim 96 further comprising a bubbler configured to transfer heat between the liquid and air within the pressure cell.

[0506] 102. The energy storage and recovery system of claim 101 wherein the liquid comprises water.

[0507] 103. The energy storage and recovery system of claim 96 further comprising a sensor configured to detect a volume of liquid present within the chamber, the sensor in electronic communication with the controller and referenced to determine the operational parameter.

[0508] 104. The energy storage and recovery system of claim 96 further comprising a sensor configured to detect a property selected from the group comprising, a pressure, a temperature, a humidity, a position of the piston, a force on the piston, a liquid flow rate, a liquid level, a liquid volume, a speed of a shaft driven by the piston, or a torque of the shaft driven by the piston, wherein the sensor is in electronic communication with the controller and referenced to determine the operational parameter.

[0509] 105. The energy storage and recovery system of claim 96 further comprising a power generator or motor-generator configured to be in selective communication with the piston during the expansion stroke.

[0510] 106. The energy storage and recovery system of claim 96 wherein the chamber is configured to be in thermal communication with a thermal energy source.

[0511] 107. The energy storage and recovery system of claim 96 further comprising a storage tank configured to receive compressed air from the pressure cell.

[0512] 107a. The energy storage and recovery system of claim 96 wherein during the expansion the controller is configured to operate the first valve to inlet the air such that at an end of an expansion stroke of the piston, a pressure on the piston is substantially equal to a desired pressure.

[0513] 107b. The method of claim 107a, wherein the desired pressure is an input pressure of the next lowest pressure stage, or is ambient pressure.

[0514] 107c. The method of claim 107a wherein the desired pressure is calculated to maximize an efficiency of expansion.

[0515] 107d. The method of claim 107a wherein the desired pressure is calculated to produce a desired level of power output.

[0516] 107e. The method of claim 107a wherein the desired pressure is within approximately 5 psi of an input pressure of the next lowest pressure stage.

[0517] The following claims relate to a system having multiple stages.

[0518] 108. The energy storage and recovery system of claim 96, further comprising:

a second chamber having a moveable piston disposed therein and in selective communication with the energy source; and

a second pressure cell in selective fluid communication with the second chamber through a fourth valve, in selective fluid communication with the first pressure cell through a fifth valve, the fourth and fifth valves in communication with and configured to be operated by the controller.

[0519] 109. The energy storage and recovery system of claim 96, further comprising a plurality of a second chamber and second pressure cell connected in series with the first chamber and first pressure cell, such that output from the first chamber is communicated to the second chamber.

[0520] The following claims relate to a processor.

[0521] 110. An apparatus for storing and recovering energy, the apparatus comprising:

a host computer comprising a processor in electronic communication with a computer-readable storage medium, the computer readable storage medium having stored thereon one or more codes to instruct the processor to,

receive a signal indicating a property of an energy storage and recovery system comprising a first chamber having a moveable piston disposed therein and in selective communication with an energy source, and a pressure cell in selective fluid communication with the first chamber,

in response to the received signal, control an element of the energy storage and recovery system to maintain a temperature of air within the first chamber within a temperature range.

[0522] 111. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating a pressure in the pressure cell.

[0523] 112. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating a pressure in the first chamber.

[0524] 113. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating a temperature of the air in the first chamber.

[0525] 114. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating a temperature of the air in the pressure cell.

[0526] 115. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating a humidity of the air inlet to the first chamber.

[0527] 116. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating a power output.

[0528] 117. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating a humidity of the air exhausted from the first chamber.

[0529] 118. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating a position of the piston.

[0530] 119. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating a force on the piston.

[0531] 120. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating a temperature of liquid flowed to the chamber.

[0532] 121. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating rate of flow of liquid to the chamber.

[0533] 122. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating a level of liquid in the chamber.

[0534] 123. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating volume of liquid in the chamber.

[0535] 124. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating a speed of a rotating shaft in communication with the piston.

[0536] 125. The apparatus of claim 110 wherein the code stored on the computer readable storage medium is configured to receive the signal indicating torque of a rotating shaft in communication with the piston.

[0537] 126. The apparatus of claim 110 wherein in response to the received signal, the code stored on the computer readable storage medium is configured to instruct the processor to control a timing of a transfer of air from the chamber to the pressure cell during a compression cycle.

[0538] 126a. The apparatus of claim 110 wherein in response to the received signal, the code stored on the computer readable storage medium is configured to instruct the processor to control a timing of a transfer of air from the pressure cell to the chamber during an expansion cycle.

[0539] 127. The apparatus of claim 110 wherein in response to the received signal, the code stored on the computer readable storage medium is configured to instruct the processor to control a timing of a transfer of liquid to the chamber.

[0540] 128. The apparatus of claim 110 wherein in response to the received signal, the code stored on the computer readable storage medium is configured to instruct the processor to control the amount of liquid transferred to the chamber.

[0541] 129. The apparatus of claim 110 wherein in response to the received signal, the code stored on the computer readable storage medium is configured to instruct the processor to control an electrical load applied to a generator or a motor-generator in communication with the piston, during an expansion cycle.

[0542] 130. The apparatus of claim 110 wherein in response to the received signal, the code stored on the computer readable storage medium is configured to instruct the processor to control an electrical power applied to a motor or a motor-generator in communication with the piston, during a compression cycle.

[0543] 131. The apparatus of claim 110 wherein in response to the received signal, the code stored on the computer readable storage medium is configured to instruct the processor to control an electrical power applied to a pump to flow liquid into the chamber.

[0544] 132. The apparatus of claim 110 wherein in response to the received signal, the code stored on the computer readable storage medium is configured to instruct the processor to control an electrical power applied to fans associated with a heat exchanger configured to receive liquid from the pressure cell.

[0545] 133. The apparatus of claim 110 wherein in response to the received signal, the code stored on the computer readable storage medium is configured to instruct the processor to control a compression ratio.

[0546] The following claims relate to a multi-stage system.

[0547] 134. An energy storage and recovery system comprising:

a first stage comprising a first element moveable to compress air in the first stage, the first stage in selective fluid communication with an ambient air supply through a first valve;

a final stage comprising a second element moveable to compress air in the final stage, and moveable in response to expanding air within the final stage, the final stage in selective fluid communication with a compressed air storage tank through a second valve;

a controller configured to determine an amount of liquid to be injected into the first stage or the final stage to maintain a temperature of air in the first stage or in the final stage within a temperature range; and

a liquid source in communication with the controller and configured to inject the determined amount of liquid into the first stage or into the final stage.

[0548] 135. The energy storage and recovery system of claim 134, wherein the first moveable element is also moveable in response to expanding air within the first stage.

[0549] 136. The energy storage and recovery system of claim 134, wherein the first moveable element comprises a piston.

[0550] 137. The energy storage and recovery system of claim 134, wherein the first moveable element comprises a screw.

[0551] 138. The energy storage and recovery system of claim 134, wherein the first stage or the final stage comprises a pressure cell in selective fluid communication with a chamber.

[0552] 139. The energy storage and recovery system of claim 134, wherein the first stage is configured to transfer to, and receive compressed air from, the final stage through a third valve.

[0553] 140. The energy storage and recovery system of claim 139, wherein the first stage comprises a first chamber having a first piston disposed therein as the first moveable element, and the final stage comprises a second chamber having a second piston disposed therein as the second moveable element, the first and final stages lacking a pressure cell.

[0554] 141. The energy storage and recovery system of claim 134, further comprising an intermediate stage positioned in series and in selective fluid communication between the first stage and the final stage, the intermediate stage comprising a third element moveable to compress air in the intermediate stage, and moveable in response to expanding air within the intermediate stage.

[0555] 142. The energy storage and recovery system of claim 141, wherein the first moveable element is also moveable in response to expanding air within the first stage.

[0556] 143. The energy storage and recovery system of claim 142, wherein the first stage comprises a first chamber having a first piston disposed therein as the first moveable element, and the intermediate stage comprises a second chamber having a second piston disposed therein as the third moveable element.

[0557] 144. The energy storage and recovery system of claim 141, wherein the intermediate stage comprises a first chamber having a first piston disposed therein as the third moveable element, and the final stage comprises a second chamber having a second piston disposed therein as the second moveable element.

[0558] 145. The energy storage and recovery system of claim 141, wherein the first stage, the intermediate stage, or the final stage comprises a chamber in selective fluid communication with a pressure cell.

[0559] 146. The energy storage and recovery system of claim 141, wherein consecutive stages do not include a pressure cell.

[0560] 147. The energy storage and recovery system of claim 141, further comprising additional intermediate stages positioned in series between the first stage and the final stage.

[0561] 148. The energy storage and recovery system of claim 134, wherein the second moveable element comprises a piston.

[0562] 149. The energy storage and recovery system of claim 148, wherein the second moveable element comprises a liquid piston.

[0563] 150. The energy storage and recovery system of claim 148, wherein the second moveable element comprises a solid piston.

[0564] 151. The energy storage and recovery system of claim 134, wherein a compression ratio of the first stage is larger than a compression ratio of the final stage.

[0565] 152. The energy storage and recovery system of claim 141, wherein a compression ratio of the first stage is larger than a compression ratio of the intermediate stage, and the compression ratio of the intermediate stage is greater than a compression ratio of the final stage.

[0566] 153. The energy storage and recovery system of claim 134, wherein the liquid comprises water.

[0567] 154. A method of storing energy, the method comprising:

receiving ambient air in a first stage;

compressing the ambient air in the first stage;

transferring compressed air to a final stage;

further compressing air in the final stage;

transferring the further compressed air from the final stage to a storage tank; and

determining an operational parameter to maintain a temperature change of air in the first stage or in the second stage within a range during the compression or the further compression.

[0568] 155. The method of claim 154 wherein the determined operational parameter comprises a timing of opening or closing valves controlling movement of air into or out of the stages.

[0569] 156. The method of claim 154 wherein the determined operational parameter comprises an amount of liquid injected into the first stage or into the final stage during the compression or the further compression.

[0570] 157. The method of claim 154 wherein compressing the ambient air comprises placing a piston disposed within a chamber of the first stage, in communication with an energy source.

[0571] 158. The method of claim 154 wherein compressing the ambient air comprises placing a screw disposed within a chamber of the first stage, in communication with an energy source.

[0572] 159. The method of claim 154 wherein compressed air is transferred to the final stage via an intermediate stage in which additional compression takes place.

[0573] 160. The method of claim 154 further comprising:

transferring compressed air from the storage tank to the final stage;

allowing the compressed air to expand and drive a first moveable element in the final stage;

transferring air from the final stage to the first stage;

allowing compressed air in the first stage to expand and drive a second moveable element in the first stage; and

determining an operational parameter to maintain a temperature change of air in the first stage or in the second stage within a range, during expansion of air within the first stage or within the second stage.

[0574] 161. The method of claim 160 wherein the determined operational parameter comprises a timing of opening or closing valves controlling movement of air into or out of the stages.

[0575] 162. The method of claim 160 wherein the determined operational parameter comprises an amount of liquid injected into the first stage or into the final stage during expansion of air within the first stage or the second stage.

[0576] 163. The method of claim 160 wherein the first moveable element comprises a piston.

[0577] 164. The method of claim 160 wherein the second moveable element comprises a piston.

[0578] 165. The method of claim 160 wherein air is transferred from the final stage to the first stage via an intermediate stage wherein further expansion of air takes place

[0579] Embodiments in accordance with the present invention relate to the extraction of energy from a temperature difference. In particular embodiments, energy from a heat source may be extracted through the expansion of compressed air. In certain embodiments, a storage unit containing compressed gas is in fluid communication with a compressor-expander. Compressed gas received from the storage unit, expands in the compressor-expander to generate power. During this expansion, the compressor-expander is in selective thermal communication with the heat source through a heat exchanger, thereby enhancing power output by the expanding gas. In alternative embodiments, where the heat source is continuously available, a dedicated gas expander may be configured to drive a dedicated compressor. Such embodiments may employ a closed system utilizing gas having high heat capacity properties, for example helium or a high heat capacity gas (for example, carbon dioxide, hydrogen, or neon) resulting from operation of the system at an elevated baseline pressure.

[0580] Embodiments of the present invention relate generally to the extraction of energy from a temperature difference. According to certain embodiments, a temperature in the form of heat from a heat source, may be harnessed to generate useable energy from expansion of a compressed gas. A compressor-expander is in fluid communication with a compressed gas storage unit. Compressed gas received from the storage unit, expands in the compressor-expander to generate power. During expansion, the heat source is in selective thermal communication with the compressor-expander through a heat exchanger, to enhance power output. System operation may be further enhanced by introducing a

fluid during expansion, and/or by controlling air flowed into and out of the compressor-expander during expansion.

[0581] In order to operate nearly isothermally, the tendency of gas to cool as it expands while doing work (i.e. by pushing a piston or displacing hydraulic liquid), can be counteracted by heat exchange with a heat source. If some form of heat is available, it may be harnessed to improve power output during an expansion cycle.

[0582] Because in many embodiments a compressed gas system is configured to operate substantially at or near ambient temperature, the source of heat need only be a few degrees above ambient in order to be useful in this regard. The heat source must, however, have sufficient thermal mass to supply all the heat required to keep the expansion process near ambient temperature throughout the cycle. Thus, embodiments of the present invention may be able to harness low grade heat, for example in the form of waste heat from another process, to enhance the power output from compressed air

[0583] Figure 22 shows a simplified block diagram of an embodiment of a system 2280 according to the present invention, for generating energy from compressed air, although other forms of compressed gas could be used. The system includes a compressor-expander 2282 which may have a structure similar to that described in U.S. provisional patent application No. 61/221,487 ("the '487 application"), but alternatively could be of another design.

[0584] Compressor-expander 2282 is in fluid communication with compressed air storage unit 2284. Compressor-expander 2282 is in selective thermal communication through heat exchanger 2286 and valve 2288, with either heat source 2290 or heat sink 2292. Heat source 2290 may be a source of low grade heat or high grade heat. Heat source 190 may be present continuously, or may be intermittent in nature.

[0585] Compressor-expander 2282 is in physical communication with motor-generator 2294 through linkage 2296. Linkage 2296 may be mechanical, hydraulic, or pneumatic, depending upon the particular embodiment. Motor-generator 2294 is in turn in electrical communication with a power source such as the electrical grid 2298.

[0586] Operation of the system 2280 is described as follows. In a first mode, system 2280 is configured to generate power by converting compressed air stored in the storage unit 2284, into useable work. The system may be configured in this first mode, for example, at times of peak power demand on the grid, for example between 7AM and 7PM on weekdays.

[0587] In this first mode depicted in Figure 22A, compressed air is flowed from storage unit 2284 to compressor-expander 2282 which is functioning as an expander. Switch 2288 is configured to allow thermal communication between heat source 2290 and heat exchanger 2286 and/or storage unit 2284.

[0588] As a result of the contribution of heat from the heat source in this mode, air expanding in the compressor-expander experiences a reduced change in temperature, thereby producing an increased power output. This power output is in turn communicated through linkage 2296 to motor-generator 2294 that is functioning as a generator. Power output from the motor-generator may in turn be fed onto the power grid 2298 for consumption.

[0589] In a second mode of operation, system 2280 is configured to replenish the supply of compressed air in the storage tank. The system may be configured in this second mode, for example, at times of reduced demand for power on the power grid.

[0590] In this second mode shown in Figure 22B, motor-generator 2294 receives power from the power grid 2298 (or directly from another source such as a wind turbine or solar energy harvesting unit), and actuates linkage to operate compressor-expander 2282 as a compressor. Switch 2288 is configured to allow thermal communication between heat sink 2292 and heat exchanger 2286 and/or storage unit 2284.

[0591] As a result of the transfer of heat from the compressor-expander to the to the heat sink in this mode, air being compressed in the compressor-expander experiences a reduced change in temperature, thereby resulting in a lower energy loss upon its conversion into compressed air. The compressed air is in turn communicated from the compressor-expander to the compressed air storage unit 2284, for later recovery in the first mode.

[0592] In certain embodiments, switch 2288 may be temporal in nature, such that it operates according to the passage of time. An example of this would be the diurnal cycle, wherein during the day the heat exchanger and/or storage unit are in thermal communication with the sun as a heat source. Conversely, at night the heat exchanger and/or storage unit would be in thermal communication with the cooling atmosphere as a heat sink. In such embodiments, the magnitude of the heat source could be amplified by techniques such as reflection onto the heat exchanger and/or storage tank, or by providing the heat exchanger and/or storage tank with a coating configured to enhance absorption of solar radiation.

[0593] In certain embodiments, switch 2288 may be physical in nature, such that it is actuable to allow warm fluid from the heat source to be in proximity with the heat exchanger and/or storage unit, or to allow cool fluid from the heat sink to be in proximity with the heat exchanger and/or storage unit. Examples of this type of configuration include a switch that is in selectively in fluid communication with pipes leading to a power plant as the heat source, or to a body of water (such as a cooling tower, lake, or the ocean) as the heat sink.

[0594] Operation of the various embodiments of systems described above, can be enhanced utilizing one or more techniques employed alone or in combination. One such technique is the introduction of a liquid into the air as it is expanding or being compressed. Specifically where the liquid exhibits a greater heat capacity than the air, the transfer of heat from compressing air, and the transfer of heat to expanding air, would be improved. This greater heat transfer would in turn allow the temperature of the compressing or expanding air to remain more constant. Such introduction of liquid during compression and expansion is discussed in detail in the '487 Application.

[0595] In certain embodiments, the liquid is introduced as a mist through a spray device. In other embodiments, the gas may be introduced by bubbling through a liquid. Other embodiments may employ both misting and bubbling, and/or multiple stages (see below) which employ misting and/or bubbling only in certain stages.

[0596] Another technique which may employed to enhance operation of the system, is precise control over gas flows within the compressor-expander. Such precise control may be achieved utilizing a controller or processor that is configured to be in electronic communication with various elements of the compressor-expander.

[0597] For example, Figure 23 shows a simplified block diagram of an embodiment of a single-stage compressor-expander 2300 in accordance with an embodiment of the present invention. Further details regarding the structure of such a compressor-expander are provided in connection with Figure 25 below.

[0598] The compressor-expander 2300 of Figure 23 comprises a cylinder 2302 having a moveable element such a piston 2304, disposed therein. Cylinder 2302 is in selective fluid communication with a pressure cell 2306. During compression, air (and possibly liquid) inlet into the cylinder, is compressed by the piston, and then the compressed air is flowed to the pressure cell through valve 2308.

[0599] In conventional compressor designs, valve 2308 is a check valve that is physically actuated by the force resulting from pressure exerted by compressed air in the cylinder. Such check valve actuation, however, consumes some of the energy of the compressed air.

[0600] By contrast, according to certain embodiments of the present invention, the valve 2308 may be of a different type that is operated by electronic control by a processor or controller. Examples of valves suitable for control according to embodiments of the present invention include but are not limited to pilot valves, rotary valves, cam operated poppet valves, and hydraulically, pneumatically, or electrically actuated valves. The use of electronic control in this manner would avoid the loss of energy in the compressed air associated with conventional actuation of a check valve.

[0601] Precise valve control can also enhance operation during expansion. Specifically, valve 2310 may be precisely controlled to allow the cylinder to admit only a predetermined amount of air from the pressure cell during an expansion cycle. This predetermined amount of air may be calculated to result in a desired pressure on the piston at the end of the expansion stroke. This desired pressure may be approximately equal to ambient pressure where the compressor-expander has only a single stage, or the pressure cell and cylinder comprise a lowest stage of a multi-stage design. In a multi-stage design, this desired pressure may be equal to the pressure of the next-lowest stage. Alternatively, where greater power output is desired, the timing of opening and closing of valve 2310 may be controlled to admit a sufficient quantity of air such that the desired pressure at the end of the expansion stroke is a larger value.

[0602] While the above embodiments have been described in connection with use of an element configurable to function either as a compressor or an expander of gases, this is not required by the present invention. Alternative embodiments could employ separate elements that are dedicated to performing either gas compression or expansion, and remain within the scope of the present invention.

[0603] One such alternative embodiment is shown in Figure 24A, where system 2400 comprises dedicated expander 2402. The dedicated expander 2402 functions to receive compressed gas, and to allow that compressed gas to expand and be converted into useful work. For example, expansion of the compressed gas within the expander 2402 may serve to drive a common physical linkage 2416, which may be mechanical, hydraulic, pneumatic, or another type.

[0604] Dedicated expander 2402 is in turn in thermal communication with a heat exchanger 306, that is in thermal communication with heat source 2410. Energy received by the dedicated expander from the heat source 2410 via the heat exchanger 2406, may serve to enhance the power output as compressed gas flowed into the expander, expands and is converted into useful work, for example the driving of linkage 2416. Specifically, heating of the gas by the thermal source prior to or during its expansion, results in reduced thermodynamic losses attributable to non-isothermal expansion of the gas.

[0605] The linkage 2416 is in turn in physical communication with dedicated compressor 2403. Dedicated compressor 2403 may be driven by the operation of the linkage 2416, such that it compresses gas that has been output from the dedicated expander.

[0606] Dedicated compressor 2403 is in thermal communication with a heat exchanger 2405, that is in thermal communication with a thermal sink 2412. A reduced temperature experienced by the dedicated compressor by virtue of its thermal communication with thermal sink 2412 via the heat exchanger 2405, may serve to reduce the amount of energy required to compress the gas.

[0607] The linkage 2416 is also in communication with a generator 2414. Based upon movement of the linkage, generator 2414 operates to generate electrical power that is in turn fed onto power grid 2418 for consumption.

[0608] In operation, some amount of compressed gas is initially supplied to the dedicated expander, for example by driving compressor 2403 with a motor (not shown). Alternatively, generator 2414 may be operated in reverse as a motor.

[0609] Subsequently, this initial amount of compressed air is flowed out of the storage unit to the dedicated expander. Expansion of the compressed gas in the expander, serves to drive the linkage. This conversion of energy stored in compressed gas into mechanical work, is enhanced by the energy supplied from the heat source.

[0610] As a result of this energy conversion, the linkage is actuated to operate the dedicated compressor 2403 to compress gas received from the dedicated expander, and flow this compressed gas to back to the expander to allow it to operate. Specifically, cooling of the gas by the thermal sink prior to or during its compression, results in reduced thermodynamic losses attributable to non-isothermal compression of the gas.

[0611] Energy recovered from the expanding gas that exceeds the amount required to operate the compressor, may in turn be utilized to generate electricity. Specifically, actuation of the mechanical linkage may operate generator 2414 that is in communication with the power grid 2418.

[0612] Embodiments such as that shown in Figure 24A may offer certain benefits. One possible benefit is that the system of Figure 24A may operate with gases exhibiting desirable properties.

[0613] For example, helium may be a favorable candidate for use in energy storage systems, because it exhibits a relatively high heat capacity. The high heat capacity of helium allows it to efficiently absorb and transmit heat during compression and expansion processes, respectively.

[0614] The expense of helium generally limits its use in open systems. However, the embodiment of Figure 24A operates as a closed system. This closed configuration allows the gas that is expanded in the

dedicated expander to in turn be compressed and fed back to the dedicated expander. Such recycling may allow helium to be economically viable for use in the system of Figure 24A.

[0615] The closed nature of the embodiment of the system of Figure 24A, may also allow it to operate with high density gases, which improves their heat capacity. In particular, because the system of Figure 24A is closed and does not rely upon outside air, it may operate at baseline pressures that are significantly greater than ambient. Examples of such baseline pressures include but are not limited to pressures that are 5 PSI, 10 PSI, 20 PSI, 50 PSI, 100 PSI, or 200 PSI above ambient pressure. The resulting enhanced heat capacity of the high density gases in such a system, improve their ability to transmit and absorb heat during respective compression and expansion processes, potentially enhancing the thermodynamic efficiency of these processes during energy storage and recovery.

[0616] The system of the embodiment of Figure 24A may also offer the benefit of simple construction. For example, because operation of the dedicated expander and dedicated compressor is concurrent, the gas is generally consumed for expansion almost immediately after being compressed. This immediate expansion may obviate the need to provide a separate pressure-tight vessel element to store the compressed gas.

[0617] Moreover, because the gas in the system of Figure 24A does not need to be stored, it may operate utilizing relatively small differences between baseline pressure and the pressure after compression. Thus, compression of the gas in the embodiment of the system of Figure 24A can likely be accomplished utilizing only a single stage, further simplifying the design.

[0618] In certain embodiments of the present invention, performance may be enhanced by the use of a regenerator device. Figure 24B shows a simplified diagram showing an alternative embodiment of an apparatus which includes a regenerator. Specifically, apparatus 2450 comprises dedicated compressor 2453, dedicated expander 2452, and generator 2454 that are all in mechanical communication with a common rotating shaft 2466.

[0619] Regenerator 2460 is positioned between the gas flowing between dedicated compressor 2453 and dedicated expander 2452 in this closed loop system. In particular, while passing through regenerator 2460, gas that has been compressed in dedicated compressor 2453 and then cooled to the temperature of thermal sink 2462, is heated by transferring thermal energy from the nearby flowing gas that has been expanded in dedicated expander 2452 and heated to the temperature of heat source 2460. Conversely, the gas that has been expanded in dedicated expander 2452 and heated to the temperature of heat source 2460, is cooled by transferring thermal energy to the nearby flowing gas that has been cooled during compression in the dedicated compressor 2453. This exchange of thermal energy between the flowing gases in regenerator 2460, ultimately serves to enhance the amount of energy that is recovered from the expanding gas.

[0620] In alternative embodiments, an effect similar to that performed by the regenerator element, may instead by achieved by conducting expansion over a plurality of stages. Such an embodiment is shown in Figure 24C, wherein system 2480 is similar to system 2400, except that a first dedicated expander 2482 is in serial fluid communication with a second dedicated expander 2483, with both the

first and second dedicated expanders in physical communication with common link 2476. Link 2476 may be mechanical in nature such as a rotating shaft, or alternatively may be hydraulic or pneumatic. The extraction of heat using successive dedicated expansion stages 2482 and 2483 in thermal communication with a heat source 2470 through respective heat exchangers 2484 and 2486, may result in a final temperature of the gas output by the second expansion stage being comparable with the final temperature of the gas output from the regenerator of the embodiment of Figure 24B. In another embodiment, heat exchangers 2484 and 386 may be in thermal communication with separate heat sources, not necessarily at the same temperature.

[0621] Figure 24D is a simplified diagram showing a further alternative embodiment of an apparatus according to the present invention. As with Figure 24A, this figure shows a closed system wherein a gas (here helium) is recycled.

[0622] The embodiment of Figure 24D includes two expanders and two compressors all mechanically linked together on the same common rotating shaft. The particular system of Figure 24D ultimately operates to compress carbon dioxide for storage.

[0623] Specifically, Figure 24D shows an embodiment of a system for compressing carbon-dioxide gas separated from combustion flue gases, powered exclusively by the heat available in the flue gases.

[0624] Very nearly all of the parasitic losses associated with the amine method of carbon dioxide separation from coal flue gases arise from two processes:

1) Heating of the amine fluid in order to release the absorbed CO2, and

2) Compressing the separated CO2 gas to create a fluid suitable for transport or storage

[0625] Embodiments of the present invention addresses the second category – the energy required to compress the CO_2 gas – which accounts for about 35% of all the parasitic losses, or 10% of the total power generated by a coal-fired plant that incorporates CO_2 capture. Technology in accordance with embodiments of the present invention can eliminate those losses in their entirety.

[0626] The low-grade heat in the combustion flue gases may be converted into mechanical power efficiently and inexpensively, and then that mechanical power is used to operate an equally efficient CO2 compressor.

[0627] Embodiments of the present invention utilize near-isothermal gas compression and expansion. A basic result from thermodynamics is that considerably less work is required to compress a gas if the compression is done isothermally.

[0628] When compression work is done on a gas, heat is generated. If this heat is removed continuously from the system so that the temperature remains constant during compression, the compression is said to occur isothermally. Similarly, more work can be obtained from the energy stored in compressed gas if heat is added to the system as the gas expands.

[0629] The design of Figure 24D puts two devices operating on these principles on a single shaft.

[0630] A first device is a heat engine that includes coupled compression and expansion chambers operating in an Ericsson cycle. This engine uses the temperature difference between the flue gases and the ambient air to generate mechanical work – shaft torque, in this case – with high thermal efficiency.

[0631] A second device is a near-isothermal CO2 compressor.

[0632] These devices are described in detail below, beginning with the CO2 compressor, since it illustrates certain core principles underlying embodiments in accordance with the present invention.

[0633] In order to control the ΔT (that is, the temperature rise that occurs during compression) of gaseous CO2, embodiments of the present invention take advantage of the fact that liquids are much better at absorbing heat than gases are. In fact, a given volume of oil can hold about 2000 times as much heat as the same volume of CO2 gas at the temperatures of interest. Temperature equilibration between the gas and liquid phases happens more quickly if there is a large surface area where the liquid and gas are in direct contact. By spraying small droplets of liquid into the gas prior to or during compression we provide a large interface area resulting in rapid heat exchange between the two phases.

[0634] Liquid sprays, typically of lubricating oil, have been used for many years to cool gas compressors and permit higher-than-usual compression ratios (without adequate cooling, a high compression ratio creates so much heat that thermal fatigue and damage can result). Enhancements to this process according to the present invention fall into two areas:

[0635] A first area is the computation, during operation – and adjustment as necessary – the volume of liquid spray required to maintain the ΔT of compression or expansion at the desired level. This is a particularly critical requirement for this particular application: because of the nature of the amine absorption process, different stages of the system have to operate at specific temperatures.

[0636] A second area is the use of sprays to control the ΔT both for gas compression and expansion. As discussed in connection with the heat engine component, an expansion cell is required to deliver the mechanical power obtained from the waste heat available in the flue gases.

[0637] Temperature-Controlled Compression

[0638] Figure 27 illustrates the compressor mechanism schematically. CO2 gas enters a pre-mixing chamber where oil is sprayed into the gas stream and becomes entrained with it. The gas enters at about 25^0 C, and the liquid is at about 20^0 C. Before the gas-liquid aerosol enters the compression chamber, it passes through a pulsation dampening "bottle". This allows us to spray oil continuously even though the compressor is operating in a cycle. The compression chamber itself is a conventional reciprocating piston and cylinder arrangement, suitably modified to accommodate CO2 gas.

[0639] As the piston moves towards bottom dead center, the CO2 / oil-droplet aerosol is drawn into the cylinder through one of the inlet valves (the upper valves in the diagram). The heat engine (see below) then drives the piston towards top dead center, compressing the mixture. When the desired pressure is reached (about 40 atmospheres of pressure is required to liquefy CO2 at 30^0 C), the exhaust valve opens, and the mixture is exhausted into the separator. The separator (a conventional cyclone system) extracts the oil from the CO2 and sends the CO2 to a tank or pipeline for transport. The oil, now

warmed to 30^0 C by the compression process, is sent through a heat exchanger (not shown) to return it to 20°C, ready to be sprayed into the pre-mixing chamber again.

[0640] The system illustrated in Figure 27 is double-acting. As one side of the cylinder is being compressed, the other side is being exhausted. The inlet and exhaust valves on either side open and close 180 degrees out of phase with each other.

[0641] Note that the system described in Figure 27 is a single-stage compressor. The final design may require three or four stages to keep the compression ratios within a practical range. Only a single pump and a single heat exchanger are required for all the stages, however. Typically, in a multi-stage compressor, all stages have the same compression ratio. Another proprietary feature of our system is that the compression ratios are adjusted so as to produce equal ΔT's in each stage. Balancing the ΔT's maximizes efficiency and power density.

[0642] System Architecture

[0643] The compressor with its integrated liquid spray system comprise a "cell". Such a cell can operate as a gas compressor or expander, depending on how the valves are timed. In an expansion cell, gas enters the cylinder via an inlet valve, then expands to move the piston and turn the crankshaft.

[0644] In the system of Figure 24D, the CO2 compressor is one cell, and the heat engine that drives the compressor consists of three tightly-coupled cells. All four cells share a single crankshaft.

[0645] In the three cells that form the heat engine, shown inside of the dashed-line box, the first (labeled "COMPRESSOR") operates as a compressor and the other two ("EXPANDER 1" and "EXPANDER 2") are expanders. The compressor operates in the same manner as the CO2 compressor described above, except as noted below.

[0646] The expanders operate a little differently. Gas expanding and doing work on a piston will cool. By adding heat obtained from the flue gases via heat exchangers 1 and 2, the expanders will generate enough mechanical energy in the form of crankshaft torque to power both compression cells (the heat engine's compressor and the CO2 compressor). That is, by adding heat to the system via the hot flue gases, the expanders will generate more shaft torque than is required to operate the heat engine's compressor, leading to a net positive work output. The amount of excess work generated depends on the difference in temperatures between the incoming flue gases and the ambient air.

[0647] There two expanders because there are two sources of heat available at two different temperatures. The flue gases from coal combustion, which are mostly nitrogen and only about 10% CO2, are at 150 °C, while the separated CO2 stream is about 110 °C to 120 °C. As a result, to maximize the energy obtained from the heat sources, the expansion part of the heat engine uses two heat exchangers and two regenerators, each tuned to the specific temperature available.

[0648] One beneficial effect of the heat engine is that the flue gases are cooled, a process which has to occur prior to the amine absorption process regardless. Likewise, the separated CO2 gas stream has to be cooled so that it will liquefy upon compression. As a result, these heat exchangers are a necessary part of

the conventional amine process. In our system, they do double-duty, cooling the gas streams and providing energy for the CO2 compressor.

[0649] Heat addition and rejection occur at nearly constant pressure, making the heat engine's cycle an Ericsson cycle. Ericsson engines often use a double-acting piston, with compression and expansion occurring on opposite sides. In our system, compression and expansion happen in separate cylinders.

[0650] Because the compression and expansion cells of the heat engine form a closed system, any suitable gas can be used. A good choice for the gas is helium, since its heat transfer properties permit the regenerators (often the most expensive part of this kind of heat engine) to be compact and inexpensive.

[0651] The thermodynamics of the system are complex. The key analytical result is that there is enough heat energy available in the flue gases of a coal-fired power plant to operate the entire system, including thermal and mechanical losses, and to compress all the separated CO2 without any additional energy input. That is, the entire system can be self-contained: No electricity is required to operate it.

[0652] The following provides a discussion of various embodiments of apparatuses for performing compression and expansion. However, the present invention is not limited to these specific embodiments, and other apparatuses (such as dedicated compressors and expanders) could be utilized.

[0653] ***Single-Stage System***

[0654] Figure 25 depicts an embodiment of a system 2520 of the present invention. This embodiment includes mixing a liquid with the air to facilitate heat exchange during compression and expansion, and applying the same mechanism for both compressing and expanding air. By electronic control over valve timing, high power output from a given volume of compressed air can be obtained.

[0655] As best shown in Figure 25, the energy storage system 2520 includes a cylinder device 2521 defining a chamber 2522 formed for reciprocating receipt of a piston device 2523 or the like therein. The compressed air energy storage system 2520 also includes a pressure cell 2525 which when taken together with the cylinder device 2521, as a unit, form a one stage reversible compression/expansion mechanism (i.e., a one-stage 2524). There is an air filter 2526, a liquid-air separator 2527, and a liquid tank 2528, containing a liquid 2549d fluidly connected to the compression/expansion mechanism 2524 on the low pressure side via pipes 2530 and 2531, respectively. On the high pressure side, an air storage tank or tanks 2532 is connected to the pressure cell 2525 via input pipe 2533 and output pipe 2534. A plurality of two-way, two position valves 2535-2543 are provided, along with two output nozzles 2511 and 2544. This particular embodiment also includes liquid pumps 2546 and 2547. It will be appreciated, however, that if the elevation of the liquid tank 2528 is higher than that of the cylinder device 2521, water will feed into the cylinder device by gravity, eliminating the need for pump 2546.

[0656] Briefly, atmospheric air enters the system via pipe 2510, passes through the filter 2526 and enters the cylinder chamber 2522 of cylinder device 2521, via pipe 2530, where it is compressed by the action of piston 2523, by hydraulic pressure, or by other mechanical approaches (see Figure 8). Before compression begins, a liquid mist is introduced into the chamber 2522 of the cylinder device 2521 using an atomizing nozzle 2544, via pipe 2548 from the pressure cell 2525. This liquid may be water, oil, or

any appropriate liquid 2549f from the pressure cell having sufficient high heat capacity properties. The system preferably operates at substantially ambient temperature, so that liquids capable of withstanding high temperatures are not required. The primary function of the liquid mist is to absorb the heat generated during compression of the air in the cylinder chamber. The predetermined quantity of mist injected into the chamber during each compression stroke, thus, is that required to absorb substantially all the heat generated during that stroke. As the mist coalesces, it collects as a body of liquid 2549e in the cylinder chamber 2522.

[0657] The compressed air/liquid mixture is then transferred into the pressure cell 2525 through outlet nozzle 2511, via pipe 2551. In the pressure cell 2525, the transferred mixture exchanges the captured heat generated by compression to a body of liquid 2549f contained in the cell. The air bubbles up through the liquid and on to the top of the pressure cell, and then proceeds to the air storage tank 2532, via pipe 2533.

[0658] The expansion cycle is essentially the reverse process of the compression cycle. Air leaves the air storage tank 2532, via pipe 2534, bubbling up through the liquid 2549f in the pressure cell 2525, enters the chamber 2522 of cylinder device 2521, via pipe 2555, where it drives piston 2523 or other mechanical linkage. Once again, liquid mist is introduced into the cylinder chamber 2522, via outlet nozzle 2544 and pipe 2548, during expansion to keep a substantially constant temperature in the cylinder chamber during the expansion process. When the air expansion is complete, the spent air and mist pass through an air-liquid separator 2527 so that the separated liquid can be reused. Finally, the air is exhausted to the atmosphere via pipe 2510.

[0659] The liquid 2549f contained in the pressure cell 2525 is continually circulated through the heat exchanger 2552 to remove the heat generated during compression or to add the heat to the chamber to be absorbed during expansion. This circulating liquid in turn selectively exchanges heat with either a heat sink 2560 or a heat source 2562, via a switch 2564 and heat exchanger 2512. The circulating liquid is conveyed to and from that external heat exchanger 2512 via pipes 2553 and 2554 communicating with internal heat exchanger 2552.

[0660] The apparatus of Figure 25 further includes a controller/processor 2594 in electronic communication with a computer-readable storage device 2592, which may be of any design, including but not limited to those based on semiconductor principles, or magnetic or optical storage principles. Controller 2594 is shown as being in electronic communication with a universe of active elements in the system, including but not limited to valves, pumps, chambers, nozzles, and sensors. Specific examples of sensors utilized by the system include but are not limited to pressure sensors (P) 2598, 2574, and 2584, temperature sensors (T) 2570, 2578, 2586, and 2576, humidity sensor (H) 2596, volume sensors (V) 2582 and 2572, and flow rate sensor 2580.

[0661] As described in detail below, based upon input received from one or more system elements, and also possibly values calculated from those inputs, controller/processor 2594 may dynamically control operation of the system to achieve one or more objectives, including but not limited to maximized or controlled efficiency of conversion of stored energy into useful work; maximized, minimized, or

controlled power output; an expected power output; an expected output speed of a rotating shaft in communication with the piston; an expected output torque of a rotating shaft in communication with the piston; an expected input speed of a rotating shaft in communication with the piston; an expected input torque of a rotating shaft in communication with the piston; a maximum output speed of a rotating shaft in communication with the piston; a maximum output torque of a rotating shaft in communication with the piston; a minimum output speed of a rotating shaft in communication with the piston; a minimum output torque of a rotating shaft in communication with the piston; a maximum input speed of a rotating shaft in communication with the piston; a maximum input torque of a rotating shaft in communication with the piston; a minimum input speed of a rotating shaft in communication with the piston; a minimum input torque of a rotating shaft in communication with the piston; or a maximum expected temperature difference of air at each stage.

[0662] The tables previously described in conjunction with Figures 12A-C describes steps in an embodiment of a compression cycle for a single-stage system utilizing liquid mist to effect heat exchange. During a compression cycle, the heat exchanger of the pressure cell is not in thermal communication with a heat source, but it is in thermal communication with a heat sink.

[0663] The corresponding expansion cycle is shown in the tables described above in connection with Figures 13A-C. During an expansion cycle, the heat exchanger of the pressure cell is in thermal communication with a heat source.

[0664] Use of the same mechanism for both compression and expansion is not required by the present invention, but can serve to reduce system cost, size, and complexity.

[0665] ***Multi-Stage System***

[0666] When a larger compression/expansion ratio is required than can be accommodated by the mechanical or hydraulic approach by which mechanical power is conveyed to and from the system, then multiple stages should be utilized. A multi-stage compressed air energy storage system 2620 with three stages (i.e., first stage 2624a, second stage 2624b and third stage 2624c) is illustrated in schematic form in Figure 26. Systems with more or fewer stages are constructed similarly. Note that, in all figures that follow, when the letters a, b, and c are used with a number designation (e.g. 2625a), they refer to elements in an individual stage of a multi-stage energy storage system 2620. Figure 26 shows that the various stages may selectively be in communication with heat source 2650 or heat sink 2652 through a switch 2654.

[0667] A multi-stage embodiment of an apparatus having compression and expansion functions performed by the same elements, can also benefit from the use of a regenerator device. Figure 26A shows a simplified view of an alternative embodiment of a system 2650 that is similar to the system of Figure 26, except it includes a regenerator 2652. Regenerator 2652 is in selective fluid communication with conduit 2633 between the highest pressure stage 2624c and the compressed gas storage unit 2632.

[0668] When the system is operating in a compression mode, the stages 2624a-c are in thermal communication with heat sink 2652 through switch 2654. Valves 2654 and 2656 are configured to flow the inlet air directly to the first stage 2624a, avoiding conduit 2620.

[0669] When the system is operating in an expansion mode, valves 2654 and 2656 are configured to place conduit 2620 in thermal communication with the output of the first stage 2624a. In addition, the stages 2624a-c are in thermal communication with heat source 2650 through switch 2654.

[0670] As a result of this configuration, during expansion gas that is flowing out of the storage unit 2632 through regenerator 2652 is warmed by receipt of thermal energy from the nearby flowing gas that is outlet from the lowest pressure stage 2624a. In particular, the gas outlet from the lowest pressure stage 2624a has been warmed by exposure to the heat source for three consecutive stages. This exchange of thermal energy between the flowing gases in the regenerator serves to enhance the energy output from expansion of the compressed gas. In turn, the gas that had been outlet from the lowest pressure stage is cooled to ambient temperature before being released to the atmosphere.

[0671] While the embodiments of Figures 26 and 26A show all of the stages of a multi-stage device as being in thermal communication with the same temperature or heat source, this is not required by the present invention. Figure 26B shows an alternative embodiment of a system 2680 in which different stages are in selective communication with different heat sources having different temperatures. In the specific embodiment of Figure 26B, a lowest pressure stage 2624a and a second stage 2624b are selectively in thermal communication with first heat source 2682 and heat sink 2684 through first switch 2683. The final stage 2624c and the storage unit 32 are selectively in thermal communication with heat sink 2684 and second heat source 2685 through second switch 2686.

[0672] Embodiments such as are shown in Figure 26B, may allow the extracting of energy from secondary temperature differences. For example, intense heat from an industrial process may be reduced to ambient temperature through a succession of cooling steps, each having a temperature closer to ambient than the previous step.

[0673] Moreover, during compression and/or expansion the various stages of multi-stage apparatuses according to embodiments of the present invention, may experience different changes in temperature. Configurations such as are shown in Figure 26B may allow more precise matching of such stages, to heat sources with specific temperatures, thereby allowing most efficient extraction of energy available from the various temperatures.

[0674] Figure 24D shows an embodiment featuring a dedicated compressor and expander elements, which utilizes multiple expansion stages that are each in communication with different heat sources.

[0675] In summary, various embodiments of the present invention may have one or more of the following elements in common.

[0676] 1. Selective thermal communication with the heat source during expansion cycles.

[0677] 2. Near-isothermal expansion and compression of air, with the required heat exchange effected by a liquid phase in high-surface-area contact with the air.

[0678] 3. A reversible mechanism capable of both compression and expansion of air.

[0679] 4. Electronic control of valve timing so as to obtain the highest possible work output from a given volume of compressed air.

[0680] As described in detail above, embodiments of systems and methods for storing and recovering energy according to the present invention are particularly suited for implementation in conjunction with a host computer including a processor and a computer-readable storage medium. Such a processor and computer-readable storage medium may be embedded in the apparatus, and/or may be controlled or monitored through external input/output devices. Figure 20 is a simplified diagram of a computing device for processing information according to an embodiment of the present invention. This diagram is merely an example, which should not limit the scope of the claims herein. One of ordinary skill in the art would recognize many other variations, modifications, and alternatives. Embodiments according to the present invention can be implemented in a single application program such as a browser, or can be implemented as multiple programs in a distributed computing environment, such as a workstation, personal computer or a remote terminal in a client server relationship.

[0681] Figure 20 shows computer system 2010 including display device 2020, display screen 2030, cabinet 2040, keyboard 2050, and mouse 2070. Mouse 2070 and keyboard 2050 are representative "user input devices." Mouse 2070 includes buttons 2080 for selection of buttons on a graphical user interface device. Other examples of user input devices are a touch screen, light pen, track ball, data glove, microphone, and so forth. Figure 20 is representative of but one type of system for embodying the present invention. It will be readily apparent to one of ordinary skill in the art that many system types and configurations are suitable for use in conjunction with the present invention. In a preferred embodiment, computer system 2010 includes a Pentium™ class based computer, running Windows™ XP™ or Windows 7™ operating system by Microsoft Corporation. However, the apparatus is easily adapted to other operating systems and architectures by those of ordinary skill in the art without departing from the scope of the present invention.

[0682] As noted, mouse 2070 can have one or more buttons such as buttons 2080. Cabinet 2040 houses familiar computer components such as disk drives, a processor, storage device, etc. Storage devices include, but are not limited to, disk drives, magnetic tape, solid-state memory, bubble memory, etc. Cabinet 2040 can include additional hardware such as input/output (I/O) interface cards for connecting computer system 2010 to external devices external storage, other computers or additional peripherals, further described below.

[0683] Figure 20A is an illustration of basic subsystems in computer system 2010 of Figure 20. This diagram is merely an illustration and should not limit the scope of the claims herein. One of ordinary skill in the art will recognize other variations, modifications, and alternatives. In certain embodiments, the subsystems are interconnected via a system bus 2075. Additional subsystems such as a printer 2074, keyboard 2078, fixed disk 2079, monitor 2076, which is coupled to display adapter 2082, and others are shown. Peripherals and input/output (I/O) devices, which couple to I/O controller 2071, can be connected to the computer system by any number of approaches known in the art, such as serial port 2077. For example, serial port 2077 can be used to connect the computer system to a modem 2081,

which in turn connects to a wide area network such as the Internet, a mouse input device, or a scanner. The interconnection via system bus allows central processor 2073 to communicate with each subsystem and to control the execution of instructions from system memory 2072 or the fixed disk 2079, as well as the exchange of information between subsystems. Other arrangements of subsystems and interconnections are readily achievable by those of ordinary skill in the art. System memory, and the fixed disk are examples of tangible media for storage of computer programs, other types of tangible media include floppy disks, removable hard disks, optical storage media such as CD-ROMS and bar codes, and semiconductor memories such as flash memory, read-only-memories (ROM), and battery backed memory.

[0684] Figure 21 is a schematic diagram showing the relationship between the processor/controller, and the various inputs received, functions performed, and outputs produced by the processor controller. As indicated, the processor may control various operational properties of the apparatus, based upon one or more inputs.

[0685] An example of such an operational parameter that may be controlled is the timing of opening and closing of a valve allowing the inlet of air to the cylinder during an expansion cycle, as described above in connection with Figures 13A-C.

[0686] Specifically, during step 1 of the expansion cycle, a pre-determined amount of air V_0, is added to the chamber from the pressure cell, by opening valve 37 for a controlled interval of time. This amount of air V_0 is calculated such that when the piston reaches the end of the expansion stroke, a desired pressure within the chamber will be achieved.

[0687] In certain cases, this desired pressure will approximately equal that of the next lower pressure stage, or atmospheric pressure if the stage is the lowest pressure stage or is the only stage. Thus at the end of the expansion stroke, the energy in the initial air volume V_0 has been fully expended, and little or no energy is wasted in moving that expanded air to the next lower pressure stage.

[0688] To achieve this goal, valve 37 is opened only for so long as to allow the desired amount of air (V_0) to enter the chamber, and thereafter in steps 3-4, valve 37 is maintained closed. In certain embodiments, the desired pressure within the chamber may be within 1 PSI, within 5 PSI, within 10 PSI, or within 20 PSI of the pressure of the next lower stage.

[0689] In other embodiments, the controller/processor may control valve 37 to admit an initial volume of air that is greater than V_0. Such instructions may be given, for example, when greater power is desired from a given expansion cycle, at the expense of efficiency of energy recovery.

[0690] Timing of opening and closing of valves may also be carefully controlled during compression. For example in the steps 1 and 2 of the table corresponding to the addition of mist and compression, the valve 38 between the cylinder device and the pressure cell remains closed, and pressure builds up within the cylinder.

[0691] In conventional compressor apparatuses, accumulated compressed air is contained within the vessel by a check valve, that is designed to mechanically open in response to a threshold pressure. Such

use of the energy of the compressed air to actuate a check valve, detracts from the efficiency of recovery of energy from the air for performing useful work.

[0692] By contrast, embodiments of the present invention may utilize the controller/processor to precisely open valve 38 under the desired conditions, for example where the built-up pressure in the cylinder exceeds the pressure in the pressure cell by a certain amount. In this manner, energy from the compressed air within the cylinder is not consumed by the valve opening process, and efficiency of energy recovery is enhanced. Embodiments of valve types that may be subject to electronic control to allow compressed air to flow out of a cylinder include but are not limited to pilot valves, cam-operated poppet valves, rotary valves, hydraulically actuated valves, and electronically actuated valves.

[0693] While the timing of operation of valves 37 and 38 of the single stage apparatus may be controlled as described above, it should be appreciated that other valves may be similarly controlled.

[0694] Another example of a system parameter that can be controlled by the processor, is the amount of liquid introduced into the chamber. Based upon one or more values such as pressure, humidity, calculated efficiency, and others, an amount of liquid that is introduced into the chamber during compression or expansion, can be carefully controlled to maintain efficiency of operation. For example, where an amount of air greater than V_0 is inlet into the chamber during an expansion cycle, additional liquid may need to be introduced in order to maintain the temperature of that expanding air within a desired temperature range.

[0695] Variations on the specific embodiments describe above, are possible. For example, in some embodiments, a plurality of pistons may be in communication with a common chamber.

[0696] And while the above embodiments have shown the heat exchanger as being in contact with the liquid portion of the pressure cell, this is not required by the present invention. In accordance with alternative embodiments, the heat exchanger could be in contact with gas portions of the pressure cell, or with both gas and liquid portions of the pressure cell. In embodiments lacking a dedicated pressure cell (for example as shown in Figure 10), a heat exchanger could be in contact with gas or liquid present in or flowing into the cylinder, and remain within the scope of the present invention.

[0697] And while the above embodiments have shown a dedicated pressure cell, a multistage apparatus may not include a separate pressure cell. For example, in the embodiment of Figure 10, the stages are connected directly together through a heat exchanger, rather than through a pressure cell. The relative phases of the cycles in the two stages must be carefully controlled so that when Stage 1 is performing an exhaust step, Stage 2 is performing an intake step (during compression). When Stage 2 is performing an exhaust step, Stage 1 is performing an intake step (during expansion).

[0698] The timing is controlled so the pressures on either side of heat exchanger 10024 are substantially the same when valves 37 and 10058 are open. Liquid for spray nozzle 44 is supplied from an excess water in cylinder 22 by opening valve 10036 and turning on pump 10032. Similarly, liquid for spray nozzle 10064 is supplied from an excess water in cylinder 10046 by opening valve 10038 and turning on pump 10034. Such precise timing during operation may be achieved with the operation of a

controller/processor that is communication with a plurality of the system elements, as has been previously described.

[0699] 1. A system configured to recover energy from compressed gas, the system comprising:

a heat exchanger in thermal communication with a heat source; and

a first expander comprising,

a chamber having a first moveable member disposed therein, the chamber in selective liquid communication with a liquid supply; and

a first pressure cell in thermal communication with the heat exchanger and in selective fluid communication with the chamber, wherein the chamber is configured to receive liquid from the liquid supply as compressed gas from the first pressure cell expands within the chamber to move the first piston.

[0700] 2. The system of claim 1 wherein:

the first expander comprises a compressor-expander in selective fluid communication with a compressed gas storage unit; and

the heat exchanger is configured to be in thermal communication with the heat source when the compressor-expander is configured to operate as an expander, and the heat exchanger is configured to not be in thermal communication with the heat source when the compressor-expander is configured to operate as a compressor.

[0701] 3. The system of claim 2 wherein the heat exchanger is configured to be in thermal communication with a heat sink when the compressor-expander is configured to operate as a compressor.

[0702] 4. The system of claim 1 further comprising a switch allowing selective thermal communication between the heat exchanger and the heat source.

[0703] 5. The system of claim 4 wherein the heat source comprises solar energy and the switch comprises a diurnal cycle.

[0704] 6. The system of claim 4 wherein the switch allows selective thermal communication between the heat source and the compressed gas storage unit.

[0705] 7. The system of claim 1 further comprising a physical linkage between the first moveable member and a generator.

[0706] 8. The system of claim 7 wherein the physical linkage comprises a mechanical linkage, a hydraulic linkage, or a pneumatic linkage.

[0707] 9. The system of claim 7 wherein:

the expander comprises a dedicated expander; and

the system further comprises a dedicated compressor in communication with the physical linkage and configured to receive gas output from the dedicated expander.

[0708] 10. The system of claim 9 wherein the dedicated compressor is in thermal communication with a heat sink.

[0709] 11. The system of claim 9 further comprising a regenerator configured to thermally expose gas output from the dedicated expander to gas output from the dedicated compressor.

[0710] 12. The system of claim 1 further comprising a controller in communication with a valve configured to admit a quantity of gas into the chamber during an expansion cycle.

[0711] 13. The system of claim 12 wherein:

the quantity of gas is configured to produce approximately ambient pressure or a pressure approximately equal to a next lower pressure stage, when the moveable member is at an end of an expansion stroke.

[0712] 14. The system of claim 1 wherein:

the expander comprises a compressor-expander configured to flow air compressed by the moveable member in the chamber into the pressure cell through a valve; and

the system further comprises a controller in communication with the valve to open the valve when a desired pressure is reached in the chamber during a compression cycle.

[0713] 15. A method of extracting energy from a temperature difference comprising:

providing a compressed gas at a first temperature;

placing a heat source at a second temperature into thermal communication with the compressed gas that is expanding within an expander that is coupled to a linkage; and

extracting power in mechanical, pneumatic, or hydraulic form from the linkage.

[0714] 16. The method of claim 15 wherein the compressed gas is provided from a storage unit.

[0715] 17. The method of claim 16 wherein the heat source comprises solar energy .

[0716] 18. The method of claim 17 wherein the heat source is placed into selective thermal communication with the compressed gas according to a diurnal cycle.

[0717] 19. The method of claim 16 further comprising selectively placing a second heat source at a third temperature into thermal communication with the storage unit.

[0718] 20. The method of claim 15 wherein the compressed gas is provided from a compressor coupled to the linkage.

[0719] 21. The method of claim 20 wherein the compressor compresses gas output by the expander.

[0720] 22. The method of claim 21 wherein the compressed gas comprises helium.

[0721] 23. The method of claim 21 wherein the gas is output by the expander at a baseline pressure substantially greater than ambient pressure, such that the gas comprises a dense gas having high heat capacity.

[0722] 24. The method of claim 21 further comprising thermally exposing in a regenerator, the gas that is output from the expander, to the compressed gas that is output by the compressor.

[0723] 25. The method of claim 20 further comprising placing gas output by the expander, into fluid communication with a second expander that is in thermal communication with a second heat source at a third temperature.

[0724] 26. The method of claim 15 further comprising introducing fluid into the compressed gas within the expander.

[0725] The use of expansion of a liquid-gas aerosol for cooling purposes, is discussed in U.S. Provisional Patent Application No. 61/320,150, which is incorporated by reference in its entirety herein

for all purposes. Embodiments of the present invention relate to compressed gas energy storage and recovery systems which can operate using such an aerosol refrigeration cycle.

[0726] In particular, embodiments of such cooling systems operate by compressing and expanding air nearly isothermally, using a water spray to facilitate heat exchange. Because in certain embodiments the refrigerant comprises an air-water aerosol, the system can operate efficiently and reliably without greenhouse gas (GHG) emissions.

[0727] Embodiments of the present invention allow air to be compressed and expanded nearly isothermally, with only a small temperature change. This follows from a basic result in thermodynamics: less work is required to compress a gas if the heat generated by the compression process is removed during the compression stroke. Similarly, more work can be obtained from expanding air if heat is added during expansion.

[0728] Liquid water exhibits a volumetric heat capacity about five thousand times greater than the heat capacity of atmospheric air. Embodiments of the present invention spray fine water droplets into compression and expansion chambers. This allows a small amount of water spray to absorb the great majority of the heat generated, resulting in nearly isothermal operation.

[0729] Certain embodiments utilize a reciprocating piston mechanism to perform compression and expansion. Such a reciprocating piston mechanism allows the spraying of liquid directly into the compression or expansion chambers. Systems in which liquid droplets can be introduced in the form of a spray directly into an expansion chamber are described in U.S. Nonprovisional Patent Application No. 12/701,023, which is incorporated by reference in its entirety herein for all purposes. U.S. Provisional Patent Application No. 61/306,122 describes alternative embodiments in which the liquid spray can be introduced into a mixing chamber located upstream of the chamber in which gas undergoes expansion. This provisional patent application is also incorporated by reference in its entirety herein for all purposes.

[0730] In addition, the rate and timing of the liquid spray can be controlled. This permits varying of the flow rate and ΔT independently, thereby optimizing efficiency and comfort.

[0731] Coupling of a near-isothermal compressor and expander allows an aerosol refrigeration cycle to be run. In certain embodiments, this allows the use of only air and water as working fluids. Other embodiments may employ other combinations of gas and liquid, such as helium and lubricating oil. Use of gas liquid combinations delivers a high coefficient of performance (COP) without GHG emissions.

[0732] An aerosol refrigeration cycle according to embodiments of the present invention can operate efficiently despite not moving much heat via phase change. This efficiency is achieved by extracting work of the expanding gas and reinvesting that work into compression.

[0733] Figure 28 is a simplified diagram illustrating a refrigeration cycle according to one embodiment of the present invention. Specifically, the motor drives the compressor piston upward from bottom dead center (BDC), compressing the air in the cylinder, which starts off at 150 psi.

[0734] As the piston travels toward top dead center (TDC), a pump sprays water into the cylinder, keeping the temperature rise to about 10°F. When the pressure in the cylinder reaches about 500 psi, the exhaust valve opens, sending the compressed air-water droplet mixture into an air-water separator.

[0735] The separated water passes through a heat exchanger, rejecting the heat gained during compression to the outside. The air passes through a cross-flow heat exchanger on its way to the expander cylinder, where it transfers some of its heat to air traveling in the other direction (from the expander to the compressor).

[0736] The cooled air begins to enter the expander cylinder at TDC, where, once again, water is sprayed into the cylinder. The expanding air drives the piston towards BDC, turning the shaft and providing additional power to move the compressor cylinder.

[0737] The air-water mix passes through another separator, and the separated water passes through the cool side heat exchanger, drawing heat from inside the building. The separated air returns to the compressor via the cross-flow heat exchanger, completing the cycle.

[0738] A optional benefit of this design is that, if an air storage tank is placed at point A in FIG. 28, the compressor can be run during periods of low electricity demand to fill the tank. The cooling effect achieved by expansion can then be delivered at periods of peak demand (for example between 7AM-7PM on weekdays), with no additional electricity usage.

[0739] Embodiments of the present invention are not limited to the particular temperatures described above. For example, Figure 28A shows an alternative embodiment of an aerosol refrigeration cycle comprising the following steps 1-6.

[0740] 1. Cool gas (at ~65°F) expands in a reciprocating expander, drawing heat from a liquid spray entrained within. Both leave the expander at ~40°F. The work extracted is reinvested into the compressor and the pumps.

[0741] 2. The cool aerosol is separated from the gas, collected into a liquid stream, and routed to a heat exchanger, cooling the intake airstream, to ~55°F, and cycled back to be sprayed into expanding gas once more.

[0742] 3. The cool liquid-free gas is passed through a counter-flow heat exchanger, countering a flow of warm liquid-free gas. The cool gas is heated at constant pressure to slightly above ambient temperature (~120°F).

[0743] 4. Warm liquid is sprayed into the warm gas, and is then compressed. The compressor is driven in part by the expander, and in part by an electric motor. The heat of compression is drawn into the aerosol. Both leave the compressor at ~130°F.

[0744] 5. Warm liquid is separated from the gas, collected into a stream, and routed to the heat exchanger, which cools by dumping the heat to the ambient environment, and is then recycled to be sprayed into the compressing gas once again.

[0745] 6. The warm liquid-free gas is passed through the counter-flow heat exchanger, countering the flow of cool liquid-free gas. The warm gas is cooled at constant pressure to slightly below air conditioner

exhaust temperature (to ~50°F). The gas flows into the expander, is entrained with cool liquid, and the cycle continues.

[0746] Certain embodiments may achieve a COP exceeding 4 at reasonable cost. Control of parasitic losses may aid in improving the efficiency of the device. For example, the efficiency of the compressor and expander mechanisms can exceed 79% roundtrip if the efficiency of the electrical motor and drive together is 95%. This level of efficiency is achievable if high-quality mechanical components are used, and if the temperature change during compression, expansion, and across all the heat exchangers can be kept to between about 10°F to 20°F.

[0747] Embodiments of the present invention utilize an approach that is similar in certain respects to a gas refrigeration cycle with a turbine expander, such as may be used in an air-cycle cooler in jet aircraft. For example, much of the cooling occurs via transfer of sensible heat rather than latent heat.

[0748] Embodiments of an aerosol refrigeration cycle according to the present invention, however, differ from such a conventional gas refrigeration cycle in certain respects. For example, use of an aerosol in the compression and expansion processes, and the rejection of the heat via the liquid component of the aerosol, allows for a more compact and inexpensive system.

[0749] Specifically, an air-water aerosol carries more heat per unit volume at a given pressure than the same volume of air. This allows more heat to be pumped per stroke than could be achieved by a conventional (adiabatic) compressor / expander, using a high compression ratio, while tightly controlling ΔT to desired efficient ranges.

[0750] The low, tightly controlled ΔT yields high thermodynamic efficiencies. The great amount of heat pumped per stroke diminishes the effect of mechanical and fluid efficiency losses. The superior heat carrying and heat transfer capability of the water component of air-water aerosols, lowers the cost and bulk of the required heat exchanger.

[0751] Achieving near-isothermal compression and expansion in an aerosol refrigeration cycle according to embodiments of the present invention, may depend upon development of spray nozzles that will introduce water into the compression and expansion chambers at the necessary mass flow and droplet size. Such spray systems can be characterized using particle velocity imaging and computational fluid dynamics (CFD) analysis.

[0752] Figure 29 shows the velocity field for a hollow-cone nozzle that provides very uniform droplet distribution, appropriate for a high compression ratio. Figure 30 shows a CFD simulation of a fan nozzle, which provides a high mass flow.

[0753] As mentioned above, the coefficient of performance (COP) is one quantifiable characteristic of refrigeration systems. Conventional commercial air conditioning units may operate at a COP of 3.5.

[0754] Embodiments of systems utilizing an aerosol refrigeration cycle may target a COP of about 4. However, the exact value of COP actually delivered depends upon a number of values.

[0755] An example of such a computation of COP is now provided in connection with the following mathematical expressions (1)-(14), with Figure 31 showing a system diagram for an aerosol refrigeration cycle, and with Figure 32 showing a temperature-entropy diagram for a aerosol refrigeration cycle,

[0756] The work done during the isothermal compression process between points 1 and 2 is given as:

$$W_{1\to 2}\left(\frac{kJ}{kg}\right) = P_1 V_1 \ln\left(\frac{P_2}{P_1}\right) = RT_1 \ln\left(\frac{P_2}{P_1}\right) \quad (1)$$

[0757] The compressor efficiency is defined as the ratio of work done during an isothermal compression process to the actual work done.

$$\eta_{Compressor} = \frac{W_{1\to 2}}{W_{1\to 2'}} \quad (2)$$

[0758] The work during the isothermal expansion process is given as:

$$W_{3\to 4}\left(\frac{kJ}{kg}\right) = P_4 V_4 \ln\left(\frac{P_3}{P_4}\right) = RT_4 \ln\left(\frac{P_3}{P_4}\right) \quad (3)$$

[0759] The expander efficiency is given as the ratio of actual work extracted to the work extracted in an isothermal process.

$$\eta_{Expander} = \frac{W_{3\to 4'}}{W_{3\to 4}} \quad (4)$$

[0760] The heat extracted from the room by an isothermally operating expander is given as:

$$Q_{3\to 4}\left(\frac{kJ}{kg}\right) = W_{3\to 4} = RT_4 \ln\left(\frac{P_3}{P_4}\right) \quad (5)$$

[0761] The COP can now be calculated as:

$$COP = \frac{Q_{3\to 4'}}{W_{1\to 2} - W_{3\to 4}} \quad (6)$$

[0762] Specific parameters for one embodiment of a system are provided as follows:

$T_1 = 75^{\circ}F = 297K$; $T_2 = 75^{\circ}F = 297K$, $T_3 = 55^{\circ}F = 286K$, $T_4 = 55^{\circ}F = 286K$.

[0763] The pressure ratio is taken to be 2.71.

$$\frac{P_2}{P_1} = \frac{P_3}{P_4} = 2.71 \quad (7)$$

[0764] Work done in isothermal compression is now given as:

$$W_{1\to 2} = RT_1 \ln\left(\frac{P_2}{P_1}\right) = 0.287 \times 297 \times \ln(2.71) = 84.98 \frac{kJ}{kg} \quad (8)$$

[0765] Assuming thermal efficiency of expansion is 98% as well as total mechanical and leakage efficiency 95.6%, the actual work done is:

$$W_{1\to 2'} = \frac{W_{1\to 2}}{\eta_{thermal} \times \eta_{mech}} = \frac{84.98}{0.956 \times 0.98} = 90.7 \frac{kJ}{kg} \quad (9)$$

[0766] Work extracted from isothermal expansion is given as:

$$W_{3\to4} = RT_4 \ln\left(\frac{P_3}{P_4}\right) = 0.287\times 286\times \ln(2.71) = 81.83\frac{kJ}{kg} \quad (10)$$

[0767] Assuming thermal efficiency of expansion is 92.7% as well as mechanical and leakage efficiency of 95.6%, actual work extracted is given as:

$$W_{3\to4'} = \eta_{Expander} W_{3\to4} = 0.927\times 0.956\times 81.83 = 72.52\frac{kJ}{kg} \quad (11)$$

[0768] Heat extracted from the room is given by:

$$Q_{3\to4} = W_{3\to4} = 81.83\frac{kJ}{kg} \quad (12)$$

[0769] The COP is now given as:

$$COP == \left(\frac{Q_{3\to4}}{W_{1\to2'} - W_{3\to4'}}\right)\times \eta_{motor}\times \eta_{drive} = \left(\frac{81.83}{90.7 - 72.52}\right)\times 0.95\times 0.97 = 4.15 \quad (13)$$

[0770] Figure 32A is a power flow graph illustrating work and heat flowing through an embodiment of an aerosol refrigeration cycle. Power values are normalized to the electric power flowing in from the grid.

[0771] First, 1 kw of electric power is processed through a motor drive with an efficiency of 97%, followed by a motor with an efficiency of 95%. This progresses through a motor shaft, which loses 0.5% of its power as friction. This shaft drives the compressor.

[0772] The compressor may have several possible sources of inefficiency, including but not limited to spray, leakage, mechanical, and thermal. For the mass ratio of 10:1 water to helium, spray losses come to only 1% of the work cycled through the system.

[0773] Mechanical and leakage losses of a reciprocating compressor or expander, are typically around 95%. However, the friction losses are concentrated in the valve actuators, the orifice friction and pipe losses and the piston rings.

[0774] These friction losses do not scale up linearly as the pressure mounts, and valve/pipe losses are low for light gases like helium. With operation at an internally pressurize of about 25 bar, with a pressure ratio of 2.71, it may be possible to maintain these mechanical efficiencies collectively above 95.6%.

[0775] Thermal efficiencies are also shown in the embodiment of Figure 32A. Expansion efficiencies are 92.7% and compression efficiencies are 98% for the temperatures shown, when the temperature difference between the gas and liquid stays below about 5° F.

[0776] A size of a system utilizing an aerosol refrigeration cycle according an embodiment of the present invention, can be based upon a number of factors. Certain components of the system, such as reciprocating pistons, pumps, heat exchangers, and an AC motor, are standard devices that can be used either off-the-shelf or with relatively simple modifications. This allows construction of devices and prototypes of convenient sizes.

[0777] For example, a one-ton system running at 1200 RPM and 150 psi could utilize a 1 hp electric motor, two reciprocating pistons of 350cc total displacement, and fan-cooled heat exchangers with an interfacial surface area of about 15 square meters. These components may be fit into a desired form-factor (for example 1.5' x 1' x 9").

[0778] In particular embodiments, the components in a system can reasonably be expected to operate with little or no maintenance for a target specification of 10+ years. One factor affecting lifetime may involve the use of water in the compressor and expander cylinders, as water can be corrosive to many metals. Water-tolerant materials may also be useful in the constructions of elements such as sliding seals, valve seats, wear surfaces, and fasteners. Embodiments in accordance with the present invention may use aluminum components, nickel-polymer coatings, and/or PTFT sliding components, in order to improve the lifetime of elements exposed to water.

[0779] In summary, embodiments of the present invention may potential benefits as compared with conventional approaches to refrigeration. For example, conventional refrigeration apparatuses may have hot and cold temperatures nearly fixed as a function of compression ratio, leading to an overshoot of ΔT beyond that which is actually needed, and leading to potentially significant thermodynamic losses. By contrast, embodiments of the present invention are able to control ΔT independently of load and compression ratio, allow avoidance of this particularly significant efficiency loss.

[0780] Another potential advantage that may be offered by systems according to the present invention, is the capture of energy that is otherwise wasted in conventional systems. For example, a typical air conditioner performs expansion through a nozzle (for example the expansion valve). Energy is released during this process that is wasted. This may be because the relative efficiency bonus for vapor compression is small - a COP bonus of about 1.

[0781] By contrast, the relative efficiency bonus for aerosol cycles is much larger - a COP bonus of 4 or more. Accordingly, embodiments of the present invention are able to efficiently compress aerosols, exchange heat, and generate mechanical work from expansion of the aerosol. Given good mechanical and thermodynamic design, to deliver a high COP.

[0782] Still another potential advantage of refrigeration systems according to embodiments of the present invention, is the avoidance of GHGs. In particular, the components of an air-water aerosol or helium-oil aerosol do not exhibit greenhouse properties, and hence systems according to the present invention may be environmentally advantageous as compared with conventional systems utilizing HCFCs or other working fluids.

[0783] The following claims relate to aerosol cooling.

[0784] 1. A cooling method comprising:

introducing a liquid spray to exchange heat with a gas expanding within an expansion chamber;

separating the liquid from the gas following expansion;

flowing the separated liquid to a heat exchanger to provide cooling;

flowing gas from the expansion chamber to a compression chamber through a counter flow heat exchanger while compressed gas from the compression chamber is being flowed to the expansion chamber through the counter flow heat exchanger; and

introducing a second liquid spray to exchange heat with the compressed gas within the compression chamber.

[0785] 2. The refrigeration method of claim 1 wherein:

the gas comprises air; and

the first liquid spray and the second liquid spray comprise water.

[0786] 3. The refrigeration method of claim 1 wherein:

the heat exchange between the liquid spray and the gas in the expansion chamber results in near-isothermal expansion, and

the heat exchange between the second liquid spray and the gas in the compression chamber result in near-isothermal compression.

[0787] 4. The refrigeration method of claim 1 wherein:

as a result of the first liquid spray, the expansion chamber experiences a temperature change of about 20°F or less during expansion; and

as a result of the second liquid spray, the compression chamber experiences a temperature change of about 20°F or less during compression.

[0788] 5. A method comprising:

controlling a temperature of an environment by exposure to a liquid separated from a first aerosol resulting from expansion of a second aerosol that is formed by spraying first liquid droplets into a first chamber in which compressed gas is undergoing expansion; and

flowing a gas separated from the first aerosol through a counter flow heat exchanger as compressed gas is also being flowed through the counter flow heat exchanger, the compressed gas separated from a third aerosol resulting from compression of a fourth aerosol that is formed by spraying second liquid droplets into a second chamber in which gas is being compressed.

[0789] 6. The method of claim 5 wherein:

the gas comprises air; and

the first liquid spray droplets and the second liquid spray droplets comprise water.

[0790] 7. The method of claim 5 wherein:

expansion of the second aerosol to form the first aerosol occurs under near-isothermal conditions by transfer of heat from the first liquid droplets; and

compression of the fourth aerosol to form the third aerosol occurs under near-isothermal conditions by absorption of heat by the second liquid droplets.

[0791] 8. The method of claim 5 wherein:

expansion of the second aerosol to form the first aerosol occurs with a temperature change of about 20°F or less; and

compression of the fourth aerosol to form the third aerosol occurs with a temperature change of about 20°F or less.

[0792] 9. A refrigeration apparatus comprising:

a first cylinder having a first member disposed therein to define an expansion chamber, the first member moveable in response to gas expanding within the expansion chamber;

a second cylinder having a second member disposed therein to define a compression chamber, the second member moveable to compress gas within the compression chamber;

a physical linkage between the first moveable member and the second moveable member;

a motor in communication with the physical linkage;

a spray system configured to introduce liquid droplets to form a first aerosol in the expansion chamber and to introduce liquid droplets to form a second aerosol in the compression chamber;

a first gas/liquid separator having an inlet in fluid communication with an outlet of the first cylinder;

a second gas/liquid separator having an inlet in fluid communication with an outlet of the second cylinder;

a first heat exchanger in liquid communication with a first outlet of the first gas/liquid separator;

a second heat exchanger in liquid communication with a first outlet of the second gas/liquid heat exchanger; and

a counter flow heat exchanger configured to flow gas received from the first gas/liquid separator to the compression chamber, and configured to flow gas received from the second gas/liquid separator to the expansion chamber, wherein the first heat exchanger serves as a refrigeration node to cool a temperature of an environment.

[0793] 10. The refrigeration apparatus of claim 9 wherein the liquid comprises water and the gas comprises air.

[0794] 11. The refrigeration apparatus of claim 9 wherein the first member comprises a first reciprocating piston and the second member comprises a second reciprocating piston.

[0795] 12. The refrigeration apparatus of claim 11 wherein the physical linkage comprises a rotatable shaft.

[0796] 13. The refrigeration apparatus of claim 9 further comprising:

a first pump configured to flow liquid from the first gas/liquid separator to the first heat exchanger; and

a second pump configured to flow liquid from the second gas/liquid separator to the second heat exchanger.

[0797] 14. The refrigeration apparatus of claim 9 wherein the spray system comprises a hollow cone spray nozzle.

[0798] 15. The refrigeration apparatus of claim 9 wherein the spray system comprises a fan spray nozzle.

[0799] In summary, embodiments in accordance with the present invention relate to the extraction of energy from a temperature difference. In particular embodiments, energy from a heat source may be extracted through the expansion of compressed air. In certain embodiments, a storage unit containing compressed gas is in fluid communication with a compressor-expander. Compressed gas received from the storage unit, expands in the compressor-expander to generate power. During this expansion, the compressor-expander is in selective thermal communication with the heat source through a heat exchanger, thereby enhancing power output by the expanding gas. In alternative embodiments, where the heat source is continuously available, a dedicated gas expander may be configured to drive a dedicated compressor. Such embodiments may employ a closed system utilizing gas having high heat capacity properties, for example helium or a high density gas resulting from operation of the system at an elevated baseline pressure.

[0800] One source of compressed air is wind. It is known that the efficiency of power generation from wind, improves with increased height of elevation of the fan blades of the wind turbine from the ground. Such elevation, however, requires provision of a large, fixed structure of sufficient mechanical strength to safely support the relatively heavy structure of the turbine, including the blades, under a variety of wind conditions.

[0801] The expense of constructing and maintaining such a support structure is an inherent expense of the system, detracting from the overall profitability of the wind generation device. Accordingly, there is a need in the art for novel structures and methods for supporting a wind turbine.

[0802] An energy storage and recovery system employs air compressed utilizing power from an operating wind turbine. This compressed air is stored within one or more chambers of a structure supporting the wind turbine above the ground. By functioning as both a physical support and as a vessel for storing compressed air, the relative contribution of the support structure to the overall cost of the energy storage and recovery system may be reduced, thereby improving economic realization for the combined turbine/support apparatus. In certain embodiments, expansion forces of the compressed air stored within the chamber may be relied upon to augment the physical stability of a support structure, further reducing material costs of the support structure.

[0803] An embodiment of a method in accordance with the present invention comprises storing compressed gas generated from power of an operating wind turbine, within a chamber defined by walls of a structure supporting the wind turbine.

[0804] An embodiment of an apparatus in accordance with the present invention comprises a support structure configured to elevate a wind turbine above the ground, the support structure comprising walls defining a chamber configured to be in fluid communication with a gas compressor operated by the wind turbine, the chamber also configured to store gas compressed by the compressor.

[0805] An embodiment of an apparatus in accordance with the present invention comprises an energy storage system comprising a wind turbine, a gas compressor configured to be operated by the wind turbine, and a support structure configured to elevate the wind turbine above the ground, the support structure comprising walls defining a chamber in fluid communication with the gas compressor, the

chamber configured to store gas compressed by the gas compressor. A generator is configured to generate electrical power from expansion of compressed gas flowed from the chamber.

[0806] As previously described, a wind turbine operates to capture wind energy more effectively the higher it is elevated above the ground. In particular, wind speed is roughly proportional to the seventh root of the height. Power is proportional to the cube of the wind speed, and also proportional to the area of the wind turbine. A greater height, H, could theoretically allow a larger diameter turbine, giving area proportional to H2 and power proportional to Hx, with x perhaps as great as 2 3/7. The support structure is thus a necessary element of the system. According to embodiments of the present invention, this support structure can perform the further duty of housing one or more chambers or vessels configured to receive and store compressed air generated from output of the wind turbine.

[0807] Such a support structure for a wind turbine is initially well suited for this task, as it is typically formed from an exterior shell that encloses an interior space. This structure provides the desired mechanical support for the wind turbine at the top, while not consuming the large amount of material and avoiding the heavy weight that would otherwise be associated with an entirely solid supporting structure.

[0808] Figure 33 shows a simplified schematic view of an embodiment of a system in accordance with the present invention. Specifically, system 3300 comprises a nacelle 3301 that is positioned on top of support tower 3306. Nacelle 3301 includes a wind turbine 3302 having rotatable blades 3304.

[0809] Nacelle 3301 may be in rotatable communication (indicated by arrow 3320) with support tower 3306 through joint 3311, thereby allowing the blades of the wind turbine to be oriented to face the direction of the prevailing wind. An example of a wind turbine suitable for use in accordance with embodiment of the present invention is the model 1.5 sle turbine available from the General Electric Company of Fairfield, Connecticut.

[0810] Upon exposure to wind 3308, the blades 3304 of the turbine 3302 turn, thereby converting the power of the wind into energy that is output on linkage 3305. Linkage 3305 may be mechanical, hydraulic, or pneumatic in nature.

[0811] Linkage 3305 is in turn in physical communication with a motor/generator 3314 through gear system 3312 and linkage 3303. Gear system 3312 is also in physical communication with compressor/expander element 3316 through linkage 3307. Linkages 3303 and 3307 may be mechanical, hydraulic, or pneumatic in nature.

[0812] The gear system may be configured to permit movement of all linkages at the same time, in a subtractive or additive manner. The gear system may also be configured to accommodate movement of fewer than all of the linkages. In certain embodiments, a planetary gear system may be well-suited to perform these tasks.

[0813] Compressed gas storage chamber 3318 is defined within the walls 3318a of the support tower. Compressor/expander 3316 is in fluid communication with storage chamber 3318 through conduit 3309.

[0814] Several modes of operation of system 3300 are now described. In one mode of operation, the wind is blowing, and demand for power on the grid is high. Under these conditions, substantially all of the energy output from rotation of the blades of the turbine, is communicated through linkages 3305 and

3303 and gear system 3312 to motor/generator 3314 that is acting as a generator. Electrical power generated by motor/generator 3314 is in turn communicated through conduit 3313 to be output onto the grid for consumption. The compressor/expander 3316 is not operated in this mode.

[0815] In another mode of operation, the wind is blowing but demand for power is not as high. Under these conditions, a portion of the energy output from rotation of the blades of the turbine is converted into electrical power through elements 3305, 3312, 3303, and 3314 as described above.

[0816] Moreover, some portion of the energy output from the operating turbine is also communicated through linkages 3305 and 3307 and gear system 3312 to operate compressor/expander 3316 that is functioning as a compressor. Compressor/expander 3316 functions to intake air, compress that air, and then flow the compressed air into the storage chamber 3318 located in the support tower. As described below, energy that is stored in the form of this compressed air can later be recovered to produce useful work.

[0817] Specifically, in another mode of operation of system 3300, the compressor/expander 3316 is configured to operate as an expander. In this mode, compressed air from the storage chamber is flowed through conduit 3309 into the expander 3316, where it is allowed to expand. Expansion of the air drives a moveable element that is in physical communication with linkage 3307. One example of such a moveable element is a piston that is positioned within a cylinder of the compressor/expander 3316.

[0818] The energy of actuated linkage 3307 is in turn communicated through gear system 3312 and linkage 3303 to motor/generator 3314 that is acting as a generator. Electrical power generated by motor/generator as a result of actuation of linkage 3303, may in turn be output to the power grid through conduit 3313.

[0819] In the mode of operation just described, the wind may or may not be blowing. If the wind is blowing, the energy output by the compressor/expander 3316 may be combined in the gear system with the energy output by the turbine 3312. The combined energy from these sources (wind, compressed air) may then be communicated by gear system 3312 through linkage 3303 to motor/generator 3314.

[0820] In still another mode of operation, the wind may not be blowing and power demand is low. Under these conditions, the compressor/expander 3316 may operate as a compressor. The motor/generator 3314 operates as a motor, drawing power off of the grid to actuate the compressor/expander 3316 (functioning as a compressor) through linkages 3303 and 3307 and gear system 3312. This mode of operation allows excess power from the grid to be consumed to replenish the compressed air stored in the chamber 3318 for consumption at a later time.

[0821] Embodiments of systems which provide for the efficient storage and recovery of energy as compressed gas, are described in the U.S. Provisional Patent Application No. 61/221,487 filed June 29, 2009, and in the U.S. nonprovisional patent application No. 12/695,922 filed January 28, 2010, both of which are incorporated by reference in their entireties herein for all purposes. However, embodiments of the present invention are not limited to use with these or any other particular designs of compressed air storage and recovery systems. Also incorporated by reference in its entirety herein for all purposes, is the provisional patent application no. 61/294,396, filed January 12, 2010.

[0822] As previously mentioned, certain embodiments of the present invention may favorably employ a planetary gear system to allow the transfer of mechanical energy between different elements of the system. In particular, such a planetary gear system may offer the flexibility to accommodate different relative motions between the linkages in the various modes of operation described above.

[0823] Figure 33A shows a simplified top view of one embodiment of a planetary gear system which could be used in embodiments of the present invention. Figure 33AA shows a simplified cross-sectional view of the planetary gear system of Figure 33A taken along line 33A-33A'.

[0824] Specifically, planetary gear system 3350 comprises a ring gear 3352 having a first set of teeth 3354 on an outer periphery, and having a second set of teeth 3356 on an inner portion. Ring gear 3352 is engaged with, and moveable in either direction relative to, three other gear assemblies.

[0825] In particular, first gear assembly 3340 comprises side gear 3342 that is positioned outside of ring gear 3352, and is fixed to rotatable shaft 3341 which serves as a first linkage to the planetary gear system. The teeth of side gear 3342 are in mechanical communication with the teeth 3354 located on the outer periphery of the ring gear. Rotation of shaft 3341 in either direction will translate into a corresponding movement of ring gear 3352.

[0826] A second gear assembly 3358 comprises a central (sun) gear 3360 that is positioned inside of ring gear 3352. Central gear 3360 is fixed to rotatable shaft 3362 which serves as a second linkage to the planetary gear system.

[0827] Third gear assembly 3365 allows central gear 3360 to be in mechanical communication with the second set of teeth 3356 of ring gear 3352. In particular, third gear assembly 3365 comprises a plurality of (planet) gears 3364 that are in free rotational communication through respective pins 3367 with a (planet carrier) plate 3366. Plate 3366 is fixed to a third shaft 3368 serving as a third linkage to the planetary gear system.

[0828] The planetary gear system 3350 of Figures 33A-33AA provides mechanical communication with three rotatable linkages 3341, 3362, and 3368. Each of these linkages may be in physical communication with the various other elements of the system, for example the wind turbine, a generator, a motor, a motor/generator, a compressor, an expander, or a compressor/expander.

[0829] The planetary gear system 3350 permits movement of all of the linkages at the same time, in a subtractive or additive manner. For example where the wind is blowing, energy from the turbine linkage may be distributed to drive both the linkage to a generator and the linkage to a compressor. In another example, where the wind is blowing and demand for energy is high, the planetary gear system permits output of the turbine linkage to be combined with output of an expander linkage, to drive the linkage to the generator.

[0830] Moreover, the planetary gear system is also configured to accommodate movement of fewer than all of the linkages. For example, rotation of shaft 3341 may result in the rotation of shaft 3362 or vice-versa, where shaft 3368 is prevented from rotating. Similarly, rotation of shaft 3341 may result in the rotation of only shaft 3368 and vice-versa, or rotation of shaft 3362 may result in the rotation of only shaft 3368 and vice-versa. This configuration allows for mechanical energy to be selectively

communicated between only two elements of the system, for example where the wind turbine is stationary and it is desired to operate a compressor based upon output of a motor.

[0831] Returning to Figure 33, certain embodiments of compressed gas storage and recovery systems according to the present invention may offer a number of potentially desirable characteristics. First, the system leverages equipment that may be present in an existing wind turbine system. That is, the compressed air energy storage and recovery system may utilize the same electrical generator that is used to output power from the wind turbine onto the grid. Such use of the generator to generate electrical power both from the wind and from the stored compressed air, reduces the cost of the overall system.

[0832] Another potential benefit associated with the embodiment of Figure 33 is improved efficiency of power generation. Specifically, the mechanical energy output by the rotating wind turbine blades, is able to be communicated in mechanical form to the compressor without the need for conversion into another form (such as electrical energy). By utilizing the output of the power source (the wind turbine) in its native mechanical form, the efficiency of transfer of that power into compressed air may be enhanced.

[0833] Still another potential benefit associated with the embodiment of Figure 33 is a reduced number of components. In particular, two of the elements of the system perform dual functions. Specifically, the motor/generator can operate as a motor and as a generator, and the compressor/expander can operate as a compressor or an expander. This eliminates the need for separate, dedicated elements for performing each of these functions.

[0834] Still another potential benefit of the embodiment of Figure 33 is relative simplicity of the linkages connecting various elements with moving parts. Specifically, in the embodiment of Figure 33, the turbine, the gear system, the motor/generator, and the compressor/expander are all located in the nacelle. Such a configuration offers the benefit of compatibility with a rotational connection between a nacelle and the underlying support structure. In particular, none of the linkages between the elements needs to traverse the rotating joint, and thus the linkages do not need to accommodate relative motion between the nacelle and support structure. Such a configuration allows the design and operation of those linkages to be substantially simplified.

[0835] According to alternative embodiments, however, one or more of the gear system, the compressor/expander, and the motor/generator may be positioned outside of the nacelle. Figure 34 shows a simplified view of such an alternative embodiment of a system 3400 in accordance with the present invention.

[0836] In this embodiment, while the turbine 3402 is positioned in the nacelle 3401, the gear system 3412, compressor/expander 3416, and motor generator 3414 are located at the base of the tower 3406. This placement is made possible by the use of an elongated linkage 3405 running between turbine 3402 and gear system 3412. Elongated linkage 3405 may be mechanical, hydraulic, or pneumatic in nature.

[0837] The design of the embodiment of Figure 34 may offer some additional complexity, in that the linkage 3405 traverses rotating joint 3411 and accordingly must be able to accommodate relative motion of the turbine 3402 relative to the gear system 3412. Some of this complexity may be reduced by

considering that linkage 3405 is limited to communicating energy in only one direction (from the turbine to the gear system).

[0838] Moreover, the cost of complexity associated with having linkage 3405 traverse rotating joint 3411, may be offset by the ease of access to the motor/generator, compressor/expander, and gear system. Specifically, these elements include a large number of moving parts and are subject to wear. Positioning these elements at the base of the tower (rather than at the top) facilitates access for purposes of inspection and maintenance, thereby reducing cost.

[0839] Still other embodiments are possible. For example, while Figure 34 shows the gear system, motor/generator, and compressor/expander elements as being housed within the support structure, this is not required. In other embodiments, one or more of these elements could be located outside of the support structure, and still communicate with the wind turbine through a linkage extending from the support tower. In such embodiments, conduits for compressed air and for electricity, and mechanical, hydraulic, or pneumatic linkages could provide for the necessary communication between system elements.

[0840] Embodiments of the present invention are not limited to the particular elements described above. For example, while Figures 1 and 2 show compressed gas storage system comprising compressor/expander elements and motor/generator elements having combined functionality, this is not required by the present invention.

[0841] Figure 35 shows an alternative embodiment a system 3500 according to the present invention, utilizing separate, dedicated compressor 3550, dedicated expander 3516, dedicated motor 3554, and dedicated generator 3514 elements. Such an embodiment may be useful to adapt an existing wind turbine to accommodate a compressed gas storage system.

[0842] Specifically, pre-existing packages for wind turbines may feature the dedicated generator element 3514 in communication with the turbine 3502 through gear system 3512 and linkages 3503 and 3505. Generator 3514, however, is not designed to also exhibit functionality as a motor.

[0843] To such an existing configuration, a dedicated expander 3516, a dedicated compressor 3550, a dedicated motor 3554, linkages 3507 and 3573, and conduit 3570 may be added to incorporate a compressed gas storage system. In one embodiment, a dedicated expander 3516 may be positioned in the nacelle 3501 in communication with the gear system 3512 through linkage 3507. Dedicated expander 3516 is in fluid communication with a top portion of the compressed gas storage chamber 3518 defined within the walls 3506a of support tower 3506 through conduit 3509.

[0844] Dedicated compressor 3550 and a dedicated motor 3554 are readily included, for example at or near the base of the support tower, thereby facilitating access to these elements. Dedicated compressor 3550 is in fluid communication with storage chamber 3518 through conduit 3570, and in physical communication with dedicated motor 3554 through linkage 3572. Dedicated motor 3554 is in turn in electronic communication with the generator and/or grid to receive power to operate the compressor to replenish the supply of compressed gas stored in the chamber 3518.

[0845] As shown in Figure 35, this embodiment may further include an optional elongated mechanical, hydraulic, or pneumatic linkage 3574 extending between the gear system 3512 in the nacelle 3501, and the dedicated compressor 3550 located outside of the nacelle 3501. Such a linkage would allow the dedicated compressor to be directly operated by the output of the turbine, avoiding losses associated with converting mechanical into electrical form by the dedicated generator, and re-converting the electrical power back into mechanical form by the dedicated motor in order to operate the compressor.

[0846] Figure 35A shows a simplified view of yet another embodiment of a system in accordance with the present invention. In the embodiment of the system 3580 of Figure 35A, only the turbine 3582, linkage 3583, and dedicated compressor 3586 elements are located in the nacelle 3581 that is positioned atop support tower 3596. Dedicated compressor 3586 is in communication with the turbine through linkage 3583 (which may be mechanical, hydraulic, or pneumatic), which serves to drive compression of air by the dedicated compressor. Compressed air output by the dedicated compressor is flowed through conduit 3589 across joint 3591 into chamber 3598 present in the support tower 3596.

[0847] The remaining elements are positioned outside of the nacelle, either in the support tower, or alternatively outside of the support tower. For example, a dedicated expander or expander/compressor 3588 is in communication with the chamber 3598 defined within walls 3596a, to receive compressed air through conduit 3593. Element 3588 is configured to allow expansion of the compressed air, and to communicate energy recovered from this expansion through linkage 3592 to generator or generator/motor 3584. Element 3584 in turn operates to generate electricity that is fed onto the grid.

[0848] The embodiment of Figure 35A can also function to store energy off of the grid. Where element 3584 is a generator/motor and element 3588 is an expander/compressor, element 3584 may operate as a motor to drive element 3588 operating as a compressor, such that air is compressed and flowed into chamber 3598 for storage and later recovery.

[0849] The embodiment of Figure 35A offers a potential advantage in that power is transported from the top to the bottom of the tower utilizing the chamber, without requiring a separate elongated linkage or conduit. Another possible advantage of the embodiment of Figure 35A is a reduction in the weight at the top of the tower. While this embodiment may incur losses where the mechanical power output of the turbine is converted first into compressed air and then back into mechanical power for driving the generator, such losses may be offset by a reduction in weight at the top of the tower, allowing the tower to be higher and to access more wind power.

[0850] The present invention is not limited to a support structure having any particular shape. In the particular embodiments shown in Figures 33 and 34, the support structure exhibits a cross-sectional shape that varies along its length. For example, the support structure 3306 is wide at its base, and then tapers to a point at which it meets the wind turbine. By allocating material to where it will best serve the supporting function, such a design minimizes materials and reduces cost.

[0851] However, the present invention also encompasses supporting structures having other shapes. For example, Figure 36 shows a support structure 3600 comprising a hollow tube having a circular or

elliptical cross section that is substantially uniform. The walls 3600a of this hollow tube 3600 in turn define a chamber 3602 for storing compressed gas. While possibly utilizing more mass, such a tube is a simpler structure that is employed for a various applications in many other industries. Accordingly, such a tube is likely available at a relatively low price that may offset any greater material cost.

[0852] Still further alternative embodiments are possible. For example, in certain embodiments a support structure may be designed to take advantage of the forces exerted by the compressed air stored therein, in order to impart additional stability to the support structure.

[0853] Thus, Figure 37 shows an embodiment wherein the support structure 3700 comprises a portion 3706a having thinner walls 3706b exhibiting less inherent strength than those of the prior embodiments. This reduced strength may be attributable to one or more factors, including but not limited to, use of a different design or shape for the support, use of a reduced amount of material in the support, or use of a different material in the support.

[0854] According to embodiments of the present invention, however, any reduction in the inherent strength of the support structure 3706 may be offset by expansion forces 3724 exerted by the compressed air 3726 that is contained within the chamber 3718. Specifically, in a manner analogous to the stiffening of walls of an inflated balloon, the expansion force of the compressed air may contribute additional strength to the support structure. This expansion effect is shown grossly exaggerated in Figure 37, for purposes of illustration.

[0855] One possible application for such a design, employs a support structure that is fabricated from a material that is capable of at least some flexion, for example carbon fiber. In such an embodiment, expansion forces from the compressed air within the chamber of a flexible support member, may act against the walls of the chamber, thereby stiffening it and contributing to the structural stability of that support. Such a support structure could alternatively be formed from other materials, and remain within the scope of the present invention.

[0856] A design incorporating carbon fiber could offer even further advantages. For example, carbon fiber structures may exhibit enhanced strength in particular dimensions, depending upon the manner of their fabrication. Thus, a carbon fiber support structure could be fabricated to exhibit strength and/or flexion in particular dimensions, for example those in which the expansion forces of the compressed air are expected to operate, and/or dimension in which the support is expected to experience external stress (e.g. a prevailing wind direction).

[0857] Of course, a design taking advantage of expansion forces of the stored compressed air, would need to exhibit sufficient inherent strength in the face of expected (and unexpected) changes in the quantity of compressed air stored therein, as that compressed air is drawn away and allowed to expand for energy recovery. Nevertheless, expansion forces associated with minimal amounts of compressed air remaining within the support structure, could impart sufficient stability to support structure to reduce its cost of manufacture and maintenance.

[0858] 1. A method comprising:

storing compressed gas generated from power of an operating wind turbine, within a chamber defined by walls of a structure supporting the wind turbine.

[0859] 2. The method of claim 1 further comprising operating a compressor from output of the wind turbine to generate the compressed gas.

[0860] 3. The method of claim 1 further comprising:

flowing at least a portion of the compressed air from the chamber; and

allowing the portion of the flowed compressed gas to expand and generate power.

[0861] 4. The method of claim 3 wherein the portion of the compressed gas is flowed from the chamber to an expander in physical communication with a generator.

[0862] 5. The method of claim 1 wherein an expansion force of the compressed gas imparts stability to the support structure.

[0863] 6. The method of claim 5 wherein the walls comprise a flexible material.

[0864] 7. An apparatus comprising:

a support structure configured to elevate a wind turbine above the ground, the support structure comprising walls defining a chamber configured to be in fluid communication with a gas compressor operated by the wind turbine, the chamber also configured to store gas compressed by the compressor.

[0865] 8. The apparatus of claim 7 wherein the support structure comprises a hollow tube.

[0866] 9. The apparatus of claim 8 wherein the hollow tube exhibits a cross-section that is substantially constant along its length.

[0867] 10. The apparatus of claim 7 further comprising a nacelle in rotational communication with the support structure through a joint, the nacelle housing the turbine.

[0868] 11. The apparatus of claim 10 wherein the nacelle further houses a gear system, a first physical linkage between the gear system and the turbine, a generator, a second physical linkage between the generator and the gear system, an expander in fluid communication with the chamber, and a third physical linkage between the expander and the gear system, such that the first, second, and third physical linkages do not traverse the joint.

[0869] 12. The apparatus of claim 11 wherein the generator comprises a motor/generator configured to operate the gas compressor.

[0870] 13. The apparatus of claim 11 wherein the gas compressor and the expander are combined as a compressor/expander.

[0871] 14. The apparatus of claim 11 wherein the gear system comprises a planetary gear system.

[0872] 15. The apparatus of claim 10 further comprising a gear system, a generator, a first physical linkage between the generator and the gear system, an expander in fluid communication with the chamber, a second physical linkage between the expander and the gear system, and a third physical linkage between the turbine and the gear system, wherein the gear system, the generator, the first physical linkage, the expander, and the second physical linkage are located outside the nacelle, and wherein the third physical linkage traverses the joint.

[0873] 16. The apparatus of claim 15 wherein the generator comprises a motor/generator, and the expander comprises a compressor/expander.

[0874] 17. The apparatus of claim 15 wherein the generator comprises a dedicated generator, and the expander comprises a dedicated expander.

[0875] 18. The apparatus of claim 15 wherein the gear system comprises a planetary gear system.

[0876] 19. The apparatus of claim 10 wherein:

the nacelle houses a gear system, a dedicated generator, a first physical linkage between the dedicated generator and the gear system, a dedicated expander in fluid communication with the chamber, a second physical linkage between the dedicated expander and the gear system, and a third physical linkage between the turbine and the gear system; and

the apparatus further comprises,

a dedicated compressor in fluid communication with the storage chamber and in physical communication with a dedicated motor through a fourth linkage, wherein the dedicated compressor, the dedicated motor, and the fourth linkage are located outside the nacelle.

[0877] 20. The apparatus of claim 19 further comprising a fifth linkage between the gear system and the dedicated compressor.

[0878] 21. The apparatus of claim 19 wherein the gear system comprises a planetary gear system.

[0879] 22. The apparatus of claim 10 wherein:

the compressor comprises a dedicated compressor housed by the nacelle, the compressor in physical communication with the turbine through a first linkage and in fluid communication with the chamber across the joint by a first conduit; and

the system further comprises,

an expander located proximate to a base of the support structure, the expander in fluid communication with the chamber and in communication with a generator through a second physical linkage.

[0880] 23. The apparatus of claim 22 wherein the expander comprises an expander/compressor, and the generator comprises a generator/motor.

[0881] 24. An energy storage system comprising:

a wind turbine;

a gas compressor configured to be operated by the wind turbine;

a support structure configured to elevate the wind turbine above the ground, the support structure comprising walls defining a chamber in fluid communication with the gas compressor, the chamber configured to store gas compressed by the gas compressor; and

a generator configured to generate electrical power from expansion of compressed gas flowed from the chamber.

[0882] 25. The system of claim 24 further comprising a nacelle in rotational communication with the support structure through a joint, the nacelle housing the wind turbine, the generator, and an expander in fluid communication with the chamber and in physical communication with the generator.

[0883] In summary, embodiments of energy storage and recovery systems employ air compressed utilizing power from an operating wind turbine. This compressed air is stored within one or more chambers of a structure supporting the wind turbine above the ground. By functioning as both a physical support and as a vessel for storing compressed air, the relative contribution of the support structure to the overall cost of the energy storage and recovery system may be reduced, thereby improving economic realization for the combined turbine/support apparatus. In certain embodiments, expansion forces of the compressed air stored within the chamber, may be relied upon to augment the physical stability of a support structure, further reducing material costs of the support structure.

[0884] In certain embodiments, storage and recovery of energy from compressed gas may be enhanced utilizing one or more techniques, applied alone or in combination. One technique introduces a mist of liquid droplets to a dedicated chamber positioned upstream of a second chamber in which gas compression and/or expansion is to take place. In some embodiments, uniformity of the resulting liquid-gas mixture may be enhanced by interposing a pulsation damper bottle between the dedicated mixing chamber and the second chamber, allowing continuous flow through the mixing chamber. Another technique utilizes valve configurations actuable with low energy, to control flows of gas to and from a compression and/or expansion chamber. The valve configuration utilizes inherent pressure differentials arising during system operation, to allow valve actuation with low consumption of energy.

[0885] Figure 38 shows a simplified block diagram of one embodiment of an energy storage and recovery system 3801 in accordance with the present invention. Figure 38 shows compressor/expander 3802 in selective fluid communication with a compressed air storage unit 3803. Motor/generator 3804 is in selective communication with compressor/expander 3802.

[0886] In a first mode of operation, energy is stored in the form of compressed air, and motor/generator 3804 operates as a motor. Motor/generator 3804 receives power from an external source, and causes compressor/expander 3802 to function as a compressor. Compressor/expander 3802 receives uncompressed air, compresses the air in a chamber 3802a utilizing a moveable element 3802b such as a piston, and flows the compressed air to the storage unit.

[0887] In a second mode of operation, energy stored in the compressed air is recovered, and compressor/expander 3802 operates as an expander. Compressor/expander 3802 receives compressed air from the storage unit 3803, and then allows the compressed air to expand in the chamber 3802a. This expansion drives the moveable member 3802b, which is in communication with motor/generator 3804 that is functioning as a generator. Power generated by motor/generator 3804 can in turn be input onto a power grid and consumed.

[0888] The processes of compressing and decompressing the air as described above, may experience some thermal and mechanical losses. However, a compression process will occur with reduced thermal loss if it proceeds with a minimum increase in temperature, and an expansion process will occur with reduced thermal loss if it proceeds with a minimum decrease in temperature.

[0889] Accordingly, embodiments of the present invention may introduce a liquid during the compression and/or expansion processes. An elevated heat capacity of the liquid relative to the gas,

allows the liquid to receive heat from the air during compression, and to transfer heat to the air during expansion. This transfer of energy to and from the liquid may be enhanced by a large surface area of the liquid, if the liquid is introduced as a mist within the compressing or expanding air.

[0890] The conditions (such as droplet size, uniformity of droplet distribution, liquid volume fraction, temperature, and pressure) of the liquid/gas mixture that is introduced during compression and/or expansion, may be important in determining the transfer of energy to and from the gas. However, due to the inherent nature of compression and expansion, the conditions such as temperature, volume, and pressure are likely changing as those processes occur.

[0891] Accordingly, in order to achieve greater control over the liquid/gas mixture, and to ensure consistency and reproducibility of the thermal properties of that mixture during compression and expansion, embodiments of the present invention utilize a separate mixing chamber 3805 that is located upstream of the second chamber in which expansion and compression are taking place. This separate mixing chamber 3805 is in selective fluid communication with chamber 3802a through valve 3807. In this manner, a liquid-gas mixture prepared under relatively stable conditions in the mixing chamber 3805, is flowed into the compression/expansion chamber 3802a in order to absorb heat from, or transfer heat to, gas within the compression/expansion chamber.

[0892] While the embodiment described above utilizes a single apparatus that is configured to operate as a gas compressor and as a gas expander, this is not required by the present invention. Alternative embodiments could utilize separate, dedicated elements for performing compression and expansion, and remain within the scope of the present invention.

[0893] For example, Figure 39 shows a simplified diagram of an apparatus 3900 for performing gas compression in accordance with an embodiment of the present invention. A stream of gas 3902 enters through an inlet pipe 3904 and flows into a mixing chamber 3906.

[0894] Liquid spray 3908 is sprayed into the mixing chamber 3906 through manifold 3911 in fluid communication with a plurality of nozzles 3910, and becomes entrained with the gas stream 3902. Owing to the presence and the configuration of the mixing chamber 3906 (for example its dimensions and/or the number and arrangement of spray orifices or nozzles), the liquid spray 3908 becomes evenly distributed within the gas to form a uniform mixture, such as a gas-liquid aerosol, prior to encountering the compression chamber 3912.

[0895] In certain embodiments, it may be desirable to create a mixture having liquid droplets of an average diameter of about 20 um or less. In some embodiments, formation of a mixture having droplets of the appropriate size may be facilitated by the inclusion of a surfactant in the liquid. One example of a surfactant which may be used is octylphenoxypolyethoxyethanol, CAS #: 9002-93-1 and known as Triton X-100.

[0896] Before the gas-liquid aerosol enters the compression chamber 3912, it passes through another feature, the pulsation damper bottle 3914. This volume of this pulsation damper bottle is significantly larger than the volume of the compression chamber, and in general at least 10x the volume of that chamber.

[0897] The pulsation damper bottle 3914 also exhibits a width dimension (w) that is different from that of the inlet 3916 and outlet 3918 to the bottle 3914. The difference in dimension between the bottle and its inlet and outlet, creates a succession of impedance mismatches for any acoustic waves attempting to travel from the inlet valves 3920a-b of the compression chamber 3912, back to the mixing chamber 3906. In particular, these impedance mismatches disrupt unwanted changes in fluid movement in the mixing chamber, that would otherwise disrupt the uniformity of the gas-liquid mixture being created therein.

[0898] Specifically, such unwanted fluid movement can arise because of cyclic operation of the compressor, with inlet valves 3920a and 3920b alternatively being opened and closed, as is discussed in detail below in connection with Figures 39A-B. This cyclic valve operation can give rise to pulsations, that would potentially cause nonuniformities in the gas-liquid mixture being created in the mixing chamber 3906.

[0899] By imposing the pulsation damper bottle between the valves and the mixing chamber, embodiments according to the present invention can suppress these pulsations.

[0900] The compression chamber 3912 comprises an arrangement including a reciprocating piston 3924 within cylinder 3913. The piston is in physical communication with an energy source (not shown).

[0901] The compression chamber 3912 is in selective fluid communication with inlet conduit 3950 and with outlet conduit 3952 through valves 3920a-b and 3922a-b, respectively. One particular configuration of these valves that may be particularly suited for use in an apparatus combining compression and expansion functions, is described in detail below in connection with Figure 41.

[0902] Operation of the compressor is now described in detail in connection with Figures 39A-B. Figure 39A shows that as the piston moves towards bottom dead center, the liquid-gas mixture is drawn into a left portion 3913a of the cylinder through inlet valve 3920b. At the same time, the outlet valve 3922a is opened, exhausting into the separator 3930 the liquid-gas mixture that was compressed in the lower portion of the chamber in the previous stroke. Inlet valve 3920a is closed during this piston stroke.

[0903] Figure 39B shows the next stroke, where inlet valve 3920b is closed and the piston is driven toward the top dead center. This compresses the liquid-gas mixture in the left portion 3913a of the cylinder. When a desired pressure is reached, the exhaust valve 3922b opens, and the compressed mixture is exhausted into the separator 3930. During the piston stroke shown in Figure 39B, inlet valve 3920a is opened to admit additional gas-liquid mixture for compression in the next cycle. Outlet valve 3922a is closed during this piston stroke.

[0904] Separator 3930 serves to separate the liquid from the gas-liquid mixture. Examples of separator types which may be used in accordance with embodiments of the present invention include but are not limited to cyclone separators, centrifugal separators, gravity separators, and demister separators (utilizing a mesh type coalescer, a vane pack, or another structure).

[0905] While the above figures show the separator as a single element, it may comprise one or more apparatuses arranged in series. Thus the separator could employ a first structure designed to initially remove bulk amounts of liquid from the flowed gas-liquid mixture. An example of such a structure is a

chamber having a series of overlapping plates or baffles defining a serpentine path for the flowed mixture, and offering a large surface area for the coalescence of water. This initial structure could be followed up in series by another structure, such as a cyclone separator, that is designed to remove smaller amounts of liquid from the mixture.

[0906] The compressed gas is then flowed from the separator to a compressed gas storage unit 3932 through valve 3933.

[0907] Liquid recovered by separator 3930 collects in the liquid reservoir 3934. This liquid is circulated by pump 3936 through heat exchanger 3938 to nozzles 3910, where it is again injected into the incoming gas stream as a spray.

[0908] The system illustrated in Figure 39 is double-acting. In particular, as a liquid-gas mixture on one side of the cylinder is being compressed, the liquid-gas mixture on the other side of the cylinder is being exhausted. Thus, the inlet valves 3920a-b and the exhaust valves 3922a-b on either side of the cylinder, are configured to open and close 180 degrees out of phase with each other. It is this repeated opening and closing of valves that can give rise to the acoustic waves that are suppressed by the pulsation damper bottle.

[0909] The apparatus of Figure 39 further includes a controller/processor 3996 in electronic communication with a computer-readable storage device 3994, which may be of any design, including but not limited to those based on semiconductor principles, or magnetic or optical storage principles. Controller 3996 is shown as being in electronic communication with a universe of active elements in the system, including but not limited to valves, pumps, chambers, nozzles, and sensors. Specific examples of sensors utilized by the system include but are not limited to pressure sensors (P), temperature sensors (T), volume sensors (V), and a humidity sensor (H) located at the inlet of the system.

[0910] As described in detail below, based upon input received from one or more system elements, and also possibly values calculated from those inputs, controller/processor 296 may dynamically control operation of the system to achieve one or more objectives, including but not limited to maximized or controlled efficiency of conversion of stored energy into useful work; maximized, minimized, or controlled power output; an expected power output; an expected output speed of a rotating shaft in communication with the piston; an expected output torque of a rotating shaft in communication with the piston; an expected input speed of a rotating shaft in communication with the piston; an expected input torque of a rotating shaft in communication with the piston; a maximum output speed of a rotating shaft in communication with the piston; a maximum output torque of a rotating shaft in communication with the piston; a minimum output speed of a rotating shaft in communication with the piston; a minimum output torque of a rotating shaft in communication with the piston; a maximum input speed of a rotating shaft in communication with the piston; a maximum input torque of a rotating shaft in communication with the piston; a minimum input speed of a rotating shaft in communication with the piston; a minimum input torque of a rotating shaft in communication with the piston; or a maximum expected temperature difference of air at each stage.

[0911] While the above example describes the use of a piston, other types of moveable elements could be utilized and still remain within the scope of the present invention. Examples of alternative types of apparatuses which could be utilized include but are not limited to screw compressors, multi-lobe blowers, vane compressors, gerotors, and quasi-turbines.

[0912] Features of various possible embodiments of mixing chambers are now described. A goal of the mixing chamber is to inject liquid into a flow of gas, that results in a uniform gas-liquid mixture. A mixing chamber can be designed to achieve such a uniform gas-liquid mixture utilizing one or more features.

[0913] For example, one manner of injection of liquid into a gas may be accomplished by flowing liquid through one or more orifices formed in a wall of a conduit along which the gas is flowing. The cross-sectional dimensions and orientation of such orifices relative to the gas flow, may be used to determine the characteristics of the resulting gas-liquid mixture.

[0914] Alternatively, liquid may be introduced by spraying through a nozzle structure designed to impose changes on the properties (velocity, pressure change) of the injected liquid in a manner that is calculated to result in the desired mixture. Certain nozzle designs may utilize forms of energy in addition to a pressure change, to achieve desired spray characteristics. The application of ultrasonic energy may result in the formation of particularly fine droplets having small diameters, for example in the range of between about 5-10 um.

[0915] Figure 39CA shows an overhead view of a mixing chamber 3950, along the direction of flow of the gas, showing possible trajectories 3951 of liquids injected according to one embodiment of the present invention. As shown in this figure, the liquid trajectories are oriented to maximize exposure of various portions of the column of flowing gas to the liquid, viewed here as arrows intersecting the circular cross-section of the gas column defined by the walls of the mixing chamber. The orifices or nozzles 3953 producing these trajectories 3951 need not be present at the same level of the mixing chamber, but instead may be staggered at different points along its length.

[0916] Figure 39CB shows an overhead view of an alternative design of a mixing chamber 3960, along the direction of flow of the gas, showing possible trajectories 3962 liquids injected according to an embodiment of the present invention. As shown in this figure, the liquid trajectories may be oriented according to the so-called Fibonacci spiral. Again, the orifices or nozzles 3963 producing these trajectories 3962 need not be present at the same level of the mixing chamber, but instead may be at points along its length.

[0917] Aspects other than relative orientation of spray trajectories may be used to design a mixing chamber for a particular application. As discussed in detail below, certain embodiments may perform compression or expansion over several stages, with the inlet gas flowed to each stage at a different pressure. Accordingly, a mixing chamber configured to inject liquid into gases at a higher pressure, may have a design that is different from a mixing chamber intended for use with lower pressure gas flows.

[0918] Specifically, embodiments for injection into higher pressure gas flows may exhibit dimensions that are elongated and narrower relative to lower pressure mixing chambers. Such a design would

overcome the difficulty of spray trajectories penetrating into the center of high pressure gas flows.

[0919] Returning to Figure 39, the particular embodiment shown in that figure is an apparatus dedicated to performing compression. According to other embodiments, a similar apparatus can operate as an expander.

[0920] Figure 40 shows an embodiment of an expander apparatus according to the present invention. During an expansion cycle, compressed gas would enter the mixing chamber 4006 from a storage unit 4032 via inlet pipe 4004.

[0921] Through manifold 4011, a liquid spray 4008 would be injected using nozzles 4010. The liquid-gas mixture would flow through the pulsation damper bottle 4014 to the chamber of cylinder 4013, which would be acting as an expander.

[0922] As shown in Figure 40A, in this mode the expansion of that gas within chamber 4013a of the cylinder 4013 will move the piston 4024 to the right and turn a crankshaft (not shown). Also during that piston stroke, gas expanded during the prior piston stroke would be output from the other chamber 4013b of the cylinder 4013.

[0923] Figure 40B shows the following piston stroke, wherein expansion of gas within the other chamber 4013b moves the piston in the opposite direction to turn the crankshaft. The gas that has previously expanded in the first chamber 4013a is output from the cylinder.

[0924] Separator 4030 receives the expanded liquid-gas output from the chamber, and separates the liquid from the gas-liquid mixture. Examples of separator types which may be used in accordance with embodiments of the present invention include but are not limited to cyclone separators, centrifugal separators, gravity separators, and demister separators (utilizing a mesh type coalescer, a vane pack, or another structure). The gas is then flowed out of the system.

[0925] Liquid recovered by separator 4030 collects in the liquid reservoir 4034. This liquid is circulated by pump 4036 through heat exchanger 4038 to nozzles 4010, where it is again injected into the gas stream as a spray.

[0926] The apparatus of Figure 40 will operate somewhat differently during an expansion cycle than during a compression cycle. Specifically, gas expanding and doing work on a piston will cool. In certain embodiments, heat obtained from a heat source may be added to the compressed gas that is inlet to the compressor or to the liquid that is sprayed into the mixing chamber, such that the expanders will generate mechanical energy in the form of crankshaft torque. That is, by adding heat to the system, the expanders will generate more shaft torque and power output can be enhanced. The amount of power output depends on the difference in temperature between the heat source and ambient air.

[0927] In certain embodiments, to maximize the energy obtained from one or more heat sources, heat may be transferred to the gas through a regenerator, which exchanges heat efficiently.

[0928] ***Combined Compression/Expansion***

[0929] Certain embodiments previously described relate to structures configured to operate as dedicated compressors or expanders. Alternative embodiments, however, may be configurable to operate

either in a compression mode or an expansion mode.

[0930] Figure 41 shows a simplified diagram of one embodiment of a such an apparatus that is able to perform in both compression and expansion roles. In Figure 41, solid lines are used to show the configuration of three-way valves in a compression mode, and dashed lines are used to show the configuration of three-way valves in an expansion mode. Figure 41 also shows the compression/expansion cylinder and valve configuration, as well as conduits leading thereto for purposes of illustration, and this figure should not be understood as depicting the relative sizes of the elements.

[0931] Apparatus 4100 comprises a first combined mixing chamber/pulsation damper bottle 4182 that is in fluid communication with inlet 4150 through air filter 4152. In a compression mode, outlet of element 4182 is in selective communication through three-way valve 4164 with compression/expansion cylinder and valve configuration 4108 whose operation is described in detail below. In the compression mode, the output of element 4108 is flowed through a second three-way valve 4166 to separator 4170, where separated liquid is flowed to reservoir 4135. The separated gas is in turn flowed through three-way valve 4165 to compressed gas storage unit 4132. Liquid from the reservoir 4135 is pumped by pump 4176 through heat exchanger 4190 for re-injection into the mixing chamber of the mixing chamber/pulsation bottle structure 4182.

[0932] In an expansion mode, compressed gas from storage unit 4132 is flowed through three way valve 4165 into second combined mixing chamber/pulsation damper bottle 4183. The outlet of element 4183 is in turn in selective communication through three-way valve 4166 with compression/expansion cylinder and valve configuration 4108 whose operation is described in detail below. In the expansion mode, the output of element 4108 is flowed through three-way valve 4164 to separator 4172, where separated liquid is flowed to reservoir 4136. The separated gas is in turn flowed out of the system through outlet 4134. Liquid from the reservoir 4136 is pumped by pump 4174 through heat exchanger 4192 for re-injection into the mixing chamber of the mixing chamber/pulsation bottle structure 4183.

[0933] A particular cylinder and valve configuration 4108 of the embodiment of Figure 41 is now described. Cylinder and valve configuration 4108 features double-acting piston 4124 disposed within cylinder 4112, thereby defining a first chamber 4113a and a second chamber 4113b. First valve 4120 is actuable to allow fluid communication between first chamber 4113a and first, low pressure side conduit 4102. Second valve 4122 is actuable to allow fluid communication between first chamber 4113a and second high pressure side conduit 4104.

[0934] Third valve 4121 is actuable to allow fluid communication between second chamber 4113b and the first conduit 4102. Fourth valve 4123 is actuable to allow fluid communication between second chamber 4113b and the second conduit 4104.

[0935] Figure 41 is provided for purposes of illustration only, and should not be understood as limiting the scope of the invention. For example, while this figures shows the piston as being moveable in the vertical direction, this is not required. The direction of movement of a piston could be different (for example in the horizontal direction) depending upon a particular implementation.

[0936] And while Figure 41 shows the various valves as being positioned in the side walls of the

cylinder, such a configuration is also not required. In accordance with alternative embodiments, valves could be positioned in other locations (for example the end walls of the cylinder), and the structure would remain within the scope of the present invention.

[0937] Operation of the cylinder and valve configuration 4108 in various modes is now described in connection with the detailed view of Figures 41A-D. Each of the first through fourth valves 4120-4123 comprise a valve plate 412_a that is moveable relative to respective valve seat 412_b. Respective solenoids 412_c are in physical communication to actuate the valves 4120-4123 by moving the valve plates relative to the valve seats. Solenoids 412_c are in communication with a controller/processor, such as controller/processor 4196 of Figure 41.

[0938] According to certain configurations, the valve seats and valve plates of the various valves may be oriented to convey flows of gas with low consumption of energy. For example, Figures 41A-B show the case where cylinder 4112 is configured to operate as a compressor. Specifically, as piston 4124 moves down in Figure 41A, valves 4121 and 4123 are initially closed, and a gas within the second chamber 4113b is compressed, increasing the pressure in the second chamber 4113 relative to the pressure in first conduit 4102. This pressure differential serves to naturally bias valve plate 4121a against valve seat 4121b, thereby allowing solenoid 4121c to maintain valve 4121 in a closed position with minimal expenditure of energy.

[0939] As shown in Figure 41B, the piston continues to move down, ultimately causing the pressure within the second chamber 4113b to reach that of the high pressure side. Again, the specific configuration of the valve plate 4121a relative to valve seat 4121b allows valve 4121 to remain closed with minimal energy from solenoid 4121c during this process.

[0940] Moreover, relatively little energy need be consumed by solenoid 4123c to open valve 4123 to allow the compressed gas to flow out of the second chamber 4113b. This is because the pressure within second chamber 4113b approximates that of the high pressure side conduit 4104, and thus actuation of the valve 4123 need not overcome a large pressure differential.

[0941] During the piston stroke shown in Figures 41A-B, valve 4120 is opened to allow an incoming flow of gas to fill first chamber 4113a for compression in the next piston stroke. The specific configuration of the valve plates and valve seats of valves 4120 and 4122 also allows this task to be accomplished with minimal energy consumption.

[0942] In particular, as piston 4124 moves down in Figures 41A-B, the effective volume of first chamber 4113a increases and the pressure within that chamber decreases relative to the first conduit 4102. This pressure differential serves to naturally bias valve plate 4120a away from valve seat 4120b, allowing the solenoid 4120c to open valve 4120 with minimal expenditure of energy. In addition, the low pressure in first chamber 4113a relative to second conduit 4104 naturally results in the biasing of valve plate 4122a toward valve seat 4122b, thereby desirably maintaining valve 4122 in a closed position with minimum energy from solenoid 4122c.

[0943] In the subsequent compression stroke (not shown here), piston 4124 moves upward to compress air in the first chamber. In a manner similar to that described above in conjunction with

Figures 41A-B, the orientation of the valve plates relative to the valve seats allows this compression to take place with minimal consumption of energy. In particular, the pressure differentials that naturally occur during this compression stroke tend to bias valves 4120 and 4123 shut, and allow valves 4121 and 4122 to open.

[0944] Figures 41C-D show the case where cylinder 4112 is configured to operate as an expander. Again, the orientation of the plates and seats of certain valves allows for this expansion to be accomplished with reduced energy consumption.

[0945] In particular, as piston 4124 moves downward in Figure 41C, valve 4122 is opened with valve 4120 remaining closed, and compressed air is admitted into the first chamber 4113a for expansion. At this point, the pressure within the first chamber 4113a is high relative to that of the first conduit 4102 on the low pressure side. This pressure differential serves to naturally bias valve plate 4120a against valve seat 4120b, allowing the solenoid 4120c to maintain valve 4120 in a closed position with minimal expenditure of energy.

[0946] As also shown in Figure 41C, valve 4123 is closed and valve 4121 opened, allowing reduced pressure air expanded during the previous piston stroke, to be flowed out of the second chamber 4113b to the first conduit 4102. Here, the pressure of the expanded air within the second chamber approximates that of the conduit 4102 on the low pressure side, requiring little or no energy for solenoid 4121c to open valve 4121. In addition, the pressure differential between second conduit 4104 and second chamber 4113b naturally biases the valve plate 4123a against the valve seat 4123b, allowing solenoid to maintain valve 4123 closed with low expenditure of energy.

[0947] As shown in Figure 41D, once valve 4122 is closed and air expands in the first chamber 4113a to further drive piston 4124 downward, the valve 4123 remains closed based upon the pressure differential between the second conduit and the second chamber. Because of the orientation of valve plate 4123a relative to valve seat 4123b, this closed state of valve 4123 may be maintained with a minimum of energy expenditure by solenoid 4123c.

[0948] Figure 41D also shows valve 4120 as remaining closed. Because of the orientation of valve plate 4120a relative to valve seat 4120b, the closed state of valve 4120 may be maintained based upon the pressure differential between the first chamber 4113a and the first conduit 4102, with a minimal energy consumption by solenoid 4120c.

[0949] In the subsequent expansion stroke (not shown here), piston 4124 moves upward as air expands in the second chamber. In a manner similar to that described above in conjunction with Figures 41C-D, the orientation of certain valve plates relative to the valve seats allows this expansion to take place with minimal consumption of energy. In particular, the inherent pressure differential tends to naturally bias shut the valves 4121 and 4122.

[0950] To avoid wasting energy in valve actuation, the system may be designed such that following expansion, the gas within the cylinder is at a pressure nearly equal to that of the low pressure side. Such pressure balancing reduces the amount of energy required to actuate valve 4121 in Figures 41C-D, and valve 4120 in the piston's subsequent stroke during expansion.

[0951] In addition, valve 4121 in Figure 41C may be closed before piston 4124 reaches the bottom of the stroke. The remaining air in second chamber 4113b is compressed as the piston continues to the bottom of its stroke. The time at which valve 4121 is closed is chosen so that the final pressure in chamber 4113b is substantially the same as the pressure in manifold 4104, thereby reducing the energy required to open valve 4123 and reducing the losses that would occur if gas were allowed to expand across a pressure drop without doing work. In another embodiment, water may be admitted to chamber 4113b through a valve (not shown) to equalize the pressure across valve 4123.

[0952] The particular cylinder and valve configuration of Figures 41-41D provides another advantage by automatically reverting to a compression mode in the event of a system failure. In particular, where no valve actuation instructions are received by the controller, relative pressure differentials in the cylinder arising from continued motion of the piston, will by default cause valves 4120-4123 to admit gas from the low pressure side into the cylinder. This will in turn result in the failsafe mode being compression, with remaining kinetic energy in the system gradually absorbed and the system brought to a halt.

[0953] The specific valve and cylinder configuration shown in Figures 41A-D is not limited to use in systems involving the injection of liquid into gas for heat exchange, and could be employed in systems not requiring such liquid injection. Moreover, the specific valve and cylinder configuration shown in Figures 41A-D is not limited to use in systems where the cylinder is used for both compression and expansion, and could be employed in dedicated compression or dedicated expansion systems.

[0954] While the particular embodiment of Figures 41A-D shows the gas flow valves as being selectively actuated by a solenoid, the present invention is not limited to using any particular type of valve for liquid injection. Examples of valves which may be suitable for liquid injection according to embodiments of the present invention include, but are not limited to, solenoid-actuated valves, spool valves, gate valves, cylindrical valves, needle valves, or poppet valves.

[0955] One example of an alternative gas flow valve design which may be suitable for use in the present invention, is a voice coil-actuated valve that includes a servo loop. Use of such a valve structure may be advantageous to control the velocity profile of actuation, for example reducing velocity at the end of plate travel prior to a stop, thereby relieving stress on valve components.

[0956] Other approaches to valve dampening are possible. For example, certain embodiments could use air cushions, dimples, cylindrical holes, and or other geometries of depression in the valve body or valve seat, with corresponding raised areas on the opposite member, to create air springs that absorb some of the energy of the motion of the movable component of the valve as it approaches the valve seat.

[0957] According to other embodiments the gas flow valves may be pneumatically actuated, an example being a proportional pneumatic air valve. In still other embodiments, the valves may be hydraulically actuated, for example a high pressure hydraulic valve.

[0958] And while Figures 41A-D show timing of the opening and closing of the valves according to certain embodiments, this timing scheme is not required. In accordance with other embodiments, alternative timing of the valves could be employed and remain within the present invention.

[0959] For example, Figures 49A-C show relations between pressure and volume in a chamber undergoing compression and expansion. These plots are representative, idealized plots, and do not include valve losses. In particular, Figure 49A plots pressure versus volume, within a chamber experiencing a compression cycle.

[0960] During the first piston stroke, the piston moves from a Top Dead Center (TDC) position at time t_1 to reach the Bottom Dead Center (BDC) position at time t_3. At time t_1 the volume within the chamber is a clearance volume (V_C) extant in the chamber when the piston head is at TDC. At time t_3 the volume within the chamber is that where the piston is at the BDC position (V_{BDC}).

[0961] At a time t_2 between t_1 and t_3, a pressure within the chamber is less than that of the low pressure side, causing opening of a valve to admit gas to the chamber from the low pressure side at an inlet pressure (P_{in}).

[0962] At the end of the first piston stroke (time t_3), the valve is closed. In the next stroke of the piston, the piston begins to move in the opposite direction (from BDC to TDC) to compress the gas within the chamber. At time t_4, the pressure within the chamber reaches an outlet pressure (P_{out}) of a high pressure side. A valve between the chamber and the high pressure side then opens, and continued movement of the piston flows the compressed gas to the higher pressure side.

[0963] At time t_5 the piston has reached the end of the second stroke. The valve between the chamber and the high pressure side closes and then the piston begins to move in the opposite direction to commence another compression cycle.

[0964] The valves of the compression cycle shown in Figure 49A operate efficiently. In particular, the first valve opens (at time t_2) when the pressure within the chamber has matched that of the low pressure side, requiring little energy for valve actuation. In addition, the balancing of pressure at this point minimizes the energy wasted in flowing gas from the low pressure side into the chamber.

[0965] Similarly, the second valve opens (at time t_4) when the pressure within the chamber has matched that of the high pressure side, again requiring little energy for valve actuation. This balancing of pressure further minimizes the energy that is wasted in flowing gas from the chamber to the high pressure side.

[0966] Figure 49B plots pressure versus volume, within a chamber that is undergoing a conventional expansion cycle. During the first piston stroke of the conventional expansion cycle, the piston moves from a TDC position at time t_1 to reach the BDC position at time t_3. At t_1 the volume within the chamber is a clearance volume (V_C). At t_3 the volume within the chamber is V_{BDC}.

[0967] At time t_1 the valve between the chamber and the high pressure side is opened. Owing to the existing pressure differential, gas flows rapidly through the valve into the chamber, expanding to fill the available volume and causing the pressure to rapidly reach P_{in} at time t_2. The air within the chamber expands between times t_2 and t_3, and the piston moves toward BDC.

[0968] At the end of the first piston stroke (time t_3), the valve is closed and a valve between the chamber and the low pressure side is opened. The pressure in the chamber rapidly drops to P_{out}. In the

next stroke, the piston moves in the opposite direction (from BDC to TDC) to exhaust the expanded gas from the chamber to the low pressure side (P_{out}).

[0969] At time t_5 the piston has reached the end of the second stroke. The outlet valve closes and the piston begins to move in the opposite direction to commence another expansion cycle.

[0970] In contrast with the compression cycle of Figure 49A, valves in the conventional expansion cycle of Figure 49B may operate less efficiently. In particular, energy of the compressed gas may be lost to recovery, during either or both of the steps of admitting air into the chamber, and exhausting the expanded air from the chamber.

[0971] For example, at the time of opening the valve between the high pressure side and the chamber (at time t_1), a pressure differential exists. The valve must be actuated against this pressure differential, consuming energy at the expense of efficiency. In addition, available energy of the compressed gas is wasted as it flows rapidly into the chamber between times t_1 and t_2. This energy is lost and not available to be recovered by movement of the piston, further reducing system efficiency.

[0972] Efficiency may also be lost in the flowing of expanded gas from the chamber. In particular, at the time of actuation of the valve between the chamber and the low pressure side at time t_3, the pressure within the chamber may exceed that of the low pressure side. In such a case, the valve must be actuated against this pressure differential, consuming energy at the expense of efficiency. Furthermore, available energy of the gas would be consumed would be consumed as it flows rapidly into the low pressure side between times t_3 and t_4. This energy is lost and not available to be recovered by movement of the piston, further reducing system efficiency.

[0973] Accordingly, embodiments of the present invention are configured to control valve actuation in an expansion mode to allow more efficient operation. Figure 49C plots in dashed lines, the pressure-volume relationship of an embodiment of an expansion cycle in accordance with an embodiment of the present invention.

[0974] The plot of Figure 49C is similar to that of Figure 49B, except that the timing of opening of valves is not necessarily coincident with the end of the piston strokes. For example, the valve between the high pressure side and the chamber is closed at time t_3, prior to the piston reaching the BDC position. As a result of this actuation timing, a smaller amount of gas is introduced for expansion, and the resulting pressure of gas within the chamber at the end of the expansion stroke, may match the low pressure side. Such a reduced pressure differential permits low energy actuation of the valve between the chamber and the low pressure side, and reduces energy losses associated with rapid flows of gas expanded within the chamber, to the low pressure side.

[0975] The valve between the chamber and the low pressure side may be closed at a time t_1, prior to the piston reaching the TDC position. As a result of this valve actuation timing, there remains in the chamber some amount of gas when the valve between the high pressure side and the chamber is again opened. This residual gas serves to lower a pressure differential at the time of inlet of the compressed gas into the chamber. The reduced pressure differential in turn slows the rate of flow of compressed gas into the chamber at the moment the inlet valve is opened, making more energy available for recovery by

expansion. The reduced pressure differential also lowers the amount of energy needed to actuate the valve against the pressure differential to admit the compressed gas into the chamber for expansion.

[0976] The total amount of power extracted by following the curve of Figure 49B is greater than that of Figure 49C, but efficiency is lower. By controlling the valve timing, any intermediate curve between Figure 49B and Figure 49C may be followed, allowing the system to trade off power output for efficiency.

[0977] Figures 41EA-EE show timing of opening and closing of valves during expansion mode in accordance with an alternative embodiment of the present invention. Figures 41EA-EE show the valves in an end wall of the cylinder for purposes of illustration, but the valves could be positioned anywhere in the chamber proximate to the maximum upward extent of the piston head, as generically depicted in the previous Figures 41-41D.

[0978] In Figure 41EA, the piston 4124 is approaching the top of the cylinder 4112, and gas expanded during the previous piston stroke is now being exhausted to the low pressure side through open valve 4120. As shown in Figure 41EB, in one approach valve 4120 may be maintained open until the piston reaches the very end of its expansion stroke, thereby exhausting all of the expanded air.

[0979] Such timing of actuation of valve 4120, however, could result in the loss of energy from the system. As specifically shown in Figure 41EC, at the beginning of the next (downward) stroke of the piston, valve 4122 in communication with the high pressure side would open, and high pressure gas would rush into the chamber. The energy associated with such rapid flow of the high pressure gas would be lost to subsequent expansion, thereby reducing the power output.

[0980] According to the alternative valve timing approach of Figure 41ED, this energy loss may be avoided by closing valve 4120 prior to the piston head reaching the top of the cylinder. In this configuration, the remaining expanded gas 4185 within the cylinder would be compressed by continued upward movement of the piston. This compression would elevate the pressure in the top of the cylinder, reducing the pressure differential as valve 4122 is subsequently opened in Figure 41EE. In this manner, the incoming gas would flow at a lower rate, reducing energy losses associated with pressure differentials.

[0981] The approach of Figures 41ED-41EE would also reduce the energy consumed by valve actuation. In order to open, solenoid 4122c must move the plate of valve 4122 against the pressure exerted by the high pressure side. However, the increased backpressure within the cylinder resulting from early closing of valve 4120, would provide additional bias to assist this movement of the valve plate during opening of valve 4122.

[0982] The valve timing approach just described utilizes the presence of residual gas within the cylinder, to reduce the pressure differential at the end of a piston stroke during expansion. Alternatively or in conjunction with this approach, a liquid material could be introduced to the cylinder to reduce this pressure differential.

[0983] Figures 41FA-41FC show cross-sectional views of such an embodiment. In Figure 41FA, the piston is again approaching the top of the cylinder, with expanded air being exhausted to the low pressure

side through valve 4120. In Figure 41FB, valve 4120 is closed prior to the piston reaching the top of the cylinder. A liquid 4187 such as water, is admitted to the cylinder through valve 4117 from reservoir 4119. The liquid serves to reduce the volume available in the cylinder for the remaining gas, making it easier to compress that remaining gas to a higher pressure. As shown in Figure 41FC, as the piston begins to descend in the next stroke, the increased pressure in the cylinder attributable to the presence of water, would reduce the pressure differential across valve 4122 and corresponding energy losses as that valve is opened to permit the flow of gas from the high pressure side. If the pressure differential is reduced to zero, there would be no free expansion, and efficiency would be maximized.

[0984] Liquid may be introduced into cylinder in a number of ways. In certain embodiments (for example those employing liquid injection to reduce the clearance volume) a separate valve could allow selective communication between the cylinder and a liquid supply. Certain embodiments could alternatively provide some or all of the liquid within the cylinder from the liquid injection, and some as droplets from the mist.

[0985] In embodiments where liquid is present within the cylinder, the amounts of liquid that are introduced or remain within the cylinder could be controlled to optimize system performance. For example, a sensor within the chamber could indicate the liquid levels, and operation of system elements controlled to vary this liquid amount. In certain embodiments, liquid could be removed from the cylinder by a drain, with rates of liquid flowing out of the cylinder being controlled by the processor or controller.

[0986] Returning to Figure 41, this embodiment includes two separate mixing chambers and pulsation damper bottles. The use of such separate structures may be desirable, as conditions of formation of the liquid-gas mixture will likely be different for compression versus expansion. For example in a compression mode the gas flow that is receiving the liquid spray, will be at low pressure. By contrast in the expansion mode, the gas flow that is receiving the liquid spray will be at a higher pressure. Use of separate mixing chambers as in the embodiment of Figure 4, allows for optimal liquid introduction under these different conditions.

[0987] According to embodiments of the present invention, a combined compression/expansion chamber, a dedicated compression chamber, or a dedicated expansion chamber, may be in fluid communication with the mixing chamber (as well as any intervening structures such as a pulsation damper bottle) through a variety of valve designs. As shown in the embodiment of Figures 39-41D, a plurality of valves may allow selective fluid communication between a mixing chamber and more than one compression/expansion chamber (for example, the two chambers defined by the presence of double-acting piston within a cylinder).

[0988] As shown in the previous embodiments, the valves may be mechanically actuated by a solenoid in physical communication with a shaft to cause movement of a valve plate relative to a valve seat. Such designs may include additional features to enhance system performance.

[0989] For example, Figure 41G shows a simplified view of one embodiment of a valve design which utilizes an ultrasonic transducer. This figure is provided for purposes of illustration only, and the relative dimensions and sizes of the components of this figure are not to scale.

[0990] In particular, valve 4189 includes a valve seat 4191 having apertures 4193, and includes a valve plate 4195 having apertures 4197 and which is moveable to engage the valve seat. The apertures of the valve seat are offset relative to the apertures of the valve plate, such that upon their engagement, gas is prevented from flowing through the valve.

[0991] When the valve seat and the valve plate are not engaged, sufficient space exists between these elements allowing gas to traverse the valve by passing through the apertures 4197 and 4193. As shown in Figure 41G, however, the path imposed upon gas flowing through the open valve can be torturous, with sharp turns potentially resulting in coalescence of liquid droplets 4187 on exposed surfaces. Such coalescence can undesirably alter the uniformity of those droplets in the chamber during compression or expansion. Coalescence can be reduced by shaping the edges of the valve plate and seat to minimize sharp turns, but the effect may not be eliminated by this method alone.

[0992] Thus, according to one embodiment, a valve structure of the present invention may be placed into communication with an ultrasonic transducer. The ultrasonic energy received from this transducer can serve to disrupt the coalescence of liquid on the valve, allowing that liquid to flow into the chamber for heat exchange during compression and/or expansion.

[0993] Figure 41G shows one embodiment, wherein valve plate 4195 is moveable relative to valve seat 4191 by a shaft 4175 in communication with a solenoid 4177. In this embodiment, an ultrasonic transducer 4173 may be fixed to the shaft 4175. Actuation of the ultrasonic transducer 4173 results in the communication of ultrasonic waves to 4191 the valve plate, which vibrates and disperses liquid that may have coalesced on its surfaces. The ultrasonic energy may also reach the valve seat to disrupt liquid coalescence on its surfaces.

[0994] While Figure 41G shows an embodiment wherein the ultrasonic transducer is in direct contact with the valve plate through the shaft, this is not required by the present invention. In alternative embodiments, the ultrasonic transducer could be separated from the valve plate and/or seat by some distance, with ultrasonic energy impinging upon these valve elements to disrupt coalescence of liquid upon their surfaces.

[0995] While the apparatus of Figure 41G positions an ultrasonic transducer in acoustic communication with a valve structure controlling flows of gas to a chamber, an ultrasonic transducer could alternatively be positioned in other locations and remain within the scope of the present invention.

[0996] For example, the coalescence of droplets from an injected liquid mist is not limited to the surfaces of a valve plate or valve seat. Such coalescence can also occur within the cylinder itself, on the walls of the chamber and/or on the piston head and piston shaft.

[0997] Accordingly, certain embodiments of the present invention may position an ultrasonic transducer within the cylinder itself. In such an embodiment, ultrasonic energy from the transducer could be communicated to the chamber walls and/or the surface of the piston.

[0998] Such transmission of ultrasonic energy to within the cylinder could enhance heat exchange for compression or expansion processes in at least a couple of ways. First, the ultrasonic energy would disperse liquid from the surfaces back into the gas, where the liquid is better suited to thermally interact with the gas. In addition, the ultrasonic energy may serve to break up the coalesced liquid into finer droplets having smaller diameters, thereby creating a larger surface area and enhancing heat exchange.

[0999] Returning to the subject of valve structure, embodiments of the present invention are not limited to the use of solenoid-actuated valves. Alternative embodiments my utilize other valve types and remain within the scope of the present invention.

[1000] One example of such an alternative valve design which may be suitable for use in the present invention, is a voice coil-actuated valve that includes a servo loop. Use of such a valve structure may be advantageous to control the velocity profile of actuation, for example reducing velocity at the end of plate travel prior to a stop, thereby relieving stress on valve components.

[1001] According to other embodiments the valves may be pneumatically actuated, an example being a proportional pneumatic air valve. In still other embodiments, the valves may be hydraulically actuated, for example a high pressure hydraulic valve.

[1002] Embodiments of valves for use in accordance with the present invention may be designed to exhibit specific time profiles of opening and/or closing. For example, Figure 41H shows one possible embodiment wherein valve plate 4140 is actuated relative to valve plate 4145 through shaft 4148, by contact between a cam follower 4142 and a surface 4143a of cam 4143 as the cam rotates about shaft 4144. The cam follower is held in contact with the cam surface by spring 4141. In this embodiment, the particular shape of the cam, and the corresponding orientation of its surfaces relative to the cam follower, can be designed to determine the time profile of the actuation of the valve, in the closing and opening directions. Valve timing may be varied by providing a mechanism to vary the angle or effective profile of the cam.

[1003] Moreover, embodiments in accordance with the present invention are not limited to the use of two-way valves. In accordance with certain embodiments, a mixing chamber may be in selective fluid communication with a plurality of compression/expansion chambers, through a multi-way valve having two or a greater number of outputs.

[1004] A system employing a valve between a mixing chamber and compression/expansion chambers, having more than two outputs, is shown in the embodiment of Figure 46A. In this structure, the output of mixing chamber 4699 is in selective fluid communication with one of a plurality of compression/expansion chambers 4602a-c, through a pulsation damper bottle 4694 and a multi-way valve 4698.

[1005] This embodiment of a system is designed such that at most times, a gas/liquid mixture is generally being flowed to at least one of the compression/expansion chambers 4602a-c. Such ongoing operation of the mixing chamber to create the gas/liquid mixture, helps to ensure the uniformity of the properties of that mixture over time, as flows of gases, liquids, and the resulting gas/liquid mixture itself,

is not repeatedly halted and restarted depending upon the varying demands of the different compression/expansion chambers.

[1006] In still another embodiment shown in Figure 46B, a gas/liquid mixture prepared in the mixing chamber 4659, is not required at all times by one of the compression/expansion chambers 4654a-c. However, the benefits of ongoing generation of the gas/liquid mixture may be achieved by placing one output of the multi-way valve 4658 in fluid communication with a dump 4656. Thus when the gas/liquid mixture is not required for compression/expansion in any chamber , the mixture is flowed from the mixing chamber 4659 through a pulsation damper bottle 4654 to the dump 4656, where the liquid may or may not be recovered for later use, such as re-injection.

[1007] It is further noted that the character of the gas/liquid mixture generated in the mixing chamber and flowed to the compression/expansion chamber, may or may not be the same during expansion cycles and compression cycles. Thus, where the desired gas-liquid mixture is to be changed, it may be advantageous to flow the transitional mixture to the dump until uniform conditions of the changed gas/liquid mixture have been achieved.

[1008] One particular embodiment in which it may be useful to selectively route a liquid-gas mixture to a dump, is depicted in Figures 48A-48C. In particular, some embodiments may employ precise control over valve actuation to admit a predetermined limited volume of the liquid-gas mixture during an expansion cycle.

[1009] Specifically, a pre-determined amount of air V_0, is added to the chamber from the high pressure side (such as the previous stage or the storage tank), by opening an inlet valve 4800 for a controlled interval of time. This amount of air V_0 is calculated such that when the piston 4802 reaches the end of the expansion stroke, a desired pressure within the chamber 4804 will be achieved.

[1010] In certain cases, this desired pressure will be approximately equal that of the next lower pressure stage, or will be approximately atmospheric pressure if the stage is the lowest pressure stage or is the only stage. In certain embodiments, the desired pressure within the chamber may be within 1 PSI, within 5 PSI, within 10 PSI, or within 20 PSI of the pressure of the next lower stage. Thus at the end of the expansion stroke, the energy in the initial air volume V_0 has been fully expended, and little or no energy is wasted in moving that expanded air to the next lower pressure stage.

[1011] To achieve this goal, inlet valve 4800 is opened only for so long as to allow the desired amount of air (V_0) to enter the chamber. Thereafter, as shown in Figures 48B-C, valve 4800 is maintained closed.

[1012] In such a configuration, the inlet valve 4800 is closed before the piston has completed its expansion stroke. Moreover, the timing of closing of inlet valve 4800 may not be exactly synchronized with the opening of another inlet valve to admit a liquid-gas flow into another chamber (or portion thereof in the case of a double-acting piston.). Thus, at the time of closing of inlet valve 4800, no other chamber may yet be ready to receive a flow of a compressed liquid-gas mixture for expansion. Accordingly, such embodiments could benefit from the ability to shunt the continuously flowing liquid-

gas mixture to a dump, until such time (shown in Figure 48C) that a chamber in the system is to configured to receive that flow for expansion.

[1013] In other embodiments, a controller/processor may control inlet valve 4800 to cause it to admit to the expansion chamber an initial volume of air that is greater than V_0. Such instructions may be given, for example, when greater power is desired from a given expansion cycle, at the expense of efficiency of energy recovery.

[1014] As described in detail above, embodiments of systems and methods for storing and recovering energy according to the present invention are particularly suited for implementation in conjunction with a host computer including a processor and a computer-readable storage medium. Such a processor and computer-readable storage medium may be embedded in the apparatus, and/or may be controlled or monitored through external input/output devices.

[1015] Figure 47 is a schematic diagram showing the relationship between the processor/controller, and the various inputs received, functions performed, and outputs produced by the processor controller. As indicated, the processor may control various operational properties of the apparatus, based upon one or more inputs.

[1016] An example of such an operational parameter that may be controlled is the timing and configuration of the valves that control the flow of air and liquids into the mixing chamber, and in turn from the mixing chamber to the compression/expansion chamber. For example, as described above, in some embodiments the valve between the mixing chamber and the compression/expansion chamber is selectively opened and closed to allow flow of a gas/liquid mixture into an appropriate compression/expansion chamber. In a system where multiple such chambers are in communication with the mixing chamber, the valve would need to be carefully controlled to route the gas/liquid mixture to the proper chamber for the proper period, and in certain embodiments to route the gas/liquid mixture to a dump as appropriate.

[1017] Such timing of operation of the valve between the mixing chamber and the compression/expansion chamber may also need to be controlled to ensure that only a pre-determined amount of the air and gas/liquid mixture is introduced into the compression/expansion chamber. This is discussed above in connection with Figures 48A-C.

[1018] Timing of opening and closing of valves may also be carefully controlled during compression. For example, embodiments of the present invention may utilize the controller/processor to precisely open an outlet valve of a compression chamber under the desired conditions, for example where the built-up pressure in the cylinder exceeds a pressure in a next stage or a final storage pressure by a certain amount. In this manner, energy from the compressed air within the cylinder is not consumed in actuating the outlet valve (as is the case with a conventional check valve), and energy stored in the compressed air is maintained for later recovery by expansion.

[1019] While the timing of operation of inlet and outlet valves of a compression and/or expansion chamber may be controlled as described above, it should be appreciated that in certain embodiments other valves, or system elements other than valves, may be similarly controlled. For example, another

example of a system parameter that can be controlled by the processor, is the amount of liquid introduced into the chamber. Based upon one or more values such as pressure, humidity, calculated efficiency, and others, an amount of liquid that is introduced into the chamber during compression or expansion, can be carefully controlled to maintain efficiency of operation. For example, where an amount of air greater than V_0 is inlet into the chamber during an expansion cycle, additional liquid may need to be introduced in order to maintain the temperature of that expanding air within a desired temperature range. This can be accomplished by processor control over a valve connecting the fluid reservoir with the spray nozzles, or a pump responsible for flowing fluid to the spray nozzles

[1020] ***Multi-Stage System***

[1021] The particular embodiments just described employ compression or expansion over a single stage. However, alternative embodiments in accordance with the present invention may utilize more than one compression and/or expansion stage.

[1022] For example, when a larger compression/expansion ratio is required than can be accommodated by the mechanical or hydraulic approach by which mechanical power is conveyed to and from the system, then multiple stages can be utilized.

[1023] Figure 42A presents a highly simplified view of an embodiment of a multi-stage system 4220 for compressing air for storage in tank 4232 with three stages (i.e., first stage 4224a, second stage 4224b and third stage 4224c). Systems with more or fewer stages may be constructed similarly. As shown in the system 4220 of Figure 42A, in multi-stage embodiments the output of one compression stage is flowed to the inlet of a successive compression stage for further compression, and so on, until a final desired pressure for storage is reached. In this manner, gas can be compressed over several stages to final pressures that would be difficult to achieve with only one stage.

[1024] Figure 42B presents a detailed view of one embodiment of a multi-stage dedicated compressor apparatus 4200 according to the present invention. In particular, Figure 42B shows system 4200 including first stage 4202, second stage 4204, and storage unit 4232. First stage 4202 comprises mixing chamber module A_0 in fluid communication with separator module B_1 through compression chamber module C_{01}. First stage 4202 receives air for compression through air filter 4250.

[1025] First stage 4202 is in turn in fluid communication with second stage 4204. Second stage comprises mixing chamber module A_1 in fluid communication with separator module B_2 through compression module C_{12}. Second stage 4204 is in turn in fluid communication with storage unit 4232.

[1026] Figures 42BA, 42BB, and 42BC show simplified views of the different component modules of the multi-stage apparatus of Figure 42B. In particular, the mixing module A_x comprises gas inlet 4206 in fluid communication with mixing chamber 4208. Mixing chamber 4208 is configured to receive a flow of liquid through liquid inlet 4213, and to inject that liquid into a flowing gas through manifold 4210 and spray nozzles 4212. Mixing module A_x further includes a pulsation damper bottle 4214 in fluid communication with an outlet 4216.

[1027] Separator module B_y is shown in Figure 42BB. Separation module comprises an inlet 4230 in fluid communication with a liquid-gas separator 4232. Liquid separated by separator is configured to flow to liquid reservoir 4234. Gas from the separator is configured to flow to outlet 4236 of the separator module. Pump 4238 is configured to flow liquid from reservoir to liquid outlet 4240.

[1028] A compression module C_{xy} is shown in Figure 42BC. The architecture of one embodiment of a compression module is described in detail above in connection with Figures 41-41B. In particular, the compression module comprises a conduit 4250 in fluid communication with an inlet 4252 and in fluid communication with a cylinder 4254 through valves 4256a and 4256b. Conduit 4258 is in fluid communication with cylinder 4254 through valves 4257a and 4257b, and in fluid communication with an outlet 4259.

[1029] Double-acting piston 4255 is disposed within cylinder 4254. Double-acting piston is in communication with an energy source (not shown), and its movement serves to compress gas present within the cylinder. Such compression is generally shown and described above in connection with Figures 39-39B and 41-41B.

[1030] In the first stage 4202 of multi-stage dedicated compressor apparatus 4200, the liquid outlet of the separator module B_1 is in fluid communication with the liquid inlet of the mixing module A_0, through a first heat exchanger $H.E._{01}$. In the second stage 4204 of multi-stage dedicated compressor apparatus 4200, the liquid outlet of the separator module B_2 is in fluid communication with the liquid inlet of the mixing module A_1, through a second heat exchanger $H.E._{02}$.

[1031] The embodiment of Figure 42B may utilizes the pressure differential created by a stage, to facilitate injection of liquid. In particular, the embodiment of Figure 42B has the separated liquid flowed back to the into a gas flow having the reduced pressure of the previous lower pressure stage. This reduces the force required for the liquid injection, and thus the power consumed by the pump in flowing the liquid.

[1032] A dedicated multi-stage compressor apparatus according to the present invention is not limited to the particular embodiment shown in Figure 42B. In particular, while the embodiment of Figure 42B shows an apparatus wherein separated liquid is recycled for re-injection into the gas flow within an individual stage, this is not required by the present invention.

[1033] Figure 42C thus shows an alternative embodiment of a dedicated multi-stage compressor apparatus in accordance with the present invention. In the system 4260 according to this embodiment, liquid injected into the mixing chamber 4262 of a first stage, is subsequently separated by separator 4264 and then flowed for injection into the mixing chamber 4266 of the next stage. This configuration results in accumulation of the finally separated liquid in the tank 4268.

[1034] While Figures 42A-C shows compression over two stages, embodiments of the present invention are not limited to this approach. Alternative embodiments in accordance with the present invention can also perform expansion over any number of stages, with the output of one expansion stage flowed to the inlet of a successive expansion stage for further expansion, and so on, until an amount of

energy has been recovered from the compressed gas. In this manner, energy can be recovered from gas expanded over several stages, that would be difficult to obtain with expansion in only one stage.

[1035] Figure 43 presents a detailed view of one embodiment of a multi-stage dedicated expander apparatus according to the present invention. In particular, Figure 43 shows apparatus 4360 including storage unit 4332, first stage 4362, and second stage 4364. First stage 4362 comprises mixing chamber module A_3 in fluid communication with separator module B_4 through expansion module E_{34}. First stage 4362 receives air for compression from storage unit 4332.

[1036] First stage 4362 is in turn in fluid communication with second stage 4364. Second stage 4364 comprises mixing chamber module A_2 in fluid communication with separator module B_3 through expansion module E_{23}. Second stage 4364 is in turn in fluid communication with an outlet 4357.

[1037] The different component modules of the multi-stage dedicated expander apparatus 4360 may also be represented in Figures 42BA and 42BB as described above. Dedicated expander apparatus 4360 further includes expansion module E_{xy} shown in Figure 43A.

[1038] In particular, the architecture and operation of one embodiment of such an expansion module is described in detail above in connection with Figures 41 and 41C-D. In particular, the expansion module comprises a conduit 4350 in fluid communication with an inlet 4352 and in fluid communication with a cylinder 4354 through valves 4366a and 4366b. Conduit 4358 is in fluid communication with cylinder 4354 through valves 4367a and 4367b, and in fluid communication with an outlet 4359.

[1039] Double-acting piston 4355 is disposed within cylinder 4354. Double-acting piston is in communication with an apparatus (not shown) for converting mechanical power into energy, for example a generator. Expansion of air within the cylinder serves to drive movement of the piston. Such expansion is generally shown and described above in connection with Figures 40-40B, 41, and 41C-D.

[1040] In the first stage 4362 of multi-stage dedicated expander apparatus 4360, the liquid outlet of the separator module B_4 is in fluid communication with the liquid inlet of the mixing module A_3, through a first heat exchanger $H.E._{43}$. In the second stage 4364 of multi-stage dedicated expander apparatus 4360, the liquid outlet of the separator module B_3 is in fluid communication with the liquid inlet of the mixing module A_2, through a second heat exchanger $H.E._{32}$.

[1041] A dedicated multi-stage expander apparatus according to the present invention is not limited to the particular embodiment shown in Figure 43. In particular, while the embodiment of Figure 43 shows an apparatus wherein separated liquid is recycled for re-injection into the gas flow within an individual stage, this is not required by the present invention.

[1042] Figure 43B shows an alternative embodiment of a dedicated multi-stage expander apparatus in accordance with the present invention. In the system 4300 according to this embodiment, liquid injected into the mixing chamber 4302 of a first stage, is subsequently separated by separator 4304 and then flowed for injection into the mixing chamber 4306 of the next stage. This configuration results in accumulation of the finally separated liquid in the tank 4308.

[1043] The embodiment of Figure 43B does not require liquid to be injected against the pressure differential that is created by a stage. In the particular embodiment of Figure 43A the separated liquid is

flowed back to the into the inlet gas flow having the elevated pressure of the previous higher pressure stage. By contrast, the embodiment of Figure 43B has the separated liquid flowed into the expanded gas that is inlet to the next stage, reducing the power consumed by the pump in flowing the liquid.

[1044] While the embodiments of multi-stage apparatus described so far are dedicated to either compression or expansion, alternative embodiments in accordance with the present invention could perform both compression and expansion. Figure 44 shows a simplified schematic view of one embodiment of such an two-stage apparatus that allows both compression and expansion.

[1045] In particular, the embodiment of Figure 44 combines a number of design features to produce a system that is capable of performing both compression and expansion. One feature of system 4400 is connection of certain elements of the system through three-way valves 4404. Figure 44 depicts the configuration of the three-way valves as solid in the compression mode, and as dashed in the expansion mode.

[1046] One feature of the system 4400 is the use of the same mixing chamber 4405 for the introduction of liquid in both the compression mode and in the expansion mode. Specifically, during compression the mixing chamber 4405 is utilized to inject liquid into gas that is already at a high pressure by virtue of compression in the previous stage. During expansion, the mixing chamber 4405 is utilized to inject gas into the high pressure gas at the first stage. In multi-stage apparatuses having mixing chambers commonly used in both compression and expansion, the pressures of inlet gas flows to those mixing chambers would be approximately the same in order achieve the desired gas-liquid mixture.

[1047] Still another feature of the system 4400 is the use of a pulsation damper bottle 4406 that is elongated in one or more dimensions (here, along dimension d). The elongated shape of the pulsation damper bottle 4406 allows for multiple connections between the bottle and adjacent elements, while allowing the conduits for fluid communication with those adjacent elements to remain short.

[1048] Specifically, the size of the pulsation damper bottle offers a relatively large volume for receiving the liquid-gas mixture. This volume accommodates the liquid droplets within the main body of the gas flow, with relatively low proportional exposure to the surface area of the walls of the bottle. By minimizing such exposure of the liquid droplets to the walls, the liquid droplets will tend to remain dispersed within the gas flow and hence available for heat exchange, rather than coalescing on the surfaces.

[1049] Figure 44 is a simplified view showing the elongated pulsation damper bottle in schematic form only, and the shape of the elongated bottle should not be construed as being limited to this or any other particular profile. For example, alternative embodiments of a pulsation damper bottle could include one or more lobes or other elongated features.

[1050] Absent the use of such a pulsation damper bottle having an elongated shape, corresponding fluid conduits exhibiting greater complexity (for example having a longer length and/or more turns) could used to connect the bottle with different system elements. Such complex conduits could create localized pressure differences that disrupt the uniformity of the liquid-gas mixture, for example by giving rise to undesirable localized coalescence of liquid within the conduits.

[1051] Under operation in a compression mode, gas enters system through inlet 4450 and is exposed to two successive liquid injection and compression stages, before being flowed to storage unit 4432. Separated liquid accumulates in tank 4435, which may be insulated to conserve heat for subsequent re-injection to achieve near-isothermal expansion in an expansion mode.

[1052] Specifically, under operation in an expansion mode, compressed gas from storage unit is exposed to two successive liquid injection and expansion compression stages, before being flowed out of the system at outlet 4434. Separated liquid accumulates in tank 4436, and may be subsequently re-injected to achieve near-isothermal compression in a compression mode.

[1053] In the embodiment of the system of Figure 44, the flow of separated liquid across different stages results in accumulation at a final separator, in a manner analogous to the embodiments of Figure 42C (dedicated compressor) and Figure 43B (dedicated expander). Such embodiments require the fluid reservoirs to be larger to accommodate the directional flows of liquids which occur.

[1054] Figure 45 is a simplified diagram showing a multi-stage apparatus in accordance with an embodiment of the present invention, which is configurable to perform both compression and expansion. In particular, system 4500 represents a modification of the embodiment of Figure 44, to include additional three-way valves 4502 and additional conduits between certain separator elements and certain mixing chambers. Again, Figure 45 depicts the configuration of the three-way valves as solid in the compression mode, and as dashed in the expansion mode.

[1055] While the embodiment of Figure 45 offers some additional valve and conduit complexity, it may eliminate certain elements. In particular, it is noted that compression and expansion do not occur simultaneously, and hence all three heat exchangers and pumps of the embodiment of Figure 44 are not required to be in use at the same time. Thus, system 4500 utilizes only two heat exchangers (H.E.1 and H.E.2) and two pumps (4504), versus the three heat exchangers and three pumps of the embodiment of Figure 44.

[1056] Moreover, the embodiment of Figure 45 restricts the circulation of liquids to within a stage. Thus, the flow of liquids is not such that liquids accumulate in one reservoir, and so the liquid reservoirs do not need to be made larger as in the embodiment of Figure 44.

[1057] In summary, various embodiments according to the present invention may incorporate one or more of the following elements:

[1058] 1. Use of a mixing chamber for mixing gas and liquid, upstream of a chamber in which compression and/or expansion of gas is to take place.

[1059] 2. Use of a pulsation damper bottle between a mixing chamber and a chamber in which compression and/or expansion of gas is to take place.

[1060] 3. Continuous generation of a gas/liquid mixture within a mixing chamber, with the gas/liquid mixture either being continuously flowed to compression/expansion chamber(s), or being flowed to a dump when not needed.

[1061] 4. Near-isothermal expansion and compression of gas, with the required heat exchange effected by a liquid phase in high-surface-area contact with the gas, as created in a mixing chamber separate from that in which compression/expansion is occurring.

[1062] 5. A mechanism capable of both compression and expansion of air.

[1063] 6. Electronic control of valve timing so as to obtain high work output from expansion of a given volume of compressed air.

[1064] Various configurations described herein use and generate power in mechanical form, be it hydraulic pressure or the reciprocating action of a piston. In most applications, however, the requirement will be for the storage of electrical energy. In that case, a generator, along with appropriate power conditioning electronics, can be used to convert the mechanical power supplied by the system during expansion, to electrical power. Similarly, the mechanical power required by the system during compression may be supplied by a motor. Since compression and expansion are never done simultaneously by the same chamber, in certain embodiments a motor/generator may be used to perform both functions.

[1065] If the energy storage system utilizes a hydraulic motor or a hydro turbine, then the shaft of that device may connect directly or via a gearbox to the motor/generator. If the energy storage system utilizes reciprocating pistons, then a crankshaft or other mechanical linkage that can convert reciprocating motion to shaft torque, may be used.

[1066] Moreover, embodiments of the present invention do not require the use of a mixing chamber with every stage. Certain embodiments could employ a mixing chamber in only some stages, with other stages having gas introduced to the compression/expansion chamber by other than a mixing chamber, for example by injection of a mist or spray directly into the chamber in which compression/expansion is taking place.

[1067] Still other embodiments may utilize stages in which liquid is introduced into the gas by other than a spray, for example by bubbling gas through a liquid. For example, in certain embodiments some (lower-pressure) stages might employ the liquid mist technique utilizing a mixing chamber, while other (higher-pressure) stages may employ the bubbles technique to store and remove energy therefrom.

[1068] 1. A method comprising:

spraying a liquid into a first chamber containing a flowing gas to generate a liquid-gas mixture;

flowing the liquid-gas mixture into a second chamber;

subjecting the portion of the liquid-gas mixture to compression by a piston coupled to the second chamber, the liquid of the liquid-gas mixture absorbing thermal energy generated by the compression; and

transferring at least a portion of the compressed liquid-gas mixture from the second chamber.

[1069] 2. The method of claim 1 further comprising continuing to generate the liquid-gas mixture when the liquid-gas mixture is not flowed to the second chamber.

[1070] 3. The method of claim 2 further comprising flowing the liquid-gas mixture to a third chamber when the liquid-gas mixture is not flowed to the second chamber.

[1071] 4. The method of claim 2 further comprising flowing the liquid-gas mixture to a dump when the liquid-gas mixture is not flowed to the second chamber.

[1072] 5. The method of claim 1 further comprising flowing the liquid-gas mixture to the second chamber through a pulsation damper bottle.

[1073] 6. The method of claim 1 further comprising separating liquid from the portion of the compressed liquid-gas mixture to form a compressed gas.

[1074] 7. The method of claim 6 further comprising flowing the compressed gas to a storage unit.

[1075] 8. The method of claim 6 further comprising flowing the separated liquid through a heat exchanger to be sprayed into the first chamber.

[1076] 9. The method of claim 6 further comprising flowing the compressed gas to a next stage for further compression.

[1077] 10. The method of claim 9 further comprising flowing the separated liquid through a heat exchanger to be sprayed into the next stage.

[1078] 11. A method comprising:

spraying a liquid into a first chamber containing a flowing gas to generate a liquid-gas mixture;

flowing the liquid-gas mixture into a second chamber;

allowing the liquid-gas mixture to expand to drive a piston coupled to the second chamber, the liquid of the liquid-gas mixture transferring thermal energy during the expansion; and

transferring at least a portion of the expanded liquid-gas mixture from the second chamber.

[1079] 12. The method of claim 11 further comprising continuing to generate the liquid-gas mixture when the liquid-gas mixture is not flowed to the second chamber.

[1080] 13. The method of claim 12 further comprising flowing the liquid-gas mixture to a third chamber when the liquid-gas mixture is not flowed to the second chamber.

[1081] 14. The method of claim 12 further comprising flowing the liquid-gas mixture to a dump when the liquid-gas mixture is not flowed to the second chamber.

[1082] 15. The method of claim 11 further comprising flowing the liquid-gas mixture to the second chamber through a pulsation damper bottle.

[1083] 16. The method of claim 11 further comprising separating liquid from the portion of the compressed liquid-gas mixture.

[1084] 17. The method of claim 11 further comprising flowing the separated liquid through a heat exchanger to be sprayed into the first chamber.

[1085] 18. The method of claim 11 wherein the flowing gas is received from a storage unit.

[1086] 19. The method of claim 11 wherein the flowing gas is received from a previous expansion stage.

[1087] 20. The method of claim 19 further comprising flowing the separated liquid through a heat exchanger to be sprayed into the previous expansion stage.

[1088] 21. An apparatus comprising:

a first chamber configured to receive a gas flow and in liquid communication with a liquid source through a sprayer to generate a liquid-gas mixture within the first chamber;

a second chamber in selective fluid communication with the first chamber through a pulsation damper bottle and a valve, the second chamber having a moveable member disposed therein.

[1089] 22. The apparatus of claim 21 wherein the moveable member is in communication with an energy source to compress air within the second chamber.

[1090] 23. The apparatus of claim 21 wherein the moveable member is in communication with a generator to generate power upon expansion of air within the second chamber.

[1091] 24. The apparatus of claim 21 wherein the valve comprises a valve plate disposed to move toward a valve seat when a pressure within the second chamber exceeds a pressure within the first chamber.

[1092] 25. The apparatus of claim 21 further comprising a separator in fluid communication with the second chamber through a second valve.

[1093] 26. The apparatus of claim 25 wherein:

the valve comprises a first valve plate disposed to move toward a first valve seat when a pressure within the second chamber exceeds a pressure within the first chamber; and

the second valve comprises a second valve plate configured to move away from a second valve seat when a pressure within the second chamber exceeds a pressure within the separator.

[1094] 27. The apparatus of claim 25 further comprising a liquid reservoir in liquid communication with the separator.

[1095] 28. The apparatus of claim 27 further comprising a conduit, a pump, and a heat exchanger, wherein the liquid reservoir comprises the liquid source in liquid communication with the first chamber through the conduit, the pump, and the heat exchanger.

[1096] 29. The apparatus of claim 21 wherein the moveable member is in selective communication with a generator and in selective communication with an energy source.

[1097] 30. The apparatus of claim 29 further comprising:

a third chamber configured to receive a second gas flow and in liquid communication with a second liquid source through a second sprayer to generate a second liquid-gas mixture within the third chamber, the third chamber in selective fluid communication with the second chamber through a second pulsation damper bottle and a second valve;

a first three-way valve between the first pulsation damper bottle and the valve, the first three-way valve configurable to flow an output from the second chamber to a first separator; and

a second three-way valve between the second pulsation damper bottle and the second valve, the second three-way valve configurable to flow an output from the second chamber to a second separator.

[1098] 31. The apparatus of claim 30 wherein:

the valve comprises a first valve plate disposed to move toward a first valve seat when a pressure within the second chamber exceeds a pressure within the first chamber; and

the second valve comprises a second valve plate configured to move away from a second valve seat when a pressure within the second chamber exceeds a pressure within the first separator.

[1099] 32. The apparatus of claim 30 further comprising:

a first liquid reservoir comprising the first liquid source and in liquid communication with the first separator and in liquid communication with the first chamber through a first conduit, a first pump, and a first heat exchanger; and

a second liquid reservoir comprising the second liquid source and in liquid communication with the second separator and in liquid communication with the third chamber through a second conduit, a second pump, and a second heat exchanger.

[1100] 33. The apparatus of claim 25 further comprising a next stage in fluid communication with the separator.

[1101] 34. The apparatus of claim 33 wherein the separator is in liquid communication with a liquid reservoir, and the next stage is in liquid communication with the liquid reservoir through a conduit, a pump, and a heat exchanger.

[1102] 35. The apparatus of claim 21 further comprising a previous stage in fluid communication with the first chamber.

[1103] 36. The apparatus of claim 35 wherein the previous stage is in liquid communication with a liquid reservoir, and the liquid reservoir is in liquid communication with the first chamber through a conduit, a pump, and a heat exchanger.

[1104] 37. The apparatus of claim 33 wherein:

the next stage comprises a third chamber in fluid communication with a fourth chamber through a second pulsation damper bottle, the fourth chamber having a second moveable member disposed therein; and

wherein the apparatus further comprises a network of three-way valves configurable in a compression mode to flow gas compressed in the first chamber to the next stage, and configurable in an expansion mode to flow gas expanded in the fourth chamber to the first chamber.

[1105] 38. The apparatus of claim 37 wherein the network of three-way valves comprises:

a first three-way valve positioned between the first pulsation damper bottle and the second chamber,

a second three-way valve positioned between the second chamber and the third chamber;

a third three-way valve positioned between the second pulsation damper bottle and the fourth chamber; and

a fourth three-way valve positioned between the fourth chamber and a compressed gas storage unit.

[1106] 39 The apparatus of claim 38 wherein in the compression mode:

the first three-way valve is configured to place the first pulsation damper bottle in fluid communication with the second chamber;

the second three-way valve is configured to place the second chamber in fluid communication with a first separator;

the third three-way valve is configured to place the second pulsation damper bottle in fluid communication with the third chamber; and

the fourth three-way valve is configured to place the fourth chamber in fluid communication with a second separator that is in fluid communication with the storage unit.

[1107] 40. The apparatus of claim 38, wherein in the expansion mode:

the fourth three-way valve is configured to place the third chamber in fluid communication with the storage unit;

the third three-way valve is configured to place the second pulsation damper bottle in fluid communication with the fourth chamber;

the second three-way valve is configured to place the fourth chamber in fluid communication with a first separator; and

the first three-way valve is configured to place the second chamber in fluid communication with a second separator that is in fluid communication with an outlet.

[1108] 41. The apparatus of claim 37, wherein the second pulsation damper bottle is elongated.

[1109] 42. The apparatus of claim 41, wherein the second pulsation damper bottle is elongated in a dimension facilitating connection with the second chamber and with the fourth chamber.

[1110] 43. The apparatus of claim 21 further wherein the liquid source is in communication with the sprayer through a manifold.

[1111] 44. The apparatus of claim 21 wherein the sprayer comprises an orifice in a wall of the first chamber.

[1112] 45. The apparatus of claim 21 wherein the sprayer comprises a nozzle.

[1113] 46. The apparatus of claim 21 further comprising a plurality of sprayers in liquid communication with a manifold and configured to inject a plurality of liquid spray trajectories.

[1114] 47. The apparatus of claim 46 wherein the plurality of sprayers are located at different positions in a direction of flow of gas through the first chamber.

[1115] 48. The apparatus of claim 21 wherein the valve comprises a solenoid-actuated valve, a pneumatic-actuated valve, a hydraulic-actuated valve, a voice coil-actuated valve, or a cam-actuated valve.

[1116] 49. The apparatus of claim 21 further comprising an ultrasonic transducer in acoustic communication with the valve.

[1117] 50. The apparatus of claim 21 wherein the moveable member comprises a solid piston comprising a piston shaft and a piston head.

[1118] 51. The apparatus of claim 50 wherein the moveable member comprises a double-acting piston disposed within a cylinder to define the first chamber and a third chamber in fluid communication with the first chamber through a second valve.

[1119] 52. The apparatus of claim 51 wherein the second chamber is in fluid communication with a separator through a third valve, and the third chamber is in fluid communication with the separator through a fourth valve.

[1120] 53. The apparatus of claim 52 wherein:

the valve comprises a first valve plate disposed to move toward a first valve seat when a pressure within the second chamber exceeds a pressure within the first chamber;

the second valve comprises a second valve plate disposed to move toward a second valve seat when a pressure within the third chamber exceeds a pressure within the first chamber;

the third valve comprises a third valve plate configured to move away from a third valve seat when the pressure within the second chamber exceeds a pressure within the separator; and

the fourth valve comprises a fourth valve plate configured to move away from a fourth valve seat when the pressure within the third chamber exceeds the pressure within the separator.

[1121] 54. A method comprising:

providing a chamber having a moveable member disposed therein, the chamber in selective fluid communication with a high pressure side through a first valve, and in selective fluid communication with a low pressure side through a second valve;

in a first expansion stroke of the moveable member,

closing the second valve and opening the first valve to admit compressed gas from the high pressure side into the chamber, and

allowing the compressed gas to expand within the chamber and drive the moveable member to generate energy; and

in a second expansion stroke of the moveable member in an opposite direction as the first expansion stroke,

opening the second valve to allow gas expanded during the first expansion stroke to flow to the low pressure side, and

raising a pressure within the chamber prior to the end of the second expansion stroke.

[1122] 55. The method of claim 54 wherein the pressure is raised by closing the second valve prior to an end of the second expansion stroke.

[1123] 56. The method of claim 55 further comprising introducing liquid into the cylinder prior to the end of the second expansion stroke.

[1124] 57. The method of claim 56 wherein the liquid is injected into the compressed gas outside of the chamber.

[1125] 58. The method of claim 56 wherein the liquid is flowed directly into the chamber.

[1126] 59. The method of claim 54 wherein the pressure is raised by introducing liquid into the cylinder prior to an end of the second expansion stroke.

[1127] 60. The method of claim 59 wherein the liquid is injected into the compressed gas outside of the chamber.

[1128] 61. The method of claim 59 wherein the liquid is flowed directly into the chamber.

[1129] 62. The method of claim 54 further comprising closing the first valve during the first expansion stroke once a quantity of compressed gas has been admitted to the chamber to give rise to a pressure approximately equal to the low pressure side at an end of the first expansion stroke.

[1130] 63. The method of claim 54 wherein:

the first valve comprises a first valve plate disposed to move away from a first valve seat when pressure within the chamber exceeds a pressure on the high pressure side; and

the second valve comprises a second valve plate disposed to move toward a second valve seat when pressure within the chamber exceeds a pressure on the low pressure side.

[1131] 64. The method of claim 54 wherein:

providing the chamber comprises providing the chamber having a double acting piston disposed therein to define the chamber and a second chamber, the second chamber in selective fluid communication with a high pressure side through a third valve, and in selective fluid communication with a low pressure side through a fourth valve; and

wherein in the first expansion stroke of the moveable member, the method further comprises,

opening the fourth valve to allow gas expanded in the second chamber during a previous expansion stroke to flow to the low pressure side, and

and raising a pressure within the second chamber prior to the end of the first expansion stroke.

[1132] 65. The method of claim 64 wherein the pressure is raised by closing the fourth valve prior to an end of the first expansion stroke.

[1133] 66. The method of claim 65 further comprising introducing liquid into the cylinder prior to the end of the first expansion stroke.

[1134] 67. The method of claim 66 wherein the liquid is injected into the compressed gas outside of the second chamber.

[1135] 68. The method of claim 66 wherein the liquid is flowed directly into the second chamber.

[1136] 69. The method of claim 64 wherein the pressure is raised by introducing liquid into the cylinder prior to an end of the first expansion stroke.

[1137] 70. The method of claim 69 wherein the liquid is injected into the compressed gas outside of the second chamber.

[1138] 71. The method of claim 69 wherein the liquid is flowed directly into the second chamber.

[1139] 72. The method of claim 64 wherein:

the first valve comprises a first valve plate disposed to move away from a first valve seat when pressure within the chamber exceeds a pressure on the high pressure side;

the second valve comprises a second valve plate disposed to move toward a second valve seat when pressure within the chamber exceeds a pressure on the low pressure side;

the third valve comprises a third valve plate disposed to move away from a third valve seat when pressure within the second chamber exceeds a pressure on the high pressure side; and

the fourth valve comprises a fourth valve plate disposed to move toward a fourth valve seat when pressure within the second chamber exceeds a pressure on the low pressure side.

[1140] Storage and recovery of energy from compressed gas may be enhanced utilizing one or more techniques, applied alone or in combination. One technique introduces a mist of liquid droplets to a dedicated chamber positioned upstream of a second chamber in which gas compression and/or expansion is to take place. In some embodiments, uniformity of the resulting liquid-gas mixture may be enhanced by interposing a pulsation damper bottle between the dedicated mixing chamber and the second chamber, allowing continuous flow through the mixing chamber. Another technique utilizes valve configurations actuable with low energy, to control flows of gas to and from a compression and/or expansion chamber. The valve configuration utilizes inherent pressure differentials arising during system operation, to allow valve actuation with low consumption of energy.

[1141] Certain embodiments of the present invention may provide a liquid-gas mixture during the compression and/or expansion processes. An elevated heat capacity of the liquid relative to the gas, allows the liquid to receive heat from the gas during compression, and allows the liquid to transfer heat to the gas during expansion. This transfer of energy to and from the liquid may be enhanced by a large surface area of the liquid, if the liquid is introduced as a mist or a spray of droplets within the compressing or expanding air.

[1142] In general, liquid introduced to a gas compression or expansion chamber to accomplish heat exchange according to embodiments of the present invention, is not expected to undergo combustion within that chamber. Thus while the liquid being injected to perform heat exchange may be combustible (for example an oil, alcohol, kerosene, diesel, or biodiesel), in many embodiments it is not anticipated that the liquid will combust within the chamber. In at least this respect, liquid introduction according to embodiments of the present invention may differ from cases where liquids are introduced into turbines and motors for combustion.

[1143] Cost and inefficiency of variable frequency drives are another possible area of improvement. A synchronous motor generator with load control could instead be used, and on the compressor/expander, the valve pulse length and frequency may be controlled to vary the power for voltage and frequency regulation. Such an approach could trade off efficiency in exchange for increased or decreased power in real time.

[1144] According to embodiments of the present invention, energy may be imparted to a gas by compression, and/or recovered from a gas by expansion, utilizing a moveable member present within the chamber. In certain embodiments the moveable member may be in communication with other system

elements (such as a motor or generator) through one or more physical linkages mechanical, hydraulic, pneumatic, magnetic, electro-magnetic, or electrostatic in nature.

[1145] In some embodiments, the moveable member may communicate exclusively through linkages of one particular type. For example, certain embodiments of the present invention may communicate energy to/from the moveable member exclusively utilizing mechanical linkages which may include a rotating shaft. Such configurations may offer enhanced efficiency by avoiding losses associated with conversion of energy between one form and another.

[1146] Certain embodiments may utilize hydraulic linkages with the moveable member.

[1147] Conditions of the liquid/gas mixture (including but not limited to droplet size, uniformity of droplet distribution, spray velocity, liquid volume fraction, temperature, and pressure) may influence the exchange of thermal energy between the gas and the liquid. While certain embodiments previously described introduce liquids utilizing a mixing chamber, this is not required by the present invention. Some embodiments may utilize liquid injection directly into a compression chamber, expansion chamber, or chamber in which expansion and compression are performed.

[1148] For example, Figure 50A shows a simplified schematic diagram of one possible embodiment of an energy storage apparatus according to the present invention, which may utilize compressed air as the gas, and water as the injected liquid. Figure 50A shows system 5002 comprising moveable member 5006 (here a reciprocating solid piston comprising a piston head and piston rod) disposed within cylinder 5008 having compression chambers 5018a and 5018b.

[1149] In certain embodiments (not limited to that particularly shown in Figure 50A), the piston may be of a cross-head design. Such embodiments may provide additional benefit by further isolating the water of the expansion/compression cylinder from the oil or other liquid likely present in a crankcase.

[1150] The moveable member may be in selective physical communication with a motor, generator, or motor/generator 5098 through one or more linkages 5099. These linkages may be mechanical, hydraulic, or pneumatic in nature.

[1151] In certain embodiments the piston may be a free piston. Such a free piston could communicate energy through a physical linkage such as a magnetic or electromagnetic linkage.

[1152] In certain embodiments the piston may comprise a piston head and a piston rod that is coupled to a linkage. This linkage could comprise circular gears, and/or gears having another shape (such as elliptical). In certain embodiments the teeth of one or more gears could have a straight, beveled, or helical shape, with the latter possibly providing a thrust bearing. In certain embodiments worm gears could be used.

[1153] A wide variety of mechanical linkages are possible. Examples include but are not limited to multi-node gearing systems such as planetary gear systems. Examples of mechanical linkages include shafts such as crankshafts, chains, belts, driver-follower linkages, pivot linkages, Peaucellier-Lipkin linkages, Sarrus linkages, Scott Russel linkages, Chebyshev linkages, Hoekins linkages, swashplate or wobble plate linkages, bent axis linkages, Watts linkages, track follower linkages, and cam linkages. Cam linkages may employ cams of different shapes, including but not limited to sinusoidal and other

shapes. Various types of mechanical linkages are described in Jones in "Ingenious Mechanisms for Designers and Inventors, Vols. I and II", The Industrial Press (New York 1935), which is hereby incorporated by reference in its entirety herein for all purposes.

[1154] While the particular embodiment shown in Figure 50A utilizes a piston that is disposed to move horizontally, the present invention is not limited to such a design. Alternative embodiments could employ pistons or other types of members that are disposed to move in other directions (for example vertically, diagonally),

[1155] For example, in certain embodiments, it may be useful to have the piston be configured to reciprocate in the vertical direction, with the compression and/or expansion chamber located below. An example of this type of configuration has already been shown in FIG. 6, although such embodiments do not require bubbling and liquid introduction by spraying could alternatively be used. This type of configuration could help to avoid liquid from leaking out of the chamber through the packing under the force of gravity, and undesirably entering a crankcase or other space.

[1156] Particular embodiments of the present invention may include one or more stages having a moveable member that moves in other than a linear manner. For example, members of certain apparatuses such as screws, quasi-turbines, gerotors, and other structures, are configured to move in a rotational manner.

[1157] Various types of structures that may be useful for the compression and/or expansion of gas are disclosed by Charles Fayette Taylor in "The Internal Combustion Engine in Theory and Practice, Vols. 1 and 2", 2nd Ed., Revised, The MIT Press (1985), which is incorporated by reference in its entirety herein for all purposes.

[1158] Certain embodiments in accordance with the present invention may utilize tuned intake and exhaust ports. Specifically, the inlet manifold, conduits, valves, and cylinder (or cylinders) in general form a complex resonant system. The gas to be compressed or expanded moves through this resonant system, reflecting off of walls whenever there is a change in the cross-sectional area, and compressing and reflecting off of the gas trapped in closed cavities. An example of such a closed cavity is a conduit with a closed valve at the far end.

[1159] The inertia of the gas and these reflections generate compression and expansion waves. Analyzed using the techniques of computational fluid dynamics (CFD), it is possible to tune the geometry of the intake system so as to time the arrival of the compression waves to coincide with the closing of the intake valve or valves. This may be done, for example, by adjusting the length of the pipe leading to the cylinder.

[1160] For example, as shown in Figure 135A, shortly after the inlet valve 13500 opens at TDC of a piston 13502 moveable within a cylinder 13504, the pressure drops relative to the intake port 13506. As shown in Figure 135B, this generates an expansion wave 13508 that moves away from the valve and down the pipe.

[1161] The expansion wave travels at a speed of (s-v), where s is the speed of sound and v is the velocity of the fluid. The fluid may be a mixture of gas and liquid droplets.

[1162] As shown in Figure 135C, the wave is reflected by the opening at the far end of the pipe. The wave then travels back towards the valve as a compression wave at speed (s+v).

[1163] The arriving compression wave will help to fill the cylinder. If the pipe length is L, the total round-trip travel time for the wave is:

$$\Delta t_1 + \Delta t_2 = \frac{2sL}{s^2 - v^2}$$

[1164] To maximize the beneficial effect, this travel time may be about the same time the valve is open during a crank revolution ($\theta/2\pi N$) , where θ is the open angle and N is the rotational speed. For this to be the case:

$$L = \frac{\theta(s^2 - v^2)}{4\pi sN}$$

[1165] Thus as shown in Figure 135D, L is the pipe length that maximizes air flow into the cylinder.

[1166] Figure 135E shows the effect of varying the intake port length on the volumetric efficiency (that is, the amount of gas that can be drawn through a valve) for a typical cylinder design at different rotation speeds. The optimal pipe length is a function of rotational speed, among other variables.

[1167] The tuning just described may have the effect of pumping additional gas into the cylinder, improving volumetric efficiency. Similarly, adjusting the geometry of the exhaust system can aid in exhausting gas from the cylinder more completely, likewise improving volumetric efficiency. An analysis of these effects may be found in John L. Lumley, Engines, An Introduction, Cambridge University Press, Cambridge (1999), which is incorporated by reference in its entirety herein for all purposes.

[1168] The optimal intake and exhaust system geometry can depend on engine speed. An efficiency advantage may ensue if the mechanism is run at the particular speed that optimizes the performance of the design.

[1169] The above description has focused in large part upon use of compression/expansion apparatuses involving liquid injection. However, tuning approaches of the present invention are not limited to such devices. According to alternative embodiments, intake and/or exhaust system geometries may be tuned to use the sonic energy in the flow to improve volumetric efficiency in a variety of types of gas compressors and gas expanders.

[1170] Returning now to the particular embodiment shown in Figure 50A, on a low pressure side the compression chamber 5018a is in selective fluid communication with outside air through air cleaner 5020, low pressure side conduit 5010, suction bottle 5011, and valve 5012. Valve 5012 comprises valve plate 5012a moveable relative to valve seat 5012b to open or close the valve. In certain embodiments the valve may be actuated by a solenoid or other controllable actuator, such as a hydraulic or pneumatic piston or electric motor. Compression chamber 5018b is similarly in selective fluid communication with

the outside air through the air cleaner, the low pressure side conduit, the suction bottle, and a valve 5013 comprising a valve plate 5013a moveable relative to a valve seat 5013b.

[1171] On a high pressure side, compression chamber 5018a is in selective fluid communication with a compressed gas storage tank 5032 through valve 5022, discharge bottle 5023, high pressure side conduit 5024, baffle separator 5026, and cyclone separator 5028, respectively. Valve 5022 comprises valve plate 5022a moveable relative to valve seat 5022b to open or close the valve.

[1172] The valves of various embodiments of the present invention may be actuated by a solenoid. Various types of valve actuation are possible, including but not limited to cam-driven actuation, piezoelectric actuation, hydraulic actuation, electronic actuation, magnetic actuation, pneumatic actuation, and others. Depending upon the particular embodiment, valve actuation may be driven according to variable timing, or may be driven according to fixed timing.

[1173] While the above embodiment is described as utilizing gas flow valves in the form of plate valves, this is not required. The present invention is not limited to apparatuses utilizing any particular gas valve type, and other gas valve types may be suited for use in various embodiments. Examples of valves according to embodiments of the present invention include but are not limited to pilot valves, rotary valves, cam operated poppet valves, and hydraulically, pneumatically, or electrically actuated valves.

[1174] In certain embodiments, valves and other components may be fabricated utilizing materials which will enhance their performance. For example, certain embodiments of valves may bear a hydrophobic coating, such as TEFLON, on one or more surfaces. In some embodiments, the hydrophobic coating may include a texture to further impart a super-hydrophobic character.

[1175] Other types of coatings can be used. Certain types of coatings can inhibit corrosion and wear. One example of a possible type of coating is diamond-like carbon (DLC). Nickel/polymer coatings could also be used.

[1176] In certain embodiments, the function of one or more gas or liquid flow valves may be performed by the moveable member itself. For example as shown in Figure 84 described elsewhere in this document, in certain embodiments movement of the piston head may selectively obstruct a port to the chamber, thereby effectively serving as a valve.

[1177] Compression chamber 5008b is similarly in selective fluid communication with the air storage tank through valve 5027, the high pressure side conduit, the baffle separator, and the cyclone separator, respectively. Valve 5027 comprises a valve plate 5027a moveable relative to a valve seat 5027b, in certain embodiments by a solenoid.

[1178] The compressed gas storage tank 5032 is in fluid communication with a muffler 5052 through a pressure regulator 5054. The air storage tank 5032 is also in liquid communication with a pressurized water tank 5030 of the liquid circulation system through a float valve.

[1179] A variety of types of compressed gas storage units may be suitable for use in different embodiments of the present invention. For example, in certain embodiments a compressed gas storage unit may comprise enclosed volumes having a high capacity, for example man-made structures such as

abandoned mines, or oil or natural gas fields. High volumes of compressed gas may also be stored in naturally-occurring geological formations such as caverns, salt domes, or other porous features.

[1180] Other suitable compressed gas storage units may include vessels specially constructed for this purpose. In certain embodiments the gas may be stored in one or more steel tanks (which may be selectively connected with each other) having a length of about 1.6 meters and which are capable of storing air at 200 atmospheres and equipped with a valve. Some embodiments may utilize larger steel tank(s) having a length of about 16 meters long, which could reduce a cost of spinning the tank closed and to a neck, and could also reduce the cost of the valves.

[1181] Embodiments of the present invention may utilize a compressed gas storage unit made out of other than a simple metal material such as steel. For example, as been previously described above, certain embodiments of a compressed gas storage unit may have a special shape and/or comprise a composite material including carbon fiber or other materials.

[1182] In certain embodiments, the gas storage unit may be constructed of a composite material consisting of one or more layers of high tensile-strength wire or fiber, this wire or fiber being made of metal or natural or synthetic material and wrapped in a helical manner around an impermeable liner and secured in place by a matrix material. The advantage of using high tensile-strength drawn wire is that it is much stronger in tension than the equivalent weight of the same alloy in bulk form, so less material may be used, reducing cost.

[1183] In certain embodiments, a compressed gas storage unit may be in thermal communication with an energy source. For example, in certain embodiments the storage unit may comprise a tank in thermal communication with the sun. The tank could be coated with a thermal-absorbing material (for example black paint). In certain embodiments the storage unit could be positioned behind a transparent barrier (such as glass), such that infra-red (IR) solar energy is trapped and further promotes thermal communication.

[1184] Operation of the system of Figure 50A is similar to that described in many of the figures shown above. The moveable member 5006 moves in a reciprocating manner within the cylinder. Movement of the member 5006 to the right side corresponding to Bottom Dead Center (BDC) of chamber 5018a, results in a pressure differential arising between chamber 5008a and the suction bottle of the low pressure side. This pressure differential biases valve plate 5012a away from valve seat 5012b, allowing valve 5012 to open and admit uncompressed air into the chamber 5018a. This pressure differential between chamber 5018a and discharge bottle also biases valve plate 5022a toward valve seat 5022b, closing valve 5022 to allow the admitted uncompressed air to accumulate in the chamber 5018a.

[1185] The same motion of the moveable member (toward BDC) of chamber 5018a, which is TDC of chamber 5018b) in this stroke, also creates a pressure differential between the chamber 5018b and the suction bottle. Specifically, air admitted into the chamber 5018b during the previous stroke is compressed, thereby biasing valve plate 5013a toward valve seat 5013b and closing valve 5013.

[1186] The pressure differential between chamber 5018b and the discharge bottle maintains valve 5027 in the closed state. However, as the moveable member continues to move toward BDC, the

pressure within chamber 5018b rises. When this pressure within chamber 5018b reaches that of the discharge bottle on the high pressure side, valve plate 5027a ceases to be biased toward valve seat 5027b, and the valve 5027 is opened, allowing the compressed gas to move out to the discharge bottle and ultimately to the storage unit through the conduit and the baffle and cyclone separators.

[1187] In the following stroke of the moveable member 5006 toward the left, which is Top Dead Center (TDC) of chamber 5018a and BDC of chamber 5018b, the compression chambers 5018a and 5018b switch roles. That is, uncompressed gas is admitted into chamber 5018b through open valve 5013, while uncompressed gas previously admitted to chamber 5018a is compressed by the moveable member until it reaches high pressure and flows out through valve 5022 actuated by a slight pressure differential over the high pressure side.

[1188] As shown in Figure 50A, a suction bottle positioned on the low pressure side upstream of the inlet valves to the compression chambers, and a discharge bottle is positioned on the high pressure side downstream of the outlet valves of the compression chambers. The volumes of these bottles are significantly larger than the volumes of each of the compression chambers, and in general at least 10x the volume of those compression chambers.

[1189] The bottles exhibit a width dimension (w, w') that is different from that of their inlets and outlets. The dimensional difference creates a succession of impedance mismatches for any acoustic waves attempting to travel from the valves of the compression chamber to the rest of the system, thereby disrupting unwanted changes in pressure. By imposing the suction bottle and the discharge bottle between the gas valves and the other elements of the system, embodiments according to the present invention can suppress these pulsations.

[1190] During compression, gas within the chamber experiences an increase in temperature. To allow this compression to proceed in a thermodynamically efficient manner, embodiments of the present invention create a liquid-gas mixture by directly spraying droplets of liquid (here water) into the chamber. The liquid component of the liquid-gas mixture absorbs thermal energy from the gas under compression, thereby reducing the magnitude of any temperature increase.

[1191] Accordingly, Figure 50A also shows a liquid circulation system that is configured to flow liquid for injection into the chambers for exchange of heat with the gas undergoing the compression process. In particular, this liquid circulation system comprises a pressurized water tank 5030 in fluid communication with the compression chambers through a conduit 5088, transfer pump 5042, heat exchanger 5044, valve 5047, a multi-stage water pump 5031, valves 5033 and 5034, and respective spray nozzles 5035 and 5036. An accumulator 5039 is in fluid communication with the liquid circulation system to absorb pulsations of energy arising therein.

[1192] Valves 5033 and 5034 are actuable to allow water to flow through the spray nozzles 5035 and 5036 into the respective compression chambers 5018a and 5018b at select times. In certain embodiments, the valves may be configured to be opened to flow liquid into the compression chambers at the same time that air is being admitted. In such embodiments, direct liquid injection coincident with

inlet air flow, may promote mixing of the water droplets within the air, enhancing the effectiveness of the desired heat exchange.

[1193] In certain embodiments, the valves 5033 and 5034 may be configured to be opened to flow liquid into the compression chambers only once the air has already been admitted and the respective gas inlet valve has been closed. In such embodiments, direct liquid injection into the closed chamber may serve to compress the air in addition to performing heat exchange.

[1194] In certain embodiments, the valves 5033 and 5034 may be configured to be opened during movement of the member within the closed chamber to compress the gas. As is discussed below, in certain embodiments liquid injection into gas undergoing compression, may take place utilizing more than one subsystem of sprayers having different characteristics.

[1195] In some embodiments, actuation of the valves 5033 and 5034 may allow a flow of liquid to the chamber over multiple periods of a compression cycle. For example, the valves may be actuated both during and after air inlet but prior to compression, or may be actuated after air inlet and during compression, or may be actuated during air inlet and during compression.

[1196] As just indicated, in certain embodiments the liquid may not be continuously introduced into the compression chamber. Moreover, during periods when liquid is not being introduced, the compression chamber may experience changing pressures as the member moves within the chamber, and/or compressed gas flows from the chamber.

[1197] Accordingly, the valves 5033 and 5034 in Figure 50A can serve to isolate the sprayers from other components of the liquid circulation system during such periods of non-injection. This isolation helps to prevent changes in liquid pressure (such as transient back pressures), that could adversely affect the flows of liquid through the system. In embodiments where liquid is being introduced in a continuous manner, the liquid flow valves may not be needed.

[1198] The liquid circulation system may include other features that are designed to avoid the effects of pressure changes within the liquid. For example during system operation the circulating water is injected into the gas to create a liquid-gas mixture that undergoes compression to a higher pressure. Liquid is then removed from this high pressure liquid-gas mixture by the separators.

[1199] As a result of the compression process, however, some amount of gas may be dissolved in the liquid. Then, as the separated liquid flowed through the liquid circulating system encounters the inlet gas at low pressure, this dissolved gas may come out of solution (outgas).

[1200] Such outgassing can create unwanted bubbles in various portions of the liquid circulation system, most notably in the valves 5033 and 5034, spray nozzles 5035 and 5036, and/or the respective conduits 5060 and 5061 between those elements. The presence of such bubbles in these locations of the liquid circulation system could interfere with the predictability and/or reliability of the controlled flows of liquid into the compression chambers.

[1201] Accordingly, certain embodiments of the present invention may seek to make as short as possible, the lengths (d, d') of the conduits between the liquid flow valves and the spray nozzles that are

exposed to the low pressure. Such minimization of distance can effectively reduce the opportunity for outgassing from the pressurized liquid, thereby desirably avoiding bubble formation.

[1202] In the particular embodiment of Figure 50A, the liquid flow valves 5033 and 5034 are shown as being selectively actuated by a solenoid. However, the present invention is not limited to using any particular type of valve for liquid injection. Examples of valves which may be suitable for liquid injection according to embodiments of the present invention include, but are not limited to, solenoid-actuated valves, spool valves, gate valves, cylindrical valves, needle valves, or poppet valves.

[1203] One example of an alternative valve design which may be suitable for use in the present invention, is a voice coil-actuated valve that includes a servo loop. Use of such a valve structure may be advantageous to control the velocity profile of actuation, for example reducing velocity at the end of plate travel prior to a stop, thereby relieving stress on valve components.

[1204] Other approaches to valve dampening are possible. For example, certain embodiments could use air cushions, dimples, cylindrical holes, and or other geometries of depression in the valve body or valve seat, with corresponding raised areas on the opposite member, to create air springs that absorb some of the energy of the motion of the movable component of the valve as it approaches the valve seat.

[1205] According to other embodiments the valves may be pneumatically actuated, an example being a proportional pneumatic air valve. In still other embodiments, the valves may be hydraulically actuated, for example a high pressure hydraulic valve

[1206] In certain embodiments, it may be desirable to create a mixture having liquid droplets of a particular size. In some embodiments, formation of such a mixture may be facilitated by the inclusion of a surfactant in the liquid. One example of a surfactant which may be used is octylphenoxypolyethoxyethanol and known as Triton X-100.

[1207] After compression, the liquid-gas mixture is flowed through the respective outlet valves 5022 and 5027 to the discharge bottle 5023, the high pressure side conduit 5024, and the separators 5026, 5028 where liquid is removed. The baffle separator structure 5026 employs a first structure designed to initially remove bulk amounts of liquid from the flowed gas-liquid mixture. An example of such a structure is a chamber having a series of overlapping plates or baffles defining a serpentine path for the flowed mixture, and offering a large surface area for water coalescence.

[1208] In the specific embodiment of Figure 50A, the initial baffle separator structure is followed in series by the second separator structure 5028 (here a cyclone separator), that is designed to remove smaller amounts of liquid from the mixture. Embodiments of the present invention are not limited to this or any particular type of separator or separator configuration. Examples of separators which may potentially be used, include but are not limited to, cyclone separators, centrifugal separators, gravity separators, and demister separators (utilizing a mesh type coalescer, a vane pack, or another structure). Various separator designs are described in M. Stewart and K. Arnold, Gas-Liquid and Liquid-Liquid Separators, Gulf Professional Publishing (2008), which is incorporated by reference in its entirety herein for all purposes.

[1209] Liquid removed from the mixture by the separators 5026 and 5028, is returned via respective float valves 5027 and conduits to the pressurized water tank 5030, which includes a pressure relief valve and a drain valve. From the pressurized water tank, the liquid is recirculated utilizing transfer pump 5042 through heat exchanger 5044 for cooling, and then by multi-stage water pump 5031 for reinjection into the compression chambers.

[1210] The liquid circulation system of Figure 50A is also in selective fluid communication with a water supply tank 5046 through valve 5048. This tank receives unpressurized water through a filter 5050 from a base water supply (such as a municipal water supply). Water from this supply tank may be selectively flowed through valve 5048 to initially charge, or to replenish, the water of the circulation system. Water supply tank 5046 also includes a vacuum relief valve and a drain valve.

[1211] In the particular embodiment of Figure 50A, the sprayers are arranged on opposing end walls of the cylinder that do not also include the gas flow valves. The sprayers may comprise an arrangement of one or more orifices or nozzles that create liquid droplets, jets, or sheets, and facilitate exchange of thermal energy with gas inside the chamber. These nozzles or orifices may be in liquid communication with a common manifold.

[1212] The present invention is not limited to the introduction of liquid into the chamber through any particular type of sprayer. Some examples of possible nozzle structures which may be suited for use in accordance with embodiments of the present invention are described in the following U.S. patents, each of which is incorporated by reference herein for all purposes: U.S. Patent No. 3,659,787; U.S. Patent No. 4,905,911; U.S. Patent No. 2,745,701, U.S. Patent No. 2,284,443; U.S. Patent No. 4,097,000; and U.S. Patent No. 3,858,812.

[1213] One type of spray structure which may be utilized to introduce liquid according to embodiments of the present invention, is an impingement sprayer. An example of such an impingement sprayer structure is the PJ Misting Nozzle available from BETE Fog Nozzle, Inc., of Greenfield, Massachusetts. In certain embodiments, a liquid sprayer may use energy in addition to liquid flow, for example sonic energy, in order to form droplets having the desired characteristics.

[1214] Still other types of spray structures are known. Examples of spray structures which may be suited for use in accordance with embodiments of the present invention, include but are not limited to rotating disk atomizers, electrostatic atomizers, pressure swirl nozzles, fan jet nozzles, impact nozzles, and rotating cup atomizers.

[1215] In certain embodiments, a plurality of sprayers may be configured to interact with one another to produce a spray having the desired character. For example, the spray of one nozzle may fill a vacant portion of an adjacent nozzle. The following patents and published patent applications describing various configurations of sprayers, are incorporated by reference in their entireties herein for all purposes: U.S. Patent No. 6,206,660; U.S. Patent Publication No. 2004/0244580; and U.S. Patent Publication No. 2003/0180155.

[1216] Embodiments according to the present invention are not limited to the use of sprayers to introduce liquids into gases. According to alternative embodiments, one or more stages of a compressed

gas energy storage apparatus according to the present invention could introduce liquids through the use of bubblers, as has previously been described in connection with Fig. 6.

[1217] At high pressures, the volume fraction of liquid to achieve a high mass fraction of liquid, may be so large that a liquid droplet – gas aerosol may be difficult to sustain. Instead, the volume fraction may turn into "slug flow" or "annular flow".

[1218] Such slug flow or annular flow may be undesirable in that it does not permit rapid heat transfer. In addition, such slug flow or annular flow may cause mechanical problems or degradation of valve performance.

[1219] Introducing gas into the liquid in bubble form, however, supports a high surface area of contact between gas and liquid without leading to non-uniform flows. Certain embodiments may utilize a sparger pattern that creates a convection-like flow within the liquid. Such flow may increase the rate of heat transfer between the gas in the bubbles and the liquid, by distributing the bubbles more uniformly in the cylinder.

[1220] The apparatus of Figure 50A further includes a controller/processor 5096 in electronic communication with a computer-readable storage device 5094, which may be of any design, including but not limited to those based on semiconductor principles, or magnetic or optical storage principles. Controller/processor 5096 is shown as being in electronic communication with a universe of active elements in the system, including but not limited to valves, pumps, sprayers, and sensors. Specific examples of sensors utilized by the system include but are not limited to pressure sensors (P), temperature sensors (T), volume sensors (V), a humidity sensor (H) located at the inlet of the system, and other sensors (S) which may indicate the state of a moveable component such as a valve or piston, or another parameter of the system.

[1221] As described in detail below, based upon input received from one or more system elements, and also possibly values calculated from those inputs, controller/processor 96 may dynamically control operation of the system to achieve one or more objectives, including but not limited to maximized or controlled efficiency of compression, controlled consumption of power to store energy in the form of compressed gas; an expected input speed of the moveable member that is performing compression; a maximum input speed of a rotating shaft in communication with the moveable member; a maximum input torque of a rotating shaft in communication with the moveable member; a minimum input speed of a rotating shaft in communication with the moveable member; a minimum input torque of a rotating shaft in communication with the moveable member; or a maximum expected temperature increase of water at different stages of a multi-stage apparatus (discussed below); or a maximum expected temperature increase of air at different stages of a multi-stage apparatus.

[1222] Code that is present on the computer-readable storage medium may be configured to direct the controller or processor to cause the system to perform in various modes of operation. For example, while Figure 50A shows an apparatus that is configured to operate as a dedicated compressor, this is not required by the present invention. Alternative embodiments could be configurable to function as

dedicated expanders, converting the energy stored in the compressed gas, into power to perform useful work (for example electrical power output onto a power grid).

[1223] Figure 50B shows a simplified view of such an embodiment of a dedicated expander. The embodiment of Figure 50B operates along similar principles as that of Figure 50A, except that chambers serve to receive compressed air from the storage tank on the high pressure side. The piston rod moves in response to gas expanding within the chamber. Liquid injected into the chambers serves to transfer heat to expanding air, reducing an amount of a temperature decrease. The liquid separators (depicted here as a single unit for ease of illustration) are positioned on the low pressure side to remove the liquid for recirculation, and then the expanded air is flowed out of the system.

[1224] Figure 51 shows a simplified schematic view of an alternative embodiment of an apparatus 500 for use in a compressed gas storage system according to the present invention. This alternative embodiment is configurable to perform compression or expansion.

[1225] Specifically, in one mode of operation the apparatus consumes power to store energy in the form of compressed gas. Compressor/expander 5102 receives energy through linkage 5132 from motor/generator 5130, which drives movement of member 5106 to compress gas that has been admitted to chamber 5108 from low pressure side conduit 5110 through valve 5112.

[1226] During compression, gas within the chamber experiences an increase in temperature. To allow this compression to proceed in a thermodynamically efficient manner, embodiments of the present invention create a liquid-gas mixture by spraying liquid droplets into the chamber. The liquid component of the liquid-gas mixture receives thermal energy from the gas under compression, thereby reducing the magnitude of any temperature increase.

[1227] Compressed gas is then flowed through valve 5122 to the high pressure side conduit 5120 and separator element 5124 (which may comprise multiple separators) to storage unit 5126. Liquid removed from the mixture is contained in reservoir 5125, from where it can be cooled by exposure through heat exchanger 5150 to heat sink 5140, and then flowed by pump 5134 for re-injection into the chamber containing additional gas for compression.

[1228] In another mode of operation of the system 5100, energy is recovered by expansion of the compressed gas. Compressor/expander 5102 receives compressed gas from storage unit 5126 through high pressure side conduit 5120 and valve 5122, and allows the compressed gas to expand in the chamber 5108 to cause motion of the moveable member 5106. The expanded air is flowed through valve 5112 and low pressure side conduit 5110 as exhaust. Motor/generator 5130 operates as a generator, receiving energy from the motion of the moveable member, and outputting electrical power.

[1229] During expansion, gas within the chamber experiences a decrease in temperature. To allow this expansion to proceed in a thermodynamically efficient manner, embodiments of the present invention create a liquid-gas mixture by spraying liquid droplets into the chamber. The liquid component of the liquid-gas mixture transfers thermal energy to the gas under expansion, thereby reducing the magnitude of any temperature decrease.

[1230] After expansion, the liquid-gas mixture is flowed through valve 5112 and low pressure side conduit 5110 to liquid separator 5114. Liquid removed from the mixture is contained in reservoir 5115, from where it can be heated by exposure through heat exchanger 5152 to heat source 5154, and then flowed by pump 5134 for re-injection into the chamber containing additional compressed gas for expansion.

[1231] While the particular embodiment of Figure 51 shows a cylinder housing a single piston acting in the vertical direction and accessed via a valve assembly comprising two valves, the present invention is not limited to this particular configuration. Embodiments according to the present invention may utilize other configurations, for example a double acting piston moveable in the horizontal direction and housed within a valve and cylinder assembly comprising four valves, as has been previously described in detail.

[1232] As described in detail above, embodiments of systems and methods for storing and recovering energy according to the present invention are particularly suited for implementation in conjunction with a host computer including a processor and a computer-readable storage medium. Such a processor and computer-readable storage medium may be embedded in the apparatus, and/or may be controlled or monitored through external input/output devices.

[1233] Figure 52 is a schematic diagram showing the relationship between the processor/controller, and the various inputs received, functions performed, and outputs produced by the processor controller. As indicated, the processor may control various operational properties of the apparatus, based upon one or more inputs. Such operational parameters include but are not limited to the timing of opening/closing of gas flow valves and liquid flow valves, as described in detail above.

[1234] Figures 20-20A previously described show simplified diagrams of a computing device for processing information according to an embodiment of the present invention. This diagram is merely an example, which should not limit the scope of the claims herein. One of ordinary skill in the art would recognize many other variations, modifications, and alternatives. Embodiments according to the present invention can be implemented in a single application program such as a browser, or can be implemented as multiple programs in a distributed computing environment, such as a workstation, personal computer or a remote terminal in a client server relationship.

[1235] Because of its ubiquity and large heat capacity, liquid water is one medium that is commonly used in exchanging thermal energy with a heat sink or heat source. However, the thermal exchange properties of liquid water can be limited by changes in phase.

[1236] For example, liquid water at room temperature can absorb heat from a compressed gas and experience a positive temperature change of about > +80ºC, before undergoing a phase change to a gas. However, room temperature liquid water can transfer heat to an expanding gas and experience a negative temperature change of only about < -15ºC, before undergoing a phase change to a solid.

[1237] This narrower range of available temperature drop, can serve as a constraint in the operation of any one stage of a multi-stage apparatus for gas expansion. However, embodiments of the present invention are not limited to the use of liquid water as a heat exchange medium. Various embodiments

could utilize other fluids for heat exchange, and remain within the scope of the present invention. For example, the freezing point of propylene glycol solutions can be well below that of liquid water, depending upon the relative amount of propylene glycol that is present. Such alternative heat exchange media could be used in environments not amenable to the flow of pure liquid water, for example at high latitudes or high elevations.

[1238] Examples of liquids or components thereof that may be used in various embodiments of the present invention, may include but are not limited to anti-freezes, surfactants, boiling point elevating agents, anti-corrosive agents, lubricating agents, foaming agents, dissolved solids, and dissolved gases.

[1239] Particular embodiments shown and described above, depict systems in which gases are inlet and exhausted to an exterior environment. An example of such a system is one that is based upon the compression and expansion of atmospheric air.

[1240] The present invention, however, is not limited to such embodiments. Alternative embodiments may be drawn to closed systems, wherein the gas that is inlet to the system for compression, is that which was exhausted during a prior expansion process. One example of such a system is where the compressed gas comprises other than air, for example helium or other gases exhibiting favorable heat capacity.

[1241] Examples of gases which may be compressed, expanded, or compressed and expanded according to certain embodiments of the present invention, in an open system or a closed system, include but are not limited to the following (ASHRAE =American Society of Heating, Refrigerating, and Air-Conditioning Engineers):

(ASHRAE No./Name/Formula/CAS No.; where available):
R-600/Butane/CH3CH2CH2CH3/106-97-8; R-600a/Isobutane/CH(CH3)2CH3/75-28-5;
R-601/Pentane/CH3CH2CH2CH2CH3/109-66-0;
R-601a/Isopentane/(CH3)2CHCH2CH3/78-78-4;
R-610/Diethyl ether/C2H5OC2H5/60-29-7; R-611/Methyl formate/C2H4O/107-31-3;
R-630/Methylamine/CH2NH2/74-89-5; R-631/Ethylamine/C2H5NH2/75-04-7;
R-702/Hydrogen/H2/1333-74-0; R-704/Helium/He/7440-59-7;
R-717/Ammonia/NH3/7664-41-7; R-718/Water/H2O/7732-18-5; R-720/Neon/Ne/7440-01-9;
R-728/Nitrogen/N2/7727-37-9; R-732/Oxygen/O2/7782-44-7; R-740/Argon/Ar/7440–37–1;
R-744/Carbon dioxide/CO2/124-38-9; R-744A/Nitrous oxide/N2O/10024-97-2;
R-764/Sulfur dioxide/SO2/7446-09-5; R-784/Krypton/Kr/7439-90-9;
R-1112a/1,1-Dichloro-2,2-difluoroethylene/C2Cl2F2/79-35-6;
R-1113/Chlorotrifluoroethylene/C2ClF3/79-38-9; R-1114/Tetrafluoroethylene/C2F4/116-14-3;
R-1120/Trichloroethylene/C2HCl3/79-01-6;
R-1130/cis-1,2-Dichloroethylene/C2H2Cl2/156-59-2;
R-1132/1,1-Difluoroethylene/C2H2F2/75-38-7; R-1140/Chloroethylene/C2H3Cl/75-01-4;
R-1141/Fluoroethylene/C2H3F/75-02-5; R-1150/Ethylene/C2H4/74-85-1;
R-1216/Hexafluoropropylene/C3F6/116-15-4;
NA/Hexafluoropropene trimer/(C3F6)3/6792-31-0; R-1270/Propylene/C3H6/115-07-1;
R-10/Tetrachloromethane/CCl4/56-23-5; R-11/Trichlorofluoromethane/CCl3F/75-69-4;
R-12/Dichlorodifluoromethane/CCl2F2/75-71-8;
R-12B1/Bromochlorodifluoromethane/ CBrClF2/353-59-3;
R-12B2/Dibromodifluoromethane/CBr2F2/75-61-6;
R-13/Chlorotrifluoromethane/CClF3/75-72-9; R-13B1/Bromotrifluoromethane/CF3Br/75-63-8
R-14/Tetrafluoromethane/CF4/75-73-0; R-20 Trichloromethane CHCl3 67-66-3;
R-21/Dichlorofluoromethane/CHFCl2/75-43-4; R-22/Chlorodifluoromethane/CHClF2/75-45-6;

R-22B1/Bromodifluoromethane/CHBrF2/1511-62-2; R-23/Trifluoromethane/CHF3/75-46-7;
R-30/Dichloromethane/CH2Cl2/75-09-2; R-31 Chlorofluoromethane CH2FCl 593-70-4;
R-32/Difluoromethane/CH2F2/75-10-5; R-40/Chloromethane/CH3Cl/74-87-3;
R-41/Fluoromethane/CH3F/593-53-3; R-50/Methane/CH4/74-82-8;
R-110/Hexachloroethane/C2Cl6/67-72-1; R-111/Pentachlorofluoroethane/C2FCl5/354-56-3
R-112/1,1,2,2-Tetrachloro-1,2-difluoroethane/C2F2Cl4/76-12-0;
R-112a/1,1,1,2-Tetrachloro-2,2-difluoroethane/C2F2Cl4/76-11-9;
R-113/1,1,2-Trichlorotrifluoroethane/C2F3Cl3/76-13-1;
R-113a/1,1,1-Trichlorotrifluoroethane/C2F3Cl3/354-58-5;
R-114/1,2-Dichlorotetrafluoroethane/C2F4Cl2/76-14-2;
R-114a/1,1-Dichlorotetrafluoroethane/C2F4Cl2/374-07-2;
R-114B2/Dibromotetrafluoroethane/C2F4Br2/124-73-2;
R-115/Chloropentafluoroethane/C2F5Cl/76-15-3; R-116/Hexafluoroethane/C2F6/76-16-4;
R-120/Pentachloroethane/C2HCl5/76-01-7;
R-121/1,1,2,2-Tetrachloro-1-fluoroethane/C2HFCl4/354-14-3;
R-121a/1,1,1,2-Tetrachloro-2-fluoroethane/C2HFCl4/354-11-0;
R-122/1,1,2-Trichloro-2,2-difluoroethane/C2HF2Cl3/354-21-2;
R-122a/1,1,2-Trichloro-1,2-difluoroethane/C2HF2Cl3/354-15-4;
R-122b/1,1,1-Trichloro-2,2-difluoroethane/C2HF2Cl3/354-12-1;
R-123/2,2-Dichloro-1,1,1-trifluoroethane/C2HF3Cl2/306-83-2;
R-123a/1,2-Dichloro-1,1,2-trifluoroethane/C2HF3Cl2/354-23-4;
R-123b/1,1-Dichloro-1,2,2-trifluoroethane/C2HF3Cl2/812-04-4;
R-124/2-Chloro-1,1,1,2-tetrafluoroethane/C2HF4Cl/2837-89-0;
R-124a/1-Chloro-1,1,2,2-tetrafluoroethane/C2HF4Cl/354-25-6;
R-125/Pentafluoroethane/C2HF5/354-33-6;
R-E125/(Difluoromethoxy)(trifluoro)methane/C2HF5O/3822-68-2;
R-130/1,1,2,2-Tetrachloroethane/C2H2Cl4/79-34-5;
R-130a/1,1,1,2-Tetrachloroethane/C2H2Cl4/630-20-6;
R-131/1,1,2-trichloro-2-fluoroethane/C2H2FCl3/359-28-4;
R-131a/1,1,2-trichloro-1-fluoroethane/C2H2FCl3/811-95-0;
R-131b/1,1,1-trichloro-2-fluoroethane/C2H2FCl3/2366-36-1;
R-132/Dichlorodifluoroethane/C2H2F2Cl2/25915-78-0;
R-132a/1,1-Dichloro-2,2-difluoroethane/C2H2F2Cl2/471-43-2;
R-132b/1,2-Dichloro-1,1-difluoroethane/C2H2F2Cl2/1649-08-7;
R-132c/1,1-Dichloro-1,2-difluoroethane/C2H2F2Cl2/1842-05-3;
R-132bB2/1,2-Dibromo-1,1-difluoroethane/C2H2Br2F2/75-82-1;
R-133/1-Chloro-1,2,2-Trifluoroethane/C2H2F3Cl/431-07-2;
R-133a/1-Chloro-2,2,2-Trifluoroethane/C2H2F3Cl/75-88-7;
R-133b/1-Chloro-1,1,2-Trifluoroethane/C2H2F3Cl/421-04-5;
R-134/1,1,2,2-Tetrafluoroethane/C2H2F4/359-35-3;
R-134a/1,1,1,2-Tetrafluoroethane/C2H2F4/811-97-2;
R-E134/Bis(difluoromethyl)ether/C2H2F4O/1691-17-4;
R-140/1,1,2-Trichloroethane/C2H3Cl3/79-00-5;
R-140a/1,1,1-Trichloroethane/C2H3Cl3/71-55-6;
R-141/1,2-Dichloro-1-fluoroethane/C2H3FCl2/430-57-9;
R-141B2/1,2-Dibromo-1-fluoroethane/C2H3Br2F/358-97-4;
R-141a/1,1-Dichloro-2-fluoroethane/C2H3FCl2/430-53-5;
R-141b/1,1-Dichloro-1-fluoroethane/C2H3FCl2/1717-00-6;
R-142/Chlorodifluoroethane/C2H3F2Cl/25497-29-4;
R-142a/1-Chloro-1,2-difluoroethane/C2H3F2Cl/25497-29-4;
R-142b/1-Chloro-1,1-difluoroethane/C2H3F2Cl/75-68-3;
R-143/1,1,2-Trifluoroethane/C2H3F3/430-66-0 300;
R-143a/1,1,1-Trifluoroethane/C2H3F3/420-46-2 3,800;
R-143m/Methyl trifluoromethyl ether/C2H3F3O/421-14-7;
R-E143a/2,2,2-Trifluoroethyl methyl ether/C3H5F3O/460-43-5;
R-150/1,2-Dichloroethane/C2H4Cl2/107-06-2;

R-150a/1,1-Dichloroethane/C2H4Cl2/75-34-3;
R-151/Chlorofluoroethane/C2H4ClF/110587-14-9;
R-151a/1-Chloro-1-fluoroethane/C2H4ClF/1615-75-4;
R-152/1,2-Difluoroethane/C2H4F2/624-72-6;
R-152a/1,1-Difluoroethane/C2H4F2/75-37-6;
R-160/Chloroethane/C2H5Cl/75-00-3;
R-161/Fluoroethane/C2H5F/353-36-6;
R-170/Ethane/C2H6/74-84-0;
R-211/1,1,1,2,2,3,3-Heptachloro-3-fluoropropane/C3FCl7/422-78-6;
R-212/Hexachlorodifluoropropane/C3F2Cl6/76546-99-3;
R-213/1,1,1,3,3-Pentachloro-2,2,3-trifluoropropane/C3F3Cl5/2354-06-5;
R-214/1,2,2,3-Tetrachloro-1,1,3,3-tetrafluoropropane/C3F4Cl4/2268-46-4;
R-215/1,1,1-Trichloro-2,2,3,3,3-pentafluoropropane/C3F5Cl3/4259-43-2;
R-216/1,2-Dichloro-1,1,2,3,3,3-hexafluoropropane/C3F6Cl2/661-97-2;
R-216ca/1,3-Dichloro-1,1,2,2,3,3-hexafluoropropane/C3F6Cl2/662-01-1;
R-217/1-Chloro-1,1,2,2,3,3,3-heptafluoropropane/C3F7Cl/422-86-6;
R-217ba/2-Chloro-1,1,1,2,3,3,3-heptafluoropropane/C3F7Cl/76-18-6;
R-218/Octafluoropropane/C3F8/76-19-7;
R-221/1,1,1,2,2,3-Hexachloro-3-fluoropropane/C3HFCl6/422-26-4;
R-222/Pentachlorodifluoropropane/C3HF2Cl5/134237-36-8;
R-222c/1,1,1,3,3-Pentachloro-2,2-difluoropropane/C3HF2Cl5/422-49-1;
R-223/Tetrachlorotrifluoropropane/C3HF3Cl4/134237-37-9;
R-223ca/1,1,3,3-Tetrachloro-1,2,2-trifluoropropane/C3HF3Cl4/422-52-6;
R-223cb/1,1,1,3-Tetrachloro-2,2,3-trifluoropropane/C3HF3Cl4/422-50-4;
R-224/Trichlorotetrafluoropropane/C3HF4Cl3/134237-38-0;
R-224ca/1,3,3-Trichloro-1,1,2,2-tetrafluoropropane/C3HF4Cl3/422-54-8;
R-224cb/1,1,3-Trichloro-1,2,2,3-tetrafluoropropane/C3HF4Cl3/422-53-7;
R-224cc/1,1,1-Trichloro-2,2,3,3-tetrafluoropropane/C3HF4Cl3/422-51-5;
R-225/Dichloropentafluoropropane/C3HF5Cl2/127564-92-5;
R-225aa/2,2-Dichloro-1,1,1,3,3-pentafluoropropane/C3HF5Cl2/128903-21-9;
R-225ba/2,3-Dichloro-1,1,1,2,3-pentafluoropropane/C3HF5Cl2/422-48-0;
R-225bb/1,2-Dichloro-1,1,2,3,3-pentafluoropropane/C3HF5Cl2/422-44-6;
R-225ca/3,3-Dichloro-1,1,1,2,2-pentafluoropropane/C3HF5Cl2/422-56-0;
R-225cb/1,3-Dichloro-1,1,2,2,3-pentafluoropropane/C3HF5Cl2/507-55-1;
R-225cc/1,1-Dichloro-1,2,2,3,3-pentafluoropropane/C3HF5Cl2/13474-88-9;
R-225da/1,2-Dichloro-1,1,3,3,3-pentafluoropropane/C3HF5Cl2/431-86-7;
R-225ea/1,3-Dichloro-1,1,2,3,3-pentafluoropropane/C3HF5Cl2/136013-79-1;
R-225eb/1,1-Dichloro-1,2,3,3,3-pentafluoropropane/C3HF5Cl2/111512-56-2;
R-226/Chlorohexafluoropropane/C3HF6Cl/134308-72-8;
R-226ba/2-Chloro-1,1,1,2,3,3-hexafluoropropane/C3HF6Cl/51346-64-6;
R-226ca/3-Chloro-1,1,1,2,2,3-hexafluoropropane/C3HF6Cl/422-57-1;
R-226cb/1-Chloro-1,1,2,2,3,3-hexafluoropropane/C3HF6Cl/422-55-9;
R-226da/2-Chloro-1,1,1,3,3,3-hexafluoropropane/C3HF6Cl/431-87-8;
R-226ea/1-Chloro-1,1,2,3,3,3-hexafluoropropane/C3HF6Cl/359-58-0;
R-227ca/1,1,2,2,3,3,3-Heptafluoropropane/C3HF7/2252-84-8;
R-227ca2/Trifluoromethyl 1,1,2,2-tetrafluoroethyl ether/C3HF7O/2356-61-8;
R-227ea/1,1,1,2,3,3,3-Heptafluoropropane/C3HF7/431-89-0;
R-227me/Trifluoromethyl 1,2,2,2-tetrafluoroethyl ether/C3HF7O/2356-62-9;
R-231/Pentachlorofluoropropane/C3H2FCl5/134190-48-0;
R-232/Tetrachlorodifluoropropane/C3H2F2Cl4/134237-39-1;
R-232ca/1,1,3,3-Tetrachloro-2,2-difluoropropane/C3H2F2Cl4/1112-14-7;
R-232cb/1,1,1,3-Tetrachloro-2,2-difluoropropane/C3H2F2Cl4/677-54-3;
R-233/Trichlorotrifluoropropane/C3H2F3Cl3/134237-40-4;
R-233ca/1,1,3-Trichloro-2,2,3-trifluoropropane/C3H2F3Cl3/131221-36-8;
R-233cb/1,1,3-Trichloro-1,2,2-trifluoropropane/C3H2F3Cl3/421-99-8;
R-233cc/1,1,1-Trichloro-2,2,3-trifluoropropane/C3H2F3Cl3/131211-71-7;

R-234/Dichlorotetrafluoropropane/C3H2F4Cl2/127564-83-4;
R-234aa/2,2-Dichloro-1,1,3,3-tetrafluoropropane/C3H2F4Cl2/17705-30-5;
R-234ab/2,2-Dichloro-1,1,1,3-tetrafluoropropane/C3H2F4Cl2/149329-24-8;
R-234ba/1,2-Dichloro-1,2,3,3-tetrafluoropropane/C3H2F4Cl2/425-94-5;
R-234bb/2,3-Dichloro-1,1,1,2-tetrafluoropropane/C3H2F4Cl2/149329-25-9;
R-234bc/1,2-Dichloro-1,1,2,3-tetrafluoropropane/C3H2F4Cl2/149329-26-0;
R-234ca/1,3-Dichloro-1,2,2,3-tetrafluoropropane/C3H2F4Cl2/70341-81-0;
R-234cb/1,1-Dichloro-2,2,3,3-tetrafluoropropane/C3H2F4Cl2/4071-01-6;
R-234cc/1,3-Dichloro-1,1,2,2-tetrafluoropropane/C3H2F4Cl2/422-00-5;
R-234cd/1,1-Dichloro-1,2,2,3-tetrafluoropropane/C3H2F4Cl2/70192-63-1;
R-234da/2,3-Dichloro-1,1,1,3-tetrafluoropropane/C3H2F4Cl2/146916-90-7;
R-234fa/1,3-Dichloro-1,1,3,3-tetrafluoropropane/C3H2F4Cl2/76140-39-1;
R-234fb/1,1-Dichloro-1,3,3,3-tetrafluoropropane/C3H2F4Cl2/64712-27-2;
R-235/Chloropentafluoropropane/C3H2F5Cl/134237-41-5;
R-235ca/1-Chloro-1,2,2,3,3-pentafluoropropane/C3H2F5Cl/28103-66-4;
R-235cb/3-Chloro-1,1,1,2,3-pentafluoropropane/C3H2F5Cl/422-02-6;
R-235cc/1-Chloro-1,1,2,2,3-pentafluoropropane/C3H2F5Cl/679-99-2;
R-235da/2-Chloro-1,1,1,3,3-pentafluoropropane/C3H2F5Cl/134251-06-2;
R-235fa/1-Chloro-1,1,3,3,3-pentafluoropropane/C3H2F5Cl/677-55-4;
R-236cb/1,1,1,2,2,3-Hexafluoropropane/C3H2F6/677-56-5;
R-236ea/1,1,1,2,3,3-Hexafluoropropane/C3H2F6/431-63-0;
R-236fa/1,1,1,3,3,3-Hexafluoropropane/C3H2F6/690-39-1;
R-236me/1,2,2,2-Tetrafluoroethyl difluoromethyl ether/C3H2F6O/57041-67-5;
R-FE-36/Hexafluoropropane/C3H2F6/359-58-0;
R-241/Tetrachlorofluoropropane/C3H3FCl4/134190-49-1;
R-242/Trichlorodifluoropropane/C3H3F2Cl3/134237-42-6;
R-243/Dichlorotrifluoropropane/C3H3F3Cl2/134237-43-7;
R-243ca/1,3-Dichloro-1,2,2-trifluoropropane/C3H3F3Cl2/67406-68-2;
R-243cb/1,1-Dichloro-2,2,3-trifluoropropane/C3H3F3Cl2/70192-70-0;
R-243cc/1,1-Dichloro-1,2,2-trifluoropropane/C3H3F3Cl2/7125-99-7;
R-243da/2,3-Dichloro-1,1,1-trifluoropropane/C3H3F3Cl2/338-75-0;
R-243ea/1,3-Dichloro-1,2,3-trifluoropropane/C3H3F3Cl2/151771-08-3;
R-243ec/1,3-Dichloro-1,1,2-trifluoropropane/C3H3F3Cl2/149329-27-1;
R-244/Chlorotetrafluoropropane/C3H3F4Cl/134190-50-4;
R-244ba/2-Chloro-1,2,3,3-tetrafluoropropane/C3H3F4Cl;
R-244bb/2-Chloro-1,1,1,2-tetrafluoropropane/C3H3F4Cl/421-73-8;
R-244ca/3-Chloro-1,1,2,2-tetrafluoropropane/C3H3F4Cl/679-85-6;
R-244cb/1-Chloro-1,2,2,3-tetrafluoropropane/C3H3F4Cl/67406-66-0;
R-244cc/1-Chloro-1,1,2,2-tetrafluoropropane/C3H3F4Cl/421-75-0;
R-244da/2-Chloro-1,1,3,3-tetrafluoropropane/C3H3F4Cl/19041-02-2;
R-244db/2-Chloro-1,1,1,3-tetrafluoropropane/C3H3F4Cl/117970-90-8;
R-244ea/3-Chloro-1,1,2,3-tetrafluoropropane/C3H3F4Cl;
R-244eb/3-Chloro-1,1,1,2-tetrafluoropropane/C3H3F4Cl;
R-244ec/1-Chloro-1,1,2,3-tetrafluoropropane/C3H3F4Cl;
R-244fa/3-Chloro-1,1,1,3-tetrafluoropropane/C3H3F4Cl;
R-244fb/1-Chloro-1,1,3,3-tetrafluoropropane/C3H3F4Cl/2730-64-5;
R-245ca/1,1,2,2,3-Pentafluoropropane/C3H3F5/679-86-7 560;
R-245cb/Pentafluoropropane/C3H3F5/1814-88-6;
R-245ea/1,1,2,3,3-Pentafluoropropane/C3H3F5/24270-66-4;
R-245eb/1,1,1,2,3-Pentafluoropropane/C3H3F5/431-31-2;
R-245fa/1,1,1,3,3-Pentafluoropropane/C3H3F5/460-73-1;
R-245mc/Methyl pentafluoroethyl ether/C3H3F5O/22410-44-2;
R-245mf/Difluoromethyl 2,2,2-trifluoroethyl ether/C3H3F5O/1885-48-9;
R-245qc/Difluoromethyl 1,1,2-trifluoroethyl ether/C3H3F5O/69948-24-9;
R-251/Trichlorofluoropropane/C3H4FCl3/134190-51-5;
R-252/Dichlorodifluoropropane/C3H4F2Cl2/134190-52-6;

R-252ca/1,3-Dichloro-2,2-difluoropropane/C3H4F2Cl2/1112-36-3;
R-252cb/1,1-Dichloro-2,2-difluoropropane/C3H4F2Cl2/1112-01-2;
R-252dc/1,2-Dichloro-1,1-difluoropropane/C3H4F2Cl2;
R-252ec/1,1-Dichloro-1,2-difluoropropane/C3H4F2Cl2;
R-253/Chlorotrifluoropropane/C3H4F3Cl 134237-44-8;
R-253ba/2-Chloro-1,2,3-trifluoropropane/C3H4F3Cl;
R-253bb/2-Chloro-1,1,2-trifluoropropane/C3H4F3Cl;
R-253ca/1-Chloro-2,2,3-trifluoropropane/C3H4F3Cl/56758-54-4;
R-253cb/1-Chloro-1,2,2-trifluoropropane/C3H4F3Cl/70192-76-6;
R-253ea/3-Chloro-1,1,2-trifluoropropane/C3H4F3Cl;
R-253eb/1-Chloro-1,2,3-trifluoropropane/C3H4F3Cl;
R-253ec/1-Chloro-1,1,2-trifluoropropane/C3H4F3Cl;
R-253fa/3-Chloro-1,3,3-trifluoropropane/C3H4F3Cl;
R-253fb/3-Chloro-1,1,1-trifluoropropane/C3H4F3Cl/460-35-5;
R-253fc/1-Chloro-1,1,3-trifluoropropane/C3H4F3Cl;
R-254cb/1,1,2,2-Tetrafluoropropane/C3H4F4/40723-63-5;
R-254pc/Methyl 1,1,2,2-tetrafluoroethyl ether/C3H4F4O/425-88-7;
R-261/Dichlorofluoropropane/C3H5FCl2/134237-45-9;
R-261ba/1,2-Dichloro-2-fluoropropane/C3H5FCl2/420-97-3;
R-262/Chlorodifluoropropane/C3H5F2Cl/134190-53-7;
R-262ca/1-Chloro-2,2-difluoropropane/C3H5F2Cl/420-99-5;
R-262fa/3-Chloro-1,1-difluoropropane/C3H5F2Cl;
R-262fb/1-Chloro-1,3-difluoropropane/C3H5F2Cl;
R-263/Trifluoropropane/C3H5F3;
R-271/Chlorofluoropropane/C3H6FCl/134190-54-8;
R-271b/2-Chloro-2-fluoropropane/C3H6FCl/420-44-0;
R-271d/2-Chloro-1-fluoropropane/C3H6FCl;
R-271fb/1-Chloro-1-fluoropropane/C3H6FCl;
R-272/Difluoropropane/C3H6F2;
R-281/Fluoropropane/C3H7F;
R-290/Propane/C3H8/74-98-6;
R-C316/Dichlorohexafluorocyclobutane/C4Cl2F6/356-18-3;
R-C317/Chloroheptafluorocyclobutane/C4ClF7/377-41-3;
R-C318/Octafluorocyclobutane/C4F8/115-25-3;
R-3-1-10/Decafluorobutane/C4F10;
R-329ccb/ 375-17-7;
R-338eea/ 75995-72-1;
R-347ccd/ 662-00-0;
R-347mcc/ Perfluoropropyl methyl ether/C4H3F7O/375-03-1;
R-347mmy/ Perfluoroisopropyl methyl ether/C4H3F7O/22052-84-2;
R-356mcf/
R-356mffm/
R-365mfc/1,1,1,3,3-Pentafluorobutane/C4H5F5
FC-72/Tetradecafluorohexane/C6F14 355-42-0
R-400 R-12/R-114 (60/40 wt%) binary blend
R-401A R-22/R-152a/R-124 (53/13/34)
R-401B R-22/R-152a/R-124 (61/11/28)
R-401C R-22/R-152a/R-124 (33/15/52)
R-402A R-125/R-290/R-22 (60/2/38)
R-402B R-125/R-290/R-22 (38/2/60)
R-403A R-290/R-22/R-218 (5/75/20)
R-403B R-290/R-22/R-218 (5/56/39)
R-404A R-125/R-143a/R-134a (44/52/4)
R-405A R-22/R-152a/R-142b/R-C318 (45/7/5.5/42.5)
R-406A R-22/R-600a/R-142b (55/04/41)
R-407A R-32/R-125/R-134a (20/40/40)

R-407B R-32/R-125/R-134a (10/70/20)
R-407C R-32/R-125/R-134a (23/25/52)
R-407D R-32/R-125/R-134a (15/15/70)
R-407E R-32/R-125/R-134a (25/15/60)
R-408A R-125/R-143a/R-22 (7/46/47)
R-409A R-22/R-124/R-142b (60/25/15)
R-409B R-22/R-124/R-142b (65/25/10)
R-410A R-32/R-125 (50/50)
R-410B R-32/R-125 (45/55)
R-411A R-1270/R-22/R-152a (1.5/87.5/11)
R-411B R-1270/R-22/R-152a (3/94/3)
R-412A R-22/R-218/R-142b (70/5/25)
R-413A R-218/R-134a/R-600a (9/88/3)
R-414A R-22/R-124/R-600a/R-142b (51/28.5/4.0/16.5)
R-414B R-22/R-124/R-600a/R-142b (50/39/1.5/9.5)
R-415A R-22/R-152a (82/18)
R-415B R-22/R-152a (25/75)
R-416A R-134a/R-124/R-600 (59/39.5/1.5)
R-417A R-125/R-134a/R-600 (46.6/50.0/3.4)
R-418A R-290/R-22/R-152a (1.5/96/2.5)
R-419A R-125/R-134a/R-E170 (77/19/4)
R-420A R-134a/R-142b (88/12)
R-421A R-125/R-134a (58/42)
R-421B R-125/R-134a (85/15)
R-422A R-125/R-134a/R-600a (85.1/11.5/3.4)
R-422B R-125/R-134a/R-600a (55/42/3)
R-422C R-125/R-134a/R-600a (82/15/3)
R-422D R-125/R-134a/R-600a (65.1/31.5/3.4)
R-423A R-134a/R-227ea (52.5/47.5)
R-424A R-125/R-134a/R-600a/R-600/R-601a (50.5/47/.9/1/.6)
R-425A R-32/R-134a/R-227ea (18.5/69.5/12)
R-426A R-125/R-134a/R-600/R-601a (5.1/93/1.3/.6)
R-427A R-32/R-125/R-143a/R-134a (15/25/10/50)
R-428A R-125/R-143a/R-290/R-600a (77.5/20/.6/1.9)
R-500 R-12/R-152a (73.8/26.2)
R-501 R-22/R-12 (75/25)
R-502 R-22/R-115 (48.8/51.2)
R-503 R-23/R-13 (40.1/59.9)
R-504 R-32/R-115 (48.2/51.8)
R-505 R-12/R-31 (78/22)
R-506 R-31/R-114 (55.1/44.9)
R-507 R-125/R-143a (50/50)
R-508A R-23/R-116 (39/61)
R-508B R-23/R-116 (46/54)
R-509A R-22/R-218 (44/56)

[1242] In certain embodiments of the present invention, mixtures of one or more of the above gases may also be subjected to compression, expansion, or compression and expansion. One example of such a gas mixture is natural gas that is commonly used for combustion.

[1243] According to certain embodiments of the present invention, energy for performing useful work may be recovered by the expansion of compressed gas (such as natural gas) that is flowed through a network. For example, a conventional "city gate" or other passive pressure regulator allows gas to

expand from a higher pressure to a lower pressure freely. The resulting low pressure gas has higher entropy, meaning that less work can be extracted from it.

[1244] In certain applications it may be desirable to minimize this loss of the work available in the gas. An example of such an application occurs during the expansion of gas in a natural gas pipeline to city pressure via a city gate system.

[1245] Accordingly, embodiments of the present invention may include an active regulator in which the gas does mechanical work against a piston or other movable member as it expands. That mechanical work can be used to operate a generator, creating electricity, or to drive some other mechanical system.

[1246] Thus rather than allowing gas to expand freely, the active regulator 13600 disclosed in Figure 136 uses the pressure of the expanding gas to drive a piston 13602. This movement of the piston, in turn, may be harnessed to provide useful work. For example, in the embodiment of Figure 136, the piston rotates crankshaft 13604 to operate generator 13606 to create electricity.

[1247] In order to maximize the efficiency of the process and to prevent any moisture in the gas from freezing during expansion, a liquid compatible with the gas is sprayed through sprayer 13607 into the cylinder 13608 during expansion. As described above, this liquid transfers heat into the cylinder, controlling the temperature of the expansion process, for example making this temperature near-constant.

[1248] The expanded gas-liquid mixture is exhausted from the cylinder via a valve 13610 and passed through a gas-liquid separator 13612. The liquid is pumped by pump 13613 through a heat exchanger 13614 to return it to near-ambient temperature before being sprayed into the cylinder again.

[1249] The specific embodiments just described, perform compression or expansion over a single stage. However, alternative embodiments in accordance with the present invention may utilize more than one compression and/or expansion stage arranged in series.

[1250] For example, when a larger compression/expansion ratio is required than can comfortably be accommodated by the mechanical or hydraulic approach by which mechanical power is conveyed to and from the system, then multiple stages can be utilized.

[1251] Figure 53A presents a highly simplified view of an embodiment of a multi-stage system 5320 for compressing air for storage in tank 5332 with three stages (i.e., first stage 5324a, second stage 5324b and third stage 5324c). Systems with more or fewer stages may be constructed similarly. As shown in the system 5320 of Figure 53A, in multi-stage embodiments the output of one compression stage is flowed to the inlet of a successive compression stage for further compression, and so on, until a final desired pressure for storage is reached. In this manner, gas can be compressed over several stages to final pressures that would be difficult to achieve with only one stage.

[1252] Figure 53B presents a view of one embodiment of a multi-stage dedicated compressor apparatus 5300 according to the present invention. In particular, Figure 53B shows system 5300 including first stage 5302, second stage 5304, and storage unit 5332. First stage 5302 comprises inlet module A_0 in fluid communication with separator module B_1 through compression chamber module C_{01}. First stage 5302 receives air for compression through air filter 5350.

[1253] First stage 5302 is in turn in fluid communication with second stage 5304 comprising inlet module A_1 in fluid communication with separator module B_2 through compression module C_{12}. Second stage 5304 is in turn in fluid communication with storage unit 5332.

[1254] Figures 53BA, 53BB, and 53BC show simplified views of the different component modules of the multi-stage compression apparatus of Figure 53B. In particular, the inlet module A_x comprises gas inlet 5306 in fluid communication through conduit 5312 with a pulsation damper bottle 5314, that is in fluid communication with an outlet 5316.

[1255] The separator module B_y is shown in Figure 53BB. Separation module comprises an inlet 5330 in fluid communication with a liquid-gas separator 5332. Liquid separated by separator is configured to flow to liquid reservoir 5334. Gas from the separator is configured to flow to outlet 5336 of the separator module.

[1256] Pump 5338 is configured to flow liquid from the reservoir to the liquid outlet 5340 through liquid valve 5341. Liquid valve 5341 serves to control the liquid flow out of the separator module to the sprayer structures of the compression module. Actuation of the liquid flow valve can serve to isolate the pump and reservoir from pressure fluctuations occurring within the chamber when injection of liquid is not taking place. In certain embodiments, the liquid flow conduit may be in communication with an accumulator structure to dampen pressure changes.

[1257] A compression module C_{xy} is shown in Figure 53BC. The architecture of one embodiment of a compression module is described in detail above. In particular, the compression module comprises a conduit 5350 in fluid communication with an inlet 5352 and in fluid communication with a cylinder 5354 through valves 5356a and 5356b. Conduit 5358 is in fluid communication with cylinder 5354 through valves 5357a and 5357b, and in fluid communication with an outlet 5359.

[1258] Double-acting piston 5355 is disposed within cylinder 5354. Double-acting piston is in communication with an energy source (not shown), and its movement serves to compress gas present within the cylinder. Such compression is generally shown and described above.

[1259] Sprayers 5343 are in liquid communication with the cylinder to introduce liquid therein. Sprayers 5343 receive the liquid from the liquid outlet of the separator module. In certain embodiments, the distance between the liquid flow valve and the sprayers may be minimized to reduce an opportunity for outgassing.

[1260] In the first stage 5302 of multi-stage dedicated compressor apparatus 5300, the liquid outlet of the separator module B_1 is in fluid communication with the compression module C_{01} through a first heat exchanger $H.E._{01}$. In the second stage 5304 of multi-stage dedicated compressor apparatus 5300, the liquid outlet of the separator module B_2 is in fluid communication with the liquid inlet of the compression module C_{12} through a second heat exchanger $H.E._{12}$.

[1261] The embodiment of Figure 53B may thus utilize the pressure differential created by a stage, to facilitate injection of liquid. In particular, the embodiment of Figure 53B has the separated liquid flowed back into a gas flow having the reduced pressure of the previous lower pressure stage. This reduces the force required for the liquid injection, and thus the power consumed by a pump in flowing the liquid.

[1262] A dedicated multi-stage compressor apparatus according to the present invention is not limited to the particular embodiment shown in Figure 53B. In particular, while the embodiment of Figure 53B shows an apparatus wherein separated liquid is recycled for re-injection into the gas flow within an individual stage, this is not required by the present invention.

[1263] Figure 53C thus shows an alternative embodiment of a dedicated multi-stage compressor apparatus in accordance with the present invention. In the system 5360 according to this embodiment, liquid injected into the compression chamber 5362 of a first stage, is subsequently removed by separator 5364 and then flowed for injection into the compression chamber 5366 of the next stage. This configuration results in accumulation of the finally separated liquid in the tank 5368. The embodiment of Figure 53C may offer a benefit, in that energy of the compressed gas is conserved and not consumed by the flowing liquids for reinjection into the compression chamber of the same stage.

[1264] While Figures 53A-C show compression over multiple stages, embodiments of the present invention are not limited to this approach. Alternative embodiments in accordance with the present invention can also perform expansion over multiple stages, with the output of one expansion stage flowed to the inlet of a successive expansion stage for further expansion, and so on, until an amount of energy has been recovered from the compressed gas. In this way, energy can be recovered from gas expanded over several stages in a manner that would be difficult to obtain with expansion in only one stage.

[1265] Figure 54 presents a detailed view of one embodiment of a multi-stage dedicated expander apparatus according to the present invention. In particular, Figure 54 shows apparatus 5460 including storage unit 5432, first stage 5462, and second stage 5464. First stage 5462 comprises inlet module A_3 in fluid communication with separator module B_4 through expansion module E_{34}. First stage 5462 receives air for compression from storage unit 5432.

[1266] First stage 5462 is in turn in fluid communication with second stage 5464. Second stage 5464 comprises inlet module A_2 in fluid communication with separator module B_3 through expansion module E_{23}. Second stage 5464 is in turn in fluid communication with an outlet 5457.

[1267] Certain of the different component modules of the multi-stage dedicated expander apparatus 5460 may also be represented in Figures 53BA and 53BB as described above. Dedicated expander apparatus 5460 further includes expansion module E_{xy} shown in Figure 54A.

[1268] The architecture and operation of one embodiment of such an expansion module has been previously described. In particular, the expansion module comprises a conduit 5458 in fluid communication with an inlet 5459 and in fluid communication with a cylinder 5454 through valves 5467a and 5467b. Conduit 5450 is in fluid communication with cylinder 5454 through valves 5466a and 5466b, and in fluid communication with an outlet 5452.

[1269] Double-acting piston 5455 is disposed within cylinder 5454. Double-acting piston is in communication with an apparatus (not shown) for converting mechanical power into energy, for example a generator. Expansion of air within the cylinder serves to drive movement of the piston. Such expansion is generally shown and described above.

[1270] In the first stage 5462 of multi-stage dedicated expander apparatus 5460, the liquid outlet of the separator module B_4 is in fluid communication with the chamber of the expansion module E_{34} through a first heat exchanger $H.E._{43}$. In the second stage 5464 of multi-stage dedicated expander apparatus 5460, the liquid outlet of the separator module B_3 is in fluid communication with the chamber of the expansion module E_{23}, through a second heat exchanger $H.E._{32}$.

[1271] A dedicated multi-stage expander apparatus according to the present invention is not limited to the particular embodiment shown in Figure 54. In particular, while the embodiment of Figure 54 shows an apparatus wherein separated liquid is recycled for re-injection into the gas flow within an individual stage, this is not required by the present invention.

[1272] Figure 55 shows an alternative embodiment of a dedicated multi-stage expander apparatus in accordance with the present invention. In the system 5500 according to this embodiment, liquid injected into the expansion chamber 5502 of a first stage, is subsequently separated by separator 5504 and then flowed for injection into the expansion chamber 5506 of the next stage. This configuration results in separator 5507 causing accumulation of the finally separated liquid in the tank 5508.

[1273] The embodiment of Figure 55 does not require liquid to be injected against a pressure differential. In the particular embodiment of Figure 54A, the separated liquid is flowed back to the into the inlet gas flow having the elevated pressure of the previous higher pressure stage. By contrast, the embodiment of Figure 55 has the separated liquid flowed into the expanded gas that is inlet to the next stage, reducing the power consumed by the pump in flowing the liquid.

[1274] While the embodiments of multi-stage apparatus described so far have been dedicated to either compression or expansion, alternative embodiments in accordance with the present invention could perform both compression and expansion. Figure 56 shows a simplified schematic view of one embodiment of such an two-stage apparatus that allows both compression and expansion.

[1275] In particular, the embodiment of Figure 56 combines a number of design features to produce a system that is capable of performing both compression and expansion. One feature of system 5600 is connection of certain elements of the system through three-way valves 5604. Figure 56 depicts the configuration of the three-way valves as solid in the compression mode, and as dashed in the expansion mode.

[1276] One feature of the system 5600 is the use of the same reservoir 5605 to contain liquid for introduction in both the compression mode and in the expansion mode. Specifically, during compression the reservoir 5605 is utilized to inject liquid into gas that is already at a high pressure by virtue of compression in the previous stage. During expansion, the reservoir 5605 is utilized to inject gas into the high pressure gas at the first stage. In multi-stage apparatuses having mixing chambers commonly used in both compression and expansion, the pressures of inlet gas flows to those mixing chambers would be approximately the same in order achieve the desired gas-liquid mixture.

[1277] Still another feature of the system 5600 is the use of a pulsation damper bottle 5606 that is elongated in one or more dimensions (here, along dimension d). The elongated shape of the pulsation damper bottle 5606 allows for multiple connections between the bottle and adjacent elements, while

allowing the conduits for fluid communication with those adjacent elements to remain short. This bottle functions to dampen pulsations in fundamentally the same manner as has been previously described for the bottles of the single-stage embodiments.

[1278] Figure 56 is a simplified view showing the elongated pulsation damper bottle in schematic form only, and the shape of the elongated bottle should not be construed as being limited to this or any other particular profile. For example, alternative embodiments of a pulsation damper bottle could include one or more lobes or other elongated features.

[1279] Under operation in a compression mode, gas enters system 5600 through inlet 5650 and is exposed to two successive liquid injection and compression stages, before being flowed to storage unit 5632. Separated liquid accumulates in tank 5635, which may be insulated to conserve heat for subsequent reinjection to achieve near-isothermal expansion in an expansion mode.

[1280] Specifically, under operation in an expansion mode, compressed gas from storage unit 5632 is exposed to two successive liquid injection and expansion compression stages, before being flowed out of the system at outlet 5634. Separated liquid accumulates in tank 5636, and may be subsequently re-injected to achieve near-isothermal compression in a compression mode.

[1281] In the embodiment of the system of Figure 56, the flow of separated liquid across different stages results in accumulation at a final separator, in a manner analogous to the embodiments of Figure 53C (dedicated compressor) and Figure 55 (dedicated expander). Such embodiments require the fluid reservoirs to be larger to accommodate the directional flows of liquids which occur. These accumulated liquids can be flowed back to their original reservoirs by reversing the mode of operation of the system.

[1282] Figure 57 is a simplified diagram showing a multi-stage apparatus in accordance with an embodiment of the present invention, which is configurable to perform both compression and expansion. In particular, system 5700 represents a modification of the embodiment of Figure 56, to include additional three-way valves 5702 and additional conduits between certain separator elements and certain compression/expansion chambers. Again, Figure 57 depicts the configuration of the three-way valves as solid in the compression mode, and as dashed in the expansion mode.

[1283] While the embodiment of Figure 57 offers some additional valve and conduit complexity, it may eliminate certain elements. In particular, it is noted that compression and expansion do not occur simultaneously, and hence all three heat exchangers and pumps of the embodiment of Figure 57 are not required to be in use at the same time. Thus, system 5700 utilizes only two heat exchangers (H.E.1 and H.E.2) and two pumps (5704), versus the three heat exchangers and three pumps of the embodiment of Figure 56.

[1284] Moreover, the embodiment of Figure 57 restricts the circulation of liquids to within a stage. Thus, the flow of liquids is not such that liquids accumulate in one reservoir, and so the liquid reservoirs do not need to be made larger as in the embodiment of Figure 56. In addition, the embodiment of Figure 57 does not erode the energy of the compressed air in accomplishing liquid injection across stages.

[1285] Certain of the previous embodiments have described the use of one or more pumps to flow liquids for introduction into gas undergoing compression or expansion. In certain embodiments, one or

more such pumps may be actuated separately from the moveable member (such as a piston) present within the compression or expansion chamber. For example the pump(s) could be powered by electricity, which may or may not be that which is generated by operation of the system.

[1286] Embodiments discussed previously have shown liquid as being flowed through the system utilizing a pump, which can be of various types, including non-positive displacement pumps such as centrifugal, diaphragm, or other forms. Because, however, the pressure within a compression or expansion chamber is generally changing, certain embodiments of the present invention may benefit from the use of positive displacement pumps to provide a liquid flow into an expansion/compression chamber.

[1287] Accordingly, Figure 85 shows an embodiment where a positive displacement pump 8500 in the form of a piston 8502 moveable within liquid-filled cylinder 8504, is used. Liquid is flowed out of the cylinder 8504 through valve 8508 and conduit 8506 leading to sprayers 8509 within compression and/or expansion chamber 8510.

[1288] The positive displacement pump of Figure 85 may provide a flow of liquid having desirable characteristics. In particular, as piston 8514 moves, the pressure changes within cylinder 8510. If nozzles 8509 were supplied with liquid at a fixed pressure, the differential pressure across the nozzle could vary over the course of a piston stroke.

[1289] Thus at certain times the differential pressure could have been higher than needed (possibly wasting energy). At other times the differential pressure could have been too low (making the spray ineffective and thus reducing compressor efficiency). By driving the nozzles with a constant displacement pump, however, the differential pressure may be maintained at a desirable value throughout a stroke by controlling the pump synchronous with the compressor piston.

[1290] During compression, it may be beneficial for pistons 8514 and 8502 to move in phase with each other. During expansion, it may be advantageous for the pistons to move 180° out of phase. In other embodiments, different phase angles may be appropriate. Other embodiments may be effective with asynchronous actuation of pump and compressor/expander elements.

[1291] In addition to providing more uniform flows of liquid in the face of varying pressures within compression/expansion cylinder, the particular embodiment of Figure 85 may efficiently harness available energy. Specifically, because the piston 8502 of the liquid pump 8500 is driven by the same physical linkage 8512 (here a crankshaft) as the piston 8514 of the compression/expansion cylinder, energy is not consumed from a second source, nor is the original energy of the compression/expansion needed to be converted into another form in order to drive the flow of the liquid.

[1292] While the particular embodiment of Figure 85 shows liquid flowed to a chamber from a positive displacement pump in the form of a piston pump, this is not required by the present invention. Certain embodiments could employ other forms of positive displacement pumps to flow liquid, including but not limited to peristaltic pumps, progressing cavity pumps, gear pumps, or roots-type pumps.

[1293] Certain embodiments of systems according to the present invention may utilize a plurality of liquid pumps. For example Figure 86 shows an embodiment of a compression system including a non-positive displacement (centrifugal) transfer pump in fluid communication with a positive displacement

multi-stage water pump. Flows of liquid from the transfer pump to the multi-stage water pump utilize a Proportional-Integral-Derivative (PID) loop around the transfer pump as shown. The PID loop is configured to maintain a target pressure (or other parameter such as flow rate) into the multi-stage water pump.

[1294] While certain embodiments of the present invention may employ a pump to flow liquid through a system, in other embodiments a separate liquid pump structure may not be required. For example, Figure 87 shows an embodiment wherein liquid is flowed utilizing pressure within a compression or expansion chamber.

[1295] Specifically, in Figure 87 liquid from reservoir 8700 of is flowed into sprayer 8702 of chamber 8704 of stage 8706 of multi-stage system 8708. Reservoir 8700 includes a head space 8710 containing gas whose pressure provides the force that flows the liquid to the sprayer.

[1296] In particular, the head space 8710 is in selective gaseous communication with the chambers of other stages 8712, through liquid flow valve network 8714. Liquid flow valve network 8714 is precisely actuated based upon inputs received by a controller.

[1297] At a point when a gas pressure within another stage is strong enough to flow liquid from the reservoir into the chamber 8704, the liquid flow valve network 8714 is actuated to allow gaseous communication between head space 8712 and that other stage. Precise control over the liquid flow valve network can allow conveyance of only an amount of pressure necessary to flow the liquid, thereby conserving overall energy within the system.

[1298] In certain embodiments, the function of one or more gas or liquid flow valves may be performed by the moveable member itself. For example, passive port valves are conventionally used in two-stroke internal combustion engines. These ports control the transfer of air-fuel mixture from the crankcase to the cylinder, where combustion occurs, and the exhausting of the combusted gases from the cylinder.

[1299] Figure 84 shows an embodiment in which vertical movement of the piston 8400 may selectively obstruct a port 8402 to the chamber 8404 (here a gas flow inlet port to a compression chamber), thereby effectively serving as an inlet valve. Such a configuration has been employed in the design of conventional two-stroke engines.

[1300] By eliminating the need for some valve structures, such embodiments may simplify the design of the apparatus, potentially reducing cost and maintenance. Embodiments obviating the need for certain valves may also facilitate introduction of liquid into the chamber, for example as droplets created in an upstream mixing chamber. In particular, elimination of elements (such as valve seats, valve plates) otherwise offering surfaces for possible coalescence of liquid droplets, could ultimately improve the quality (volume, velocity, droplet size uniformity, number of droplets, etc.) of liquid introduced for heat exchange during compression/expansion.

[1301] While the embodiment of Figure 84 shows movement of the piston serving to control flows of gas into a chamber for compression, the present invention is not limited to this particular configuration. Various embodiments could employ movement of a piston to control flows of liquids to/from a chamber, and/or flows of gases inlet or outlet from a chamber in which expansion or compression is taking place.

[1302] Moreover, while the particular embodiment of Figure 84 shows a piston and chamber having symmetrical shapes, this is also not required by the present invention. In alternative embodiments a piston and cylinder surfaces may be shaped to allow flows of material while achieving goals such as minimizing dead volume and/or accommodating the actuation of other valves within the chamber.

[1303] Embodiments of the present invention utilizing port valves may exhibit one or more possible benefits over other valve types such as plate and poppet valves. One possible benefit is that port valves lack moving parts beyond the moveable member itself, and are therefore less expensive and more reliable. Another possible benefit of systems utilizing port valves is that the port valve opening can be quite large, allowing a high flow rate.

[1304] Still another possible benefit is that gas can pass through the port valve without having to make rapid turns or changes in direction. Such a configuration may further improve flow rate. This configuration also may allow gas-liquid aerosols (for example as may have been created in an upstream mixing chamber) to pass through with minimal obstruction, thereby making it easier to keep the liquid droplets entrained in the gas.

[1305] Passive port valves may not be able to be controlled separately from the piston or other moveable member. If the port valve or valves are to be controlled separately from the moveable member, this can be accomplished for example by using a second piston (or other type of moveable member) controlled via a second linkage such as a crankshaft or other mechanism.

[1306] For example, Figure 139 shows a simplified view of a system 13900 comprising a piston actuator 13902 and one or more port openings 13904 in the side of a cylindrical chamber 13906 that is in fluid communication with the compression/expansion chamber 13908. The port openings 13904 may be used to introduce gas (or a mixture of gas and liquid droplets) into the compression/expansion chamber 13908.

[1307] The piston actuator may move separately from, and in the opposite direction to, the moving member 13910 (for example, a piston) responsible for compression or expansion of gas.

[1308] In some embodiments, the actuator piston may be operated via a mechanical linkage connected to the same crankshaft or other mechanism that is driving the movable member. In these embodiments, the actuator piston and the movable member move synchronously and reach TDC simultaneously.

[1309] In some embodiments, the timing of the actuator piston is independent of that of the movable member. This may allow control of the compression / expansion ratio and other system parameters.

[1310] Some embodiments utilizing passive port valves may include a moveable sliding window that can partially occlude the opening of the port. This allows the flow of gas or gas-liquid mixture through the port to be controlled. Such flow control may in turn allow the system power to be "throttled" - that is, increased or decreased during operation. According to certain embodiments a position of a moveable sliding window may be adjusted by a separate actuating mechanism that is under computer or mechanical control.

[1311] While certain embodiments according to the present invention utilize a liquid for injection in a plurality of the stages, this is not required. For example one or more stages of particular multi-stage embodiments may not utilize the introduction of liquids at all. Moveable members suitable for use in

such stages include regular turbines, blowers, and centrifugal pumps, in addition to those previously described above.

[1312] Moreover, while certain embodiments of multi-stage apparatuses may utilize the injection of the same liquid between stages, this is not required by the present invention, and certain embodiments may feature the injection of different liquids in different stages. In some such embodiments, these liquids may be maintained entirely distinct between the stages, for example utilizing separate, dedicated gas-liquid separators, reservoirs, and pumps.

[1313] According to alternative embodiments, however, different liquids sharing one or more components could be injected at various stages. In such embodiments, the non-common component of the liquid could be separated, allowing the common component to be circulated between stages.

[1314] For example, in some embodiments one or more expansion stages may utilize injection of liquid as pure water, while other expansion stages utilize injection of liquid as a water-propylene glycol solution. In such embodiments, the propylene glycol could be separated prior to flowing the water between the stages.

[1315] Moreover, as described above, some embodiments of single or multi-stage apparatuses may be configured to use the same chamber(s) for both compression and expansion. Certain embodiments of such apparatuses may introduce different liquids, depending upon their particular operational mode.

[1316] According to certain embodiments of the present invention, these different liquids introduced during compression and expansion, may be maintained separate, within a stage and/or between stages. And where the different liquids share common components, liquid-liquid separation may be employed to allow circulation of liquid components between different stages or within the same stage operating in different modes.

[1317] Embodiments of the present invention utilizing separation of components from a liquid may be depicted generically in Figure 88 as including liquid flow and separation network 8800 receiving liquid separated from gas in separator structures 8802. Liquid flow and separation network 8800 may comprise a variety of elements selected from conduits, valves, pumps, reservoirs, heat exchangers, accumulators, filters, and separator structures, arranged in appropriate combinations. In certain embodiments, such a liquid flow and separation network may be combined with a liquid flow valve network as described above in Figure 87.

[1318] In some embodiments, motive force driving the liquid through the spray nozzle or nozzles into the cylinder may arise from the pressure differential created by the action of the compressor or expander. Figure 138 shows a simplified view of an embodiment 13800 of such as system.

[1319] In the case of compression, the liquid separated from the gas-liquid mixture via the gas-liquid separator 13802 is at a higher pressure than that of the gas entering the compression chamber. Thus, there is a pressure differential across the spray nozzle 13804.

[1320] In some embodiments, this differential is sufficient to overcome the pressure drop through the nozzle. The system can be designed to provide the proper pressure difference to cause the liquid to introduced into the nozzle to create the desired spray.

[1321] In some embodiments the system could be designed with a variable flow valve 13806 to provide the proper pressure difference. Certain embodiments of systems may be designed with suitable choices of system components and geometry to achieve the proper pressure difference.

[1322] Once expansion has begun, the gas-liquid mixture flowing from the next higher-pressure stage will have a higher pressure than the cylinder contents. This pressure differential from the high-pressure gas 13810 can be used (as in the compression case described above) to drive the liquid separated from the gas via the gas-liquid separator through the spray nozzle.

[1323] Some embodiments previously described use a spray nozzle structure to introduce liquid spray into a cylinder during compression or expansion. However this is not required by the present invention, and certain embodiments may utilize other types of spray systems.

[1324] For example, Figure 137 shows a simplified cross-sectional view of one such embodiment of an apparatus 13700. Specifically, liquid 13702 is introduced into a volume between the top of the piston 13704 and a nozzle plate 13706 via a liquid inlet 13708 and valve 13710 when the piston is near BDC.

[1325] During compression, as the piston is driven from BDC towards TDC, the piston pushes the liquid volume against the nozzle plate. The motion of the nozzle plate is resisted by the force of a compressible member 13712 (for example a spring) connecting the top of the cylinder 13720 to the nozzle plate.

[1326] The force differential between the pressure exerted by the cylinder and the spring drives the liquid through the orifices (which may define internal spaces more complex than simple openings) in the nozzle plate. This creates a spray in the upper portion of the cylinder.

[1327] During expansion the behavior is similar, although in the opposite direction. The spring is compressed at the beginning of the expansion stroke near TDC. As the spring expands, it pushes the nozzle plate down into the liquid volume, driving some of the liquid through the orifices to form a spray.

[1328] Embodiments of the present invention do not require the direct injection of liquids into the compression or expansion chamber of every stage. Certain embodiments could employ direct liquid injection in no stages or only in some stages. Stages not employing direct liquid injection may be coupled with stages having a gas-liquid mixture introduced to the compression/expansion chamber through a separate mixing chamber.

[1329] Certain embodiments may utilize one or more stages in which liquid is introduced into the gas by other than a spray, for example by bubbling gas through a liquid. For example, in certain embodiments some (typically lower-pressure) stages might employ the liquid mist technique utilizing a mixing chamber or direct injection, while other (typically higher-pressure) stages may employ the introduction of liquid by bubbling.

[1330] Embodiments of compressed gas storage systems in accordance with the present invention are not limited to any particular size. In certain applications, it may be useful for the system to fit within a particular form factor, such as a standard shipping container. Another example of a form factor are standard sizes/weights of the trailer of a tractor-trailer rig, which could potentially allow the use of embodiments of energy storage systems in portable applications.

[1331] In some cases it may be useful for the system to be able to be assembled by a single person, for example with the system assembled from individual components weighing 50lbs or less. In some instances it may be desirable for the system to be installable in one day or less.

[1332] Particular embodiments of the present invention may allow for control over the temperature change of one or more stages. Certain embodiments may allow the compression and/or expansion of gas across multiple stages, wherein approximately the same change in temperature of the gas occurs at each stage.

[1333] In designing a system, the designer may choose the initial and final gas temperature, and then iteratively solve a system of equations to determine the other system parameters, notably the compression ratio, that will achieve the desired delta-T.

[1334] In operating a system, a temperature change during the compression or expansion stroke may be a number chosen by the designer (or operator) of the system. This temperature change may represent a trade-off against efficiency. The higher the delta-T, the higher the power but the lower the efficiency.

[1335] According to some embodiments, such substantially equivalent change in gas temperature at different stages may be achieved where each of the stages does not necessarily utilize the same compression or expansion ratio. In some embodiments, the compression ratio or expansion ratio of a stage may be dynamically controlled, for example based upon a timing of actuation of valve responsible for the intake or exhaust of gas from the compression and/or expansion chamber.

[1336] Figure 58 shows a simplified block diagram of one embodiment of a single-stage system 5801 in accordance with the present invention. Figure 58 shows compressor/expander 5802 in fluid communication with gas inlet 5805, and with compressed gas storage unit 5803. Motor/generator 5804 is in selective communication with compressor/expander 5802.

[1337] In a first mode of operation, energy is stored in the form of a compressed gas (for example air), and motor-generator 5804 operates as a motor. Motor/generator 5804 receives power from an external source, and communicates that power (W_{in}) to cause compressor/expander 5802 to function as a compressor. Compressor/expander 5802 receives uncompressed gas at an inlet pressure (P_{in}), compresses the gas to a greater pressure for storage (P_{st}) in a chamber utilizing a moveable element such as a piston, and flows the compressed gas to the storage unit 5803.

[1338] In a second mode of operation, energy stored in the compressed gas is recovered, and compressor-expander 5802 operates as an expander. Compressor/expander 5802 receives the compressed gas at the stored pressure P_{st} from the storage unit 5803, and then allows the compressed gas to expand to a lower outlet pressure P_{out} in the chamber. This expansion drives a moveable member which is in communication with motor/generator 5804 that is functioning as a generator. Power output (W_{out}) from the compressor/expander and communicated to the motor/generator 5804, can in turn be input onto a power grid and consumed.

[1339] The processes of compressing and decompressing the gas as described above, may experience some thermal and mechanical losses. However, these processes will occur with reduced thermal loss if they proceed at near-isothermal conditions with a minimum change in temperature. Thus compression

will occur with reduced thermal loss if it proceeds with a minimum increase ($+\Delta T_C$) in temperature, and expansion will occur with reduced thermal loss if it proceeds with a minimum decrease ($-\Delta T_E$) in temperature.

[1340] Embodiments of the present invention may seek to minimize the change in temperature associated with gas compression and/or expansion, and hence accompanying thermal losses, by performing such compression/expansion over a plurality of stages. Such compression and expansion over multiple stages is now discussed below.

[1341] Figure 58A shows a simplified generic view of an embodiment of a multi-stage compression-expansion apparatus. Figure 58A shows compressor/expander 5802 in fluid communication with gas inlet 5805, and with compressed gas storage unit 5803. Motor/generator 5804 is in selective communication with compressor/expander 5802.

[1342] In this embodiment, compressor/expander 5802 actually comprises a plurality of stages 5802a-c that are connected in serial fluid communication. While the particular embodiment of Figure 58A shows a system having three such stages, in accordance with embodiments of the present invention two or any greater number of stages could be employed.

[1343] In a compression mode of operation, each stage of the compressor/expander 5802 is configured to receive an inlet gas at a lower pressure, to compress that gas to a higher pressure, and then to flow the compressed gas to the next higher pressure stage (or in the case of the highest pressure stage, to flow the compressed gas to the storage unit). Thus Figure 58A shows inlet gas experiencing a first increase in pressure from P_{in} to P_1 in stage 5802a, experiencing a second increase in pressure from P_1 to P_2 in stage 5802b, and then experiencing a final increase in pressure from P_2 to P_{st} in third stage 5802c.

[1344] At each stage, a certain amount of power (here W_{in1}, W_{in2}, and W_{in3}, respectively) is consumed from motor/generator 5804 that is operating as a motor. Also at each stage, the increased pressure of the compressed gas is associated with a corresponding increase in the temperature of the gas (here $+\Delta T_1$, $+\Delta T_2$, and $+\Delta T_3$ respectively).

[1345] In an expansion mode of operation, each stage of the compressor/expander 5802 is configured to receive an inlet gas at a higher pressure, to allow that gas to expand to a lower pressure, and then to flow the expanded gas either to the next lower pressure stage (or in the case of the lower pressure stage, to flow the expanded air out of the system). Thus Figure 58A also shows stored gas experiencing a first decrease in pressure from P_{st} to P_3 in stage 5802c, experiencing a second decrease in pressure from P_3 to P_4 in stage 5802b, and then experiencing a final decrease in pressure from P_4 to P_{out} in third stage 5802c. It is noted that the pressure output from the system can, but need not be the same as the original inlet pressure.

[1346] At each stage, a certain amount of power (here W_{out3}, W_{out2}, and W_{out1}, respectively) is produced and output to motor-generator 5804, operating as a generator. Also at each stage, the decreased

gas pressure is associated with a corresponding decrease in temperature of the gas (here $-\Delta T_4$, $-\Delta T_5$, and $-\Delta T_6$ respectively).

[1347] While Figure 58A shows an apparatus in which each stage is in communication with the preceding and following stages, this is not required by the present invention. Figure 58B shows a simplified view of an embodiment of a system 5880 wherein the stages 5882a-c are in fluid communication with a valve network 5888, whose actuation allows selective routing of gas flows between stages. Thus utilizing the embodiment of Figure 58B, one or more stages could selectively be utilized, or by-passed, depending upon the specific conditions. For example, where prior expansion of gas from the storage tank has reduced the pressure to a low relatively value, continued expansion may not need to be performed over all of the stages. Similarly, compression to lower pressures may not require all stages, and use of the valve network permits one or more stages to be selectively by-passed.

[1348] And while Figures 58A-B show apparatuses that are configurable to perform either compression or expansion in each stage, the present invention is not limited to such embodiments. Alternative embodiments of apparatuses in accordance with the present invention can be drawn to multi-stage apparatuses dedicated to performing only compression or only expansion. A simplified view of such an embodiment is shown in Figure 58C.

[1349] In certain embodiments according to the present invention, a temperature change experienced by each stage may be substantially equivalent (whether the process comprises gas compression or gas expansion). As referenced herein, the term "substantially equivalent" refers to a temperature change that differs by 500°C or less, by 300°C or less, by 100°C or less, by 75°C or less, by 50°C or less, by 25°C or less by 20°C or less, by 15°C or less, by 10°C or less, or by 5°C or less. The temperature change experienced by one or more particular stages, may be controlled according to embodiments of the present invention, utilizing one or more techniques applied alone or in combination.

[1350] Controlling Compression/Expansion Ratio

[1351] Temperature of one or more stages may be may be realized by regulating a compression or expansion ratio of the stages. According to some embodiments comprising multiple stages, the compression or expansion ratios of the stages may differ significantly from one another.

[1352] Each stage of a multi-stage apparatus for performing compression, expansion, or compression and expansion, will be characterized by a compression ratio and/or expansion ratio. These compression and/or expansion ratios may or may not be the same for different stages.

[1353] In certain embodiments, the compression and/or expansion processes taking place in each stage, may be performed utilizing a piston that is moveable within a cylinder. Figures 59-59B show generic views of such an apparatus.

[1354] In particular, Figure 59 shows that compression and/or expansion stage 5900 comprises cylinder 5902 having walls 5904. Disposed within cylinder 5902 is a moveable piston 5906 comprising a piston head 5906a connected to piston rod 5906b.

[1355] Where the stage is configured to perform compression, the piston rod is in physical communication with an energy source (not shown) through a linkage, which may be mechanical in nature such as a crankshaft. Alternatively, the linkage between the energy source and the piston rod may be hydraulic or pneumatic in nature. The energy source drives movement of the piston within the cylinder to compress air therein.

[1356] Where the stage is configured to perform expansion, the piston shaft is in physical communication with a generator (not shown) through the linkage. The generator generates energy from the movement of the piston rod communicated through the linkage.

[1357] Figure 59 presents only a simplified generic view of an embodiment of a compression/expansion stage, and the present invention should not be understood as being limited to a specific element of this diagram. For example, while Figure 59 shows the piston as being moveable in the vertical direction, this is not required and in various embodiments the piston could be moveable in the horizontal or other directions.

[1358] Also, in the particular embodiment of Figure 59, the gas flow valves 5910 and 5912 are formed in an end wall of the cylinder 5902. Figures 59A-59B also show the valves in an end wall of the cylinder for purposes of illustration, but the valves could be positioned elsewhere in the chamber.

[1359] Valve 5910 is selectively actuable by an element 5911 such as a solenoid, to move valve plate 5910a away from valve seat 5910b, thereby allowing fluid communication between the compression and/or expansion chamber 5908 and a conduit 5914 on a low pressure side 5916. Valve 5912 is selectively actuable by an element 5913 such as a solenoid to move valve plate 5912a away from valve seat 5912b, thereby allowing fluid communication between the compression and/or expansion chamber 5908 and a conduit 5918 on a high pressure side 5920.

[1360] As mentioned previously, embodiments of the present invention are not limited to use with valves having any particular structure or configuration relative to the chamber(s). As also mentioned previously, embodiments of the present invention are not limited to a moveable member comprising a reciprocating piston, and other structures could be used, including but not limited to screws, quasi-turbines, and gerotors.

[1361] Figure 59A shows the stage 5900 where the piston head 5906a has moved to be at the top (Top Dead Center - TDC) of the cylinder. Figure 59A shows that at TDC, there is some amount of dead volume (V_{dead}) between the upper surface of the piston head 5906, and the end wall of the cylinder.

[1362] According to particular embodiments of the present invention, a multi-stage compressor, expander, or compressor/expander may be designed to meet certain criteria regarding the temperature change at each stage.

[1363] Figure 59B shows the stage 5900 where the piston head 5906 has moved to be at the bottom (Bottom Dead Center - BDC) of the cylinder. Figure 59B shows two volumes.

[1364] A total volume (V_{total}) of the stage is defined between the top surface of the piston and the upper wall of the cylinder at BDC. A displacement volume ($V_{displacement}$) of the stage is defined between the top

surface of the piston at BDC and at (Top Dead Center -TDC). The dead volume represents the difference between the total volume and the displacement: $V_{dead} = V_{total} - V_{displacement}$.

[1365] A value quantifying the action of stage 5900 is its compression ratio or expansion ratio, generically referred to here as *r*. The compression or expansion ratio may be expressed in the following Equation (1'):

$r = \frac{V_{total}}{V_{closed}}$ (1'), where:

Where V_{closed} is the volume of the cylinder when the intake valve closes during expansion or the exhaust valve opens during compression.

[1366] In the expansion case, the volumes V_{closed} and V_{total} may differ from each other due not only to the dead volume, but also due to closure of a gas inlet valve prior to the piston reaching BDC during an expansion stroke, and also due to closure of a gas exhaust valve prior to the piston reaching TDC during an exhaust stroke. In the case of compression, V_{closed} may differ from V_{total} due not only to the dead volume, but also due to opening of a gas exhaust valve prior to the piston reaching TDC during a compression stroke.

[1367] In a multi-stage compression/expansion apparatus having the same compression or expansion ratio at each stage, a stage's compression or expansion ratio *r* is the *Nth* root of the overall compression or expansion ratio. That is:

$r = \sqrt[N]{R}$ (2')

Where R is the overall compression or expansion ratio, and *N* is the number of stages.

[1368] This is an idealization where intercooling (or interheating) occurs between stages. That is, if the temperature of the compressed or expanded gas is brought back to ambient temperature before it enters the next stage. The formula (2') also neglects any volumetric inefficiency.

[1369] The different stages can have different compression or expansion ratios, so long as the product of the compression or expansion ratios of all of the stages is R. That is, in a three-stage system, for example:

$r_1 \times r_2 \times r_3 = R$. (3')

[1370] In a multi-stage system, the relative displacements of the cylinder chambers are governed by the following equation:

$V_i = V_T \frac{r_i}{\sum_{j=1}^{N} r_j}$ (4'), where:

V_i is the displacement volume of the i^{th} cylinder device, and V_T is the total displacement of the system (that is, the sum of the displacements of all of the cylinder devices).

[1371] According to certain embodiments of the present invention, each stage of a multi-stage compression or expansion apparatus may be configured to operate with a particular temperature change during the course of the expansion or compression stroke. The design and operation of such embodiments may be accomplished utilizing a series of mathematical relationships defining the

performance of individual stages in terms of physical quantities. One example of such a set of mathematical relationships is described below in Equations (5')-(16') in connection with a gas expansion stage.

[1372] The final temperature of the gas following compression or expansion, and the related final pressure of the gas following compression or expansion depend on a host of quantities. The following Equations (6', 7') express these final values for the pressure and temperature of a stage.

[1373] The pressure ratio of such a stage is given by:

$$r = \frac{(T_{gas\ initial} + \Delta T_{gas-liquid})}{T_{gas\ initial}} \left(\frac{V_{closed}}{V_{displacement}}\right)^{\gamma effective} \quad (5') \text{ or,}$$

$$p_{final} = p_{initial} \frac{(T_{gas\ initial} + \Delta T_{gas-liquid})}{T_{gas\ initial}} \left(\frac{V_{closed}}{V_{displacement}}\right)^{\gamma effective} \quad (6')$$

$$T_{gas\ final} = (T_{gas\ initial} + \Delta T_{gas-liquid}) \left(\frac{V_{closed}}{V_{displacement}}\right)^{\gamma effective - 1} \quad (7')$$

V_{closed} is the volume of the cylinder when the intake valve closes during expansion or the exhaust valve opens during compression (V_{total}/r).

$V_{displacement}$ is the total displacement of the cylinder.

$\Delta T_{gas-liquid}$ is the difference is temperature between the gas and the liquid inside the compression / expansion chamber at the end of the stroke.

$\gamma_{effective}$ is the effective polytropic index.

[1374] As will be described in detail below, the quantities $\gamma_{effective}$ and $\Delta T_{gas-liquid}$ depend upon a number of values. Based upon these values, Equations (5', 6' ,7') may be solved to determine the resulting temperature change for a single expansion stage.

[1375] Control over expansion ratio may be achieved in several possible ways. In one approach, the expansion ratio may be determined by controlling V_{closed}. For example V_{closed} may be controlled through the timing of actuation of valves responsible for admitting flows of compressed gas into the chamber for expansion.

[1376] Figures 61A-C accordingly show an expansion stage 6100 where piston 6106 is undergoing an expansion stroke. Figure 61A shows valve 6110 closed with piston 6106 moving downward, and valve 6112 open to admit a flow of compressed gas into the chamber for energy recovery by expansion. In Figure 61B, valve 6112 is closed to halt the inlet of gas prior to the piston reaching the BDC position, thereby limiting to V_{closed} the quantity of gas that may be expanded during this piston stroke. Figure 61C shows the continued movement of the piston in the downward direction as the gas quantity V_{closed} expands.

[1377] Thus by regulating the timing of closing of valve 6112, the quantity of gas which is expanded in the cylinder is limited. Specifically, because in Figure 61B the valve 6112 is closed prior to the piston

reaching BDC, the volume of gas in the cylinder is limited, and the expansion ratio and temperature change experienced by the stage are also correspondingly limited.

[1378] The timing of actuation of the inlet valve 6112, may be regulated by a controller or processor, such as the controller that is performing the iterated calculation over multiple stages that has been previously described. Accordingly, Figures 61A-C show the actuating element 6111 of valve 6112 as being in electronic communication with a controller 6196. Controller 496 is in turn in electronic communication with a computer-readable storage medium 6194, having stored thereon code for instructing actuation of valve 6112.

[1379] An adjustment of expansion ratio as described above, may represent a trade-off with the amount of energy stored or released by the system. Specifically, expansion of a smaller volume of gas in Figures 61B-C than could be otherwise be contained within the cylinder, reduces the power output to the piston by the expanding gas. Such an energy loss, however, may be desirable in order to achieve a desired temperature change, for example to bring the temperature change of a stage in line with that experienced by other stages.

[1380] Liquid introduced in an expansion chamber can also serve to alter the expansion ratio. A cylinder with no water in it has an expansion ratio of $r = V_{total} / V_{closed}$. If a volume of water, V_{water} is introduced to the cylinder, the expansion ratio becomes $r = (V_{total} - V_{water}) / (V_{closed} - V_{water})$. Thus the expansion ratio depends on V_{water}.

[1381] Returning to Equations (5', 6', 7'), the quantity $\gamma_{effective}$ is derived from a number of values. Calculation of γ_{eff} is now discussed in connection with Equations (8') and (9'):

$$\gamma_{effective} = \frac{\hat{c}_{p_{effective}}}{\left(\hat{c}_{p_{effective}} - 1\right)\left(1 + \phi_p\right)} \quad (8')$$

$$\hat{c}_{p_{effective}} = \hat{c}_{p_{gas}}\left(1 + m_v \frac{c_{p_{liquid}}}{c_{p_{gas}}}\right) \quad (9')$$

ϕ_p ≡ polytropic non-uniformity (the factor by which the polytropic index is increased due to a non-uniform distribution of liquid droplets in the compression / expansion chamber)

$\hat{c}_{p_{gas}}$ ≡ constant pressure heat capacity of the gas divided by R

$c_{p_{liquid}}$ ≡ constant pressure heat capacity of the liquid

m_v ≡ mass ratio of liquid to gas

R ≡ gas constant

[1382] The quantity $\Delta T_{gas\text{-}liquid}$ appearing in Equations (6', 7') is also derived from a number of variables. This is now discussed in connection with Equations (10')-(17'):

$$\Delta T_{gas-liquid} \equiv \frac{\Delta T_{gas-liquid_{initial}}}{\left(1 - \frac{\Delta T_{gas-liquid_{initial}}}{T_{gas_{initial}}}\right)} \quad (10')$$

$$\Delta T_{gas-liquid_{initial}} \equiv \left[\frac{\gamma_{effective}}{\left(h_{v_{gl}} \frac{V_{closed}}{V_{total}}\right)}\right]\left(\frac{P_{max}}{V_{total}}\right)\left(\frac{m_r c_{p_{liquid}}}{c_{p_{gas}} + m_r c_{p_{liquid}}}\right) \quad (11')$$

$h_{v_{gl}} \equiv \frac{3h_{gas-liquid}\alpha_{liquid}}{r_{droplet}}$ is the volumetric thermal conductivity between gas and liquid (12')

$h_{gas-liquid} \equiv \frac{k_{gas}Nu}{r_{droplet}}$ is the overall thermal conductivity from gas to liquid (13')

$\frac{P_{max}}{V_{total}} = -\omega p_{gas}\frac{dV/d\theta}{V_{total}}$ (14')

$r_{droplet} =$ mean radius of liquid droplets

$\alpha_{liquid} =$ proportion of liquid

$k_{gas} =$ thermal conductivity of the gas

ω = rotational speed

$dV/d\theta =$ change in compression / expansion chamber volume with crank angle θ

$$Nu \equiv 2\left[1 + 0.419 Pr^{1/3}\left(\frac{a_{gravity}\rho_{gas}}{\mu_{gas}^2 c_{drag}}(\rho_{liquid} - \rho_{gas})\right)^{1/4} r_{droplet}^{3/4}\right]$$ is the Nusselt number (15')

$a_{gravity}$ = acceleration due to gravity

ρ = density

μ = viscosity

$c_{drag} =$ drag coefficient of droplet (sphere = .47)

$Pr \equiv \frac{\mu_{gas} c_{p_{gas}}}{k_{gas}}$ is the Prandtl number (16')

[1383] The Equations (5', 6', 7') may also be used to determine properties of multiple expansion stages arranged in series with each other. As discussed further below, the equations may be solved for each stage, with the temperature and pressure output by one stage being fed as inputs to the equations for the next successive stage.

[1384] In addition, the Equations (5', 6', 7') showing properties of each stage in a multi-stage system, may be solved in an iterative manner to determine the structure and/or operational parameters of individual stages exhibiting changes in temperature when arranged in series with one another. Such iterative solution of these equations as applied to multiple expansion stages, is further described below.

[1385] If, in a multi-stage compression or expansion apparatus the mass flow rate, intake pressures, and dead volumes are fixed, the temperature change during the compression / expansion stroke and the compression / expansion ratio represent a single free parameter. That is, controlling one gives the other. Thus, when designing each stage, choosing a compression / expansion ratio using equation (5'), will, nominally, result in the desired temperature change occurring during the course of the compression or expansion stroke. By choosing a suitably effective heat exchanger, it is possible to design a multi-stage system iteratively such that each stage exhibits the desired temperature change.

[1386] The various relationships described in connection with Equations (5')-(16') can be used to produce an output for a given expansion stage. In particular, the various types of inputs to the equations, produce a corresponding output in the form of the temperature and pressure ($T_{gas\ final}$, p_{final}) of the gas exhausted from that expansion stage, as well as the temperature change ($\Delta T_{gas,\ final\text{-}initial}$) experienced by the expansion stage.

[1387] These outputs (T_{gas_final1}, p_{final1}) can in turn be fed as inputs representing the initial temperature and pressure ($T_{gas_initial2}$, $p_{initial2}$) to the equations (5', 6', 7') to calculate the behavior of a next expansion stage receiving this expanded gas for further expansion. The pressure and temperature outputs (T_{gas_final2}, p_{final2}) of a stage may be being fed as inputs ($T_{gas_initial3}$, $p_{initial3}$) to a third expansion stage, to produce the final output temperature and pressure (T_{gas_final3}, p_{final3}).

[1388] In the calculation, values of the initial temperature and/or pressure of the system ($T_{gas_initial1}$, $p_{initial_1}$), and/or values of the final temperature and/or pressure of the system (T_{gas_final3}, p_{final3}), may be predetermined. For example the pressure and/or temperature of the inlet gas, may be dictated by the current capacity of a compressed gas storage unit (which as discussed below, may change over time as compressed gas is consumed).

[1389] In another example, the pressure and/or temperature of the outlet gas may be dictated by the environment to which it is being exhausted. For example, air being exhausted into the outside environment at sea level may not have an output pressure of less than 1 ATM.

[1390] Other factors may constrain the calculation. For example, where liquid water at ambient temperature is being used for heat exchange, the temperature change experienced by any one stage could not be lower than about 15 °C in order to avoid freezing.

[1391] In addition, the corresponding equations showing properties of each stage in a multi-stage compression system, may be solved in an iterative manner to determine the structure or operational parameters of individual stages that will exhibit substantially equal changes in temperature when arranged in series with one another.

[1392] A system configured to determine conditions under which each stage will experience a substantially equivalent temperature change may include a controller in electronic communication with a computer-readable storage medium which may be based upon magnetic, optical, and/or semiconductor principles. This computer-readable storage medium has stored thereon code that is configured to instruct the processor to perform certain tasks.

[1393] For example, code stored on the computer-readable storage medium may instruct the controller to predetermine the initial pressure and/or temperature parameters that are input to the calculation. Code stored on the computer-readable storage medium may also instruct the controller to predetermine the final pressure and temperature parameters that are to be output by the multi-stage system calculation.

[1394] Code stored on the computer-readable storage medium may further instruct the controller to predetermine certain of the variables present in inputs to the respective equations. For example, certain of these variables may be predetermined by the identity of the gas (for example air) that is subject to compression, and/or the identity of the liquid (for example water) that is being injected for heat exchange.

[1395] Code stored on the computer-readable storage medium may further instruct the controller to determine one or more variables present in inputs to the respective equations. For example, results of a prior iteration may indicate changing an input variable in a particular manner (direction, magnitude) to produce a desired per-stage temperature change. Thus, based upon an algorithm expressed by code present in the computer-readable storage medium, the controller may change the value of an input from a previous iteration. A standard technique such as conjugate gradient or steepest descent may be used.

[1396] Successful convergence of the iterative calculations to define parameters of stages exhibiting substantially equivalent temperature changes, may be determined based upon numerical analysis techniques. Examples of such numerical analysis to obtain such a solution include but are not limited to conjugate gradient, steepest descent, Levenberg-Marquardt, Newton-Raphson, neural networks, genetic algorithms, or binary search.

[1397] According to certain embodiments, a calculation based on equations (5' – 16') may be performed during the design process, to fix certain unchanging parameters of a design. According to other embodiments, an iterative calculation described above may be performed on an ongoing basis, with properties of the multi-stage system adjusted to reflect changing conditions. One example of such a changing condition is the inlet temperature ($T_{gas_initial}$) to the system.

[1398] Specifically, as a compression system is operated over the course of a day, the temperature of the outside air may change over time. Where this outside air is inlet for compression, its temperature will change over time (for example rising during the day, and cooling at night). The controller may be in electronic communication with a sensor to detect this change in temperature, and provide it as an input to the calculation. The controller may also be in communication with additional sensors to detect a state of other changing properties.

[1399] The controller may be in electronic communication with various elements of a gas compression system. Based upon the results of the calculation, the controller may instruct operation of system elements to ensure that even temperature changes are maintained at the different stages.

[1400] For example, in certain embodiments the controller may actuate a valve responsible for admitting gas into a compression chamber. In certain embodiments, the controller may actuate a valve responsible for exhausting gas from an expansion chamber, and/or a valve responsible for flowing liquid

into a compression chamber. Control over the timing of actuation of these valve elements may affect the compression ratios of individual stages, and hence the temperature changes experienced by those stages.

[1401] Equation (17') shows T_{gas_final} to depend upon V_{closed}:

$$T_{gas_{final}} = T_{gas_{initial}} + \Delta T_{gas-liquid}\left(\frac{V_{closed}}{V_{displacement}}\right)^{r_{effective}} \quad (17')$$

[1402] Equation (18') shows that V_{closed} can be expressed in terms of compression ratio (r):

V_{closed} = the chamber volume when the compression intake valve closes = $\frac{V_{total}}{r}$ (18')

[1403] Thus, the compression ratio of a stage can determine the magnitude of a temperature change experienced by that compression stage. Such control over compression ratio may be achieved in several possible ways.

[1404] In one approach, the compression ratio may be determined by controlling V_{closed}. For example V_{closed} may be controlled through the timing of actuation of valves responsible for admitting flows of gas into the chamber for compression.

[1405] In a manner analogous to that discussed above, the controller may be in electronic communication with various elements of a gas compression system. Based upon the results of the calculation, the controller may instruct operation of system elements to ensure that even temperature changes are maintained at the different stages.

[1406] For example, in certain embodiments the controller may actuate a valve responsible for admitting gas into a compression chamber. Figures 63A-C show an example of such inlet valve actuation in the case of compression. Specifically, Figures 63A-B shows a compression stage 6300 where piston 6306 is undergoing a stroke prior to compression, and then Figure 63C shows the initial portion of the compression stroke.

[1407] Figure 63A shows valve 6312 closed with piston 6306 moving downward, and valve 6310 open to admit a flow of gas into the chamber for compression. In Figure 63B, valve 6310 is closed to halt the inlet of gas prior to the piston reaching BDC, thereby limiting to V_{closed} the quantity of gas that may be compressed in the subsequent stroke of the piston. Figure 63C shows that in the subsequent compression stroke, as piston 6306 moves upward to compress the gas quantity V_{closed}.

[1408] By regulating the timing of closing of valve 6310, the quantity of gas which is compressed in the cylinder is determined. Specifically, because in Figure 63B the valve 6310 is closed prior to the piston reaching BDC, the effective volume of gas in the cylinder for compression is limited, and the compression ratio (r) of the stage is also limited.

[1409] The timing of actuation of the inlet valve 6310, may be regulated by a controller or processor. Accordingly, Figures 63A-C show the actuating element 6311 of valve 6310 as being in electronic communication with a controller 6396. Controller 6396 is in turn in electronic communication with a

computer-readable storage medium 6394, having stored thereon code for instructing actuation of valve 6310.

[1410] Timing of actuation of a gas outlet valve in a compression mode, can also be regulated to control the compression ratio. In a manner similar to that described above, closure of the outlet valve can be timed to retain some residual compressed gas within the compression chamber, thereby reducing V_{closed} to less than the full value of ($V_{displacement}$) in the subsequent piston stroke to intake more gas for compression. Such valve timing would thus also reduce the compression ratio (r).

[1411] In a manner similar to that previously described in connection with prior figures, liquid introduced in a compression chamber can also serve to alter the compression ratio (r). A cylinder with no water in it has a compression ratio of $r = V_{total} / V_{closed}$. If a volume of water, V_{water} is introduced to the cylinder, the compression ratio becomes $r = (V_{total} - V_{water}) / (V_{closed} - V_{water})$. Thus the compression ratio depends on V_{water}.

[1412] Performance of an expander may be controlled by an active control loop whose inputs may include control parameters and sensor data, and whose outputs may include valve actuation. In one embodiment, control inputs include but are not limited to:

$P_f \equiv$ The final pressure we expand down to before opening the exhaust valve

$\Delta V_i \equiv$ The change in volume during intake

$\Delta V_e \equiv$ The change in volume after exhaust

$S \equiv$ The rotational speed of the crank, in RPM

$\Theta_o \equiv$ The crank angle at which a spray valve is opened

$\Theta_c \equiv$ The crank angle at which a spray valve is closed

$F \equiv$ The flow rate of a spray pump

[1413] Measured values from sensors include but are not limited to:

$P_i \equiv$ The input pressure

$P_o \equiv$ The output pressure

$\Theta \equiv$ The crank angle relative to TDC

$T_i \equiv$ The average inlet temperature

$T_f \equiv$ The average exhaust temperature

$W \equiv$ The shaft power output by the expander

[1414] In an embodiment, the control loop may proceed as follows. Starting with the piston at TDC, the intake valve is opened, admitting gas at P_i.

[1415] The intake valve remains open as the piston moves until the piston has swept out a volume of ΔV_i. This may be computed from the measured crank angle and the known piston and linkage dimensions.

[1416] At this point, the intake valve is closed and the gas expands, doing work on the piston as the pressure inside the cylinder decreases. When the pressure inside the cylinder has fallen below P_f, the exhaust valve is opened. This may be before or at BDC.

[1417] The exhaust valve remains open until ΔV_e before TDC (which may be computed from the measured crank angle), at which time the exhaust valve is closed. The piston continues to move to TDC, and the cycle repeats.

[1418] The spray can be controlled with this control loop. In some embodiments, the liquid is simply sprayed continuously into the cylinder.

[1419] According to certain embodiments, the spray may be turned on by a controllable valve such as a solenoid valve, during a portion of a cycle. For example, the spray may be turned on from a crank angle A to a crank angle B from TDC. A might be 0, 5, 10, 45, 90, 120, 180, 200, 240, 270 degrees. B might be 180 or 360 degrees, plus or minus 20 degrees or more.

[1420] The pressure or flow rate to the spray nozzles may be controlled. This may be done, for example, by controlling a variable frequency drive connected to a spray pump.

[1421] The rotational speed of the system may be controlled. This may be done, for example, by varying the load on a generator in mechanical communication with the piston.

[1422] The control input parameters, in conjunction with operating conditions, lead to particular results, including but not limited to final temperature (T_f,) or shaft power (W). The relationship between control input parameters and outputs may be modeled from physical principles, and/or it may be measured during controlled tests, creating a map. This map may be interpolated to approximate a smooth multi-dimensional surface.

[1423] During operation of the expander it may be desirable to achieve a certain target performance, such as outputting a particular power (W) to meet a particular demand. The map that has been created may be used to arrive at an initial set of control values for operation.

[1424] During operation, as the desired performance parameter (in this case, W) is measured, the gradient of the map may be used to alter the control parameters in a direction that reduces or minimizes the difference between the measured value and the desired value. Examples of target performance metrics include but are not limited to power output, efficiency (computed from measured values), or a weighted sum of other metrics.

[1425] Certain embodiments may utilize the metric of minimizing $T_i - T_f$ subject to a constraint such as $T_f > T_{min.}$ This might be used to obtain a high efficiency from the expander while keeping the temperature above a freezing point of the liquid.

[1426] While performance of an expander utilizing a control loop has been described above, the present invention is not limited to these particular embodiments. According to alternative embodiments, performance of a compressor may be controlled by an active control loop whose inputs may include control parameters and sensor data, and whose outputs may include valve actuation.

[1427] In one embodiment, control inputs include but are not limited to:

$\Delta P_f \equiv$ The difference between the final pressure in the cylinder before opening the exhaust valve and the pressure on the other side of the exhaust valve (P_o)

$\Delta P_i \equiv$ The difference between the initial pressure in the cylinder before opening the intake valve and the pressure on the other side of the intake valve (P_i)

$\Delta V_i \equiv$ The change in volume during intake

$\Delta V_e \equiv$ The change in volume after exhaust

$S \equiv$ The rotational speed of the crank, in RPM

$\Theta_o \equiv$ The crank angle at which a spray valve is opened

$\Theta_c \equiv$ The crank angle at which a spray valve is closed

$F \equiv$ The flow rate of a spray pump

[1428] Measured values from sensors include but are not limited to:

$P_i \equiv$ The input pressure

$P_o \equiv$ The output pressure

$\Theta \equiv$ The crank angle relative to TDC

$T_i \equiv$ The average inlet temperature

$T_f \equiv$ The average exhaust temperature

$W \equiv$ The shaft power output by the expander

[1429] In an embodiment, the control loop may proceed as follows. Starting with the piston at TDC and the gas in the cylinder at some pressure P, the piston begins to move towards BDC.

[1430] When the pressure drops below $P_i - \Delta P_i$ the intake valve is opened. This may be before or at TDC.

[1431] The piston moves to BDC, at which time the intake valve is closed. As the piston heads back towards TDC the piston compresses the gas as the pressure inside the cylinder increases.

[1432] When the pressure inside the cylinder has risen above $P_o - \Delta P_f$, the exhaust valve is opened. This may be before or at TDC.

[1433] The exhaust valve remains open until ΔV_e before TDC (as may be computed from the measured crank angle), at which time the exhaust valve is closed. The piston continues to move to TDC, and the cycle repeats.

[1434] Spray may be controlled with this control loop. In some embodiments, the liquid is simply sprayed continuously into the cylinder.

[1435] In certain embodiments, the spray may be turned on (for example by a controllable valve such as a solenoid valve) during a portion of a cycle. For example, the spray may be turned on from a crank angle A to a crank angle B from TDC. A might be 0, 5, 10, 45, 90, 120, 180, 200, 240, 270 degrees. B might be 180 or 360 degrees, plus or minus 20 degrees or more.

[1436] The pressure or flow rate to the spray nozzles may be controlled, for example by controlling a variable frequency drive connected to a spray pump. The rotational speed of the system may be controlled, for example by varying the load on a generator in mechanical communication with the piston.

[1437] The control input parameters in conjunction with operating conditions, lead to particular results, such as final temperature (T_f) or shaft power (W). The relationship between control input parameters and outputs may be modeled from physical principles, or it may be measured during

controlled tests, creating a map. This map may be interpolated to approximate a smooth multi-dimensional surface.

[1438] During operation of the compressor, it may be desirable to achieve a certain target performance such as outputting a particular power (W) to meet a particular demand. The map created above may be used to first arrive at an initial set of control values for operating the apparatus.

[1439] During operation, as the desired performance parameter (in this case, W) is measured, the gradient of the map may be used to alter the control parameters in a direction that reduces or minimizes the difference between the measured value and the desired value. Some target performance metrics might be power input, efficiency (computed from measured values). Another metric might be a weighted sum of other metrics.

[1440] Another metric may be minimizing $T_i - T_f$ subject to a constraint such as $T_f > T_{min.}$ This metric might be used to get the high efficiency from the expander while keeping the temperature below a boiling point of the liquid.

[1441] Thus, the compression ratio of a stage can determine the magnitude of a temperature change experienced by that compression stage. Such control over compression ratio may be achieved in several possible ways.

[1442] In one approach, the compression ratio may be determined by controlling V_{closed}. For example V_{closed} may be controlled through the timing of actuation of valves responsible for admitting flows of gas into the chamber for compression.

[1443] The controller may be in electronic communication with various elements of a gas compression system. Based upon the results of the solution to the iterated calculation, the controller may instruct operation of system elements to ensure that even temperature changes are maintained at the different stages.

[1444] For example, in certain embodiments the controller may actuate a valve responsible for admitting gas into a compression chamber. Figures 63A-C show an example of such inlet valve actuation in the case of compression. Specifically, Figures 63A-B shows a compression stage 6300 where piston 6306 is undergoing a stroke prior to compression, and then Figure 63C shows the initial portion of the compression stroke.

[1445] Figure 63A shows valve 6312 closed with piston 6306 moving downward, and valve 6310 open to admit a flow of gas into the chamber for compression. In Figure 63B, valve 6310 is closed to halt the inlet of gas prior to the piston reaching BDC, thereby limiting to V_{closed} the quantity of gas that may be compressed in the subsequent stroke of the piston. Figure 63C shows that in the subsequent compression stroke, as piston 6306 moves upward to compress the gas quantity V_{closed}.

[1446] By regulating the timing of closing of valve 6310, the quantity of gas which is compressed in the cylinder is determined. Specifically, because in Figure 63B the valve 6310 is closed prior to the piston reaching BDC, the effective volume of gas in the cylinder for compression is limited, and the compression ratio (c_r) of the stage is also limited.

[1447] The timing of actuation of the inlet valve 6310, may be regulated by a controller or processor. Accordingly, Figures 63A-C show the actuating element 6311 of valve 6310 as being in electronic communication with a controller 6396. Controller 6396 is in turn in electronic communication with a computer-readable storage medium 6394, having stored thereon code for instructing actuation of valve 6310.

[1448] Timing of actuation of a gas outlet valve in a compression mode, can also be regulated to control the compression ratio. In a manner similar to that described above, closure of the outlet valve can be timed to retain some residual compressed gas within the compression chamber, thereby reducing V_{closed} to less than the full value of (V_{disp}) in the subsequent piston stroke to intake more gas for compression. Such valve timing would thus also reduce the compression ratio (c_r).

[1449] In a manner similar to that previously described in connection with prior figures, liquid introduced in a compression chamber can also serve to alter the compression ratio (c_r). A cylinder with no water in it has a compression ratio of $c_r = V_{total} / V_{closed}$. If a volume of water, V_{water} is introduced to the cylinder, the compression ratio becomes $c_r = (V_{total} - V_{water}) / (V_{closed} - V_{water})$. Thus the compression ratio depends on V_{water}.

[1450] The above approaches have focused upon controlling compression and/or expansion ratio by volume control utilizing the regulation of valve (inlet/outlet) timing and/or liquid injection. However, this is not required by the present invention, and alternative embodiments could achieve control over temperature by regulating other elements affecting compression or expansion ratio.

[1451] For example, other techniques of changing the compression or expansion ratio may employ mechanical approaches. Examples of such approaches include but are not limited to altering the length of a piston stroke, or operating a plunger to vary chamber dead volume.

[1452] The temperature change occurring at a given stage may be controlled by varying the speed of that stage. For example, lower pressure stages may exhibit a smaller ΔT than higher pressure stages at the same speed and gas and liquid mass flow rate.

[1453] Increasing the speed, and reducing the displacement by the same factor will give the same mass flow rate (for example to match subsequent stages), but a higher ΔT. The size of such a stage will be reduced, lowering cost.

[1454] Each stage could run at a different speed, either with a fixed or variable gear ratio between separate cranks or other linkages actuating the movable member of each stage. Alternatively, a separate motor/generator could be provided for each stage, or group of stages.

[1455] If more than one speed is independently controllable, these speeds may be adjusted dynamically to achieve a desired operating performance. One way of dynamically adjusting parameters that control compression/expansion ratios and ΔT values, is to use a function of weighted inputs.

[1456] In certain embodiments, these inputs may include but are not limited, to raw sensor data such as intake pressure, discharge pressures, intake temperature, discharge pressure, liquid flow rate, gas flow rate, storage tank pressure, and measured power into or out of the motor/generator. These inputs may

include computed values based on raw sensor data and other sources, such as power demand requirements, user input parameters, estimated ΔT, and estimated efficiency.

[1457] Embodiments of the present invention having multiple stages of compression or expansion that experience a substantially equivalent temperature change according to the present invention, may offer a number of potential benefits. One potential benefit is the ability to maximize efficiency of the system.

[1458] As mentioned above, compression and expansion proceed with minimum thermal loss and maximum efficiency, where they occur under near-isothermal conditions. The problem of designing an apparatus to efficiently perform such compression or expansion across multiple stages, is simplified by requiring the temperature change of each of the stages to be the same. With this condition in place, other elements of the multi-stage system are able to be designed to minimize this uniform temperature change.

[1459] Moreover, in order to achieve the near-isothermal conditions that are desirable for efficient operation, each stage of a multi-stage system is in thermal communication with a thermal source or thermal sink to exchange energy. In the case of a stage performing compression, the stage is in thermal communication with a heat sink to transfer thermal energy from the heated gas. In the case of a stage performing expansion, the stage is in thermal communication with a heat source to transfer thermal energy to the cooled gas.

[1460] Figure 64A shows the case of a multi-stage system 6400 where each of the stages 6402, 6404, and 6406 is expected to exhibit a different change in temperature. To reliably and efficiently exchange the necessary amounts of thermal energy, the system of Figure 64A would generally employ different heat exchangers 6408, 6410, and 6412 for each stage. Moreover, because the circulating fluids would be at different temperatures, separate circulation systems (including a pump) would be used between each heat exchanger and a respective thermal source or sink having the relevant thermal capacity.

[1461] Where, however, each stage is expected to exhibit a substantially equivalent temperature change, a simpler heat exchanger design may be used. Figure 64B shows such a system 6450, where each stage 6452, 6454, and 6456 is in thermal communication with a tube-in-shell heat exchanger 6458 of the same type. Moreover, because each heat exchanger is expected to exchange a same amount of thermal energy at each stage, these heat exchangers can all share a common circulation system having a single pump 6460 and thermal sink or thermal source. Such a configuration desirably eliminates the use of multiple pumps and fluid conduit loops, thereby reducing the complexity and expense of the system.

[1462] As described above, elements of compressed gas systems according to the present invention may be in communication with other structures through one or more linkages, as generically depicted in Figure 65. Such linkages between a compressed gas energy system 6500 and external elements can include physical linkages 6502 such as mechanical linkages, hydraulic linkages, magnetic linkages, electro-magnetic linkages, electric linkages, or pneumatic linkages.

[1463] Other possible types of linkages between embodiments of systems according to the present invention include thermal linkages 6504, which may comprise conduits for liquid, gaseous, or solid

materials, conduits, pumps, valves, switches, regenerators, and heat exchangers, including cross-flow heat exchangers.

[1464] As further shown in Figure 65, other possible types of linkages between embodiments of systems according to the present invention and outside elements, include fluidic linkages 6506, and communications linkages 6508. Examples of the former include flows of material in the gas or liquid phase, and may include conduits, valves, pumps, reservoirs, accumulators, bottles, sprayers, and other structures.

[1465] Examples of communications linkages include wired or optical fiber linkages 6510a and wireless communications networks 6510b, that are locally active or which operate over a wide area. Examples of communications networks which may be suited for use by embodiments in accordance with the present invention include, but are not limited to, ethernet, CAN, WiFi, Bluetooth, DSL, dedicated microwave links, SCADA protocols, DOE's NASPInet, DoD's SIPRNet, IEEE 802.11, IEEE 802.15.4, Frame Relay, Asynchronous Transfer Mode (ATM), IEC 14908, IEC 61780, IEC 61850, IEC 61970/61968, IEC 61334, IEC 62056, ITU-T G.hn, SONET, IPv6, SNMP, TCP/IP, UDP/IP, advanced metering infrastructure, and Smart Grid protocols.

[1466] An amount of stored work that is present in a volume of air at a given pressure, and hence an amount of work that is stored in system 6500 of Figure 65, may be calculated as follows.

[1467] The quantity $\frac{W}{V_0}$ represents the amount of work stored per unit volume in a storage vessel. This is the storage energy density. This energy density can be determined utilizing the following formula:

$$\frac{W}{V_0} = P_a \cdot \left[1 + \left(\frac{P_0}{P_a} \right) \left[\ln\left(\frac{P_0}{P_a} \right) - 1 \right] \right]$$; where:

W = stored work;
V_0 = volume of the storage unit; and
P_a = ambient pressure in an open system, or the low pressure in a closed system; and
P_0 = pressure in the tank.

[1468] Expression of this energy density from volume in units of liters (L) and from pressure in units of atmospheres (atm), requires the use of a conversion factor:

$$\frac{W}{V_0} = 101.325 \cdot P_a \cdot \left[1 + \left(\frac{P_0}{P_a} \right) \left[\ln\left(\frac{P_0}{P_a} \right) - 1 \right] \right] \left(\frac{Joule}{L} \right)$$, where:

W = stored work (Joule);
V_0 = volume of storage unit (L);
P_a = ambient pressure in an open system, or low pressure for a closed system (atm); and
P_0 = pressure in the tank (atm).

[1469] So, under standard conditions where:

$V_0 = 1$ L;
$P_a = 1$ atm; and
$\frac{P_0}{P_a} \equiv r$:

W/ $V_0 = 101.325\ [1 + r\ (\ln r - 1)]\ \left(\frac{Joule}{L}\right)$, or

W/ $V_0 = 0.101325\ [1 + r\ (\ln r - 1)]\ \left(\frac{kJoule}{L}\right)$

[1470] The inverse of W/ V_0 represents the volume of a tank required to store a given amount of energy. This formula may be expressed in units of L / kW·h according to the following:

V_0/ W $\left(\frac{L}{kW \cdot h}\right)$ = 3600 / (W/ V_0), where:

1 Joule = 1 W·s;
3600 Joule = 1 W·h; and
3600 kJoule = 1 kW·h

[1471] This yields the following results at the given exemplary pressures:

P_0	W/ $V_0 \left(\frac{kJoule}{L}\right)$	V_0/ W $\left(\frac{L}{kW \cdot h}\right)$
300 atm	143	25.16
310 bar	146.5	24.57
10 atm	1.42	2533
8 atm	0.976	3687

[1472] Consideration of efficiency results in alteration of the above equation as follows:

$$\frac{W}{V_0} = 101.325 \cdot P_a \cdot \left[1 + \left(\frac{P_0}{P_a}\right)\left[\ln\left(\frac{P_0}{P_a}\right) - 1\right]\right] \cdot e \quad \left(\frac{kJoule}{L}\right), \text{ where:}$$

e = one-way efficiency of the system.

[1473] So in a system recovering compressed air to a final pressure (P_a) of 1 atm from a storage pressure (P_0) of 300 atm with an efficiency (e) of 0.8, the quantity V_0/ W = 31.45 $\left(\frac{L}{kW \cdot h}\right)$.

[1474] The ability of systems according to embodiments of the present invention, to rapidly recover energy stored in the form of compressed gas, may render such systems potentially suitable for a variety of roles. Several such roles involve the energy system's placement within the network responsible for providing electrical power to one or more end-users. Such a network is also referred to hereafter as a power grid.

[1475] Incorporated by reference in its entirety herein for all purposes, is the following document: "Energy Storage for the Electricity Grid: Benefits and Market Potential Assessment Guide: A Study for the DOE Energy Storage Systems Program", Jim Eyer & Garth Corey, Report No. SAND2010-0815, Sandia National Laboratories (February 2010).

[1476] Figure 66 presents a generic description of an embodiment of a network for the generation, transmission, distribution, and consumption of electrical power. The embodiment shown in Figure 66 represents a substantial simplification of an actual power network, and should not be understood as limiting the present invention.

[1477] Power distribution network 6601 comprises a generation layer 6602 that is in electrical communication with a transmission layer 6604. Power from the transmission layer is flowed through distribution layer 6605 to reach the individual end users 6606 of the consumption layer 6608. Each of these layers of the power distribution network are now described in turn.

[1478] Generation layer 6602 comprises a plurality of individual generation assets 6610a, 6610b that are responsible for producing electrical power in bulk quantities onto the network. Examples of such generation assets 6610a, 6610b can include conventional power plants that burn fossil fuels, such as coal-, natural gas-, or oil-fired power plants. Other examples of conventional power plants include hydroelectric, and nuclear power plants that do not consume fossil fuels. Still other examples of generation assets include alternative energy sources, for example those exploiting natural temperature differences (such as geothermal and ocean depth temperature gradients), wind turbines, or solar energy harvesting installations (such as photovoltaic (PV) arrays and thermal solar plants).

[1479] The assets of the generation layer generally deliver electrical power in the form of alternating current at relatively low voltages (<50kV) compared to the transmission layer. This electrical power is then fed to the transmission layer for routing. Specifically, the interface between a generation asset and the transmission layer is hereafter referred to as a busbar 6612.

[1480] The transmission layer comprises respective transformer elements 6620a and 6620b that are positioned at various points along a transmission line 6622. The step-up transformer 6620a is located proximate to the generation assets and corresponding busbars, and serves to increase the voltage of the electricity for efficient communication over the transmission line. Examples of voltages present in the transmission layer may be on the order of hundreds of kV.

[1481] At the other end of the transmission line, a step-down transformer 6620b serves to reduce the voltage for distribution, ultimately to individual end users. Power output by the step-down transformers of the transmission layer may lie in the voltage range of the low tens of kV.

[1482] Figure 66 presents the transmission layer in a highly simplified form, and transmission of power may actually take place utilizing several stages at different voltages, with the stages demarcated by transmission substation(s) 6665. Such a transmission substation may be present at the point of interface between transmission line 6622 and second transmission line 6663.

[1483] The distribution layer receives the power from the transmission layer, and then delivers this power to the end users. Some end users 6606a receive relatively high voltages directly from primary substation 6630a. The primary substation serves to further reduce the voltage to a primary distribution voltage, for example 12,000 V.

[1484] Other end users receive lower voltages from the secondary substations 6630b. Feeder lines 6632 connect the primary substation with the secondary substation, which further reduces the primary

distribution voltage to the final voltage delivered to end users at a meter 6634. An example of such a final voltage is 120 V.

[1485] Figure 66 provides a general description of the physical elements of a power network which may be used in the generation, transmission, distribution, and consumption of electric power. Because it forms a vital part of the public infrastructure, and requires cooperation from a multitude of distinct geographic and political entities, such power networks are highly regulated at many levels (local, national, international).

[1486] Figure 66 thus also provides a framework for classifying the regulation of various network elements by different regulatory agencies. For example, an element of the power network may be regulated based upon its classification as an asset of the generation layer, transmission layer, distribution layer, or consumption layer, of the power network. Such regulatory classification can play an important role in determining properties of an energy storage system that is integrated within a power network.

[1487] According to certain embodiments of the present invention, a compressed gas system may be incorporated within a generation layer of a power supply network. In certain embodiments energy recovered from the compressed gas may supply stable electricity over a short term period of time. According to some embodiments, energy recovered from the compressed gas may supply electricity to smooth or levelize variable output from a generation asset comprising a renewable energy source, for example a wind farm.

[1488] The various assets of the generation layer of the power network of Figure 66, may be categorized in terms of the types of power that are to be produced. For example, baseload generation assets typically comprise apparatuses that are configured to produce energy at the cheapest price. Such baseload power generation assets are generally operated continuously at full power in order to afford a highest efficiency and economy. Examples of typical baseload generation assets include large power plants, such as nuclear, coal, or oil-fired plants.

[1489] Load following generation assets generally comprise apparatuses that are more capable of responding to changes in demand over time, for example by being turned on/off or operating at enhanced or diminished capacities. Examples of such load following generation assets include but are not limited to steam turbines and hydroelectric power plants.

[1490] A load following generation asset may be called upon to provide additional power to meet shifting demand, with as little advance notice as 30 minutes. Because load following generation assets typically do not operate continuously at full capacity, they function less efficiently and their power is in general more expensive than that available from baseline generation assets.

[1491] A third type of generation asset are the peak generation assets. Peak generation assets are utilized on an intermittent basis to meet the highest levels of demand. Peak generation assets are capable of operating on relatively short notice, but with reduced efficiency and correspondingly greater expense. A natural gas turbine, is one example of an apparatus that is typically employed as a peak generation asset. Another is a diesel generator.

[1492] While they are capable of providing power on relatively short notice, even peak generation assets require some lead time before they are able to produce power of the quantity and quality necessary to meet the requirements of the power network. Examples of such power quality requirements include stability of voltage within a given tolerance range, and the necessity of synchronizing frequency of output with the frequency that is already extant on the network.

[1493] Embodiments of compressed gas energy storage and recovery systems have previously been described in U.S. Provisional Patent Application Nos. 61/221,487 and 61/294,396, and U.S. Nonprovisional patent application nos. 12/695,922, each of which are incorporated by reference in their entireties herein for all purposes. Incorporated by reference in its entirety herein for all purposes is U.S. Provisional Patent Application No. 61/358,776 (Attorney Docket No. 800KT-001300US).

[1494] One potential feature of such compressed gas energy storage and recovery systems, is their availability on short notice, to provide energy stored in relatively stable form. Specifically, the compressed gas may be maintained at an elevated pressure within a storage unit having a large volume. Examples of such storage structures include but are not limited to man-made structures such as tanks or abandoned mines or oil wells, or naturally-occurring geological formations such as caverns, salt domes, or other porous features.

[1495] Upon demand, the energy stored in the form of compressed gas may be accessed by actuating a gas flow valve to provide fluid communication between the storage unit and an expander apparatus. This simple valve actuation allows rapid conversion of the energy in the compressed gas into mechanical or electrical form.

[1496] For example, as described below expansion of the compressed gas within a chamber may serve to drive a piston also disposed therein. The piston may be in mechanical communication with a generator to create the electricity. Such a configuration allows for stable power to be rapidly generated because no warm-up period characteristic of a combustion engine is required. The energy in the air is available immediately, and need only overcome the system's inertia in order to deliver full power. A few seconds is sufficient.

[1497] Such ready availability of energy stored in the form of compressed gas, stands in marked contrast to combustion-type apparatuses, where stable power output may only be achieved upon regulation of multiple flows of material. For example, stable operation of a natural gas turbine may only occur by exercising precise control over flows of air and natural gas, the mixing of these flows, and the ignition of the mixture under substantially unvarying conditions. Operation of a gas turbine to produce stable, reliable output also requires careful management of the heat resulting from the combustion, to produce expanding gas that is converted to mechanical energy in the form of spinning turbine blades.

[1498] Depending upon the particular role upon which it is called upon to perform, a generation asset may operate with certain performance characteristics. Certain such characteristics are described in the table of Figure 62.

[1499] According to certain embodiments, the compressed gas energy storage and recovery system may be physically co-situated with the generation asset, and may be in electrical communication with the

power network through a common busbar. Alternatively, the generation asset and the energy storage and recovery system may be in electrical communication with the power network through a same transmission line.

[1500] Compressed gas energy storage and recovery systems according to the present invention, may be incorporated into the generation layer of a power network to levelize output of renewable energy sources that are variable in nature. For example, the output of a wind turbine is tied to the amount of wind that is blowing. Wind speed can rise or fall over relatively short periods, resulting in a corresponding rise and fall in the power output. Similarly, the output of a solar energy harvesting apparatus is tied to the amount of available sunshine, which can change over relatively short periods depending upon such factors as cloud cover.

[1501] Conventionally however, power networks have relied upon energy sources such as fossil fuel power plants, that exhibit an output that is substantially constant and controllable over time. This difference between renewable energy sources and those traditionally relied upon by power networks, may pose a barrier to the adoption renewable energy sources such as solar and wind power that are intermittent and/or variable in nature.

[1502] Accordingly, embodiments of compressed gas energy storage and recovery systems of the present invention may be coupled with renewable energy sources, in order to levelize their output onto the power network. Figure 67 shows a simplified view of such a levelizing function.

[1503] For example, over the time period A shown in Figure 67, the compressed gas energy storage and recovery system provides sufficient output to make up for differences between the variable output of the renewable alternative energy resource and a fixed value Z. This fixed value may be determined, for example, based upon terms of a contract between the owner of the generation asset and the network operator.

[1504] Moreover, at the time period starting at point B in Figure 67, the energy provided by the renewable generation asset falls off precipitously, for example based upon a complete loss of wind or an approaching storm front. Under such circumstances, the compressed gas energy storage and recovery system may be configured to supply energy over a time period following B, until another generation asset can be ramped up to replacement energy coverage over the longer term.

[1505] In certain embodiments, the compressed gas energy storage and recovery system could be configured to transmit a message to the replacement generation asset to begin the ramp-up process. Such a message could be carried by a wide area network such as the internet or a smart grid, where the compressed gas energy storage and recovery system is not physically co-situated with the replacement generation asset.

[1506] Specifically, incorporation of embodiments of compressed gas storage and recovery systems into a power network, is also shown in Figure 66. According to certain embodiments, a compressed gas energy storage and recovery system 6640b may be incorporated in the generation layer located along the same transmission line as a power generation asset 6610a or 6610b. In other embodiments, a compressed

gas energy storage and recovery system 6640a according to the present invention may be physically co-situated with the power generation asset, possibly behind the same busbar.

[1507] Locating a compressed gas energy storage and recovery system with a power generation asset, may confer certain benefits. One such potential benefit is a cost advantage afforded by allowing more efficient operation.

[1508] For example, in certain embodiments the compressor element of the compressed gas energy storage and recovery system could be in physical communication with a moving member of a power generation asset through a physical linkage 6641. Thus, as described above, in a particular embodiment, the spinning blades of a gas or wind turbine could be in physical communication with the compressor of a compressed gas energy storage system through a mechanical, hydraulic, or pneumatic linkage.

[1509] The direct physical communication afforded by such a linkage may allow power to be transferred more efficiently between these elements, thereby avoiding losses associated with having to convert the power into electrical form. In this manner, power from an operating gas or wind turbine could be utilized to store compressed gas for later recovery in an output levelizing or ramp-up coverage role.

[1510] Moreover, co-situation of the compressed gas storage and recovery system with a generation asset, may allow efficient communication between them of other forms of energy flows. For example, certain embodiments of an energy storage system may be in thermal communication through a thermal link 6642, with a co-situated generation asset. Thus in some embodiments, an efficiency of expansion of compressed gas by the compressed gas energy storage system, could be enhanced utilizing heat that is communicated from the generation asset.

[1511] In this manner, waste heat from a thermal solar power plant could be leveraged to enhance gas expansion in the chamber of an energy storage system. Under certain circumstances, the system and thermal solar plant could be co-situated. In other embodiments, the compressed gas could be brought to the generation asset through an elongated conduit.

[1512] Siting of an energy storage system with a generation asset may also afford actual fluid communication between these elements through a fluid link 6644. For example, where an energy storage system is co-situated with a gas turbine generator, the fluid link could allow compressed gas stored by the system to be flowed directly to such a gas turbine for combustion, thereby enhancing the efficiency of operation of the gas turbine.

[1513] Another possible benefit which may be realized by co-situation of the energy storage system with a power generation asset, is the ability to leverage off of existing equipment. For example, an existing generation asset typically already includes a generator for converting mechanical energy into electrical power. A compressed gas energy storage and recovery system according to the present invention could utilize the same generator element to convert motion from gas expansion into electrical power. Similarly, a compressed gas energy storage and recovery system could utilize a power generation asset's existing interface with the network (busbar), in order to communicate power to the network.

[1514] Yet another possible benefit which may be realized by locating an energy storage system behind the busbar in the network's generation layer, is the resulting form of regulatory oversight. As part of the generation layer, an energy storage system's contact with the network is relatively simple and limited. In particular, the energy storage system would contact the network through a single interface, and the magnitude and direction of flows of power through the interface would be based upon expected operation of the generator and the energy storage system.

[1515] Co-situation of the energy storage system with a power generation asset, may further enhance coordinated action between the two elements. In particular, the communication link 6650 between the compressed gas energy storage system 6640a and the co-situated generation asset may be local in nature, and hence potentially faster and more reliable than a larger area network.

[1516] Such close proximity between the energy storage system and the generation asset may help to facilitate a seamless transition between power being output onto the network from the storage system, to power being output onto the network from the generation asset. In the output levelizing role, close proximity between the energy storage system and the alternative source of intermittent energy may facilitate rapid and smooth intervention by the storage system to produce power in the face of rapidly changing conditions.

[1517] While desirable under certain circumstances, it is not required that the compressed gas energy storage and recovery system according to the present invention be physically co-situated with a power generation asset. In particular, the increased reliability of communication over wide area networks such as the internet, has reduced the need for close proximity between different elements of the network.

[1518] Accordingly, Figure 66 also shows an embodiment of a compressed gas energy storage and recovery system 6640b that is located along the same transmission line as a power generation asset 6610a. System 6640b and power generation asset 6610a may effectively communicate over wired or wireless network link 6657.

[1519] For example, one potential role for a compressed gas energy storage and recovery system according to embodiments of the present invention, is to provide a governor response mechanism that may otherwise be lacking from certain forms of alternative energy sources. Specifically, conventional power generators involving the flows of fluids (such as steam turbines), include a governor device linking measured speed of the generator with a fluid flow valve. The governor may be operated in a manner to provide negative feedback, for example opening the valve to promote fluid flow when operational speed is too low, and closing the valve to restrict fluid flow when operational speed is too high.

[1520] Such generators may be designed to have Automatic Generation Control (AGC) capability. Where additional power is needed to stabilize frequency, voltage, or for other ancillary purposes, AGC allows a message from the system operator requesting an increase or decrease in output to be forwarded directly to the governor. This signal takes precedence over the governor's own determination of speed and other conditions.

[1521] However, certain power generation assets lack inherent AGC capability. For example, the amount of power output by a wind turbine is based upon a speed of rotation of the turbine blades by the wind. Such rotation cannot be accelerated in the conventional manner by action of a governor, in order to provide additional voltage.

[1522] Certain forms of solar energy may also lack an intrinsic governor response mechanism. For example, the amount of energy available from an array of photovoltaic cells or thermal solar system is typically dictated by sunshine, and may not necessarily be readily augmented in order to meet a demand for additional power.

[1523] Accordingly, some embodiments of compressed gas energy storage and recovery systems according to the present invention may be coupled with such non-governor generation assets of the power network. Such a storage system could essentially take the place of a governor, endowing the generation asset with AGC capability, and automatically outputting more power on short notice in response to a request for voltage stabilization by the system operator. Such a configuration would facilitate integration of an alternative energy source within the existing power grid infrastructure, and would not necessarily require physical co-situation of the energy storage system with alternative power generation asset.

[1524] Such positioning of the energy storage system in a location different from the generation asset, may be beneficial under certain circumstances. For example, the site of a renewable energy source is largely dictated by the availability of natural resources such as wind or sunlight. As a result, such alternative generation assets may be situated in remote areas, increasing the expense of inspection and maintenance of any co-situated elements such as a compressed gas energy storage and recovery system. Additional costs may be associated with transmitting the power from a remote area to where it is needed. Accordingly, providing the energy storage system in a more accessible location may improve the cost effectiveness of its operation.

[1525] Positioning a compressed gas energy storage and recovery system in a different location than a generation asset, may also endow it with greater flexibility. Specifically, operation of such a remotely located energy storage system would not necessarily be tied to any particular generation asset. Thus, the compressed gas energy storage and recovery system 6640b of Figure 66 could readily supply power onto the network in order to provide coverage over the ramp-up period for generation asset 6610a, generation asset 6610b, or both of these.

[1526] Figure 68 shows a simplified block diagram of one embodiment of a compressed gas storage and recovery system in accordance with an embodiment of the present invention. In particular, compressed gas storage and recovery system 6801 comprises compressor/expander (C/E) 6802 in fluid communication with gas inlet 6805, and in fluid communication with compressed gas storage unit 6803.

[1527] Figure 68 shows that compressor/expander 6802 is in selective physical communication with /generator (M/G) 6804 through linkage 6807. In a first mode of operation, motor/generator 6804 operates as a motor to allow energy to be stored in the form of a compressed gas (for example air). Motor/generator 6804 receives power from an external source, and communicates that power to cause

compressor/expander 6802 to function as a compressor. One possible source of power for the motor/generator 6804 is the meter 6880 that is in electrical communication through line 6881 with substation 6882 of the distribution layer of the power grid 6814. As described further in detail below, the power grid 6814 may be a smart grid containing information in addition to power.

[1528] In compression, motor/generator 6804 in turn communicates power to compressor/expander 6802 through linkage 6807, allowing compressor/expander 6802 to function as a compressor. Compressor/expander 6802 receives the gas from inlet 6805, compresses the gas, and flows the compressed gas to the storage unit 6803.

[1529] Figure 68 also shows that the system 6801 may also be configured to receive energy from a first (variable) alternative source 6810 such as a wind turbine. Here, the compressor/expander 6802 is shown as being in physical communication with the wind turbine 6810 through a linkage 6820. This linkage may be mechanical, hydraulic, or pneumatic in nature.

[1530] The direct communication between the rotating blades of the wind turbine and the compressor/expander, afforded by linkage 6820, may allow for the efficient storage of energy as compressed gas with little energy loss. Embodiments of a combined wind turbine-compressed gas storage system are described in the co-pending U.S. Nonprovisional Patent Application No. 12/730,549, which is incorporated by reference in its entirety herein for all purposes. In certain embodiments, the energy storage system and the alternative energy source may share a common generator, as indicated by the physical linkage 6821.

[1531] In certain embodiments, the alternative energy storage source may include a separate generator and provide energy in electrical form through linkage 6883 to power motor/generator 6804 that is functioning as a motor. In certain embodiments a separate generator in the wind turbine may be in electrical communication with motor/generator 6804 through linkage 6883.

[1532] Figure 68 further shows that the compressed gas energy storage and recovery system 6801 may also be configured to receive energy from a second (dispatchable) source 6850, such as a pipeline of oil or natural gas. The system may draw upon this dispatchable energy source 6850 to meet contractual commitments to supply power, for example where previous operation has exhausted the stored compressed gas supply.

[1533] In particular, the energy from the dispatchable source 6850 may be consumed by an element 6864 such as a natural gas turbine, diesel motor, or gas motor, to drive motor/generator 6804 through linkage 6822 to operate as a generator, and thereby produce electricity for output onto the grid (for example during peak demand periods). Energy from the alternative energy source 6850 may also be consumed by element 6864 to drive compressor/expander 6802 through linkage 6885 to operate as a compressor, and thereby compress gas for energy recovery, for example during off-peak demand periods.

[1534] The element 6864 may also be in thermal communication with a heat source 6862 through heat exchanger 6860. In this manner, thermal energy resulting from operation of element 6864 may improve the efficiency of expansion during recovery of energy from compressed gas.

[1535] Where element 6864 is a turbine (such as a gas turbine), in certain embodiments it may utilize expansion of compressed gas from the storage unit during a combustion process. Accordingly, Figure 68 shows element 6864 in selective fluid communication with compressed gas storage unit 6803 through a fluid conduit 6876 and a valve 6878. Utilizing the compressed gas for combustion in this manner may allow high efficiency recovery of the energy stored in that compressed gas.

[1536] In certain embodiments compressor/expander 6802 may comprise a separate compressor and a separate expander that are configurable to be arranged to operate together as a heat engine. In such an embodiment, heat from heat source 6862 may be used to drive motor/generator 6804 even after gas storage unit 6803 has been depleted.

[1537] In certain embodiments, the energy storage and recovery system 6801 may also be co-situated with another facility 6870, which may be a large consumer of electricity. Examples of such facilities include but are not limited to, manufacturing centers such as factories (including semiconductor fabrication facilities), data centers, hospitals, ports, airports, and/or large retail facilities such as shopping malls.

[1538] The facility 6870 and the energy storage and recovery system 6801 may share a common interface (such as a meter) with the power grid, although power may be routed between system 6801 and facility 6870 through a separate channel 6874. Power may be communicated directly from the energy storage and recovery system to the facility through channel 6874 to serve as an uninterruptible power supply (UPS), or to allow the facility to satisfy objectives including but not limited to peak shaving, load leveling, and/or demand response. Other links (not shown here), such as thermal, fluidic, and/or communication, may exist between the facility and the energy storage system, for example to allow temperature control.

[1539] In a second mode of operation, energy stored in the compressed gas is recovered, and compressor/expander 6802 operates as an expander. Compressor/expander 6802 receives the compressed gas and allows this compressed gas to expand, driving a moveable member in communication through linkage 6807 with motor/generator 6804 that is functioning as a generator. The resulting power from the motor/generator may be output onto the power grid via the busbar 6872 and the transmission line 6812 for consumption.

[1540] As previously described, gas undergoing compression or expansion will tend to experience some temperature change. In particular, gas will tend to increase in temperature as it is compressed, and gas will tend to decrease in temperature as it expands.

[1541] The processes of compressing and decompressing the gas as described above, may experience some thermal and mechanical losses. However, these processes will occur with reduced thermal loss if they proceed at near-isothermal conditions with a minimum change in temperature. Such near-isothermal compression and/or expansion may be achieved utilizing one or more techniques, including but not limited to injection of liquid to perform heat exchange.

[1542] Accordingly, the compressor/expander apparatus 6802 of the system 6801 is in fluid communication with one or more heat exchanger(s) 6860 that may be selectively in thermal

communication with a heat sink or a heat source 6862. In a compression mode of operation, the heat exchanger is placed into thermal communication with a heat sink, for example the atmosphere, where a fan that blows air to cool the heat exchanger. In an expansion mode of operation, the heat exchanger is placed into thermal communication with a heat source, for example an environmental air temperature or a source of waste heat. The heat source may be a structure such as a pond that is configured to receive and store heat generated by element 6864 drawing upon energy source 6850.

[1543] While the particular embodiment of Figure 68 shows an energy storage and recovery system in the form of a system utilizing compressed gas, the present invention is not limited to such a system. Alternative embodiments of the present invention could utilize other forms of energy storage and recovery systems located behind the same busbar, or in communication with the same transmission line, as a generation asset of a power supply network. Examples of such other types of energy storage and recovery systems include but are not limited to: pumped hydroelectric, flywheels, batteries, ultracapacitors, thermal storage, chemical storage, osmotic pressure storage, or superconducting rings.

[1544] The various elements of the system 6801 are in communication with a central controller or processor 6896, that is in turn in electronic communication with a computer-readable storage medium 6894. The central controller or processor 6896 may also be in communication with a power grid 6814 (for example a smart grid) through a wired connection 6816 and/or a wireless link between nodes 6818 and 6828. The central controller or processor 6896 may also be communication with other sources of information, for example the internet 6822.

[1545] Based upon instructions in the form of computer code stored on computer-readable storage medium 6894, the controller or processor 6896 may operate to control various elements of the system 6801. This control may be based upon data received from various sensors in the system, values calculated from that data, and/or information received by the controller or processor 6896 from various sources, including co-situated sources or external sources.

[1546] In certain embodiments, the controller of the system may be configured to commence operation based upon an instruction received from a generation asset. For example, a compressed gas storage and recovery system may be engaged to provide power to levelize intermittent output from a renewable energy generation asset. In such circumstances, the controller could then be configured to receive a signal indicating the variable or intermittent output from the renewable energy generation asset, and in response generate a sufficient amount of power.

[1547] In certain embodiments, the compressed gas energy storage and recovery system may transmit signals to a generation asset. For example, a system engaged in the levelizing function may receive an indication of long term loss of output from a renewable energy generation asset (due to cloudiness or of loss of wind). Upon detection of such an event, the system controller could be configured to transmit a signal instructing another generation asset to provide sufficient power coverage over longer time frame.

[1548] Figure 68A is a simplified block diagram showing the various system parameters of operation of a combination compression/expansion system in accordance with an embodiment. Figure 68A shows that under compression, motor/generator 6804 receives power from an external source, and

communicates that power (W_{in}) to cause compressor/expander 6802 to function as a compressor. Compressor/expander 6802 receives uncompressed gas at an inlet pressure (P_{in}), compresses the gas to a greater pressure for storage (P_{st}) in a chamber utilizing a moveable element such as a piston, and flows the compressed gas to the storage unit 6803.

[1549] Figure 68A also shows that in a second mode of operation, energy stored in the compressed gas is recovered, and compressor-expander 6802 operates as an expander. Compressor/expander 6802 receives the compressed gas at the stored pressure P_{st} from the storage unit 6803, and then allows the compressed gas to expand to a lower outlet pressure P_{out} in the chamber. This expansion drives a moveable member which is in communication with motor/generator 6804 that is functioning as a generator. Power output (W_{out}) from the compressor/expander and communicated to the motor/generator 6804, can in turn be input onto a power grid and consumed.

[1550] Figure 68A also shows the existence of possible physical, fluidic, communications, and/or thermal linkages between the compressed gas storage and recovery system, and other elements.

[1551] While Figures 68 and 68A have shown an embodiment of a compressed gas storage and recovery system having a combined compressor/expander (C/E) and a combined motor/generator (M/G), this is not required by the present invention. Figure 68B shows an alternative embodiment which utilizes separate, dedicated compressor and expander elements 6886 and 6888, respectively, that are in communication with separate, dedicated motor and generator elements 6887 and 6889 respectively. In certain embodiments these elements may be in physical communication through a single common linkage. In other embodiments, these elements may be in physical communication through a plurality of linkages. In still other embodiments, motor 6887 and generator 6889 may be combined into a single motor/generator unit.

[1552] In this embodiment as well as others, energy recovered from expansion of compressed gas need not be routed out of the system as electrical energy. In certain modes of operation the full amount of the energy derived from expanding gas may be consumed for other purposes, for example temperature control (such as heating or cooling) and/or the compression of more gas by a compressor.

[1553] Figure 68C shows a simplified block diagram of an alternative embodiment of a compressed gas storage and recovery system in accordance with an embodiment of the present invention. In the embodiment of Figure 68C, the dedicated compressor (C) 6886, the dedicated expander (E) 6888, a dedicated motor (M) 6887, and a dedicated generator (G) 6889, are all in selective physical communication with one another through a multi-node gear system 6899. An embodiment of such a gear system is a planetary gear system described in U.S. Nonprovisional Patent Application No. 12/730,549, which is incorporated by reference herein for all purposes.

[1554] A multi-node gearing system such as a planetary gear system as shown previously in Figures 33A-AA, may permit movement of all of the linkages at the same time, in a subtractive or additive manner. For example where the wind is blowing, energy from the turbine linkage may be distributed to drive both the linkage to a generator and the linkage to a compressor. In another example, where the

wind is blowing and demand for energy is high, the planetary gear system permits output of the wind turbine linkage to be combined with output of an expander linkage, to drive the linkage to the generator.

[1555] Moreover, a multi-node gear system may also be configured to accommodate movement of fewer than all of the linkages. For example, rotation of shaft 3341 in Figure 33A may result in the rotation of shaft 3362 or vice-versa, where shaft 3368 is prevented from rotating. Similarly, rotation of shaft 3341 may result in the rotation of only shaft 3368 and vice-versa, or rotation of shaft 3362 may result in the rotation of only shaft 3368 and vice-versa. This configuration allows for mechanical energy to be selectively communicated between only two elements of the system, for example where the wind turbine is stationary and it is desired to operate a compressor based upon output of a motor.

[1556] Certain embodiments of the present invention may favorably employ a planetary gear system to allow the transfer of mechanical energy between different elements of the system. In particular, such a planetary gear system may offer the flexibility to accommodate different relative motions between the linkages in the various modes of operation.

[1557] While Figure 68C shows an embodiment having a multi-node gear system, this is not required by the present invention. In alternative embodiments, various elements of the system could be in physical communication with each other through individual physical linkage or through physical linkages shared with fewer than all of the other elements.

[1558] In certain embodiments, a compressed gas energy storage and recovery system may utilize injection of liquid to facilitate heat exchange during compression and/or expansion. Such heat exchange may allow temperature controlled (such as near-isothermal) conditions to be maintained during the compression and/or expansion processes, thereby improving efficiency of the corresponding storage and recovery of energy.

[1559] Incorporation of compressed gas energy storage and recovery systems into the generation layer of a power network, may allow existing generation assets to be utilized in roles from which they might otherwise be precluded by virtue of their ramp-up times. For example, a potential role for generation assets may be to sell power onto energy markets.

[1560] One such market is for the sale of energy to balance supply with demand over time frames of greater than one hour. Such an embodiment may dispatch power from storage systems in near-real time in order to allow an existing generation asset to meet short-term fluctuation in demand. These fluctuations can result from natural causes, for example a change in an amount of power supplied by a variable renewable energy source (such as a wind farm). The fluctuations can also be of an artificial origins, for example changes in rate scheduling by energy markets.

[1561] Certain embodiments of compressed gas energy storage and recovery systems may be configured to facilitate the ramp-up of generation assets to sell power onto wholesale energy markets over longer time frames, for example within a day. Thus another potential role for energy storage systems of the present invention, may be to facilitate bulk intraday arbitrage by a generation asset.

[1562] In such a role, a generation asset would function to ramp-up and provide energy for sale when wholesale power is expensive. The presence of a compressed gas energy storage system would allow a generation asset to respond on short notice to opportunities for such bulk intraday arbitrage.

[1563] Power from the storage system (and later replaced by power from the generation asset after ramp-up), could be sold onto the wholesale energy market. Such a compressed gas energy storage and recovery system could be owned and operated by an Independent Power Producer (IPP), a generation utility, or some other Load Serving Entity (LSE).

[1564] Another potential role for generation assets whose ramp-up is covered by compressed gas energy storage and recovery systems, may be to perform diurnal renewable levelizing. Specifically, the fast response time of such a generation asset would allow demand to quickly be shifted from variable renewable energy sources in order to better match load and transmission availability. For example, where winds die down, energy from compressed gas could tide over the power network until a gas turbine is ramped-up to cover the loss of the renewable supply. This would increase the reliability, and hence value, of the renewable energy.

[1565] While the above description has related to systems classified as belonging to the generation layer whose recovered power is sold onto wholesale energy markets, the present invention is not limited to performing such roles. In accordance with alternative embodiments, energy storage and recovery systems could sell energy to other types of markets and remain within the scope of the present invention.

[1566] An example of such an alternative market for selling power recovered from compressed gas, is the ancillary services (A/S) market. Broadly speaking, the ancillary services market generally represents the sale of electrical power to the network for purposes other than consumption by end users. Such purposes include maintaining integrity and stability of the network, and the quality of the power provided thereon.

[1567] The ability (capacity) to provide energy to the ancillary services market, is usually sold for periods of less than one day, at a market price. The Independent System Operator (ISO) pays the capacity cost for reserving such capacity.

[1568] The actual energy itself, is sold in response to a call from the network to provide the power for a duration. When this happens, the owner of the system would be paid the market value of the energy sold.

[1569] One ancillary market exists for maintaining the capacity to provide necessary reserves needed to operate the network. That is, the operator of the network is required to be able to supply an amount of power above and beyond an existing demand, in order to ensure that the network is able to meet future demand. Such reserves are typically calculated as a percentage in excess of a supply.

[1570] One form of reserves are contingency reserves. Contingency reserves are summoned by the power network at relatively short notice in response to certain events (contingencies) that are unexpected but need to be planned for. Examples of such possible contingencies include the failure of an element of the transmission layer (such as a transmission line), an unanticipated surge in demand, or the need to shut down or reduce output of a generation element on short notice.

[1571] One form of contingency reserves are spinning reserves. Such spinning reserves are typically available on extremely short notice. Spinning reserves have traditionally taken the form of an increase in output from generating units that are operating at less than capacity, or by interruption of service to certain customers. Such reserve is referred to as "spinning" because in order to satisfy the demand on short notice, the generation asset may already be on-line and operating in a synchronous manner ("spinning") with the rest of the network.

[1572] Another form of contingency reserves are standing reserves. Standing reserves are available with a longer lead time than spinning reserves, as the generation element is not yet synchronously on-line. Standing reserves may also take the form of an interruption of service to certain customers, with a correspondingly longer notice period.

[1573] In certain embodiments, existing generation assets whose ramp-up times are covered by compressed gas energy storage and recovery systems according to the present invention, may be able to function to provide contingency reserves. Such generation assets would have the capacity to provide the necessary amount of contingency power for a duration required by the service provider. Various possible roles for ramp-up coverage are summarized above.

[1574] 1. A method comprising:

allowing compressed gas to expand to drive a moveable member positioned within a chamber;

generating electricity from movement of the moveable member; and

supplying the electricity to a power network over a ramp-up period of a generation asset of the power network.

[1575] 2. The method of claim 1 wherein the electricity is supplied to the power network through a busbar, and the generation asset is in electrical communication with the network through the busbar.

[1576] 3. The method of claim 2 wherein the electricity is supplied to the power network through a generator, and the generation asset is in physical communication with the generator.

[1577] 4. The method of claim 1 wherein the electricity is supplied to a transmission line of the power network, and the generation asset is in electrical communication with the transmission line.

[1578] 5. The method of claim 1 wherein the generation asset comprises a gas turbine or a steam turbine or a diesel generator.

[1579] 6. The method of claim 1 further comprising placing the compressed gas in thermal communication with the generation asset.

[1580] 7. The method of claim 1 further comprising placing the generation asset in fluid communication with a source of the compressed gas.

[1581] 8. The method of claim 1 further comprising placing the moveable member in physical communication with the generation asset.

[1582] 9. The method of claim 1 further comprising placing the moveable member in electronic communication with the generation asset.

[1583] 10. A method comprising:

allowing compressed air to expand to drive a moveable member positioned within a chamber;

generating electricity from movement of the moveable member; and

supplying the electricity to a power network to levelize an intermittent output of a generation asset of the power network.

[1584] 11. The method of claim 10 wherein the electricity is supplied to the power network through a busbar, and the generation asset is in electrical communication with the network through the busbar.

[1585] 12. The method of claim 11 wherein the electricity is supplied to the power network through a generator, and the generation asset is in physical communication with the generator.

[1586] 13. The method of claim 10 wherein the electricity is supplied to a transmission line of the power network, and the generation asset is in electrical communication with the transmission line.

[1587] 14. The method of claim 10 wherein the generation asset comprises a renewable generation asset.

[1588] 15. The method of claim 14 wherein the renewable generation asset comprises a wind turbine or a solar energy harvester.

[1589] 16. The method of claim 10 further comprising placing the compressed gas in thermal communication with the generation asset.

[1590] 17. The method of claim 10 further comprising placing the generation asset in fluid communication with a source of the compressed gas.

[1591] 18. The method of claim 10 further comprising placing the moveable member in physical communication with the generation asset.

[1592] 19. The method of claim 10 further comprising placing the moveable member in electronic communication with the generation asset.

[1593] 20. An apparatus comprising:

a chamber having disposed therein a member moveable in response to expansion of gas within the chamber;

a generator in physical communication with the moveable member and in electrical communication with a transmission layer of a power network; and

a compressed gas storage unit configured to be in selective fluid communication with the chamber such that the generator supplies electricity to the power network during a ramp-up period of a generation asset.

[1594] 21. The apparatus of claim 20 wherein the generator and the generation asset are in electrical communication with the transmission layer through a common busbar.

[1595] 22. The apparatus of claim 20 wherein the generation asset is in physical communication with the generator to produce electrical power.

[1596] 23. The apparatus of claim 20 wherein the generator and the generation asset are in electrical communication with the transmission layer through a common transmission line.

[1597] 24. The apparatus of claim 20 further comprising a thermal linkage between the chamber and the generation asset.

[1598] 25. The apparatus of claim 20 further comprising a fluid linkage between the compressed gas storage unit and the generation asset.

[1599] 26. The apparatus of claim 25 wherein the generation asset comprises a gas turbine.

[1600] 27. The apparatus of claim 20 further comprising a compressor in fluid communication with the compressed gas storage unit.

[1601] 28. The apparatus of claim 27 further comprising a physical linkage between the generation asset and the compressor.

[1602] 29. The apparatus of claim 27 further comprising a controller in electronic communication with the moveable member and in electronic communication with the generation asset.

[1603] 30. An apparatus comprising:

a chamber having disposed therein a member moveable in response to expansion of gas within the chamber;

a generator in physical communication with the moveable member and in electrical communication with a transmission layer of a power network; and

a compressed gas storage unit configured to be in selective fluid communication with the chamber such that the generator supplies electricity to the power network to levelize an intermittent output of a generation asset.

[1604] 31. The apparatus of claim 30 wherein the generator and the generation asset are in electrical communication with the transmission layer through a common busbar.

[1605] 32. The apparatus of claim 31 wherein the generation asset is in physical communication with the generator.

[1606] 33. The apparatus of claim 30 wherein the generator and the generation asset are in electrical communication with the transmission layer through a common transmission line.

[1607] 34. The apparatus of claim 30 further comprising a compressor in fluid communication with the compressed gas storage unit.

[1608] 35. The apparatus of claim 30 further comprising a physical linkage between the generation asset and the compressor.

[1609] 36. The apparatus of claim 35 wherein the generation asset comprises a gas turbine.

[1610] 37. The apparatus of claim 30 further comprising a thermal linkage between the chamber and the generation asset.

[1611] 38. The apparatus of claim 30 further comprising a controller in electronic communication with the moveable member and in electronic communication with the generation asset.

[1612] A compressed gas energy storage and recovery system may be incorporated within a power supply network, with an end user behind the meter. Such an energy storage and recovery system could function in power supply and/or temperature control roles. In certain embodiments, the energy recovered from expansion of compressed gas may be utilized to cool an end user. According to some embodiments, heat generated from compression of the gas could be utilized for heating. In functioning as a power supply, the compressed gas energy storage and recovery system could serve as an

uninterruptible power supply (UPS) for the end-user, and/or could function to provide power to allow the end user to perform peak shaving and/or participate in demand response programs.

[1613] According to embodiments of the present invention, a compressed gas energy storage and recovery system may be incorporated within a power supply network behind the meter of an end user. In certain embodiments energy produced by compression of the gas, or energy recovered from expansion of the gas (and possibly supplemented from other heat sources), may be utilized to provide temperature control (for example cooling and/or heating) of the end user.

[1614] Examples of some parameters for such temperature control roles are listed in the table shown as Figure 60.

[1615] In certain embodiments, compressed gas energy storage systems that are located within the consumption layer, may provide a supply of power to meet the full or partial needs of the end user. Examples of such power supply roles include but are not limited to functioning as an uninterruptible power supply (UPS), as a power supply allowing the end user to engage in daily arbitrage (i.e. the daily purchase of power from the network at times of lower price), as a power supply allowing the end user to participate in demand response programs, as a power supply allowing the end user to reduce consumption below historic peak levels, and/or as a power supply furnishing power during periods of varying or intermittent supply from a renewable energy source, such as a wind turbine or photovoltaic (PV) array.

[1616] Examples of some parameters for such power supply roles are listed in the table shown as Figure 62.

[1617] An example of a small end user includes an individual residence or a small business. Examples of a medium-sized end users include those with greater demands for power and/or temperature control, for example hospitals, office buildings, large stores, factories, or data storage centers. A large end user may include ones made up of a plurality of individual entities, for example a shopping mall, a residential subdivision, an academic or administrative campus, or a transportation node such as an airport, port, or rail line.

[1618] Figure 66 shows incorporation of various embodiments of compressed gas storage systems into a power network. Figure 66 shows that in certain embodiments, a compressed gas energy storage and recovery system 6640a may be incorporated in the consumption layer behind a meter 6634a with an end user 6606a. In such a configuration, a plurality of different types of linkages 6650 (including but not limited to physical, thermal, electrical, fluidic, and/or communication) may be present between the end user and the energy storage and recovery system.

[1619] Figure 66 also shows that in other embodiments, a compressed gas energy storage and recovery system 6640b according to the present invention may be co-situated behind a meter 6634b with both the end user 6606b and with one or more local power sources 6655. Examples of such local power sources include but are not limited to wind turbines and solar energy harvesting apparatuses such as a rooftop photovoltaic (PV) arrays and/or thermal solar systems. In such a configuration, a plurality of different types of linkages 6650 (including but not limited to physical, electronic, communication, thermal, and/or

fluidic) may be present between the end user and the energy storage and recovery system, between the end user and the local generator, and/or between the energy storage and recovery system and the local power source.

[1620] Figure 69 shows a simplified block diagram of one embodiment of a compressed gas storage and recovery system in accordance with an embodiment of the present invention. In particular, compressed gas storage and recovery system 6901 comprises a motor/generator (M/G) 6904 configured to be in electrical communication with an end user 6950 and with a meter 6992.

[1621] Motor/generator (M/G) 6904 is in selective physical communication with dedicated compressor (C) 6902 through physical linkage 6921 and clutch 6922. Motor/generator (M/G) 6904 is also in selective physical communication with dedicated expander (E) 6905 through linkage 6923 and clutch 6924.

[1622] The dedicated compressor (C) 6902 is in selective fluid communication with gas inlet 6903. A gas outlet 6947 of the dedicated compressor is in selective fluid communication with compressed gas storage unit 6932 through counterflow heat exchanger 6928 and one-way valve 6909.

[1623] In certain embodiments, the compressed gas storage unit 6932 may be in selective communication with a heat source. For example, the compressed gas storage unit could be positioned in thermal communication with the sun, such that during the daylight hours it absorbs solar energy. In certain embodiments the storage unit could be coated with a material that promotes the absorption of thermal energy, for example a dark colored paint.

[1624] In certain embodiments the compressed gas storage unit could be positioned in thermal communication with the sun behind an optically transparent barrier, such as glass. The barrier could serve to trap infrared (IR) radiation from the sun's rays, thereby further enhancing heating of the compressed gas during daylight hours.

[1625] A gas inlet 6949 of the dedicated expander (E) is in selective fluid communication with compressed gas storage unit 6932 through the counterflow heat exchanger 6928 and one-way valve 6911. The dedicated expander is in selective fluid communication with gas outlet 6907.

[1626] As mentioned above, embodiments of the present invention employ heat exchange with introduced liquid to achieve efficient energy storage and recovery utilizing gas compression and expansion under conditions of controlled temperature change. In certain embodiments, these controlled temperature conditions may result in near-isothermal gas compression or expansion.

[1627] Thermal energies extant within the system may be communicated through a variety of thermal linkages. A thermal linkage according to embodiments of the present invention may comprise one or more elements configured in various combinations to allow the transfer of thermal energy from one physical location to another. Examples of possible elements of a thermal linkage include but are not limited to, liquid flow conduits, gas flow conduits, heat pipes, heat exchangers, loop heat pipes, and thermosiphons.

[1628] For example, the dedicated compressor may be in selective thermal communication with thermal sink 6962 through a thermal linkage 6961. This thermal linkage may allow the transfer of thermal energy in the form of heat from the compressed gas.

[1629] The dedicated expander may be in selective thermal communication with thermal source 6988 through thermal linkage 6964. This thermal linkage may allow the transfer of thermal energy in the form of coolness from the expanded gas.

[1630] The dedicated compressor includes a thermal linkage 6963 that is configured to communicate thermal energy in the form of heat from the compressed gas. This thermal energy in the form of heat may be selectively flowed through switch 6984 out of the system, or through thermal linkage 6982 to the end user. In certain embodiments, thermal linkage 6982 may convey heat in the form of the compressed gas itself. In certain embodiments, the thermal linkage may convey the heat in the form of a fluid that has exchanged heat with the compressed gas.

[1631] The dedicated expander includes a thermal linkage 6973 that is configured to communicate thermal energy in the form of coolness from the expanded gas. This thermal energy in the form of coolness may be selectively flowed through switch 6981 either out of the system, or through thermal linkage 6980 to the end user. In certain embodiments, thermal linkage 6973 may convey coolness in the form of the expanded gas itself. In certain embodiments, the thermal linkage may convey the coolness in the form of a fluid that has exchanged heat with the expanded gas.

[1632] In certain embodiments, the thermal links 6980 and 6982 may be configured to interface with an existing Heating, Ventilation, and Air-Conditioning (HVAC) system in the end user. Examples of such standard HVAC systems include but are not limited to available from the following manufacturers: AAON, Addison Products Company, Allied Thermal Systems, American Standard, Armstrong, Bard, Burnham, Carrier, Coleman, Comfortmaker, Goodman,
Heil, Lennox, Nordyne, Peake Industries Limited, Rheem, Trane, and York International.

[1633] Exemplary types of residential HVAC systems may comprise air conditioners, heat pumps, packaged gas electric, packaged heat pumps, packaged air conditioners, packaged dual fuel, air handlers, and furnaces. Exemplary types of commercial HVAC systems may comprise packaged outdoor units, including packaged rooftop units using Puron® refrigerant, packaged rooftop units using R-22 refrigerant, and 100% Dedicated outdoor air units. Commercial HVAC systems packaged indoors include indoor self-contained units, water source heat pumps, and packaged terminal air conditioners.

[1634] Commercial HVAC systems may also be in the form of packaged split-systems. Examples include split systems (6 to 130 tons), split systems (1.5 to 5 tons), condensers, duct free systems, furnaces, and coils.

[1635] Examples of chillers include but are not limited to air-cooled chillers, water-cooled chillers, condenserless chillers, and may include condensors and other chiller components.

[1636] Airside equipment may include but is not limited to air handlers, air terminal coils, fan coils, heat/energy recovery units, induction units, underfloor air distribution systems and unit ventilators. Examples of heating equipment include but are not limited to boilers and furnaces.

[1637] In many embodiments the thermal linkages may comprise fluidic conduits that are part of a loop or circuit of fluid flow. In certain embodiments, fluid(s) cooled by direct or indirect heating of the end user (or heated by direct or indirect cooling of the end user) may be returned to the system.

[1638] Thus in certain embodiments, heated liquid outlet from the compressor, may be circulated back to the compressor after exposure to a heat sink (which may be an end user requiring heating). Similarly, cooled liquid outlet from the expander may be circulated back to the expander after exposure to a heat source (which may be an end user requiring cooling). In both cases, the thermal exposure could occur through one or more heat exchanger structures.

[1639] In certain embodiments, cooled gas outlet from the expander, may be circulated back to the compressor after exposure to a heat source in the form of an end user requiring cooling. Similarly, heated gas outlet from the compressor may be circulated back to the expander after exposure to a heat sink in the form of an end user requiring heating. In such cases, the thermal exposure could occur through one or more heat exchanger structures.

[1640] Again, the thermal linkages need not comprise a single element. Thermal energy could be transferred from a liquid flowing through a liquid conduit, to a gas flowing through a gas conduit (and vice-versa), utilizing heat exchangers of various types. Such heat exchangers may be positioned in a variety of different locations, ranging from the site of the original heat exchange, to inside of the end user. In certain embodiments, one or more components of a thermal linkage could comprise a heat pipe, in which a fluid changes phase between gas and liquid.

[1641] Figures 69A-D are simplified views illustrating various ways in which the thermal linkages may interface with an end user. Figure 69A shows an embodiment wherein the thermal linkage 6957 carries cold liquid, and the end user component 6950 comprises a heat exchanger 6951 wherein the cooling in the thermal linkage is transferred to air.

[1642] In some embodiments, the air moves through a plenum 6952 and then enters an air duct coupling 6953. In certain embodiments the air moves directly from the heat exchanger into the coupling.

[1643] The cold air then enters a heating, ventilation, and air conditioning (HVAC) system 6954 that may be designed to conform to certain engineering standards. The liquid warmed by its passage through the heat exchanger exits the end user component 6950 via linkage 6955. In certain embodiments this linkage may circulate the warmed liquid back to the system.

[1644] The present invention is not limited to the particular embodiment shown in Figure 69A. For example in certain embodiments the thermal flow may be in the opposite direction. Linkage 6955 may carry hot liquid to the heat exchanger, heating the air in the air plenum. Hot air is then conveyed through the air duct coupling to the HVAC system. The liquid cooled during its passage through the heat exchanger exits the end user component 6950 via thermal linkage 6957.

[1645] Figure 69B shows another embodiment, in which thermal linkage 6957 carries cold air and the end user component 6950 comprises an air duct coupling 6953 to an HVAC system 6954 as described above, and an air duct coupling 6956 from the HVAC system 6954 to the thermal link 6955 which carries warm air rejected by the HVAC system.

[1646] Alternately the thermal link 6955 carries hot air and the end user component 6950 comprises an air duct coupling to an HVAC system as described above, and an air duct coupling from the HVAC system to the thermal linkage 6957. This linkage 6957 carries cooled air rejected by the HVAC system.

[1647] Figure 69C shows another embodiment, where the thermal linkage 6957 carries cold air, and the end user component 6950 comprises a dehumidifier 6958 connected to an air duct coupling 6953 to an HVAC system 6954 as described above, and an air duct coupling 6956 from the HVAC system to the thermal linkage 6955. Linkage 6955 carries warm air rejected by the HVAC system.

[1648] Figure 69D shows still another embodiment, where the thermal linkage 6957 carries cold liquid, and the end user component 6950 comprises a pipe coupling 6959.

[1649] The pipe coupling is connected to a chiller load 6999, for example a refrigerator case in a supermarket. The liquid warmed by passage through the chiller load passes through a pipe coupling and exits end user component 6950 via thermal link 6955.

[1650] As described above, embodiments of the present invention may employ gas duct connections to communicate thermal energy. For example, the heat exchanger apparatus of the embodiment of Figure 69A may transmit hot or cold air through a plenum to an HVAC system via an air duct connection. In the embodiment of Figure 69B, thermal linkages may be configured to transmit hot or cold air directly to an HVAC system via an air duct connection. In the embodiment of Figure 69C, a thermal linkage may be configured to supply cold air to the dehumidifier, which may be connected to an HVAC system via an air duct connection. A thermal linkage may be configured to receive hot air from an HVAC system via an air duct connection.

[1651] Such a gas duct connection according to embodiments of the present invention may comprise ductworks formed from one or more of the following duct connection components:
duct sealants including liquid sealants, mastics, gaskets, tapes, heat applied materials, and mastic and embedded fabric combinations; transverse joint reinforcements including but not limited to standing drive slips, standing S's, companion angles, flange join reinforcements, slip-on flange joint reinforcements, standing seam joint reinforcements, and welded flange joint reinforcements; flexible duct connectors including but not limited to nonmetallic duct clamps, metal clamps, collars (including spin−in, flared, dovetail, spin−in conical, spin−in straight, 4" sleeve, and collar in duct min. 2"; fittings including but not limited to type re 1: radius elbow, type re 2: square throat elbow with vanes, type re 3: radius elbow with vanes, type re: 4 square throat elbow without vanes, type re 5: dual radius elbow, type re 6: mitered elbow; type re 7:
45° throat, 45° heel; type re 8: 45° throat, radius heel; type re 9: 45° throat, 90° heel; type re 10: radius throat, 90° heel.

[1652] The ductwork may conform to the HVAC Duct Construction Standards: Metal and Flexible (2005) standard of the Sheet Metal and Air Conditioning Contractor's National Association (SMACNA), which is incorporated by reference herein in its entirety for all purposes.

[1653] Various types of ductworks may be used according to embodiments of the present invention, to convey gases over pressure ranges from low pressures to pressures as high as 1000 Pa. In certain embodiments, the ducts may comprise galvanized steel. The ducts may comprise a lock forming quality to ASTM A525 specification for General Requirements for Steel Sheet, Zinc Coating (Hot Dipped Galvanized), G90 Zinc Coating.

[1654] In certain embodiments the ducts may comprise spiral, round and flat oval ductwork and fittings. In certain embodiments the ducts may comprise a spiral round duct, which may be calibrated to manufacturer's published dimensional tolerance standard. Spiral ducts 350 mm (14in) and larger may be corrugated for added strength and rigidity. Spiral seam slippage may be prevented by flat seam and mechanically formed indentation, spaced along the spiral seam.

[1655] In some embodiments the ducts may comprise manufactured flanged duct joints, examples of which include but are not limited to a tension ring with gasket type, or stiffened flanged and gasket types. Examples of standards of acceptance include but are not limited to DUCTMATE, NEXUS, and McGill Airflow Flange/Hoop Connector, SPIRALMATE, or OVALMATE.

[1656] Various sealants can be used. Certain sealant types use water based polymer, non-flammable, high velocity duct sealing compounds. Some sealants may meet the requirements of NFPA90A and 90B. Sealants may be oil resistant. Sealants may be UL Class 1 listed.

[1657] Sealant may have a temperature range of from -7°C to +93°C (20°F to +200°F). Standards of Acceptance for sealants include DYN-O-SEAL (-40°F to +200°F), Foster 32-17, and Foster 32-19.

[1658] Various tapes may be used. One example is a PVC treated, non-flammable, open weave (gauze) fiberglass tape. The tape may be UL Listed.

[1659] In certain embodiments a tape may have a width of 50 mm (2 in). Standards of acceptance include DURODYNE FT-2, and HARDCAST FS-150.

[1660] Ducts may be installed in a number of ways. Ducts may be installed in accordance with SMACNA Standards.

[1661] Pressure construction may be used in certain embodiments. Low pressure ductwork construction classifications are given in the following table:

Pressure Class, Pa (in WG)	Operating Pressure, Pa (in WG)	Maximum Velocity, m/s (fpm)
125 (1/2)	Up to 125 (1/2)	10.0 (2000)
250 (1)	125 to 250 (1/2 to 1)	12.5 (2500)
500 (2)	250 to 500 (1 to 2)	12.5 (2500)
750 (3)	500 to 750 (2 to 3)	15.0 (3000)
1000 (4)	750 to 1000 (3 to 4)	20.0 (4000)

[1662] Duct construction, sheet gauges, reinforcing and bracing classification may be according to function and as described as follows:

- supply air ductwork from discharge side of fan: 750 Pa (3 in WG) class;
- return air ductwork on suction side of fan: 250 Pa (1 in WG) class;
- exhaust air ductwork on the discharge side of fan: 250 Pa (1 in WG) class;
- exhaust air ductwork on suction of fan: 500 Pa (2 in WG) class.

[1663] Low Pressure ductwork seal classification may be according to the following table:

Seal Class	Sealing	Static Pressure construction class, Pa (in WG)
A	Seams, joints and connections made airtight with sealing compound and tape	1000 (4) and up
B	Seams, joints and connections made airtight with sealing compound	750 (3)
C	Transverse joints and connections made airtight with sealing compound. Longitudinal seams unsealed	500 (2)
D	Seams, joints and connections unsealed	250 (1)

[1664] The construction of duct seals may be as follows:

- supply air ductwork from discharge side of fan: Seal Class A;
- return air ductwork on discharge side of fan: Seal Class B
- return air ductwork on suction side of fan: Seal Class B
- exhaust air ductwork on the discharge side of fan: Seal Class B
- exhaust air ductwork on suction of fan: Seal Class B

[1665] Embodiments in accordance with the present invention may utilize flexible ducts. Applicable standards for such flexible ductwork include but are not limited to the latest editions of the following:

- UL 181;
- National Fire Protection Association (NFPA) 90A and 90B;
- SMACNA installation standards for flexible duct.

Embodiments of flexible ducts utilized in accordance with the present invention may have maximum flame spread rating of 25 and maximum smoke developed rating of 50.

[1666] Embodiments of flexible ductwork used in accordance with the present invention may comprise factory fabricated semi-rigid non-insulated aluminum ductwork. The flexible ductwork may be spirally wound and mechanically joined with triple lock seam. The seam between the ductwork may form a continuous air-tight and leak proof joint. The ductwork may be UL Class 1 listed.

[1667] In certain embodiments, the flexible ductwork may exhibit one or more of the following operational characteristics:

- a maximum positive pressure of about 2500 Pa (10 in WG);
- a maximum negative pressure of about 250 Pa (1 in WG);
- a maximum gas velocity of about 20.3 m/s (4000 ft/min);
- a temperature range of between about -50°C to 320°C (-60°F to 600°F).

[1668] According to some embodiments, thermally insulated flexible ductwork may be used. Certain embodiments may comprise factory fabricated semi-rigid thermally insulated aluminum ductwork. The

thermally insulated flexible ductwork may be spirally wound and mechanically joined with triple lock seam. Thermally insulated flexible ductwork may employ a seam to form a continuous air-tight and leak proof joint. The thermally insulted flexible ductwork may be UL Class 1 listed. The thermally insulated flexible ductwork may be factory wrapped with 25mm (1 in) fiberglass insulation covered by (Polyethylene sleeve) vapour barrier.

[1669] In certain embodiments, the thermally insulated flexible ductwork may exhibit one or more of the following performance characteristics:

- a mean thermal loss/gain not more than about 0.24 Btu/h/ft² °F;
- a maximum positive pressure of about 2500 Pa (10 in WG);
- a maximum negative pressure of about 250 Pa (1 in WG);
- a maximum gas velocity of about 20.3 m/s (4000 ft/min);
- a gas temperature range of between about -40°F to 250 °F.

[1670] Flexible ductwork according to embodiments of the present invention may be installed with a length of flexible duct feeding ceiling outlet, being not more than about 3m (10 ft). In certain embodiments, a sealing compound and/or tape may be used at a connection point between sheet metal and flexible duct. Further mechanical connection may be made using sheet metal screws. Various embodiments of flexible ductwork may have bends with a centreline radius greater than one duct diameter.

[1671] In certain embodiments, thermal energies may be communicated utilizing linkages that are configured to carry liquids. For example, the embodiment of Figure 69A includes thermal linkages configured to transmit cold and hot liquids through a heat exchanger apparatus. The embodiment of Figure 69D uses thermal linkages configured to transmit cooling and/or heating directly to a chiller load via liquid duct connections.

[1672] Such liquid duct connections according to embodiments of the present invention may be formed from one or more components, including but not limited to: pipe sealants such as fittings (which may be formed from copper, black pipe, brass, galvanized steel, or PVC), nipples (which may be formed from copper, black pipe, brass, galvanized steel, or PVC), no hub couplings, pipe clamps, and pipe hanger inserts.

[1673] A variety of types of steel pipes may be used for liquid ducting. Examples include NPS 2 & under according to schedule 40, seamless, NPS 2½ - 3 according to Schedule 40 seamless or Electric Resistant Weld (ERW), and NPS 4 – 8 according to schedule 40, ERW. Applicable standards include ASTM A53 or A135, Grade B.

[1674] Various joints may be used to connect liquid duct piping. Examples of threaded joints include NPS 2 & under utilizing tapered pipe threads and Teflon tape or pulverized lead paste jointing compound according to standard ANSI B1.20.1, or unions with black malleable iron, bronze face, ground joint according to standard ASME B16.39. Threaded joints for NPS 2 & over may also be used.

[1675] Welded joints may also be used to connect liquid duct piping. Examples of welded joints include NPS 2 & under utilizing socket weld fittings under standard ANSI B16.11. Joints for NPS 2½ & over

may include raised face flanges under CSA W47.1-1983, flange bolts & nuts under ANSI B18.2.1, B2.2.2, and flange gaskets; gaskets to be elastomeric sheet or other suitable material 1.6mm (1/16 in) thick under ANSI B16.21, B16.20, A21.11.

[1676] Grooved joints may also be used to connect liquid duct piping. Examples of grooved joints include NPS 2½ & over utilizing mechanical joint rolled, or cut grooved standard, with rigid coupling with EPDM gaskets. Standards of acceptance include Victaulic and Gruvlock. An applicable standard is CSA B242-M1980.

[1677] Various types of fittings can be used for liquid ducting expected to experience pressures up to about 1035 kPa (150 psi). Threaded fittings for NPS 2 & under in this pressure range include threaded malleable iron, Class 150 under the ANSI B16.3 standard, and unions of black malleable iron, bronze face, ground joint under the ASME B16.39 standard.

[1678] Welded fittings for liquid ducting expected to experience pressures up to 1035 kPa (150 psi) include NPS 2½ & over using forged steel, class 150, raised face pipe flanges, weld neck or Slip-on, or forged steel butt welding type; wall thickness to match pipe. Standards of acceptance include Weldbend, Tube Turns, and Bonney Forge. An applicable standard is ANSI B16.5.

[1679] Grooved fittings for liquid ducting expected to experience pressures up to 1035 kPa (150 psi) include NPS 2½ & over using malleable iron under standard ASTM A47-77, or ductile iron under standard ASTM A536-80. Standards of acceptance include Victaulic and Gruvlock.

[1680] Various types of fittings can be used for liquid ducting expected to experience pressures up to up to about 2070 kPa (300 psi). Threaded fittings of NPS 2 & under may use threaded malleable iron, Class 300 under the ANSI B16.3 standard.

[1681] Welded fittings may also be used for ducting expected to experience higher pressures. For NPS 2 & under, welded fittings of forged steel, Class 300 may be used, with a standard of acceptance of Bonney Forge and Anvil (Grinnell) under standard the ANSI 16.11 standard. Unions comprising forged steel Class 300, bronze face, ground joint under the MSS-SP-83 standard may also be used.

[1682] For NPS 2½ & over, welded fittings of forged steel, Class 300, raised face pipe flanges; weld neck or slip-on may be used. Forged steel butt welding type with a wall thickness to match pipe, may also be used. Standards of acceptance include Weldbend, Tube Turns, and Bonney Forge. Applicable standards include ANSI B16.5.

[1683] Grooved fittings may also be used for this pressure range. NPS 2½ & over may use malleable iron under the ASTM A47-77 standard, or may use ductile iron under the ASTM A536-80 standard. Standards of acceptance include Victaulic and Gruvlock.

[1684] Welded branch connection fittings may also be used for higher pressures for all pipe sizes. These fittings may be forged steel, with a wall thickness to be minimum thickness of pipe run to which branch fitting is to be welded. Standards of acceptance include Bonney Forge "O-let" fittings, and Anvil (Grinnell) "Anvilet" fittings. The fittings may conform to the ANSI B31.1 standard.

[1685] A variety of valve types may be used in liquid ducting employed for heating and cooling. Gate valves may be used for pressures up to about 1035 kPa (150 psi). For NPS 2 & under, the valves may be

soldered with a rising stem, Class 150 with bronze body and screwed bonnet, solid wedge disc. A standard of acceptance is Kitz 44.

[1686] In this pressure range, threaded gate valves may also be used, which can comprise a rising stem, Class 150 with bronze body and screwed bonnet, solid wedge disc. A standard of acceptance is Kitz 24. Threaded valves for NPS 2 and under may conform to MSS SP-80 and/or ANSI/ASME B16.34 standards.

[1687] For NPS 2½ & over, flanged gate valves can be used in this pressure range, including rising stem, Class 125 with flat faced flanges, cast iron body, bronze trim, solid wedge disc, bolted bonnet, OS&Y. A standard of acceptance is Kitz 72. Flanged gate valves may conform to the MSS SP-70 and/or ANSI/ASME B16.5 standards.

[1688] For Pressures up to 2070 kPa (300 psi), ball valves can be used. For NPS 2 & under, such ball valves may be soldered or threaded. Soldered ball valves may comprise a minimum of 600 psi WOG two piece bronze or brass body, full port chrome plated bronze or stainless steel ball, PTFE seat and seals, blowout proof stem. A standard of acceptance is Kitz 59. A threaded ball valve may comprise a minimum of 600 psi WOG two piece bronze or brass body, full port stainless steel ball, PTFE seat and seals, blowout proof stem. A standard of acceptance is Kitz 58. Such ball valves may conform to the ANSI/ASME B16.34 standard.

[1689] For NPS 2½ to 12, butterfly valves may be used. An example of such a butterfly valve is grooved, of class 150 with a long neck design malleable or ductile iron body, aluminum bronze disc, EPDM Grade "E" liner for 93°C (200°F) working temperature. A standard of acceptance is Victaulic Series 300. The valve may conform to the ANSI/ASME B16.34 or ANSI/ASME B16.5 standards.

[1690] For Pressures up to 4100 kPa (600 psi), ball valves may be used. For NPS 2 to 4, the ball valves may be grooved, with 600 psi WOG, ductile iron body, stainless steel ball and stem, standard port, lockshield where specified, TFE seat and seals. Standards of acceptance include Victaulic Series 721 and Gruvlok. The ball valves may conform to the MSS SP-70 or ANSI/ASME B16.5 standards.

[1691] For Pressures up to 1035 kPa (150 psi), swing check valves may be used. NPS 2 & Under may use soldered or threaded swing check valves. Soldered swing check valves may be Class 150, Y-Pattern bronze body, bronze swing disc, integral seat, screw in cap, with a standard of acceptance being Kitz 30-. Threaded swing check valves may be Class 150, Y-Pattern bronze body, bronze swing disc, integral seat, screw in cap, with a standard of acceptance of Kitz 29. Such soldered or threaded swing check valves may conform to the MSS SP-80 and/or ANSI/ASME B16.34 standards.

[1692] NPS 2½ & over may used flanged swing check valves of Class 125 with flat faced flanges, cast iron body, renewable bronze seat ring, bronze swing type disc. Standards of acceptance include Kitz 78. Such flanged swing check valves may conform to the MSS SP-71 and/or ANSI/ASME B16.5 standards.

[1693] Thermal linkages from systems according to certain embodiments of the present invention may be in communication with refrigeration apparatuses. Such refrigeration components may comply with Canadian Standards Association (CSA) standard B52, ARI, ASME and ASHRAE codes and standards to be used in performance testing, to establish component ratings.

[1694] An example of a refrigeration component is refrigeration tubing. Where Halogen refrigerants are to be used, factory cleaned and sealed seamless ACR copper may be employed for tubing. Such tubing may conform to the ASTM B280 standard.

[1695] Fittings are another example of a refrigeration component. For fittings, long radius type elbows and return bends may be used. These fittings may be formed from wrought copper or forged brass solder type. The fittings may conform to the ASME B16.22 standard.

[1696] Joints represent still another example of a refrigeration component. Certain embodiments may employ copper piping jointed with copper fittings. Examples of material for such joints include but are not limited to SIL-FOS-15 Phosphor-copper-silver alloy, which may comply with the CSA B52 standard.

[1697] Certain embodiments may employ brass fittings. Such fittings may comprise 2500 PSI Solder, conforming to the CSA B52 standard.

[1698] Connections to equipment or accessories in some embodiments may be achieved using 95-5 Solder, and may be in conformity with the CSA B52 standard.

[1699] In certain embodiments flexible connections may be used. Some embodiments according to the present invention may use a flexible connection comprising seamless flexible bronze hoses. Some embodiments of the present invention may use a flexible connection comprising bronze wire braid covering for larger sizes. The connection may be in conformity with the CSA B52 standard.

[1700] According to certain embodiments, the refrigeration piping may be installed as follows. Each length of refrigeration piping may be swabbed with cloth soaked in refrigerant oil if dirt, filings, or visible moisture is present. The piping ends may be kept sealed except when fabricating joints. Elbows and fittings are kept to a minimum. Horizontal pipe carrying gases are graded 1:240 down in direction of flow. Lines may be supported at intervals of not more than 8 ft and anchored.

[1701] Where appropriate, expansion swing joints, pipe guides, and anchors can be provided. The pipe guides and anchors can be copper plated when contacted with refrigeration piping.

[1702] Anchors may be properly secured to building structure. Vibration eliminators can be of "Anaconda" sized the same as refrigeration piping.

[1703] Liquid line filter drier and sight glass may be of "Sporlan" of size and capacity to suit refrigeration piping and loads and in accordance to manufacturer's recommendation. Suction line P traps may be provided at the base of each evaporator, and at every 50 feet horizontally and every 20 feet vertically. Solenoid valves shall be of "Sporlan" sized to suit capacities and the magnetic coil voltage shall be coordinated with the control system. When multiple runs are installed, pipes may be spread to 6 in minimum to allow for expansion and contraction.

[1704] "HYDRAZORB" or "CUSH-A-CLAMP" rubber grommets may be used between tubing and clamps to prevent line chafing. Where vertical risers of more than 1.7m (5 ft) occur in a suction line, the riser may be connected into the top of next horizontal section. Screwed and flanged joints may be limited to equipment connections not available in brazing format.

[1705] Dry nitrogen may be bled into piping when sweating connections. Flexible pipe vibration isolators and stub connectors may be brazed on sealed hermetic compressors using alloys which melt at 620°C (1148°F) or below.

[1706] Two evacuation fittings may be provided. One may be in the suction line at inlet side of suction line filter, and one may be in the liquid line at outlet side of filter-drier. Connection in liquid line may be valved to serve as charging valve. Connections should be at least 1/4 in. Pressure relief may be vented in accordance with latest edition of CSA B52.

[1707] Leak and pressure testing may be conducted as follows. Leak testing may be performed before evacuating the system. Testing may comply with latest edition of CSA B52, with gauge pressure of 2070 kPa (300psi) on high side and 1050 kPa (150 psi) on low side. Dry Nitrogen may be used to develop pressure. The apparatus may be built to field test pressure in high and low side with dry nitrogen. Leaks may be tested for using a soap solution, or proprietary leak detection kit such as "SNOOP", or a fluorescent tracer.

[1708] Returning to Figure 69, sensors of various types, including humidity (H), volume (V), temperature (T), and pressure (P), and other sensors (S) such as valve state sensors, may be located at various points throughout the system. These sensors may be in electronic communication with central controller 6996.

[1709] Specifically, various elements of the system 6901 are in communication with a central controller or processor 6996, that is in turn in electronic communication with a computer-readable storage medium 6994. Based upon instructions in the form of computer code stored on computer-readable storage medium 6994, the controller or processor 6996 may operate to control various elements of the system 6901. This control may be based upon data received from various sensors in the system, values calculated from that data, and/or information received by the controller or processor 6996 from various sources, including co-situated sources (such as the end user or a co-situated energy generator as discussed below), or from external sources such as the internet or a smart grid.

[1710] Operation of the compressed gas energy storage and recovery system is now described. As previously mentioned, in certain roles the system provides temperature control to the end user, for example in the form of air conditioning and/or heating. This cooling or heating is accomplished through the thermal linkages provided between the end user and the dedicated compressor and dedicated expander.

[1711] Specifically, compressed gas that is stored in the storage unit may be flowed through one-way valve 6911 into the dedicated expander. According to basic thermodynamic principles, compressed gas that is undergoing expansion within that expander, will tend to experience a drop in temperature. This flow of thermal energy from this gas expansion process, can be employed to cool the end user through the thermal linkage 6980 and switch 6981.

[1712] In particular, the thermodynamic efficiency of cooling may be enhanced by performing gas expansion under near-isothermal conditions, resulting in a minimum change in temperature and with

reduced thermal loss. In certain embodiments, such near-isothermal conditions can be achieved utilizing heat exchange between the expanding gas and a liquid (such as water or an oil) that is present within the expanding gas. Specifically, the relatively high heat capacity of the liquid, combined with the large surface area afforded by the droplets, allows for the effective transfer of heat from the liquid to the expanding gas. After separation from the expanded aerosol, the liquid cooled by transfer of heat to the expanding gas can in turn be flowed through a thermal linkage to the end user to perform a cooling function.

[1713] While the particular embodiment shown and described in Figure 69 has focused upon the storage and recovery of energy from compressed gas, this is not required by the present invention. Alternative embodiments in accordance with the present invention could utilize other forms of energy storage systems located behind a meter with an end user, as is described above in connection with positioning within the generation layer.

[1714] The embodiment of the compressed gas energy storage and recovery system shown in Figure 69 differs in certain respects from the embodiment of the refrigeration apparatus of Figure 28. For example, the refrigeration apparatus of Figure 28 couples together a compressor and an expander in a single compressor/expander unit.

[1715] In addition, the refrigeration apparatus of Figure 28 is shown without provision for a structure for storing gas that has been compressed. As discussed in connection with Figure 28, however, such an apparatus can readily be modified at point A to include such a gas storage unit.

[1716] The refrigeration apparatus as shown in Figure 28 also lacks a separate power generation capability. However, in alternative embodiments the expander element of the compressor expander unit could readily be placed into physical communication with a generator to provide power. Such power generation could be useful where: 1) a capability for storing compressed gas for later use is present, and/or where 2) the expander is in thermal communication with an external heat source to augment the magnitude of its power output.

[1717] Despite their differences, however, it is to be recognized that the refrigeration system of Figure 28 and the energy storage and recovery system of Figure 69 operate utilizing similar principles. In particular, both utilize liquid separated from a expanded gas-liquid mixture, to perform a temperature control function.

[1718] Figures 28-32 above have focused upon the effect of gas expansion to provide cooling. However the present invention is not limited to this application, and other embodiments could provide a heating effect.

[1719] According to basic thermodynamic principles, gas that is undergoing compression within the compressor, will tend to experience an increase in temperature. Thus in a manner analogous to the aerosol refrigeration described above, injected liquid that has been heated by exposure to the compressed gas, may be separated and flowed through switch 6981 and thermal linkage 6980 to heat the end user.

[1720] While the previous discussion has focused upon the use of the compressed gas energy storage and recovery system for temperature control, the embodiments of the present invention are not limited to

this application. In particular, the expansion of gas within a dedicated expander may give rise to physical work that can be harnessed to provide power.

[1721] Thus returning to Figure 69, the dedicated expander 6905 could include a moveable member that is in physical communication with linkage 6923.

[1722] The detailed view of the dedicated expander of Figure 50B, taken in combination with the embodiment of Figure 69, indicates that expansion of the gas may drives the moveable member, outputting physical energy to a link such as link 6923 of Figure 69. This physical energy, in mechanical, hydraulic, or pneumatic form, could be utilized in a number of ways.

[1723] For example, energy output on the linkage 6923 could be communicated to second linkage 6921 to drive a second moveable member that is located within the dedicated compressor 6902. In this manner, actuation of the second moveable member to compress and flow gas to the storage unit, could serve to replenish the supply of compressed gas available for expansion.

[1724] While the particular embodiment of Figure 69 shows linkages 6921 and 6923 as being separate and distinct, this is not required by the present invention. In certain embodiments the linkages 6921 and 6923 could be the same structure, for example a common crankshaft between reciprocating pistons as moveable members. Such a configuration could facilitate the efficient transfer of energy between the expander and compressor elements for the purpose of supplying compressed gas to the storage unit.

[1725] In certain modes of operation, energy from the link 6923 that is driven by the expander, could be kept primarily within the system. Specifically, the energy recovered from the compressed gas would be utilized for cooling and/or to replenish the supply of compressed gas. No net electrical power would then be output from the motor/generator.

[1726] However, other operational roles may call for the compressed gas energy storage system to serve as a power supply. Thus in certain applications (including but not limited to UPS, peak shaving, demand response, and renewable levelizing), the compressed gas storage system could supply power directly to an end user, bypassing the meter. In one or more of such power supply applications, the compressed gas energy storage system could include additional components such as a power electronics module and short term energy storage (for example in the form of a battery) that allow transition to drawing energy from the compressed air system in a smooth manner without disruption to the end user.

[1727] In other applications, the system could supply power back through the meter to the power network. For example, in a distributed generation (DG) configuration, the power network is configured to receive power back through the meter. In this manner, the electricity output by the generator driven by expansion of the compressed gas, may be fed to the power network, and the operator of the energy storage system remunerated for the supply of this power.

[1728] Such a scheme could be particularly advantages at times of peak demand, where power contributed back onto the network from DG could meet the extra load. Such a scheme could also contribute resiliency to the network, allowing for the formation of temporary local islands of electrified grid from DG, in response to a wider network failure attributable to an event such as a natural disaster or terrorist attack.

[1729] The various elements of the system 6901 are in communication with a central controller or processor 6996, that is in turn in electronic communication with a computer-readable storage medium 6994. Based upon instructions in the form of computer code stored on computer-readable storage medium 6994, the controller or processor 6996 may operate to control various elements of the system 6901. This control may be based upon data received from various sensors in the system, values calculated from that data, and/or information received by the controller or processor 6996 from various sources, including co-situated sources (such as the end user or a co-situated energy generator as discussed below), or from external sources such as the internet or a smart grid.

[1730] In certain embodiments, the controller of the system may be configured to commence operation based upon an instruction received from the end user. For example, where the end user has accepted a solicitation for demand response from the operator of the power network, the end user may in turn communicate a signal to the controller indicating the need for the storage system to provide the necessary electrical power to cover the demand response period.

[1731] In another example, a compressed gas storage and recovery system may receive a signal from the end user or from an external source (such as the internet), indicating an actual or imminent change in temperature conditions. In response, the controller could instruct the system to operate with greater cooling effect.

[1732] In certain embodiments, the compressed gas energy storage and recovery system may transmit signals to an end user. For example, where the available supply of compressed gas is becoming depleted, the energy storage system may send a message to the end user indicating a need for the end user to draw additional power from the network through the grid, in order to maintain its temperature.

[1733] A potential benefit which may be realized by locating an energy storage system behind the meter, is the resulting form of regulatory oversight. As part of the consumption layer, an energy storage system's contact with the network is relatively simple and limited. In particular, the system is expected to interact with the network through a single interface (the meter), with magnitude and direction of flows of power through that interface able to be estimated based upon patterns of consumption and even output, in the case of net metering connections. A compressed gas energy storage and recovery system located behind the meter according to embodiments of the present invention, may thus be considered analogous to an ordinary home appliance, and not subjected to the regulations governing elements of other layers of the power network, such as the generation, transmission, and distribution layers.

[1734] Co-situation of the energy storage system with an end user may further enhance coordinated action between the two entities. In particular, the communication link between the compressed gas energy storage system 6640a and the co-situated end user may be local in nature, and hence potentially faster and more reliable than wider-area communication networks.

[1735] In any one of various power supply roles, (i.e. UPS, peak shaving, demand response, renewable levelizing), such close proximity between the energy storage system and the end user may help to facilitate a seamless transition between an end user's consumption of power supplied by the network, and an end user's consumption of power supplied from the storage system.

[1736] The embodiment shown in Figure 69 may include one or more optional features shown in outline form. For example, in certain embodiments the gas outlet of the expander may be in fluid communication with the gas inlet of the compressor. The closed fluidic loop 6985 offered by such an embodiment could provide a number of potential benefits. One is the conservation of gases, thereby allowing the use of more exotic gases (such as helium or high density gases) having higher heat capacities that enhance heat exchange.

[1737] Another optional feature of the embodiment of Figure 69, is a possible thermal linkage 6986 between expander 6905 and an external heat source 6987, for example the heat emitted by the sun or a nearby facility or industrial process, or a local power source as is discussed below in connection with Figure 70. In particular, the thermal energy from such an external heat source could be captured utilized to enhance the efficiency of recovery of energy from expansion of the compressed gas. Use compressed gas storage and recovery systems according to the present invention in conjunction with sources of additional heat, is described at length in U.S. Provisional Patent Application No. 61/294,396, which is hereby incorporated by reference in its entirety herein for all purposes.

[1738] In certain embodiments, the operation of a compressed gas energy storage and recovery system according to the present invention, may be coordinated with the thermal phases of a diurnal cycle. An example of such operation is now provided.

[1739] Referring again to Figure 69, in this example the end user comprises a large office building located in a climate offering relatively large differences between day and night temperatures. On evenings and during the weekend, the office building is largely unoccupied and offers a minimal load to the power network, consuming some power to maintain a minimum temperature.

[1740] However, between 7AM and 7PM during the weekday the office building is occupied with workers and poses a large load to the power network, a substantial component of which is devoted to cooling. The price for electricity during this period is high, owing to demand from other users. In addition, the price charged to the building for electricity supplied, may be based upon historical peaks of usage.

[1741] Thus in order to reduce power costs, the office building may incorporate behind its meter, a compressed gas energy storage and recovery system according to the present invention. Such a system can function in both temperature control and power supply roles.

[1742] For example, during off-peak hours the system could consume energy from the network to operate the compressor to store compressed gas in a storage unit. The heat generated by such compression could be utilized for heating, thereby obviating the need for the office building to draw energy for that purpose from the power network.

[1743] Of even potentially greater economic significance, however, is the system's consumption of power for energy storage during off-peak times when energy is less expensive. This stored energy can subsequently recovered to reduce (or even eliminate) the load posed by the office building during peak demand times.

[1744] In particular, the energy storage and recovery system could flow compressed gas from the storage unit to the expander during times of peak demand. Such operation would reduce the office building's load on the power network for at least two reasons.

[1745] First, the gas expansion could provide a cooling effect during the day, when temperatures within the office building are expected to be high. Such cooling by gas expansion, would eliminate that portion of the load which would otherwise be drawn from of the network in order to control building temperature.

[1746] Second, in addition to eliminating some load, the power produced by gas expansion can also advantageously shift the timing of the load to periods of lower demand, further reducing cost. The stored energy has already been drawn from the power network at times of lower energy pricing. The energy available from subsequent recovery is available at that lower price, thereby reducing the effective cost of the energy.

[1747] Moreover, solar energy that is naturally available during daylight hours, may readily be harnessed to enhance the cooling effect and/or power supplied from the stored compressed air. For example, the compressed gas storage unit could be positioned in thermal communication with the sun. Thermal energy from the sun could heat the gas within the storage unit, increasing an amount of energy stored therein and available for recovery upon expansion of the gas.

[1748] Separately or in conjunction with heating stored gas, energy from the sun could also be utilized to heat liquid for injection into expanding gas. In particular, the thermal energy could be communicated to heat the liquid that has been separated following expansion of the gas-liquid mixture As described above, this liquid would have been cooled by virtue of its transfer of heat to the expanding gas under near-isothermal conditions. The natural availability of sunlight for heating gases and liquids during typical times of energy recovery, lends itself to operation of a compressed gas energy storage and recovery system run according to a diurnal cycle.

[1749] The load reduction and load shifting afforded by energy storage according to embodiments of the present invention, may further reduce cost by lowering a present load below historical peaks. In particular, elimination or reduction of cooling costs comprising the bulk of previous peak loads, may ensure that the present load does not exceed those peaks, thereby avoiding penalties or surcharges.

[1750] In summary, operation of an energy storage system coordinated with diurnal cycles, may offer reduced costs on at least two separate bases. First, energy storage and recovery may eliminate some load associated with temperature control, as the cooling associated with energy recovery by expansion coincides with daily warmth, and the heating associated with energy storage by compression coincides with nightly coolness.

[1751] Second, energy storage and recovery may shift a load on the power network from peak periods of relatively expensive power, to off-peak periods of relatively inexpensive power. Such load shifting may be understood in terms of reducing bulk rates charged for electricity consumed, and also in terms of the rates charged in view of historical peaks in demand by a particular user.

[1752] In certain situations, a compressed gas energy storage and recovery system could be configured by a system controller to perform compression and expansion simultaneously. In such an operational mode, all or a portion of the gas that is compressed, may immediately be expanded in order to provide cooling and/or power.

[1753] Such an operational mode could be prompted by a variety of conditions. For example, the stored compressed gas may be close to depletion, but temperature control is still required. In another example, ongoing supply of power may be required to shave peak load, or to meet the terms of a contractual relationship to provide power (i.e. to provide power even where the supply of compressed gas has been exhausted). In another example, a cost of power available from the network is low, justifying energy storage on a cost-effective basis.

[1754] Operation in such a mode involving simultaneous compression and expansion, may also offer certain efficiencies. In particular, as described above in connection with Figure 28, the concurrent flow of gases to and from the storage unit through the heat exchanger, allows the transfer of thermal energy between these gas flows.

[1755] The table presented as Figure 71 summarizes different modes of system operation.

[1756] Returning to Figure 66, in certain embodiments, the energy storage system and the end user may be co-situated behind a same meter with a local source of energy. Possible examples of such a local energy source include a rooftop PV array, a solar thermal system, a wind turbine, or a gas microturbine in fluid communication with the natural gas supply of the end user.

[1757] Accordingly, Figure 70 shows a simplified block diagram of one embodiment of a compressed gas storage and recovery system 7001 in accordance with an embodiment of the present invention, that is co-situated behind the meter with an end user 7050 and a local power source 7070. In the embodiment of Figure 70, the dedicated compressor (C) 7002, the dedicated expander (E) 7005, a dedicated motor (M) 7004, and a dedicated generator (G) 7003, are all in selective physical communication with one another through a multi-node gear system 7099.

[1758] An embodiment of such a gear system is a planetary gear system as described in U.S. Nonprovisional Patent Application No. 12/730,549 and described above in connection with Figures 33A-33AA. Specifically, the multi-node gear system 7099 provides mechanical communication with three rotatable linkages (for example linkages 3341, 3362, and 3368). Each of these linkages may be in physical communication with the various other elements of the system, for example a local energy source such as a wind turbine, a generator, a motor, a motor/generator, a compressor, an expander, or a compressor/expander.

[1759] The multi-node gearing system 7099 permits movement of all of the linkages at the same time, in a subtractive or additive manner. For example where the wind is blowing, energy from the turbine linkage may be distributed to drive both the linkage to a generator and the linkage to a compressor. In another example, where the wind is blowing and demand for energy is high, the planetary gear system permits output of the wind turbine linkage to be combined with output of an expander linkage, to drive the linkage to the generator.

[1760] Moreover, the planetary gear system is also configured to accommodate movement of fewer than all of the linkages. For example, rotation of shaft 3341 of the particular embodiment of Figures 33A-33AA may result in the rotation of shaft 3362 or vice-versa, where shaft 3368 is prevented from rotating. Similarly, rotation of shaft 3341 may result in the rotation of only shaft 3368 and vice-versa, or rotation of shaft 3362 may result in the rotation of only shaft 3368 and vice-versa. This configuration allows for mechanical energy to be selectively communicated between only two elements of the system, for example where the wind turbine is stationary and it is desired to operate a compressor based upon output of a motor.

[1761] Certain embodiments of the present invention may favorably employ a multi-node gear system such as a planetary gear system, to allow the transfer of mechanical energy between different elements of the system. In particular, such a planetary gear system may offer the flexibility to accommodate different relative motions between the linkages in the various modes of operation described in Figure 72.

[1762] Returning to Figure 70, while that figure shows a multi-node gear system, this is not required by the present invention. In alternative embodiments, various elements of the system could be in physical communication with each other through individual physical linkage or through physical linkages shared with fewer than all of the other elements.

[1763] Figure 70 shows the local power source as optionally being in physical communication with the multi-node gearing through linkage 7080. This configuration allows physical energy from the local power source and from the expander, to be combined in order to produce an even greater amount of electricity. This configuration also allows the local power source and the expander to separately utilize an existing asset (the same generator structure) in order to produce electricity.

[1764] Figure 70 also shows that the local power generator may be in electrical communication with the end user or the meter through an electrical linkage 7082. Such a linkage may be utilized where the local energy source outputs electricity directly, as is the case for a PV array.

[1765] Figure 70 also shows that the local power generator may be in thermal communication with the end user and/or the expander through thermal linkages 7072 and 7074 respectively. Such a linkage may be utilized where the local energy source outputs energy in thermal form directly, for example as is the case for a solar thermal system and a combustion gas microturbine.

[1766] The flexibility offered by the multi-node gearing and/or other forms of physical, thermal, fluidic, and electrical linkages, permits operation of the system in the modes that are summarized in the table of Figure 72.

[1767] Location of a compressed gas energy storage and recovery system with a local power source as in Figure 70, may endow the system with the ability to function in a number of possible roles. In one role, an energy storage unit in combination with one or more local energy sources, such as rooftop solar (PV and/or thermal solar) or a wind turbine, could potentially satisfy all of the energy demands of the end user. This would allow the end user to operate completely off of the grid, as could be desirable for reasons of security and/or economy.

[1768] Another role is to levelize the intermittent power that is output by a renewable energy source, such as a wind turbine, PV array, or solar thermal system. For example, in a DG scheme the owner of a local alternative power source may enter into a contract with the network operator, to provide electricity back onto the grid. However, the intermittent nature of certain natural resources such as sunshine and wind, may make it difficult to meet contractual obligations to provide a constant supply of power.

[1769] However, co-situation of a compressed gas energy storage and recovery system according to the present invention, may allow the owner of the local energy source to provide power on a regular basis. In particular, energy stored by the system in the form of compressed gas, could be recovered as necessary in order to make up for gaps in output attributable to a temporary lack of natural resources such as wind or sun. The energy from the system would thus serve to levelize the power output by the local alternative energy source, such that electricity ultimately output by the meter to the power network is substantially constant. A compressed gas energy storage and recovery system having a capacity of greater than one-half day that is able to replenish itself every day, would allow for levelization over a long period of the absence of the natural resource.

[1770] Location of a compressed gas energy storage and recovery system with a local power source as in the embodiment of Figure 70, may confer certain benefits. One such potential benefit is a cost advantage afforded by allowing more efficient operation.

[1771] For example, in certain embodiments the compressor element of the compressed gas energy storage and recovery system could be in physical communication with a moving member of a local power source through a linkage and gearing. Thus in an embodiment, the spinning blades of a rooftop wind turbine could be in physical communication with the compressor of a compressed gas energy storage system through a mechanical, hydraulic, or pneumatic linkage. The direct physical communication afforded by such a linkage may allow power to be transferred more efficiently between the local source and compressor elements, thereby avoiding losses associated with having to convert the power into an intermediate form such as electricity. In this manner, physical work produced by an operating wind turbine or gas microturbine could be harvested to store compressed gas for later recovery in a temperature regulation or power supply role.

[1772] Moreover, co-situation of the compressed gas storage and recovery system with a local power source may allow efficient communication of other forms of energy flows. For example, certain embodiments of an energy storage system may be in thermal communication through a thermal link, with a co-situated source of energy. Thus in some embodiments, an efficiency of expansion of compressed gas by the compressed gas energy storage system, could be enhanced utilizing heat that is communicated from the local source of thermal energy. A local source of thermal energy is generically designated with the reference number 7079 in Figure 70. Operation of a compressed gas energy storage and recovery system utilizing heat from another source is discussed in the U.S. Provisional Patent No. 61/294,396, which is incorporated by reference in its entirety herein for all purposes.

[1773] Under certain circumstances, a local power source may also be a power generator, for example a rooftop PV and/or thermal solar system, a microturbine, a diesel generator, or other local power source.

In this manner, thermal energy from such a power source, can be leveraged to enhance gas expansion in a chamber of a co-situated energy storage system.

[1774] Siting an energy storage and recovery system with a generation asset, may also allow the communication of fluids communication between these elements through a fluid link. For example, where an energy storage system is co-situated with a microturbine, the fluid link would allow compressed gas stored by the system to be flowed directly to such a microturbine for combustion, thereby enhancing the efficiency of operation of the microturbine. Similarly, the liquid heated by a thermal solar system could be the same as, or in thermal communication with, the liquid that is used to transfer heat to expanding compressed gas.

[1775] Another possible benefit which may be realized by co-situation of the energy storage system with a power generation asset, is the ability to leverage off of existing equipment. For example, an existing local source of power such as a diesel generator or microturbine, may already include a generator for converting mechanical energy into electrical power. An embodiment of a compressed gas energy storage and recovery system according to the present invention could utilize the same generator component to convert motion resulting from gas expansion, into electrical power. Similarly, a compressed gas energy storage and recovery system could utilize an end user's existing interface with the network (meter) to communicate electricity to the power network, for example in a net metering and/or distributed generation scheme.

[1776] Returning to Figure 70, the various elements of the system 7001, are in communication with a central controller or processor 7096, that is in turn in electronic communication with a computer-readable storage medium 7094. The central controller or processor 7096 is also in communication with one or more sources of information, which may be internal or external. Examples of internal information sources include various system sensors. Examples of external information sources include but are not limited to a smart grid, the internet, or a LAN.

[1777] As indicated above, based upon instructions in the form of computer code stored on computer-readable storage medium 7094, the controller or processor 7096 may operate to control various elements of the system 7001. This control may be based upon data received from various sensors in the system, values calculated from that data, and/or information received by the controller or processor 7096 from sources such as a co-situated end user or external sources.

[1778] According to embodiments of the present invention, a gas compression and/or expansion system may be configured to operate in response to data received from one or more outside sources, such as a smart grid. Based upon the external information, a controller or processor of the processor may regulate operation of system elements in a particular manner. Examples of such external information which may be received include but are not limited to, a current price of electricity, a future expected price of electricity, a current state of demand for electricity, a future state of demand for electricity, meteorological conditions, and information regarding the state of the power grid, including the existence of congestion and possible outages.

[1779] As will be discussed below, operation of a compressed gas energy storage and recovery system in accordance with embodiments of the present invention may be based upon information received by a controller or processor. In certain circumstances, operation of the system may be halted based upon information that is received. For example, where the information received indicates a high demand for electricity, operation of the system to compress air may be halted by the controller, in order to reduce a load on the grid.

[1780] Alternatively, energy received by the system controller or processor may result in commencement of operation of the system. For example, an embodiment of a system may function in the role of an uninterruptible power supply (UPS), such that it is configured to provide energy on a continuous basis in certain applications where interruption in power could have harmful results, such as industrial processes (for example a semiconductor fabrication facility), transportation nodes (for example harbors, airports, or electrified train systems), or healthcare (hospitals), or data storage (server farms). Thus receipt of information indicating either an imminent reduction (brownout) or loss (blackout) of power from the grid, or even the risk of such an event, may cause the processor or controller to instruct the compressed gas energy storage and recovery system to operate to provide the necessary power in an uninterrupted manner.

[1781] Under certain circumstances, information provided to a controller or processor may determine operation of a compressed gas storage and recovery system in a particular mode, for example a compression mode, an expansion mode, or a combined compression and expansion mode. Under certain circumstances, information received by the controller may indicate a reduced price for power, causing the energy storage and recovery system to operate in compression mode in order to store energy at low cost.

[1782] Moreover, a compressed gas energy storage and recovery system typically operates at some balance between an efficiency of energy storage/recovery, and an amount of power that is stored/produced over a given time frame. For example, an apparatus may be designed to generate power with maximum efficiency based upon expansion of compressed gas in particular volume increments. Expansion of other volume increments may result in a greater power output, but at a reduced efficiency. Similarly, compression of gas volumes in increments outside of a particular range, may result in less efficient conversion of energy into the form of compressed gas for storage.

[1783] Under certain circumstances, embodiments of systems in accordance with the present invention may be operated under conditions of optimized efficiency. For example, where the grid indicates ordinary prices and/or demand for power, a controller may instruct components of the system to operate to compress or expand gas with maximum efficiency.

[1784] Alternatively, based upon information received from the grid or from other sources such as the internet, the controller or processor may instruct the system to operate under conditions deviating from maximum efficiency. Thus where the smart grid indicates a relatively low price for electricity (for example outside of peak demand times between 7AM-5PM on weekdays), the processor or controller may instruct compression of gas in a manner calculated to consume larger amounts of power for energy storage while the price is low.

[1785] According to certain embodiments, information relevant to operation of the energy storage and recovery system may be available on an ongoing basis from the external source. In such circumstances, code present in the computer-readable storage medium may instruct the system processor or controller to actively monitor the external source to detect information availability or changes in information, and then to instruct elements of the system to operate accordingly.

[1786] In some embodiments, relevant information may be actively communicated from the external source to the controller of the energy storage and recovery system. One instance of such active communication are solicitations of a demand response system.

[1787] Specifically, in certain embodiments a processor or controller of a storage system may receive from the operator of the power grid, an active solicitation to reduce demand during peak periods as part of a demand response system. Thus, the controller or processor may instruct operation of the system to output sufficient power to compensate for an end user's reduced load on the grid as part of a such a demand response system.

[1788] When received information indicates a relatively low price for electricity (such as in the middle of the night), the processor or controller may instruct compression of gas in a manner calculated to consume larger amounts of power - for example compression of gas in large volume increments while a price is low. In such cases, the extra cost associated with the inefficiency of such compression, may be offset by the low cost of the energy that is available to perform compression.

[1789] Factors other than present demand, may influence the terms at which energy is bought and sold. For example, future power demand or future price may be considered by the controller or processor in determining conditions of operation of the apparatus.

[1790] Thus under certain circumstances where a future price of energy is expected to be particularly high, the controller or processor may operate the system in a particular manner. One example of this may be a heat wave, where demand is expected to spike based upon a meteorological forecast. In view of such an expectation, the controller or processor may instruct the system to prepare for the future conditions, for example by operating to compress additional gas - possibly with reduced efficiency - in advance of the expected spike in demand.

[1791] Other factors potentially influencing system operation, include specific contractual terms between the power network operator and the end user. Such terms can include a maximum load (and/or minimum power output in distributed generation schemes) required over a particular time frames, and incremental or tier-based bonuses, penalties, and multipliers for power output or consumption. Conformity or divergence from these contract terms can be an important factor in dictating operation of the energy storage and recovery system by the controller or processor.

[1792] Thus in certain embodiments, the controller or processor may take such contractual terms into consideration in operating the apparatus. For example, the contract between the end user and the grid operator may establish a maximum load able to be drawn by the user from the network over a particular time frame. Thus where this baseline quantity is in danger of being exceeded, the controller or processor

may instruct operation of the system under conditions of higher power output and lower efficiency to ensure satisfaction of the contractual obligation.

[1793] Still another type of information potentially influencing system operation, is the expected availability of sources of energy to the power grid. For example, where information received indicates a forecast for future cloudy conditions at the site of a solar energy farm known to provide energy to the network, a processor or controller of the apparatus could instruct the system to operate in compression and at low efficiency to store large amounts of compressed gas in advance of the expected later higher energy prices.

[1794] Yet another type of information which may be considered by a system controller or processor, is the potential availability of other sources of power. For example, the system of Figure 70 is configured to receive energy in different forms from a plurality of sources. In particular, the system may receive energy in the form of electrical power directly from the grid itself, or from operation of a local energy source such as a rooftop array of photovoltaic cells. The system may receive energy in physical form (such mechanical, hydraulic, or pneumatic) from the local source, for example a proximately-located wind turbine or microturbine. The system may receive energy in thermal form from the local source, for example a thermal solar apparatus.

[1795] Thus where information regarding favorable wind conditions is received from the local generator, the controller or processor could instruct the system to operate in compression to store compressed gas, owing to the ready availability of power directly from the wind turbine. Upon abatement of the winds, the energy stored in this compressed gas could later be recovered by operating in an expansion mode to output power to the end user directly, to the grid through the network, or to both. A similar situation may exist where energy from favorable solar conditions provide energy for the compression of gas.

[1796] Under certain circumstances, favorable solar conditions could result in operation of the system in expansion. For example, favorable solar conditions could allow the communication of heat from a thermal solar apparatus to enhance the power output from expanding gas, or to enhance the efficiency of energy recovery from expanding gas.

[1797] In certain embodiments the local energy source may be non-renewable, such as a natural-gas fed microturbine. Thus where a supply of compressed gas in the storage unit has been exhausted by prior expansion activities and power is still required, the controller may instruct the generator to create power from operation of the local microturbine that is consuming power from an energy source other than the grid (i.e. a natural gas distribution network).

[1798] Still other types of information that may be available to a controller or processor of an energy storage system, include profiles of congestion on a power grid. Thus where information is received indicating difficulty (or expected future difficulty) in transmitting power through certain local areas of the grid, the processor or controller could instruct operation of the system accordingly.

[1799] For example, prior to expected periods of grid congestion information, a controller or processor could configure the system to store energy transmitted through particular grid nodes. Later, the system

could be instructed to operate in an expansion mode to output this power on the un-congested side of the node, allowing demand to be met.

[1800] Information received by the system controller or processor can take several forms. In some embodiments, the controller may receive information directly from the power grid, for example pursuant to the Smart Grid Interoperability Standards being developed by the National Institute for Standards and Technology (NIST). Incorporated by reference herein for all purposes, are the following documents: "NIST Framework and Roadmap for Smart Grid Interoperability Standards, Release 1.0*", dated January 2010; and "SmartGrid: Enabler of the New Energy Economy", Electricity Advisory Committee (December 2008). Information expected to be available over such a smart grid includes but is not limited to, current prices for power, expected future prices for power, readings of metered power consumption or output onto the power grid including historical peaks of consumption, indications of grid congestion, grid brown-outs, or grid black-outs.

[1801] The controller or processor may also configure the system based upon information other than as directly available over a smart power grid. For example, according to some embodiments the controller may receive other types of information over the internet that could influence system operation, including but not limited to as weather forecasts or longer-term price futures for power, or for commodities such as coal or oil that are used in the generation of power. Based upon such information, the controller or processor can also control operation or non-operation of the system, a mode of operation of the system, and/or balance of efficiency versus power consumed or output over a given time frame.

[1802] Another possible source of information is a meter indicating current and historical consumption of electricity off of the power grid by a particular user. For example, in certain embodiments a compressed gas energy storage and recovery system may be situated with an end user that is a large consumer of power, such as an industrial complex. Based upon information received from the electrical meter for that site, the controller or processor may configure the system to operate in a certain manner. One example of such information is historical peak load data for the end user.

[1803] The expected power demand of an end user is another example of information that may be used as a basis for controlling the energy storage and recovery system. For example, where an industrial facility expects to operate at enhanced or reduced capacity, that information could be utilized to determine system operation

[1804] In addition to information from external sources, the controller or processor also receives information internal to the system. Such internal information may include data from sensors configured to measure physical parameters within the system, including but not limited to valve state, temperature, pressure, volume, humidity, flow rates of liquids and gases, and speeds and torques of moveable elements within the system, such as fans, pumps, pistons, and shafts in communication with pistons. Additional examples of internal information which may be provided to the controller or processor include but are not limited to power drawn by the operation of motors such as pumps or fans.

[1805] In the broadest sense, the controller or processor may regulate the function of a system element to determine whether the system operates at all. An example of such an element is the valving between

the compressed gas storage unit and the compressor/expander. Closure of this valve would prevent operation of the system in compression mode to flow gas into the storage unit. Closure of this valve would also prevent operation of the system in expansion mode to flow gas from the storage unit for energy recovery. Thus where a pressure within a storage vessel indicates near-depletion of the compressed gas, the controller or processor may halt operation of the system until conditions allow replenishment of the gas supply under economically favorable conditions.

[1806] When the system is operating, the controller or processor may regulate a system element to determine the operational mode. An example of this kind of system element is a valve such as a three-way valve. The state of such a valve could be regulated by the controller to control flows of liquids or gases within the system in a manner corresponding to a particular mode of operation. Thus where a pressure within a storage vessel indicates near-depletion of the compressed gas, the controller or processor may instruct operation of the system in a compression mode to replenish the gas supply.

[1807] The controller or processor may also regulate an element of the system to determine a manner of operation within a particular operational mode. For example, the efficiency of operation of the compressor/expander may depend upon the volume increments of gas which are compressed or expanded.

[1808] Regulation of operation of system elements by the controller may be based upon considerations in addition to, or in lieu of, output electrical power or efficiency. For example, in some applications, the system may function in a temperature control role, providing deliverable quantities in the form of heating or cooling capacity. Under such circumstances, the controller may control system operating parameters such as the injection or non-introduction of liquid in one or more stages, the conditions of liquid introduction in one or more stages, compression or expansion ratios of one or more stages, and other parameters in order to determine the end temperature of gases and/or liquids output from the system that may be used for such temperature control.

[1809] Cost is another example of a such a consideration for system operation. For example, actuation of a valve by the controller to compress gas in smaller volume increments, may be dictated by the controller where conditions warrant compression but a price of energy available from the power grid is relatively high. In another example, operation of a valve by the controller such that gas is expanded in smaller volume increments, may be dictated by the controller where conditions warrant expansion but a price for energy supplied to the power grid is relatively low.

[1810] Available capacity for storage of compressed gas represents is another factor that may be considered in system operation. For example, valve timing could be regulated for compression in smaller volume increments where the storage unit is nearing its capacity. Under other circumstances, valve timing could be regulated for expansion in smaller volume increments where the storage unit is nearing depletion.

[1811] Still another possible consideration in operating system elements by controller, is coordination of activity between individual stages of a multi-stage apparatus. Thus in embodiments comprising multiple stages, certain system elements may be operated by the controller in order to allow effective

coordination between those stages.

[1812] One example is the timing of actuation of inlet or outlet valves to compression/expansion chambers, which may be regulated by a controller in order to allow effective operation across multiple stages. Timing of actuation of valves responsible for flows of liquid between stages, is another example of an operational parameter that may be regulated by a system controller.

[1813] Moreover, in some embodiments the individual stages of certain systems may be in fluid communication with each other through intermediary structures, including but not limited to pressure cells (e.g. in the embodiment of FIG. 4), heat exchangers (e.g. in the embodiment of FIG. 10), valves/valve networks (e.g. in the embodiment of FIGS. 58B-C), gas vessels, gas/liquid separators, and/or liquid reservoirs. In such embodiments, elements governing flows of materials into and/or out of such intermediary structures, may be regulated by a system controller in order to coordinate system operation. In some cases, it may be advantageous to control the relative phase of cyclically moving members in various stages to minimize pressure differentials seen by valves between those stages.

[1814] In certain embodiments, the transfer of thermal energy between the warmer atmospheric air and the expansion chamber (or heat exchanger in thermal communication therewith), may result in the formation of liquid water by condensation. Such liquid water could be made available for certain uses (for example drinking or irrigation), and hence may offer yet another type of material that is deliverable by a system. Liquid water may also be available from desalinization carried out utilizing energy derived from embodiments of systems in accordance with the present invention.

[1815] Thus in certain embodiments, a processor or controller could be configured to regulate system operation based upon the amount of liquid water that is to be delivered by the system. Examples of other forms of deliverables include but are not limited to electrical power, compressed gas flows, carbon dioxide, cooling capacity, and heating capacity.

[1816] 1. A method comprising:

flowing a compressed gas from a storage unit through a counterflow heat exchanger to an expansion chamber;

introducing a liquid spray to exchange heat with the gas expanding within the expansion chamber;

driving an electrical generator through a linkage actuated by movement of a member in the expansion chamber in response to expansion of the gas;

flowing electricity from the electrical generator to an end user of a power network, the end user located behind a meter with the generator and the expansion chamber;

separating liquid from the gas following expansion of the gas; and

flowing the separated liquid to cool the end user.

[1817] 2. The method of claim 1 wherein the spray comprises liquid water and the expanding gas comprises air.

[1818] 3. The method of claim 1 wherein the member comprises a piston and the linkage comprises a mechanical linkage.

[1819] 4. The method of claim 1 performed during a weekday between 7AM and 7PM.

[1820] 5. The method of claim 1 further comprising driving the generator with physical energy from a local power source that is also located behind the meter.

[1821] 6. The method of claim 5 wherein the local power source comprises a turbine and the physical energy comprises rotation of a shaft.

[1822] 7. The method of claim 1 further comprising placing the expanding gas into thermal communication with a local energy source.

[1823] 8. The method of claim 7 wherein the local energy source comprises a solar thermal apparatus.

[1824] 9. The method of claim 1 further comprising:

introducing a second liquid spray to exchange heat with additional gas being compressed within a compression chamber;

separating the second liquid from the compressed additional gas; and

flowing the compressed additional gas to the storage unit through the counterflow heat exchanger while the compressed gas is flowing from the storage unit to the expansion chamber.

[1825] 10. The method of claim 9 further comprising:

compressing the additional gas within the compression chamber by movement of a second member driven by a motor.

[1826] 11. The method of claim 10 wherein the motor is powered at least in part by a local power source also located behind the meter.

[1827] 12. The method of claim 11 wherein the motor is driven by electricity from the local power source comprising a photovoltaic array.

[1828] 13. The method of claim 11 wherein the motor is driven by physical energy from the local power source.

[1829] 14. The method of claim 1 wherein the compressed gas is flowed from the storage unit in response to an instruction issued by a controller.

[1830] 15. The method of claim 14 wherein the controller issues the instruction based upon information received from the power network.

[1831] 16. The method of claim 15 wherein the information comprises a demand response solicitation.

[1832] 17. The method of claim 15 wherein the information indicates an interruption in supply of electricity through the meter.

[1833] 18. The method of claim 14 wherein the controller issues the instruction based upon information received from the end user.

[1834] 19. The method of claim 18 wherein the information comprises a temperature of the end user.

[1835] 20. The method of claim 18 wherein the information comprises an increased demand for power by the end user.

[1836] 21. The method of claim 14 wherein the controller issues the instruction based upon information received from a local energy source also located behind the meter.

[1837] 22. The method of claim 18 wherein the information comprises an availability of power from the local energy source.

[1838] 23. An apparatus comprising:

a compression chamber having an outlet in selective fluid communication with a compressed gas storage unit through a first liquid separator and a counterflow heat exchanger;

a first liquid sprayer in liquid communication with the compression chamber;

a first moveable member disposed within the compression chamber and in physical communication with a motor;

an expansion chamber having an inlet in selective fluid communication with the compressed gas storage unit through the counterflow heat exchanger;

a second liquid sprayer in liquid communication with the expansion chamber;

a second liquid separator in fluid communication with an outlet of the expansion chamber;

a second moveable member disposed within the expansion chamber and in physical communication with a generator; and

a thermal linkage between the second liquid separator and an end user, the end user located behind a meter with the motor and with the generator.

[1839] 24. The apparatus of claim 23 wherein the generator comprises a motor/generator.

[1840] 25. The apparatus of claim 24 wherein the first moveable member and the second moveable member are in physical communication with the motor/generator through a common linkage.

[1841] 26. The apparatus of claim 23 wherein the first moveable member is in physical communication with the motor through a mechanical linkage, and the second moveable member is in physical communication with the generator through the mechanical linkage.

[1842] 27. The apparatus of claim 26 wherein the mechanical linkage comprises a rotating shaft.

[1843] 28. The apparatus of claim 26 wherein the mechanical linkage comprises a planetary gear mechanism.

[1844] 29. The apparatus of claim 28 wherein the planetary gear mechanism is further in mechanical communication with a local energy source located behind the meter.

[1845] 30. The apparatus of claim 23 wherein the motor is in electrical communication with a local energy source.

[1846] 31. The apparatus of claim 23 wherein the first moveable member comprises a solid piston, and the second moveable member comprises a second solid piston.

[1847] 32. The apparatus of claim 23 further comprising a controller in electronic communication with an information source and with the motor or a gas inlet flow valve to the expansion chamber.

[1848] 33. A system comprising:

a generator disposed behind a meter of a power supply network with an end user;

a compressed gas storage unit in selective fluidic communication with a chamber;

a member disposed within the chamber and configured to move in response to gas expanding within the chamber, the member in selective physical communication with the generator;

a gas outlet in fluid communication with the gas chamber through a liquid separator;

a sprayer selectively configured to inject liquid from the liquid separator into the gas chamber;

a fluidic linkage between the liquid separator and the sprayer; and

a thermal linkage between the liquid separator and the end user.

[1849] 34. The system of claim 33 wherein thermal linkage is configured to selectively place liquid from the liquid separator into thermal communication with a heat source.

[1850] 35. The system of claim 33 further comprising:

a motor disposed behind the meter of the power supply network with the end user, the motor in selective physical communication with the member to compress gas within the chamber;

a second liquid separator disposed between the chamber and the compressed gas storage unit, the sprayer selectively configured to inject liquid from the second liquid separator into the gas chamber; and

a second thermal linkage between the second liquid separator and the end user.

[1851] 36. The system of claim 35 wherein the second thermal linkage is configured to selectively place liquid from the second liquid separator into thermal communication with a heat sink.

[1852] 37. The system of claim 35 further comprising:

a local energy source disposed behind the meter of the power supply network with the end user; and

a linkage comprising,

a physical linkage between the local energy source and the motor,

an electrical linkage between the local energy source and the motor, or

a thermal linkage between the local energy source and liquid from the liquid separator sprayed by the sprayer.

[1853] 38. The system of claim 37 wherein the member, the motor, the generator, and the linkage are in physical communication with a common gearing.

[1854] 39. The system of claim 35 wherein the motor and the generator comprise a motor/generator.

[1855] While the embodiments described above have related to placement of a compressed gas system within the generation or consumption layers of a power supply network, the present invention is not limited to such roles. Embodiments of compressed gas systems could be positioned within the transmission or distribution layers of the network and remain within the scope of the present invention.

[1856] Accordingly, Figure 66 shows an embodiment of a compressed gas energy storage system 6690 that is positioned within the transmission layer. System 6690 is in communication with transmission substation 6665 through one or more linkages 6661. In certain embodiments, the energy storage system may be in communication with a transformer of the transmission layer through one or more electrical linkages.

[1857] The location of system 6690 within the transmission layer of the power supply network, allows it to perform a number of possible roles. For example, the cost of adding or even upgrading assets of the distribution layer and particularly the transmission layer of the power network, may be relatively high owing to regulatory, environmental, and safety concerns.

[1858] Thus, certain embodiments of energy storage systems according to the present invention may be integrated within the transmission layer to defer or even avoid upgrades on transmission lines. For example, an energy storage system may be situated proximate to transmission substations of transmission lines that experience high use at peak periods. In such a role, the energy storage system may allow shifting of the time of transmission of power away from such peak times.

[1859] In certain embodiments, the compressed gas energy storage systems utilized in the transmission layer (or in the distribution layer as described below), could be physically portable. For example, such systems could be positioned on a flatbed truck, tractor trailer, or container, and moved proximate to the appropriate expected points of congestion within the transmission layer or distribution layer.

[1860] Owing to the large amounts of power that are carried through transmission assets, such an embodiment of a power storage system may need to have a high capacity for storing power. Moreover, where the storage system is situated to relieve congestion on a daily basis, its capacity must be able to meet demand over multiple hours, and be capable of renewal over the period of a day.

[1861] While congestion on the transmission layer may be characterized over relatively long time frames on the order of hours or minutes, a different form of transmission congestion can arise on much shorter time frames. For example, certain operational limits may be imposed on transmission assets based upon equipment reliability concerns under contingency factors.

[1862] Accordingly, short term transmission capacity may be constrained by such limits, apart from the actual capacity of the transmission lines. Thus another potential role for an energy storage and recovery systems incorporated within the transmission layer, is to introduce power on short time frames and thereby effectively relax limits in transmission reliability. Such an energy storage system could be configured to inject power at strategic locations within the transmission network, on short notice, for a period of from about one second to about 15 minutes or more.

[1863] Still another possible role for energy storage and recovery systems incorporated within the transmission layer, is to support renewable sources of variable energy that offer limited transmission access. For example, high winds may be found in remote geographic regions served only by existing high voltage transmission lines of relatively low capacity.

[1864] Incorporation of an embodiment of an energy storage and recovery system according to the present invention, however, could allow these existing transmission lines to carry the power generated by such a generation asset. For example, a storage system could operate to store some or all of the power output by the generation asset, allowing transmission to be deferred until existing capacity is available in the transmission layer.

[1865] Such deferral of transmission could prevent wasting of power that would otherwise not be able to be output to the network. Moreover, deferral of transmission allowed by storage systems could allow renewable generation assets to be placed into service before a corresponding transmission link is fully upgraded to handle their maximum output capacity.

[1866] Still another possible role for an energy storage and recovery system, is to provide voltage support for transmission lines. Specifically, voltage support involves injecting or absorbing power onto a network in order to maintain voltage within certain tolerance limits.

[1867] For example, reactive power (VAR) is a form of power on the network which can arise from several sources, the most common of which is the presence of one or more inductive generators. Reactive power is not available for direct consumption by end users, but nevertheless must be provided by the operator of the power network in order to maintain the stability of voltages and power within prescribed ranges.

[1868] Providing voltage control to regulate reactive power generally involves the injection of power on subsecond response times. Hence, voltage control has conventionally been provided by devices such as capacitor banks, static VAR compensators (SVCs), or synchronous condensors. These devices function to provide capacitive resistance, injecting reactive power to boost a local voltage level.

[1869] Accordingly, certain embodiments energy storage systems according to the present invention may be incorporated within the transmission layer to provide reactive power onto the network at strategic locations, thereby freeing up generation assets to provide active power that may ultimately be consumed by end users. As such voltage support typically requires power to be supplied in response times of less than one second, embodiments of storage systems according to the present invention may be coupled with capacitor banks or other fast-responding structures capable of providing the power over the required response times.

[1870] Embodiments of energy storage and recovery systems according to the present invention may also be incorporated within the distribution layer of a power network. In one role, such an energy storage and recovery system could function to reduce peak load on a substation, and to perform back-up functions.

[1871] As shown above in Figure 66, distribution substations are strategically located within the distribution layer to route power to end users. As populations grow, these substations experience overall larger loads, and typically experience an even greater increase in peak load.

[1872] The design of a distribution substation is constrained by the requirement that it meet peak demand, and thus load growth may dictate upgrade or replacement of a substation more frequently than the general load would otherwise require. Accordingly, in certain embodiments a compressed gas energy storage and recovery system may be positioned within a distribution layer to reduce such peak loads, thereby deferring the need to perform a costly upgrade or replacement of the distribution substation.

[1873] Accordingly, Figure 66 shows an embodiments of a compressed gas energy storage system that is positioned within the distribution layer. In particular, compressed gas system 6680a is in communication with substation 6630a of the primary distribution layer through one or more linkages 6667. Compressed gas system 6680b is in communication with substation 6630b of the secondary distribution layer through one or more linkages 6669. In certain embodiments the compressed gas system may be in communication with a transformer of the distribution layer through an electrical

linkage. In embodiments where the generator is configured to output voltage matching that of the distribution layer, the system may be in direct electrical communication with the distribution layer.

[1874] For example, an embodiment of a storage system that is located within the distribution layer, could be configured to store power at off-peak times. At peak times, the storage system would inject power onto the distribution layer. Such injection of power at strategic points, could reduce the peak load experienced by one or more distribution substations. As the historical peak load of the substation will not have increased, the need to upgrade the distribution substation may be deferred until a future time.

[1875] The reduction in peak load offered by embodiments of storage systems according to the present invention, may result in still other cost savings. For example, reduction in peak load may result in a corresponding reduction in the strain on substation elements, thereby improving their reliability over the long term.

[1876] The role played by storage systems in reducing peak levels on substations of the distribution layer, may determine the properties of those storage systems. For example, a storage system that is positioned to back up a primary substation, may be required to output relatively high voltages commensurate with its location in the distribution network.

[1877] In addition, as the storage system needs only to reduce a peak load, rather than shoulder the entire load, a storage capacity of such a system may be smaller as compared with other roles. The storage capacity of the system may also be dictated by the relative infrequency of its operation corresponding to times of particularly high demand.

[1878] Alternatively or in addition to positioning within the primary distribution layer, embodiments of compressed gas storage systems according to the present invention may be located within the secondary distribution layer. In such a role, the storage system would provide similar benefits of deferring upgrade on equipment, and reducing the wear on the equipment.

[1879] Moreover, positioning energy storage systems in the secondary distribution layer could provide other potential benefits. For example, such a storage system could provide a source of energy backup to consumers in the even of a brown out, rolling black out, or total blackout. The decentralized nature of such a community energy supply could also enhance the security of the power network, avoiding a complete loss of power resulting from failure of a few nodes of the network.

[1880] Positioning of energy storage within the distribution layer could also facilitate "islanding", wherein following the failure of the larger network, subsections of the grid could be independently powered up as "islands", and then ultimately linked together as the larger grid is re-established. Such an "islanding" technique can reduce the wear on the grid, and lessen the amount of time that users are completely without electricity.

[1881] An energy storage system incorporated into secondary distribution could also function to balance output onto the power network from multiple distributed generation (DG) apparatuses that are located at end users, examples of which include rooftop solar (PV and/or thermal solar) or wind. In such a role, the cost burden of an energy storage system could be distributed over a community of users rather than a single user.

[1882] Providing an energy storage and recovery system within the secondary distribution layer as part of a community energy supply, could also improve efficiency by reducing distribution losses. This is because the storage is located closer to the load, reducing the distance traveled, and hence losses incurred.

[1883] Voltage support represents still another potential role for energy storage systems according to the present invention that are located within the distribution layer. Such voltage support functions are discussed above in connection with the transmission layer.

[1884] Some embodiments of compressed gas energy storage and recovery systems may provide voltage support that is particularly relevant to the distribution layer. For example, a compressed gas energy storage system may serve to boost voltage levels at points along secondary distribution layers that extend over a wide area to serve rural geographic regions.

[1885] Embodiments of compressed gas energy storage and recovery systems may be suited for other localized roles. For example, certain facilities that are large consumers of electricity, may extend over a wide geographic area and may not use a common meter (thereby distinguishing them from a single end user, as described above). Examples of such facilities can include transportation hubs such as airports, ports, and railway lines.

[1886] Providing an energy storage system in the distribution layer proximate to such facilities, could serve to reduce their demand at peak times. Moreover, the use of an energy storage system in such a distribution layer could also be beneficial for security, ensure the integrity of the power supplied to these key facilities in the event of a natural disaster or terrorist attack.

[1887] As indicated in detail above, various embodiments of systems according to the present invention relate to compressed gas energy storage systems, whose operation is controlled based upon information received by a controller or processor. In certain embodiments information received by the controller can serve as a basis for deciding to operate, or halt operation, of the system. In some embodiments, the information can be utilized to determine system operation in a compression mode or in an expansion mode. In some embodiments, information received by the controller may be further utilized to determine efficiency of system operation, versus power consumed or output during the storage or recovery of energy. Information received by the controller may include but is not limited to, a current price of energy on a power grid, an expected future price of energy on a power grid, contractual terms governing purchase or sale of power to a power grid, a level of supply of energy from other sources to a power grid, meteorological information, and/or metering history of the system or a co-situated facility.

[1888] 1. A method comprising:

causing a controller of a compressed gas energy storage and recovery system to receive information from an external source; and

in response to receipt of the information, causing the controller to regulate a system element to determine at least one system characteristic selected from,

operation or non-operation of the system,

operation of the system in a compression mode or in an expansion mode,

an efficiency of energy storage by gas compression or an efficiency of energy recovery by gas expansion,

an amount of power consumed by the system, or

an amount of a deliverable material produced by the system.

[1889] 2. The method of claim 1 wherein the external information comprises a current price or a future price for power on a power grid.

[1890] 3. The method of claim 2 wherein the current price for power or the future price for power is received from the power grid.

[1891] 4. The method of claim 1 wherein the external information comprises a contract term governing purchase or sale of power to a power grid.

[1892] 5. The method of claim 1 wherein the element comprises a valve actuable to flow gas through the system in the compression mode or in the expansion mode.

[1893] 6. The method of claim 5 wherein the valve comprises a three-way valve configured to flow gas through the system in a first path in the compression mode, or in a second path in the expansion mode.

[1894] 7. The method of claim 1 wherein:

the element comprises a valve actuable to admit an incremental volume of gas for compression or expansion within a chamber; and

a timing of actuation of the valve is regulated to control a magnitude of the incremental volume.

[1895] 8. The method of claim 1 wherein:

the element comprises a valve actuable to exhaust from a chamber, a volume of gas subjected to compression or expansion within the chamber; and

a timing of actuation of the valve is regulated to control a pressure remaining within the chamber at a time of exhaust.

[1896] 9. The method of claim 1 wherein the element is regulated to change an efficiency of gas compression or expansion by the system.

[1897] 10. The method of claim 1 wherein the element is regulated to change an amount of power consumed by the system to compress gas.

[1898] 11. The method of claim 1 wherein the element is regulated to change an amount of power output by the system upon expansion of compressed gas.

[1899] 12. The method of claim 1 wherein the deliverable material comprises electrical power, water, or compressed carbon dioxide gas.

[1900] 13. The method of claim 1 wherein the controller regulates the element based upon additional internal information received from inside the system.

[1901] 14. The method of claim 13 wherein the additional internal information comprises a pressure in a compressed gas storage unit.

[1902] 15. The method of claim 1 wherein the energy storage and recovery system comprises a plurality of stages, and the element is regulated to coordinate operation between two of the plurality of stages.

[1903] 16. The method of claim 1 wherein the energy storage and recovery system comprises a plurality of stages, and the element is regulated to determine a number of stages that are used.

[1904] 17. The method of claim 1 wherein:

the energy storage and recovery system is in communication with a power grid; and

the information comprises,

a demand response from an operator of the power grid,

a historical peak of power consumed by the system from the grid,

an indication of a load on the power grid,

an indication of a reduced power available from the power grid, or

a indication of congestion on the power grid.

[1905] 18. The method of claim 1 wherein:

the energy storage and recovery system is in communication with a power grid through a meter shared with a co-situated facility; and

the information comprises a historical peak of power consumed from the grid at the meter.

[1906] 19. The method of claim 1 wherein:

the energy storage and recovery system is co-situated with an alternative energy source having a variable output; and

the information comprises an output of the alternative energy source.

[1907] 20. The method of claim 1 wherein the information comprises meteorological information.

[1908] 21. An apparatus comprising:

a controller in electronic communication with an element of a compressed gas energy storage and recovery system, the controller also in electronic communication with an external information source; and

a computer-readable storage medium having stored thereon, code configured to instruct the controller to regulate the element in response to information received from the external information source, the code configured to regulate the element to determine at least one system characteristic selected from,

operation or non-operation of the system,

operation of the system in an compression mode or in an expansion mode,

an efficiency of energy storage by gas compression or an efficiency of energy recovery by gas expansion,

an amount of power consumed by the system, or

an amount of a deliverable material produced by the system.

[1909] 22. The apparatus of claim 21 wherein the element comprises a valve actuable to flow gas through the system in the compression mode or in the expansion mode.

[1910] 23. The apparatus of claim 22 wherein the valve comprises a three-way valve configured to flow gas through the system in a first path in the compression mode, or in a second path in the expansion mode.

[1911] 24. The apparatus of claim 23 wherein:

the element comprises a valve actuable to admit an incremental volume of gas for compression or expansion within a chamber; and

a timing of actuation of the valve is regulated to control a magnitude of the incremental volume.

[1912] 25. The apparatus of claim 21 wherein the code is configured to instruct the controller to regulate the element to change efficiency of gas compression or expansion by the system.

[1913] 26. The apparatus of claim 21 wherein the code is configured to instruct the controller to regulate the element to change an amount of power consumed by the system to compress gas.

[1914] 27. The apparatus of claim 21 wherein the code is configured to instruct the controller to regulate the element to change an amount of power output by the system upon expansion of compressed gas.

[1915] 28. The apparatus of claim 21 wherein the code is configured to instruct the controller to change an amount of the deliverable material comprising electrical power, water, or compressed carbon dioxide gas.

[1916] 29. The apparatus of claim 21 wherein the controller is further configured to regulate the element based upon additional internal information received from inside the system.

[1917] 30. The apparatus of claim 29 wherein the additional internal information comprises a pressure in a compressed gas storage unit.

[1918] 31. The apparatus of claim 21 wherein the energy storage and recovery system comprises a plurality of stages, and the element is regulated to coordinate operation between two of the plurality of stages.

[1919] 32. The apparatus of claim 21 wherein the energy storage and recovery system comprises a plurality of stages, and the element is regulated to determine a number of stages that are used.

[1920] 33. The apparatus of claim 21 wherein the code is configured to instruct the controller to regulate the element based upon receipt of the information comprising a current price or a future price for power on a power grid.

[1921] 34. The apparatus of claim 21 wherein the controller is configured to receive the information from a power grid.

[1922] 35. The apparatus of claim 21 wherein the code is configured to instruct the controller to regulate the element based upon receipt of a contract term governing sale or purchase of power from a power grid.

[1923] 36. The apparatus of claim 21 wherein:

the energy storage and recovery system is in communication with a power grid; and

the information comprises,

a demand response from an operator of the power grid,

a historical peak of power consumed from the grid by the system,

an indication of a load on the power grid,

an indication of a reduced power available from the power grid, or

a indication of congestion on the power grid.

[1924] 37. The apparatus of claim 21 wherein:

the energy storage and recovery system is in communication with a power grid through a meter shared with a co-situated facility; and

the information comprises a historical peak of power consumed from the grid at the meter.

[1925] 38. The apparatus of claim 21 wherein:

the energy storage and recovery system is co-situated with an alternative energy source having variable output; and

the information comprises an output of the alternative energy source.

[1926] 39. The apparatus of claim 38 wherein the information comprises meteorological information.

[1927] Embodiments of the present invention relate to systems and methods employing aerosol-cycle cooling.

[1928] Vapor-compression air conditioners are simple, efficient, inexpensive and effective. Unfortunately, the use of standard refrigerants may release potent greenhouse gases. Embodiments according to the present invention may match or exceed the efficiency of vapor compression systems, while eliminating GHG emissions using a novel thermodynamic cycle called the aerosol refrigeration cycle.

[1929] Embodiments according to the present invention may utilize a cycle similar in some respects to a Stirling cycle, which uses isothermal compression and expansion of the gas used to transfer heat. According to some approaches, a fine, dense liquid spray may be injected directly into the compressing and expanding gas. This spray, with its very high heat capacity and interfacial surface area, may rapidly capture and transfer heat between the working gas and hot and cold atmospheric heat exchangers. One choice for the liquid-gas aerosol is water and air (helium is another option for the gas), the use of which will cause no GHG emissions.

[1930] Gas refrigeration cycles have been traditionally used in aircraft because of their light weight in comparison with traditional vapor compression devices. (See Nag, P., "Engineering Thermodynamics," Tata-McGraw Hill, 2nd Ed., 1995). The gas refrigeration cycles have a low COP because of the adiabatic compression and expansion carried out in these systems and therefore unsuitable in traditional refrigeration units.

[1931] A technology gaining increasing attention is the Stirling cycle coolers. Currently, small capacity Stirling cycle refrigeration systems are available commercially. Possible disadvantages of these systems is that it is difficult to design for large changes in refrigeration load. Also, a Stirling refrigerator may take a long time to reach the desired temperature from startup, and the specific power is low which

results in large sizes of the system. (See Organ, A, J., "Regenerator and the Stirling Engine," Mechanical Engineering Publications, UK.)

[1932] In theory, an air conditioner running the ideal Stirling cycle could achieve the goals set out in the FOA (Area of Interest 1a). However, in practice, no 'Stirling' air conditioner built to date even reasonably approximates the ideal Stirling cycle, which demands extremely efficient and rapid heat transfer to and from the gas during the expansion and compression processes. Failure to deliver this renders the compression and expansion processes of existing Stirling cycle systems nearly adiabatic, resulting in severe thermodynamic losses and limited power density.

[1933] Accordingly, embodiments of the present invention may utilize an aerosol refrigeration cycle. Such embodiments may allow the ability to compress and expand gas nearly isothermally (that is, with only a small temperature change). This may be achieved by entraining a fine, dense, high-heat-capacity liquid spray into the compressing and expanding gas. The heat capacity of the spray so dominates that of the gas, that the otherwise significant temperature rise of compression (and drop during expansion) can be reduced to only a few degrees.

[1934] Accordingly, a highly efficient air conditioner running such an aerosol refrigeration cycle may be created.

[1935] Figure 73 represents a simplified view according to certain embodiments. The system comprises a motor (7301), reciprocating piston compressor (7302) and expander (7303), hot and cold side air-cooled liquid heat exchangers (7304 and 7305), two pumps (7306 and 7307), two gas-liquid separators (7308 and 7309), check valves (7310 and 7311) and solenoid valves (7312 through 7315), and a counter-flow heat exchanger (7316).

[1936] The details of an embodiment of an aerosol-cycle are as follows:

1. Cool gas (at ~55^0 F) expands in a reciprocating expander (7303), drawing heat from a liquid spray entrained within. Both leave the expander at ~45^0 F. The work extracted is reinvested into the compressor (7302) and the pumps (7306 and 7307).
2. The liquid in the cool aerosol is separated from the gas (via separator 7309), collected into a liquid stream, and routed to a heat exchanger (7305), cooling the intake airstream to ~55^0 F, and then cycled back to be sprayed into expanding gas once more.
3. The cool liquid-free gas is passed through a counter-flow heat exchanger (7316), countering a flow of warm liquid-free gas. The cool gas is heated at constant pressure to slightly above ambient temperature (~105^0 F).
4. Warm liquid is sprayed into the warm gas, and is then compressed (in compressor 7302). The compressor is driven in part by the expander, and in part by an electric motor (7301). The heat of compression is drawn into the aerosol. Both leave the compressor at ~115^0 F.
5. Warm liquid is separated from the gas (via separator 7308), collected into a stream, and routed to the heat exchanger (7304), which cools by dumping the heat to the ambient environment, and is then recycled to be sprayed into the compressing gas once again.

6. The warm liquid-free gas is passed through the counter-flow heat exchanger (7316), countering the flow of cool liquid-free gas. The warm gas is cooled at constant pressure to slightly below air conditioner exhaust temperature (to ~45°F). The gas flows into the expander, is entrained with cool liquid, and the cycle continues.

[1937] As in conventional refrigeration cycles, the compressor in our design compresses gas (air or helium), heating it, and the heat is rejected to the ambient air via a heat exchanger. In certain embodiments of a cycle according to the present invention, however, there may not be a bulk phase change; the temperature change is due almost entirely to the transfer of sensible heat. Furthermore, the heat of compression is absorbed almost entirely by droplets of water that are sprayed into the compression cylinder. The heated droplets are exhausted from the cylinder at the end of the compression stroke, and are then separated from the compressed air. It is the heated liquid that is pumped through the heat exchanger in order to reject the heat.

[1938] The expansion side of the cycle is the mirror image of the compression side. Note, though, that the expansion of the gas drives a piston, which, in turn, drives the same shaft that drives the compressor. This improves efficiency as compared with a standard throttle valve in which the energy of the free expansion of the gas is lost.

[1939] A reciprocating piston mechanism, similar to those found in internal combustion engines, may permit spraying directly into the working compression/expansion chamber. Turbine-based compressors may lack the right geometry to permit uniform mixing of the liquid droplets with gas.

[1940] For the target specifications (a 75°F building temperature with a relative humidity of 60%, a 55°F exhaust temperature at a relative humidity of 100%, and a 95°F ambient temperature), a coefficient of performance (COP) exceeding 4 can be achieved at reasonable cost if a number of parasitic losses can be controlled. The efficiency of the compressor and expander mechanisms may exceed 79% roundtrip if the electrical motor and drive efficiency together is 95%. This level of efficiency may be achieved if high-quality mechanical components are used and, if the temperature change during compression, expansion, and across the heat exchangers can be kept to about 10° F.

[1941] By contrast, conventional adiabatic compressors and expanders may have a ΔT in excess of 100 degrees under similar operating conditions. A near-isothermal technology according to embodiments of the present invention may achieve the desired cooling efficiency.

[1942] Embodiments according to the present invention may utilize a liquid spray system. Specifically, the ability to maintain a fixed, small temperature rise during the compression stroke (and temperature drop during the expansion stroke) may help to deliver system efficiency. A liquid spray may absorb heat during compression and to add heat during expansion. Water is the best choice of liquid because of its high heat capacity. To achieve the heat transfer rate required, the spray may be very dense. That is, the volume fraction of water may be at least 0.25%. Additionally, the gas-water aerosol may be uniformly distributed in the compression and expansion chambers so as to avoid hot or cold spots.

[1943] Nozzles and spray manifolds can be designed, and their performance simulated using computational fluid dynamics (CFD) tools, and then fabricated and tested the nozzles using laser imaging and particle imaging velocimetry (PIV).

[1944] Embodiments of the spray system inject water directly into the compression and expansion cylinders via the cylinder head. A challenge is to miniaturize the spray system sufficiently to fit in the head of a cylinder with about one liter displacement.

[1945] Embodiments of the present invention may incorporate compressor and expander mechanisms. In principle, various compressor or expander technologies could be used for this application.

[1946] In practice, the requirement to inject a dense water spray during operation may determine this aspect. A reciprocating piston mechanism may be used. Such an approach may offer the best geometry, the most flexibility, and more than adequate speed and mechanical efficiency.

[1947] A reciprocating mechanism may be designed by modifying an off-the-shelf compressor. Custom cylinder heads may accommodate the spray system. The mechanism may be made water-tolerant, which may involve the use of specialized materials and coatings throughout. Examples include nickel-polymer and DLC (diamond-like carbon) coatings for the exposed surfaces, graphite-filled PTFE piston rings, brass nozzles, and stainless steel valve components.

[1948] Embodiments according to the present invention may use a counter-flow heat exchanger. The performance of the counter-flow heat exchanger may determine delivery of the desired system efficiency. A low ΔT (about 10° F) between the inflow and outflow airstreams at each end of the heat exchanger may be used, with an ability to tolerate an internal pressure of 120 psi or higher.

[1949] Secondly, moisture condensation may occur in the counter-flow heat exchanger when the hot gas stream is cooled. When the hot gas leaves the separator prior to the counter-flow heat exchanger, it may be saturated with moisture. The pressure drop through the heat exchanger may be low, so some of the moisture in the air may condense inside the heat exchanger. As the water remains at high pressure in a closed loop in this system, the condensate can be recovered and re-injected into the system.

[1950] Modeling the counter-flow heat exchanger involves psychrometric property values at high pressures. Existing software provides thermodynamic properties of moist air up to 27 bar pressure. Psychrometric algorithms will be used to model the moist air passing through the chilled water coil where condensation also occurs.

[1951] If the working gas used is air, it can be stored in a suitable pressure vessel following compression rather than immediately circulated to the expander. This allows the system to be charged up overnight, when the electricity used to power it is inexpensive. The cooling can be delivered (without any further electricity being consumed) at a later time – typically the next day when air conditioning is needed and electricity would be more expensive.

[1952] Embodiments according to the present invention may have an "open" design. That is, air would be drawn into the compressor from the environments and exhausted to the environment from the expander.

[1953] Embodiments according to the present invention may develop an air conditioning system that can deliver a COP of 4 both economically and without the use of greenhouse gases. Certain components (e.g. the near-isothermal compressor and expander and the counter-flow heat exchanger) can be built and tested individually, (after the appropriate analysis and simulation is complete) and then integrated into the system.

[1954] Thermodynamic Modeling may proceed as follows. An application of this device is as a high performance air conditioning system. Latent and sensible cooling may occur at the chilled water coil (cold side heat exchanger). Therefore accurate performance modeling can include appropriate psychrometric processes on the air side.

[1955] Although performance will be measured at one set of design parameters, operation at off design conditions may be important to estimate seasonal performance. Parametric studies can be performed using thermodynamic/psychrometric models to simulate system performance at various indoor and outdoor environmental conditions.

[1956] Other possible applications for various embodiments include use of the system to assist with domestic hot water heating, and/or use as a heat pump, that can be investigated using steady state thermodynamic modeling. These alternate applications may employ additional or different heat exchangers than specified in the original design. Thermodynamic simulations can also be conducted to determine the effect on system performance if some or all the heat from the hot side is used to heat domestic hot water and if the system is used as an air to air heat pump.

[1957] Component modeling may be conducted as follows. Two issues may prevent the use of off the shelf heat exchangers in this application. The first is the use of high pressures in all the main heat exchangers. Tube wall thickness may need to be increased above values normally used to provide adequate safety for the high pressures encountered.

[1958] Secondly, moisture condensation will occur in the counter-flow heat exchanger when the hot gas stream is cooled. When the hot gas leaves the separator prior to the counter-flow heat exchanger, it will be nearly saturated with moisture. The pressure drop through the heat exchanger is expected to be low so some of the moisture in the air will condense inside the heat exchanger. As all the water remains at high pressure in a closed loop in this system, the condensate needs to be recovered and re-injected into the system.

[1959] Modeling the counter-flow heat exchanger requires psychrometric property values at high pressures. Existing software provides thermodynamic properties of moist air up to 27 bar pressure. Conventional psychrometric algorithms will be used to model the moist air passing through the chilled water coil where condensation also occurs. Conventional heat transfer and fluid mechanics principles and models are expected to apply without modification to both the moist air and water inside and in the moist air external to the system.

[1960] Components may be designed as follows. The design requirements for the heat exchangers can be determined from the results of the component modeling. The design may comprise a set of specifications for each of the three main heat exchangers, the counter-flow heat exchanger between the

two gas streams and the hot water and chilled water coils. Specifications can include heat transfer duty, flow rates, pressure ratings and pressure drops, maximum dimensions and weight. Compact design requirements may impose additional challenges.

[1961] Data collection and system design may be as follows. Appropriate sensors capable of the high pressure environment may be used to text the system, together with software and hardware for data acquisition.

[1962] Testing facilities may include two environmental chambers capable of maintaining stable air temperature and humidity conditions for the air that approaches both the hot and cold side heat exchangers in the system. The majority of the data will be collected on the cold side to determine the cooling load on the system. Heat transfer rates on both the air and water sides of the heat exchangers may be obtained. It is possible that water side measurements will be more accurate than those on the moist air side. Accurate power measurements will also be obtained to determine the system C.O.P.

[1963] Facilities for testing the design of the heat exchanger may be as follows. Two separate measurement systems are possible. One is for testing the counterflow heat exchanger.

[1964] In this facility moist air may be provided at the conditions expected to leave the gas/liquid separators on both the high and low temperature sides of the compressor/expander. Temperatures, pressures, humidity values and flow rates of the moist air flowing in and out of both sides of the heat exchanger may be measured. In addition the temperature and flow rate of the condensate may also be monitored.

[1965] Hot and chilled water coils may be tested in a facility that is capable of providing known air flow rates and can heat and humidify the air in the tunnel. The facility may be capable of testing the chilled water coils, where the air needs to be heated and humidified. Using building chilled water, cooling capability for testing the hot water coils may be designed when heat needs to be removed from the air stream. The air flow rates in these tests lower than required in the ASHRAE filter tests normally conducted in this facility. Therefore, a new air flow nozzle to meter the flow with lower range than the existing nozzle may be specified for accurate flow measurements. Instrumentation will be installed in both facilities and connected to an automatic data acquisition system. System performance verification tests may be conducted.

[1966] Analysis of the thermodynamics of novel cycles using near-isothermal compression and expansion and developing the underlying technology for this system, has been performed. This work arose from efforts to use similar technology to create an inexpensive, efficient energy storage system.

[1967] Spray nozzles and control systems that will introduce the liquid into the compression and expansion chambers at mass flow and droplet size, have been studied. These spray systems may be characterized using particle velocity imaging and CFD analysis.

[1968] FIG. 29 shows the velocity field for a hollow-cone nozzle that provides very uniform droplet distribution, appropriate for a high compression ratio. FIG. 30 is a CFD simulation of a fan nozzle, which provides a high mass flow, and may be easily arranged in manifolds to entrain the spray uniformly in the working gas.

[1969] FIG. 74 is a graph of mass weighted average temperature over two compression cycles with a compression ratio of 32. For comparison, the average temperature without spray is plotted. FIG. 74A is a false color representation of temperature in Kelvin at top dead center from a CFD simulation of gas compression at an extremely high compression ratio of 32. The quantity of water injected per stroke is about 0.6% of the volume.

[1970] R&D progression:

[1971] One reason that air conditioning using compressed gas has not been aggressively pursued in the past is that the thermal efficiency of the conventional (adiabatic) compression / expansion cycle is very low. For example, the round-trip efficiency of adiabatically compressing air from 1 atm to 200 atm and expanding it back to 1 atm is about 30%. Additionally, the change in temperature of the gas –as it is compressed/expands- limits the compression ratio to about 3.5, requiring multiple stages for the compression or expansion cycle, thereby reducing the efficiency even further.

[1972] To demonstrate the performance of such system, we are planning to compress air to atm while the temperature variation ΔT is kept below 20°C by spraying water droplets into the compressor. Our criterion for pressure is set to achieve an energy density of about *25* Wh/liter, which is high enough to make the system practical for use. The criterion for ΔT is set by the target round-trip thermodynamic efficiency of 90%, as discussed below:

[1973] Thermodynamic efficiency of the system:

[1974] Fig. 75 shows an embodiment of a thermodynamic cycle used for an energy storage system. During the process 1-2' the air is compressed to a high pressure of around 200 atm with an isothermal compressor which uses proprietary water spray technology being developed by LSE. Existing experimental data suggests that a compression ratio as high as 30 can be used in isothermal compression (See Coney et. al., "Development of a reciprocating compressor using water injection to achieve quasi-isothermal compression", Int. Compressor Eng. Conf., July 16–19, 2002), whereas a traditional adiabatic compressor can only achieve compression ratios of about 3.5. Thanks to the large isothermal compression ratios, high pressures (in excess of 200 atm) can be achieved using only two stages. This compressed energy is stored in a tank for either few minutes or even hours together. In large multi-megawatt power systems it may be likely that this energy is stored for several hours. During this period the air stored in the tank will lose some heat and return back to atmospheric temperature at a constant volume. When the stored energy is needed, the compressed air is expanded back along process 2-3 which also uses water spray technology to expand air under isothermal conditions.

[1975] Thermodynamic Analysis:

[1976] Basic thermodynamic calculations showing the feasibility of this system will be presented in this section. The amount of water injected into the system should be enough to keep temperature more or less constant. The energy transfer can be given by the relation $TdS = dH - VdP$. For water droplets of size of few hundred microns, the heat transfer rates are very fast resulting in fast thermal equilibrium being achieved by air and water droplets. The discussion in the following sections on proprietary spray

technology being developed clearly shows that small droplet size is easily possible by applying relatively small percentage of the total energy. Therefore it is assumed that the air and water are at same temperature. Therefore we have $dH = C_{pa}dT + m_w C_{pw}dT$, where m_w is the mass of water per unit mass of air. C_{pa} and C_{pw} are the thermal heat capacities of air and water respectively. We can now write $\left(C_{pa} + m_w C_{pw}\right)dT/T = R\,dP/P$. Integrating the above equation results in the following relationship $\frac{T_2}{T_1} = \left(\frac{P_2}{P_1}\right)^{\frac{R}{\left(C_{pa}+m_w C_{pw}\right)}} = \left(\frac{P_2}{P_1}\right)^{\frac{n-1}{n}}$, where $n = \left(1 - R/\left(C_{pa} + m_w C_{pw}\right)\right)^{-1}$. The work done during the compression process can be shown to be $W = \int dH = \int V dp = {}^{n}/_{n-1} RT\left[\left(P_2/P_1\right)^{\frac{n-1}{n}} - 1\right]$. The efficiency of energy storage system can be defined as

$$\eta = \frac{W_{out}}{W_{in}} = RT\left[\left(P_2/P_1\right)^{\frac{n-1}{n}} - 1\right] \Big/ \left(RT\left[1 - \left(P_3/P_2\right)^{\frac{n-1}{n}}\right]\right).$$

[1977] The plot of efficiency versus the water volume fraction is shown in Fig. 76A. Fig.76A shows ideal thermodynamic efficiency of round-trip energy storage cycle (at 20 Hz with compression ratio is 14.1) when different drop sizes are sprayed into the cylinder during compression.

[1978] It is shown that to achieve an ideal round-trip thermodynamic efficiency of 90%, it is required to spray maximum of 2.5% by volume water into the compressor in the form of 100μm drops. As shown in Fig 76A, spraying this amount of water constrains the temperature increase/decrease during compression/expansion to be about ΔT = 20 *K*.

[1979] Fig. 76B shows temperature of the exhaust air with increase in water volume fraction. Fig. 76B shows air temperature increase (ΔT) during compression at 20*Hz* with compression ratio is 14.1, as a function of initial volume fraction of water @1atm.

[1980] At a water volume fraction of 2.5% when 100μm drops are sprayed, the increase in exhaust air temperature is less than 20 degrees. In comparison, when no water is used the temperature increase is in excess of 1000K.

[1981] **<u>Time Scale for Heat Exchange between air and water droplets</u>**

[1982] For the current compressor system it can be assumed that $\mathrm{Pr} \sim 0.7$ and based on the injected velocities calculated theoretically and experimentally, it can be found that $\mathrm{Re} \sim 100$. Therefore $Nu = hd_p/k = 7.33$. Assuming 100 micron droplets on average and air conductivity k = 0.027 W/m/K, we have the heat transfer coefficient 'h' as 2000 W/m^2/K. The heat transfer between a spherical water droplet and air can be written as $m_a C_{pa}\, dT_a/dt = hA_p\left(T_a - T_w\right)$, where m_a is the mass of air surrounding one droplet. T_a and T_w are air and water droplet temperature respectively. A_p is the surface area of the droplet. From calculations of injected water mass above we have $m_a = 0.5 m_d$, where m_d is the droplet

mass. The time scale associated with this heat transfer process is given as $\tau = \frac{m_a C_{pa}}{hA_p}$, which for a 100 micron droplets works out to be roughly 1 millisecond. This is significantly faster than faster than the time scale of compression process (The compressor is operating at rotation speeds of around 1200 RPM).

[1983] **CFD analysis of isothermal compressor:**

[1984] A computational flow dynamics (CFD) analysis of a isothermal compressor with compression ratio of 9 has been carried out. Complex multiphase flow simulation models along with dynamic re-meshing is being used to simulate the complex interaction between air and water phase. Individual energy, momentum and volume conservation equations for the two phases are solved.

[1985] Fig. 77 shows the temperature (K) at top dead center at a location close to the cylinder head, immediately preceding opening of exhaust valve. In the simulation, significant accumulation of water is observed along the walls due to water droplet splashing, sliding and sticking effects. The temperatures, in general, are low at high water volume fraction regions and high in the central core where the low water volume fractions exist.

[1986] Fig. 78 shows the temperature variation with and without spraying water. Fig 78 shows CFD prediction of the mass-average air temperature in cylinder (K) versus crank rotation with and without spraying water.

[1987] The average temperature of the gas without water spray would rise by about 270K, whereas the temperature rise in the presence of 200μm droplets sprayed at 0.4 liters per second (20 cc's per stroke) is only about 25*K*. These results confirm theoretical analysis and clearly show the effectiveness of a proposed approach.

[1988] Other Losses:

[1989] In addition to the thermal inefficiency, which is considerably reduced by isothermal compression/expansion cycles, there will be other losses that lead to reduction in efficiency. Such sources have already been identified and are summarized here.

[1990] Motor and Electronic Components Losses: Estimated to be about 5%. Higher efficiency components may be purchased at higher cost.

[1991] Valve Losses: Estimated at about 2.7%. The flow through valve and pressure drop are related by $\dot{Q} = C_d A_V \sqrt{2\Delta p/\rho}$. Since we know the flow rate of air and water, we can calculate the pressure drop as $\Delta p = 1/2\ \rho\left(\dot{Q}/C_d A_V\right)^2$. Typical velocities for the air and water are in the range of 10m/s near the valve ($v = \dot{Q}/A_V$). The losses are then calculated separately for air and water phase: air flow loss in units of KJ/kg-of-air is $\Delta pQ = 1/2\ \rho Q\left(\dot{Q}/C_d A_V\right)^2$, calculated to be about $1.25\,kJ/kg$. Valve Loss due to water flow in units of *kJ/kg-of-air* is $\Delta pQ = 1/2\ \rho Q\left(\dot{Q}/C_d A_V\right)^2$, calculated to be about $3.75\,kJ/kg$, which is about 1.1% of the total power generated of *456 kJ/kg*.

[1992] Friction and Leakage Losses: Such losses are mainly due to motion of piston inside the cylinder, and the leakage of compressed air through the piston rings. The combined friction and leakage loss is estimate as 4*psi* per piston ring.

[1993] Spray Loss: Estimated at about 0.16%. This power loss was estimated based on the pressure delta applied on the nozzles and the flow rate through them. The percentage loss is estimated using $\left(\Delta P_{nozzle} Q_{water} m_r / \rho_{water}\right) / \left(RT \ln(P_2 / P_1)\right)$

[1994] Spray System:

[1995] To meet spray criteria set by the abovementioned analysis, a spraying system that operates at relatively low pressure delta (<50 psi) and relatively high flow rates (~100cc/s) and generates small droplets (<100 micron) at a relatively short breakup length, may be designed. The spray nozzles may produce a relatively uniform spray inside the cylinder, should spray at shallow angles (with respect to the cylinder head), and should introduce small or zero dead volume. Then nozzles should also be easy to manufacture, and eliminate/reduce cavitation effects.

[1996] A nozzle has been designed that is small enough to fit in our cylinder and simple enough to replicate reliably and inexpensively. Nozzle development continues. Some preliminary experimental and numerical tests follow.

[1997] Figures 30 and 79-82b show CFD simulation of some of the nozzle designs that we tested. Fig. 79 shows multiphase flow simulation of jet breakup in 2D. Fig 30 shows CFD simulation of water spray emitted from one of the proprietary LSE nozzle. Fig. 80 shows CFD simulation of water spray emitted from a pyramid nozzle developed.

[1998] With CFD simulations, we are able to predict the internal flow structure of the nozzles and predict the divergence angle of the formed sheet. We are also able to obtain a rough estimate of breakup length and breakup mechanism. We then use the obtained information along with semi-empirical correlations published in scientific literature to predict a more accurate value for breakup length and droplet size.

[1999] Figure 81a shows an experimental picture of the drops taken using a Particle Image Velocimetry (PIV) system, showing liquid sheet breakup & atomization. The measure drop size distribution is also plotted in Figure 81b.

[2000] The experimental setup includes a dual-cavity Nd:Yag laser (Solo III-15, New Wave Research) capable of illuminating the view field with two sequential 50mJ 4ns laser pulses at 532nm wavelength. This setup allows us to measure spatial distribution of drop velocities.

[2001] Cost Analysis:

[2002] Assuming operation at *20 Hz* (1200 RPM, two power strokes), and efficiency of 90% in expanding air from a *200* atm tank to 1 atm, the power rating of our system is estimated at *7.75* kW/Liter-of-displacement using the following relationship:

$$P_{iso} = \eta_v P_f V_{total} \left(\ln(P_i / P_f) - 1 + \frac{P_f}{P_i} \right) \times f$$

[2003] We used truck diesel engine as a model to estimate the capital (mass-production) costs of our proposed compressor/expander. This is intuitively reasonable because the pressure values in diesel engine is similar to that in our system (~200 atm). The power rating of the diesel engine at the 2400RPM with 4 strokes (same power strokes as our system) is estimated to be about *16* kW/Liter-of-displacement using:

$$P_{diesel} = \frac{1}{2} BMEP \times V \times f$$

[2004] Assuming that a 100 hp (~*75 kW*) truck diesel engine costs about $6000, the capital cost of mass production of our compressor/expander is about *$165/kW*. The following table summarizes the capital cost estimates, including cost of other items:

Item	Cost
Compressor/Expander	*165 $/kW*
Electric Motor	*60 $/kW*
Heat Exchanger	*50 $/kW*
Balance of System (BOS) - pump, controller electronics, etc	*90 $/kW*
Total	*365$/kW*

[2005] COP

[2006] Under the target conditions, many commercial air conditioning units operate at a COP of 3.5. Our system targets a COP of 4.25. A summary of our analysis follows.

[2007] Figure 32A is a power flow graph illustrating work and heat flowing through the entire cycle. All power values are normalized to the electric power flowing in from the grid. First, 1 kw of electric power is processed through a motor drive with an efficiency of 97%, followed by a motor with an efficiency of 95%. This progresses through a motor shaft, which loses 0.5% of its power as friction. This shaft drives the compressor. The compressor has several sources of inefficiency: spray, leakage, mechanical, and thermal.

[2008] Spray losses, for the mass ratio of 10:1 water to helium, come to only 1% of the work cycled through the system. The mechanical and leakage losses of a reciprocating compressor or expander are typically 95%. However, the friction losses are concentrated in the valve actuators, the orifice friction and pipe losses and the piston rings; none of these friction losses scale up linearly as the pressure mounts, and valve/pipe losses are low for light gases like helium. Operation may be internally pressurized at 25 bar, with a pressure ratio of 2.71. These mechanical efficiencies may be kept collectively above 95.6%.

[2009] There are thermal efficiencies. The dynamic thermal performance of compressors and expanders have been analyzed, resulting in analytical bounds, numerical results, and some experimental results at small scales. The work done on expansion is less than that on compression because the gas is at a lower temperature. Expansion efficiencies are 92.7% and compression efficiencies are 98% for the

temperatures shown, as long as the temperature difference between the gas and liquid stays below 5° F – achievable according to our analytical and computational results.

[2010] Size

[2011] For a one-ton system running at 1200 RPM and 150 psi, we'd need a 1 hp electric motor, two reciprocating pistons of 350cc total displacement, and fan-cooled heat exchangers with an interfacial surface area of about 15 square meters. Fitting these components into the desired form-factor (1.5'x1'x9") may be challenging but feasible.

[2012] Lifetime

[2013] Components in the design can reasonably be expected to operate with little or no maintenance for the target specification of 14 years – they do so in other similar systems. A risk to lifetime involves the use of water in the compressor and expander cylinders, as water can be corrosive to many metals. Water-tolerant materials that are also long-lifetime are useful for the sliding seals, valve seats, wear surfaces, and fasteners. Designs in accordance with the present invention may use aluminum components, nickel-polymer coatings, and PTFT sliding components.

[2014] Cost

[2015] To reach a target of $1000 per ton, cost-engineering of the near-isothermal compression and expansion cylinders can be done. Reciprocating air compressor pumps with 350 cc displacements retail for about $370. Embodiments according to the present invention may operate as both a compressor and an expander, using custom valves, plus spray nozzles, pumps, and air-water separators. If the total cost of those components can be kept to $500, that leaves about $150 for a one hp motor, $100 each for the three heat exchangers, and $50 for the enclosure and controls.

[2016] Scalability

[2017] Because our design is based on a simple reciprocating piston mechanism, it can be scaled arbitrarily from perhaps 100 watts to 10 MW. Larger units will have a lower per-ton cost.

[2018] Near-isothermal compression to about 8 atmospheres may be demonstrated. We anticipate the stages that follow may include:

1. Demonstrate both near-isothermal air compression and expansion at low pressure (ca. 10 atmospheres), which, taken together enable low-density energy storage
2. Demonstrate near isothermal compression and expansion at high pressures (ca. 200 atmospheres). This enables very generally applicable energy storage.
3. Demonstrate an integrated system that includes an open accumulator to improve efficiency and composite air tanks to lower costs.
4. Develop a custom engine block and other components designed specifically for cost-effective implementation of the technology demonstrated in 3, above.
5. Fabricate tooling for the components developed in 4, above, and establish a pilot production facility.
6. Build an initial run of pilot energy storage units and deploy them in test facilities.

7. Tool for full production

[2019] The first three phases described above are those being proposed here and correspond roughly to years 1, 2, and 3 of the project. If the project's targets are met, the capabilities of the technology will be fully ready for commercial development: The project's final prototype deliverable will be capable of taking electricity in from the grid, storing it indefinitely in air tanks that are fully able to meet applicable safety codes, then delivering the stored electricity to grid standards. This is the basic capability required for many existing energy storage applications (e.g. demand shifting for buildings and frequency regulation).

[2020] Phase 4 is the first step taken specifically for commercialization. This is largely a manufacturing engineering phase focused on cost and quality engineering. We expect the first product to be 100 kW scale – the scale we are prototyping here. Such a system would have many applications at industrial scale (demand shifting for buildings, back-up power, "islanding" at substations, storage for large photo-voltaic arrays, etc.)

[2021] The investment required to bring the first product to market would mostly be to cover the cost of tooling, pilot production inventory, pilot testing, tooling upgrades for small-scale production, and initial production inventory. The expectation is that some purchase orders would already be in hand before full production commences, which would facilitate conventional financing for inventory and accounts receivable. Venture capital investment would be the most likely source of capital for tooling and pilot production. That is likely to be comparable to the cost of tooling a small engine, perhaps $25M to $50M.

[2022] While the above embodiments have described the introduction of liquid for heat exchange through the spraying of liquid droplets, the present invention is not limited to this approach. According to certain embodiments, liquid could be introduced in one or more stages by bubbling gas through the liquid, for example utilizing a bubbler or sparger. Such liquid introduction utilizing bubbling may be particularly favored at high pressures, where homogenous interaction between liquid droplets and gas leading to uniform heat exchange may be difficult to achieve.

[2023] And while embodiments previously described have discussed cooling utilizing a cycle in which a refrigerant remains in the gas phase, the present invention is also not limited to such approaches. Cooling according to some embodiments of the present invention could employ a cycle in which a phase of the refrigerant does change from liquid to gas and then back again.

[2024] For example, Figure 82 shows a highly simplified view of an alternative embodiment of a cooling system according to the present invention. System 8200 utilizes as a refrigerant, a material that is configured to change phase from liquid to gas, and then back to a liquid. As described below, change of phase by the refrigerant serves to absorb and remove heat for cooling in an evaporator 8202, and then later to release this absorbed heat in a condensor 8204.

[2025] The circulating refrigerant enters the compressor (C) 8206 as a gas, where it is compressed to a higher pressure. According to embodiments of the present invention, a lower temperature liquid may be introduced to the gas during this compression, through sprayer 8208 (or bubbler) that is in fluid

communication with reservoir 8210 through pump 8212 and heat exchanger 8214. This introduced liquid serves to perform heat exchange with the compressed gas, reducing the temperature change of the gas and improving thermodynamic efficiency as discussed in detail above.

[2026] The liquid that is introduced may, or may not, be the same as the refrigerant itself. A listing of liquids that may be suitable for introduction according to various embodiments of the present invention, is provided elsewhere in this document.

[2027] After compression, the introduced liquid is separated from the compressed gas using a liquid-gas separator 8216, which may be of any of the particular designs described above. This separated liquid is then flowed to the reservoir 8210.

[2028] The separated compressed gas is then flowed to condensor 8204, where it exchanges heat with and is cooled by exposure to a thermal sink 8220, thereby changing into the liquid phase. Heat from the condensed liquid is carried away by the thermal sink.

[2029] The condensed liquid refrigerant then flows through a throttle valve (TV) 8232 where it undergoes a rapid pressure decrease. That reduction in pressure causes evaporation of some portion of the liquid refrigerant, resulting in a gas and liquid mixture. This evaporation lowers the temperature of the gas/liquid mixture below that of the desired cooling temperature.

[2030] The cold gas/liquid mixture is then routed to the evaporator 8202. Heat (typically in the form of air) from the user 8230 (here shown simplistically as a dwelling) interacts with the cold gas/liquid mixture. Heat of the air from the user evaporates the liquid component of the cold refrigerant mixture, and is thereby cooled.

[2031] Finally, refrigerant gas from the evaporator is flowed back into the compressor, and the cycle begins anew.

[2032] Introduction of liquid to perform heat exchange during compression in the refrigeration cycle shown in Figure 82, serves to perform compression more efficiently by compressing more nearly isothermally. This increased efficiency improves the COP (coefficient of performance) substantially.

[2033] Embodiments of the present invention relate to compressed gas energy storage systems exhibiting one or more desirable characteristics. Such systems may be efficient (80% round-trip), cost-effective (system cost < $100 kWh), quickly rampable (< 10 minutes) energy storage clearly represents a transformational technology. Particular embodiments may use water sprays to facilitate heat transfer at high pressures during compression and expansion.

[2034] Efficient, cost-effective energy storage technology according to embodiments of the present invention uses compressed air as the storage medium. Unlike existing compressed air energy storage technology (CAES), embodiments of the present invention can be sited anywhere, are highly efficient, and need no fossil fuels to operate.

[2035] Embodiments according to the present invention offer the ability to compress and expand air nearly isothermally. Isothermal operation greatly improves efficiency, but it has proven difficult to achieve previously, particularly at high power densities. Embodiments of the present invention inject a water spray directly into the compressing or expanding air. This absorbs the heat of compression,

reducing the required work (and adds heat during expansion, increasing the work retrieved). A near-constant operating temperature allows operation at higher compression ratios and higher speeds, lowering costs; and it eliminates the need to burn fossil fuels during expansion.

[2036] Though conceptually simple, water-spray facilitated heat transfer represents a significant engineering challenge – particularly at high pressures. Embodiments in accordance with the present invention may transfer heat out of a compression chamber (and into the expansion chamber) at rates up to *ten times* higher than have ever been reported in the scientific literature.

[2037] Embodiments according to the present invention relate to practical utility-scale energy storage that uses compressed air as the storage medium. Our proposed technology can be sited anywhere, is highly efficient, and needs no fossil fuels to operate.

[2038] A focus of embodiments according to the present invention is the ability to compress and expand air nearly isothermally. Isothermal compression greatly improves efficiency, but it has proven difficult to achieve, particularly at high power densities. One approach according to embodiments of the present invention is to spray water droplets directly into the compression and expansion chambers to facilitate heat exchange.

[2039] Several tasks are employed to demonstrate this technology at a commercial scale. Analysis and modeling can be used to refine and extend mathematical models of the thermodynamic, mechanical, acoustic, and hydraulic processes occurring in the system.

[2040] The fluid dynamics of water sprays can also be modeled. Examples include flow through nozzles, droplet breakup, collisions with the cylinder walls, and two-phase flow with air.

[2041] Development of a compressor can proceed as follows. A 100 kW-scale gas compressor can be modified to operate reversibly as an expander and integrate water-spray facilitated heat transfer. A single stage may be prototyped at low pressure (300 psi), then add a second stage to reach 3000 psi or higher. A pre-mixing chamber and custom valves for the second stage may be designed to enable high volume fraction of water at high pressures.

[2042] Existing Grid-Scale Energy Storage Technology

[2043] Grid energy storage is dominated today by two technologies, pumped hydro and compressed air (CAES). These technologies operate via the transport or compression of two fluids: air and water. Air and water will always be extremely inexpensive. A challenge is in making the systems that use them efficient, scalable, and flexible.

[2044] Embodiments in accordance with the present invention relate to energy storage technology that uses compressed air as the storage medium. Research reports have concluded that compressed air offers the best opportunity for cost-effective grid-scale energy storage – and perhaps the only viable path to meeting the aggressive cost targets specified by the FOA (< $100/kWh).

[2045] Existing compressed air energy storage (CAES) uses a compressor turbine, operated by an electric motor, to compress air. In the systems implemented to date, the compressed air is stored

underground in a salt dome until it is needed. The compressed air is used to operate an expansion turbine during power delivery.

[2046] However, because the air cools so much during expansion, limiting the amount of energy that can be obtained, natural gas is burned to heat the air stream before it enters the expansion turbine. This is essentially a natural gas combustion turbine operated with a time delay between compression and expansion.

[2047] Although two CAES systems are in operation, they have not proven to be popular technology due to expense and efficiency considerations, and the requirement of fossil fuel combustion to operate.

[2048] Near-Isothermal Compressed Air Energy Storage

[2049] Several projects are underway that propose to address the disadvantages of existing CAES systems. The objective is to develop compressed air energy storage that delivers power exclusively from air expansion without the need for supplementation with fossil fuel combustion.

[2050] This new compressed air technology uses near-isothermal (rather than adiabatic) compression and expansion. It is a basic result in thermodynamics (see the Preliminary Results section below) that less work is required to compress a gas if the heat generated during compression is removed from the system during the compression stroke. Similarly, if heat is added during expansion, more power will be generated.

[2051] If the temperature is kept constant during operation, the efficiency of energy storage can, in theory, approach 100%. In fact, there are many sources of possible losses – friction, pressure drops, electrical-mechanical conversion losses, etc. Nevertheless, a round-trip efficiency approaching 80% may be achievable.

[2052] There are several approaches to achieving near-isothermal performance, with heat transferred out of the compression chamber during compression and added during expansion. This can be done by operating very slowly, so that there is time for the heat to conduct through the walls of the chamber. Such a system may have difficulty scaling, and may run slowly, limiting the system's power density (and therefore increasing its cost).

[2053] Alternatively, a heat exchanger can be incorporated into the compression chamber, and this approach has been used by Lemofouet, S., "Energy Autonomy and Efficiency through Hydro-Pneumatic Storage", http://www.petitsdejeunersvaud.ch/fileadmin/user_upload/Petits_dejeuners/EnAirys_Powertech_20081121.pdf.

[2054] Water-Spray Mechanism for Near-Isothermal Air Compression and Expansion

[2055] Embodiments according to the present invention may take yet a different approach. Specifically, a liquid with high heat capacity (such as water) is sprayed into the air during compression and expansion. Because the water can absorb so much more heat per unit volume than the air, a small amount is sufficient to keep the process near-isothermal. And because water sprays provide such a large surface area for heat exchange, large amounts of heat can be transferred very quickly.

[2056] Such liquid injection according to embodiments of the present invention, will allow the compressor / expander mechanism to run at high RPM's. The faster the system runs, the more power it can deliver for a given system cost.

[2057] Mechanical components should be capable of high-speed operation in order to take full advantage of the heat transfer capabilities of water sprays. However, previous known technology for near-isothermal air compression uses hydraulic cylinders and a hydraulic motor / pump to deliver power. Use of hydraulics, though simple to prototype, significantly limits the speed of operation. At the scale of interest here, a mechanical system – for example using reciprocating pistons and a crankshaft according to embodiments of the present invention – can operate much faster than a hydraulic circuit.

[2058] The problem of water-spray facilitated heat exchange gets harder at high pressures, however – and high pressures may be important to obtain high efficiency and a small air-storage footprint. Accordingly, embodiments of the present invention may use a higher volume fraction of water-to-air than has been reported to date in the scientific literature in order to keep compression near-isothermal at a target pressure of 200 atmospheres. This may involve the design of specialized nozzles, valves, and spray manifolds to achieve spray density and uniformity.

[2059] Embodiments of the present invention may use reciprocating mechanical pistons, much like an automobile engine. Mechanical piston designs employing a crankshaft, bearings, and a lubrication system, may be more difficult to engineer than hydraulic designs. However, for this application, embodiments according to the present invention may achieve ten times the operating speed of hydraulics for the same displacement. Such systems can therefore deliver considerably more power for a comparable cost; air compressors and automotive engines use reciprocating pistons rather than hydraulics for this reason. The added complexity of a reciprocating mechanism allows leveraging full advantage of the heat transfer capabilities of water spray.

[2060] Embodiments of the present invention may relate to an efficient energy storage system that can ramp up quickly (for example 1 minute or less) and deliver over 20 kW of power for at least an hour. A prototype system is a commercial reciprocating compressor, modified to operate near-isothermally at pressures of up to 200 atmospheres. Conventional compressors typically operate at lower pressures (about 3.5 atmospheres).

[2061] Compressor / expander

[2062] In order to create a thermodynamic model for the entire air compression / expansion process (LSE), the current model described in the Preliminary Results section below, may be modified to include effects of water vapor, continuous spray, boundary layer, and turbulent mixing effects. Closed-form bounds for the system behavior are be found, and then numerical methods may be used to determine detailed values for specific configurations and operating conditions.

[2063] In order to model water spray behavior in a cylinder with a moving piston at high pressures using computational flow dynamics (CFD), new nozzle designs (for example as described in the Preliminary Results section below) may be modeled using CFD to improve the spray density and

uniformity. CFD analysis has proven useful in determining the most productive design avenues to pursue.

[2064] Nozzle manifolds in cylinder models may be modeled across the range of bore / stroke ratio and pressures of interest. Models of spray systems at high pressures – 100 atmospheres and above – may be of particular value to reflect high spray densities that are to be achieved.

[2065] A separate set of CFD models can be run to simulate the flow in and out of valves. Optimizing valve flow may improve volumetric efficiency. Another consideration in valve design is to ensure that water droplets sprayed into the air stream in a pre-mixing chamber remain entrained with the air as the mixture passes through the valve orifice.

[2066] Some modeling indicates that piston motion and splashing effects may be relevant. These can be further developed, particularly at high pressures. The modeling described above can be performed, for example, using the ANSYS Fluent software package.

[2067] A spray system capable of creating a highly uniform volume fraction of water near 10% at 200+ atmospheres pressure is under development. High-pressure cylinders have small bores, so that the direct-injection design used for the low-pressure cylinders (where the nozzles spray directly into the cylinder) is likely to be impractical – there won't be room for the number of nozzles required.

[2068] A pre-mixing chamber upstream of the cylinder may be used. In such a mixing chamber, the appropriate volume fraction of water to air is generated, then passed through an intake valve to the cylinder. CFD can be used to design an effective chamber geometry and nozzle distribution.

[2069] A high flow-coefficient valve capable of allowing a dense air-water aerosol to pass through, is being developed. As mentioned above, the challenge is to move a dense air-water droplet mixture from the pre-mixing chamber into the cylinder while keeping the droplets in suspension.

[2070] Various valve geometries are possible. One is a rotating valve with a large cylindrical orifice that doesn't require the flow to change direction. A second geometry utilizes a port, or group of ports, in the cylinder wall, as can be found in many two-stroke engines.

[2071] In the second arrangement, the piston itself opens and closes the valve as it travels. One challenge with the port geometry may be to is to make it work for both compression (where the ports may be located just above the top of the piston at bottom dead center) and expansion (where the ports may be located near top dead center).

[2072] Certain embodiment may use liquid water to manage the dead volume in a cylinder. Near-isothermal compression and expansion allow high compression ratios to be achieved without the large temperature changes that would make such ratios impractical. However, a high compression or expansion ratio may be difficult to achieve unless the dead volume (the portion of the cylinder volume that remains uncovered when the piston is at top dead center) is too large. In a conventional gas compressor, for example, the dead volume is 25%, limiting the compression ratio to four.

[2073] Embodiments according to the present invention may achieve a compression ratio as high as 20 or more. This could be achieved using carefully designed piston/cylinder/valve assembly and/or by the use of water fill much of the dead space.

[2074] With the latter, the method by which just the right volume of water is maintained in the cylinder during operation may be hard to achieve. Solving this problem may involve modeling and experimentation with valve design and feedback-based control.

[2075] Embodiments of the present invention may seek to exercise optimal control of water spray in air compressor/expander. The performance (efficiency and power) of the compressor/expander may depend on timing and amount of water spray.

[2076] In general, the more water that is sprayed the better it is able to isothermalize the compression/expansion. However, water spray also incurs a cost (e.g. pressure drop).

[2077] It therefore may be useful to determine a strategy to inject the least amount of water while satisfying the goal of isothermalizing the process. An analytical model that can provide sufficient accuracy in order to determine the optimal timing and amount may not be readily available. Learning control approaches may be utilized, in which through repeated experiment, an optimal control strategy will be attained. Formally, such approaches are termed self-optimizing control or extremum seeking approaches.

[2078] Embodiments of the present invention may integrate a spray system, valves, dead-volume management system, and the spray control optimization, into a single-cylinder compressor / expander capable of a high compression ratio. A single cylinder may be configured to operate as a compressor or expander at 10 to 20 atmospheres or higher with a controllable ΔT. System performance may be characterized and compared with the analytical model.

[2079] Certain embodiments may utilize a multi-stage compressor capable of > 100 atmospheres pressure. In certain embodiments the compressor / expander may be configured to work with two cylinders. According to some embodiments, the water spray system may use a higher pressure of the second stage to pump water spray through the nozzles of the lower-pressure cylinder. The heat exchanger system may be configured to support the cylinders and manage the spray system to maintain equal ΔT's in both stages.

[2080] **Preliminary results**

[2081] Near-Isothermal Compression and Expansion

[2082] Air is an inexpensive storage medium. Rapid heat transfer can allow efficient energy storage. Water, sprayed finely, densely and uniformly, would allow heat transfer better than anything tried before.

[2083] Water has a greater volumetric heat capacity than air (more than 3200x). So even a small volume of water suspended as spray in the compressing air, could absorb tremendous amounts of heat of compression and likewise supply heat for expansion, without undergoing a significant temperature change.

[2084] A detailed analytical and numerical thermodynamic analysis (see below) yielded analytical upper and lower bounds for thermodynamic performance. A numerical simulation verified those bounds.

[2085] Efficient expansion of air can be achieved utilizing various approaches. While the injection of water spray could improve heat transfer, existing air motors cause significant 'free' expansion, which wastes the energy stored without doing any useful work.

[2086] Accordingly, certain embodiments of the present invention may utilize a 'controlled pulse' valve timing strategy that would recover that efficiency. This valve timing strategy would open the valves at the beginning of the expansion process for a specified time and then close the valves. This would admit enough air such that when expansion completed, the internal pressure is equal to the pressure of the lower stage or atmosphere, and all available energy extracted.

[2087] To demonstrate that: (a) a 'controlled pulse' valve strategy would avoid inefficiencies due to free expansion and (b) near-isothermal compression and expansion are both possible and allow efficient energy storage, a small prototype was built using the fluid piston concept. Air was displaced by a hydraulic fluid instead of a piston, without attempting to spray fluid into the air. A drive, controller board, and pressure cells were homebuilt. Using solenoid valves, a hydraulic motor, and a gallon of vegetable oil for the hydraulic fluid, an air motor was built that demonstrated thermodynamic efficiency at 88% of a perfect isothermal system.

[2088] Components, costs, and parasitic losses throughout this prototype system were hunted down and eliminated where possible. For example, it was recognized that a liquid piston or other hydraulic system would struggle to achieve high energy densities, low costs, and high efficiencies. High energy densities necessitate high RPMs, but the momentum and friction of liquid moving around so rapidly may make it difficult to build a stable, robust, efficient system. The fluid friction associated with moving such a significant amount of liquid around would reduce efficiency by a significant amount - by some estimates more than 5% each way.

[2089] In addition, during the compression and expansion the pressure could change, moving the hydraulic motor/pump continually off of its maximum efficiency point. Based upon available efficiency curves, efficiency could be reduced by, again, more than 5% each way.

[2090] Accordingly, mechanical approaches to compression and expansion may be favored, for example using a reciprocating piston in a cylinder.

[2091] Water spray could alleviate traditional technical problems, cooling all of the surfaces, reducing wear on sliding components. For example, a leading manufacturer makes compressors that cannot have a compression ratio exceeding 3.5: the high temperatures created would stress the materials too far. This limitation is avoided with the use of water spraying.

[2092] Additionally, water could access hard-to-reach crevices of the cylinder head and valve assemblies, taking up the 'dead-volume' that reduces the volumetric efficiency and compression ratio of compressors and engines. For example, with traditional reciprocating technology, it would take 4 stages to compress air at one atmosphere to 200 atmospheres. Embodiments according to the present invention may be able to achieve this in two stages.

[2093] Cost and inefficiency of variable frequency drives are another possible source of improvement. A synchronous motor generator with load control could instead be used, and on the compressor/expander control the valve pulse length. Such an approach could trade off some efficiency in exchange for increased or decreased power in real time.

[2094] In certain embodiments, the spray system may meet the following performance criteria: it may generate small droplets (<100 micron) at a relatively short breakup length, with a relatively low pressure delta (<50 psi), and at relatively high flow rates (~100cc/s). The spray system may produce a relatively uniform spray inside the cylinder. The spray nozzle design may introduce small or zero dead volume, be relatively easy to manufacture, and eliminate/reduce cavitation effects.

[2095] Nozzles are known that can eject streams of water requiring a low pressure delta. Other nozzle designs are known that can eject very fine mist at a high pressure delta. However, no nozzles known appears to be able to match desired parameters.

[2096] Thus, embodiments in accordance with the present invention may utilize novel nozzle designs. Fig. 79 shows a model of jet breakup from a two-dimensional CFD simulation. Red regions are for liquid and blue for air.

[2097] Fig 80 shows CFD simulation of water spray emitted from a nozzle design. Red color indicates completely liquid and blue indicates air. Fig. 80 shows CFD simulation of water spray emitted from pyramid nozzle developed by LSE. Red color indicates liquid spray and blue indicates air. Fig. 81a shows liquid sheet breakup & atomization from an embodiment of a nozzle. Fig. 81b shows droplet size distribution from an embodiment of a nozzle.

[2098] Nozzle designs in accordance with embodiments of the present invention may exhibit desirable characteristics. Nozzle designs can atomize water droplets to less than 100 microns, with a pressure drop of only 50 psi, and with a high flow rate (100 cc/s) and a short breakup length (~1 inch) that is small enough to fit in our cylinder and simple enough to replicate reliably and inexpensively.

[2099] Combination of nozzle models with a model of compression/expansion cylinder and valves, yields a full CFD model of the entire compression/expansion process. This has been used to model droplets splashing against the wall through a thin sheet of water on the surface, the mesh dynamically deforming as the piston moves and the valves open and close, and incorporating a model of the effects of droplets crowded close together, taking up an extremely high fraction of the volume available to it.

[2100] Simulation of a system with a displacement of a compression ratio of 9, and stroke taking a mere 20^{th} of a second, indicates that the average temperature of the gas without water spray would go from 300 K to 570 K. By contrast, the temperature rise in the presence of a spray of 200 micron droplets at 0.4 liters per second (20 cc's per stroke).

[2101] Figure 83 indicates the mass-average air temperature in cylinder (K) versus crank rotation from CFD simulations with and without splash model. Figure 77 indicates the temperature (K) immediately preceding opening of exhaust valve.

[2102] A thermodynamic analysis proceeded in three parts. First, the thermal behavior of a compression or expansion process was calculated, where the water was in perfect thermal equilibrium with the air, heat transfer between the mixture and the environment was negligible, and the temperatures were low enough that the saturation vapor pressure was also low, so phase-change could be neglected. The process was similar to an adiabatic compression or expansion process, with no thermal exchange

between the environment and the mixture. However, the presence of water, in intimate thermal contact with the air, increases the 'effective' heat capacity per mole of air.

[2103] In adiabatic compression or expansion of an ideal gas, the process obeys:

$pV^{\gamma} = \text{constant}$, where:

$\gamma = \frac{c_p}{c_v} = \frac{c_v + R}{c_v}$, where:

c_p and c_v are the molar heat capacities at constant pressure and volume, and where R is the molar gas constant.

[2104] Additionally, since $pV = nRT$, the temperature is given by:

$$T_{final} = T_{initial}\left(\frac{V_{initial}}{V_{final}}\right)^{\gamma-1}$$

[2105] This is true for compression or expansion of an air and water mixture, except that γ is replaced by:

$\gamma_{effective} = \frac{c_{v,effective} + R}{c_{v,effective}}$, where:

$c_{v,effective}$ is the total heat capacity of the gas and liquid at constant volume per mole of gas.

[2106] As the water spray increases in proportion, $c_{v,effective}$ increases, and $\gamma_{effective}$ approaches. Hence, by the expression for temperature given above, the temperature throughout the process becomes nearly constant.

[2107] A second part of the thermodynamic analysis, extended the above analytical result to account for the fact that droplets and air will not instantaneously come into thermal equilibrium. First, an equation for the maximum shaft power in or out during the process was determined. This allows finding an equation for the maximum temperature difference between the water and air ever attained during the process.

[2108] This in turn allows creation of a bounding process which can be shown to slightly overestimate the temperature change during compression or expansion. This bounding process also slightly overestimates the work required for compression, and underestimates the work done during expansion. The air and water are assumed to be continuously in thermal equilibrium, already warmed or cooled from their initial state by the maximum temperature difference attained.

[2109] This process then proceeds as the equilibrium process described above. These values depend on one another, but can be solved algebraically. This work gives us an analytical bound and scaling law on the ΔT attained during the compression and expansion process, and a lower bound on the thermodynamic efficiency.

[2110] Embodiments of systems according to the present invention may offer certain desirable properties as compared to other energy storage systems. For example, unlike batteries, cycle life of an air compressor is indefinite.

[2111] The cost of a compressed-air energy storage (CAES) system is the sum of two costs: that of the compression / expansion mechanism (a per kW cost, since this mechanism generates power), and that of the air storage system (a per kWh cost, since it stores energy). Embodiments of the present invention may target a cost of $400/kW and $80/kWh installed cost (assuming underground storage is not available). For a system with 12 hours of storage, the cost could be thought of as $113/kWh. However, a system with 26 hours of storage (the storage duration of the Macintosh, Alabama CAES plant) would cost only $95/kWh.

[2112] Reciprocating engines are a mature technology. Truck diesel engines typically cost about $100/kW. To that cost (assuming a comparable power density) a motor-generator, power electronics, and other components would be included. Meeting a $400/kW target is quite achievable for high-volume production.

[2113] Conventional steel tanks capable of storing air at 200 atmospheres cost about $125 / kWh (including a valve). To this should be added the cost of a manifold, connecting hoses, an enclosure, gauges, and connectors. In addition, extra capacity is needed to account for any inefficiency in delivering power from the compressed air. If the one-way efficiency is 90%, about 1.1 kWh of storage capacity can deliver 1.0 kWh. A cost of $150 / kWh may be likely for off-the-shelf technology.

[2114] If tanks are made 16 meters long, instead of their usual 1.6 meters, the cost of spinning the tank closed may be reduced, along with the cost of valves and hoses. Starting with natural gas pipeline pipe or well-casing pipe is another possible approach.

[2115] The operating time at rated power can be extended indefinitely by adding more storage tanks. Enough tanks may be added to run for at least one hour (that is, about 100 kWh of total storage).

[2116] Embodiments according to the present invention may also offer a long cycle life._As a compressed air energy storage system is mechanical, not electrochemical, its performance doesn't degrade in the same way that batteries do. Properly maintained, gas compressors can run continuously for 30 years (11,000 diurnal cycles).

[2117] Embodiments according to the present invention may also offer high round-trip efficiency. Conventional CAES systems are just over 50% efficient. 80% round-trip efficiency is theoretically possible for an isothermal system. 75% efficiency under normal operation may be a more realistic target. 90% or more efficiency may be achievable if low-grade heat (such as waste heat) is available.

[2118] Efficiency in current CAES systems is limited because the heat of compression is lost. Near-isothermal operation will give thermal efficiency of close to 100%.

[2119] However, there are a number of parasitic losses that can be minimized. Examples of such parasitic losses include but are not limited to: volumetric losses (the ability to fill the cylinder with air during the intake stroke and empty it during the exhaust stroke); motor/generator efficiency; the power used to spray water into the cylinder; the heat exchanger fan; and friction. For instance, for volumetric efficiency the proper volume of water to fill most of the dead volume in the cylinder, should be maintained.

[2120] Regarding dwell time, changing from charge to discharge mode is a matter of switching the state of several valves. The engine continues rotating in the same direction. This should happen almost instantaneously.

[2121] Regarding scalability, in an embodiment a system may be on a frame that can operate at about 1 MW when all four cylinders are attached. Operation may initially be at 100 kW, but can scale up once the basic targets have been achieved.

[2122] One potential technical challenge associated with scaling up involves efficient operation at high pressures: 3000+ psi may be desirable to reduce storage footprint and cost. Maintaining a high-enough volume fraction of water at those pressures is an objective.

[2123] Still another potential benefit offered by embodiments according to the present invention is a reduction of internal losses. Specifically, existing CAES systems store compressed air underground. Depending on the type of geology used, losses can be significant. For above-ground storage in steel or composite tanks, there is, for practical purposes, zero loss in energy stored over an arbitrarily long time period.

[2124] Regarding safety, the mechanical components and pressure vessels can be fully compliant with the appropriate engineering codes. Moreover, in many embodiments the system uses no toxic substances, just air and water.

[2125] Embodiments of the present invention may last 30 years or more, typical of heavy-duty reciprocating gas compressors. As with any engine, regular maintenance is required. Piston rings, packing, filters, and lubricating oil will require periodic replacement.

[2126] Use of water in the cylinders offer a source of corrosion. Certain coatings such as DLC, nickel/polymer, and other materials may provide long-term protection against corrosion.

[2127] As previously described, the compressed gas residing in a storage unit may serve purposes in addition to energy storage. For example, as described above, in certain embodiments the compressed gas could perform a physical support function, with forces exerted by the compressed gas serving to maintain the shape and integrity of an inflated structure. Examples of such inflated structures include but are not limited to building elements such as pillars, walls, and roofs, and/or floating members such as pontoons, buoys, barges, or vessel hulls.

[2128] As also described above, the structure of an inflatable support member that is configured to store compressed gas, may be designed to take maximum advantage of inflation forces offered by the compressed gas. One example of such a structure is described by Mauro Pedretti in " TENSAIRITY®", European Congress on Computational Methods in Applied Sciences and Engineering (ECCOMAS 2004), incorporated by reference herein for all purposes. TENSAIRITY® describes a light weight structural concept using low pressure air to stabilize compression elements against buckling.

[2129] Such an approach may allow the inclusion or arrangement of additional compression members to oppose loads from other directions. In certain embodiments a fiber may be arranged in a spiral about an inflated member, with endcaps used. Such a configuration provides resistance to internal pressure,

resistance to expansion buckling modes, and/or distribution of forces to/from compression expansion members.

[2130] In certain embodiments, the shape, material composition, and/or position of the compressed gas storage unit, may be selected at least in part based upon its role to provide physical support. In certain embodiments, the additional stabilizing force offered by compressed gas may allow the relaxation of certain tolerances in a supporting member.

[2131] For example, returning again to the example of a wind turbine support structure configured as a compressed gas storage unit, forces exerted by the compressed gas could allow the walls of the tower to be thinner. This in turn could have a cumulative effect to reduce the overall weight and cost of the structure, because a significant proportion of the material in such a tower may be dedicated to supporting the tower itself, rather than bearing the load of the wind turbine.

[2132] The design of an inflatable supporting structure could also take into account potential failure modes. For example, a significant amount of the overall strength of a wind turbine support tower may be devoted to providing sufficient force to oppose the torque of the spinning blades. In the event of a problem potentially leading to the loss of compressed gas, rotation of the turbine could be rapidly halted, thereby alleviating the need for the support structure to resist this torque. Of course, even in an uninflated state the support tower may be required to provide sufficient force to bear the weight of the turbine, and to oppose drag forces offered by the non-rotating turbine to prevailing winds.

[2133] Certain embodiments of the present invention relate to liquid spray nozzles which may inject liquid into a gas within a compression or expansion chamber. According to some embodiments, the liquid spray nozzle is formed by selective and precise removal of material from a single piece, forming a velocity elevation region in fluid communication with a narrow fan-shaped output slot. A liquid spray nozzle of certain embodiments may be defined between recesses in opposing facing surfaces of two or more pieces in mating engagement with one another. By affording access to opposing surfaces prior to their mating, such multi-piece embodiments may facilitate precise definition of interior shapes, for example by machining.

[2134] Figure 89 shows a simplified cross-sectional view of the space defining a liquid injection sprayer according to an embodiment of the present invention. The space 8902 comprises a deep region 8904 having an inlet 8904a in fluid communication with a pressurized source 8906 of liquid, for example a manifold or a liquid flow valve. Deep region 8904 may be in the form of a cylinder having a circular cross-section, or may be a modified cylinder having a cross-section of another shape.

[2135] A second end 8904b of the deep region 8904 opens to a velocity enhancing region 8908 of varying depth, that terminates short of the space (chamber) 8910 that is configured to receive the injected liquid. A shallow fan-shaped slot region 8912 extends from the second end 8904b of the deep region 8904, through the velocity -enhancing region 8908 to an reach an outlet 8912a opening to the space 8910 into which the liquid is to be injected, for example a gas compression/expansion chamber. In the particular embodiment shown in Figure 89, the sides of the fan-shaped slot region define an angle of 120°

relative to one another, although this or any other particular angular relationship is not required by the present invention.

[2136] The arrows of Figure 89 show a generalized depiction of the path of liquid flowed through the space. Pressurized liquid enters the inlet 8904a to the cylindrical region in a relatively straight flow path. The liquid then undergoes an increase in velocity as the flowing liquid experiences constriction in the reduced cross-sectional area of the region 8912, and finally is ejected in a fan-shaped trajectory as the pressurized liquid passes through the fan-shaped slot region 8912. The shape of region 8908 serves to change the velocity vectors of the liquid to be substantially perpendicular to the boundary between regions 8908 and 8912.

[2137] In certain embodiments, the spaces defining the liquid injection nozzle may be formed from a single piece of material, for example metal. Figure 90A shows a simplified end view from the inlet side, of one embodiment fabricated from a single piece of material. Figure 90B shows a simplified cross-sectional view taken along line 90B-90B' of Figure 90A. Figure 90C shows a simplified end view from the outlet side of the nozzle.

[2138] The embodiment of the nozzle 9000 of Figures 90A comprises a first inlet portion 9002 configured to receive the flow of liquid into the nozzle. In certain embodiments, this first inlet portion may readily be formed by machining a block of metal utilizing a drill bit or end mill having a diameter D.

[2139] The first inlet portion 9002 is in turn in communication with a middle portion 9004, which corresponds to the deep portion described in connection with Figure 89. The middle portion opens to a direction changing portion 9006, which can be hemispherically shaped and a velocity elevating portion 9008.

[2140] In certain embodiments, the middle portion and the direction changing portion may readily be formed at the same time, by machining a block of metal utilizing a ball end mill having a diameter D' that is inserted into the inlet side and stops short of reaching the outlet side of the block.

[2141] Finally, the middle portion 9004 and the direction changing portion 9006 are in fluid communication with the outlet through a narrow slot region 9008. Narrow slot region 9008 may readily be formed by machining the block of metal from the outlet side. In certain embodiments, the narrow slot region could be fabricated utilizing a slitting saw having a blade with a radius r and thickness t.

[2142] Embodiments according to the present invention are not limited to the particular shape shown in Figures 90A-90C. For example, while the slot portion is shown as extending at an angle parallel to the lengthwise axis A defined by the portions 9002 and 9004, this is not required.

[2143] Figures 91A-91E show different simplified views of an alternative embodiment, wherein the slot is formed perpendicular to the axis of the inlet and middle portions. Figure 91A shows a simplified end view from the perspective of the inlet. Figure 91B shows a simplified cross-section taken along line 91B-91B' of Figure 91A. Figure 91C shows a simplified view from an end opposite that of Figure 91A. Figure 91D shows a side view from the perspective of the outlet. Figure 91E shows another side view.

[2144] In particular, the alternative embodiment of Figures 91A-91E features a nozzle that is formed by milling a block of material 9150 that has been shaped to include a narrower head portion 9152 and a

broader body portion 9154. The body portion contains the entirety of the inlet space 9156, and a part of the middle space 9158. The head portion contains the remainder of the middle space 9158 and a direction changing space 9160 and the narrow outlet slot 9162.

[2145] The nozzle design of Figures 91A-91E can be fabricated by forming the inlet space and the middle space utilizing the milling techniques described above in connection with Figures 90A-90C. The slot can be formed by milling the side of the exposed head portion, again for example utilizing a slitting saw having a thickness t as shown in Figure 91D. While the drawings show the slot cut through a diameter of middle space 9158, this is not required, and the slot may be cut shallower or more deeply.

[2146] While this particular embodiment shows the slot as being cut at a 90° angle relative to the axis A, this is not required. In certain embodiments, the angle of the outlet slot could be inclined at other than 90°. This could be accomplished by determining an orientation of the piece relative to the tool at the time of formation of the slot.

[2147] Figures 92A-92E show different simplified views of an alternative embodiment, wherein the slot is formed at an angle relative to the axis of the inlet and middle portions. Figure 92A shows a simplified end view from the perspective of the inlet. Figure 92B shows a simplified cross-section taken along line 92B-92B' of Figure 92A. Figure 92C shows a simplified view from an end opposite that of Figure 92A. Figure 92D shows a side view from the perspective of the outlet. Figure 92E shows another side view.

[2148] In particular, the alternative embodiment of Figures 92A-92E features a nozzle that is formed by milling a block of material 9280 that has been shaped to include an inclined shoulder surface 9282 proximate to the velocity elevating portion 9284.

[2149] The nozzle design of Figures 92A-92E can be fabricated by forming the inlet space and the middle space utilizing the milling techniques described above in connection with Figures 92A-92C. The slot can be formed by milling the inclined surface at an angle perpendicular to that surface, for example utilizing a slitting saw machining tool. Another machining technique that may be used to create the slot is electrical discharge machining (EDM). By virtue of the orientation of the inclined surface relative to the axis of the inlet space, the resulting slot will also be angled relative to that inlet space.

[2150] While the above embodiments have described a nozzle structure formed from a single piece, the present invention is not limited to such a structure. In alternative embodiments, one or more portions of the space forming the liquid injection nozzle may be defined by recesses in opposing surfaces of mated plates. Figure 93 is a perspective view of one such plate 9300 showing and end surface 9302 defining the recess 9304 forming one-half of the sprayer structure, including the shallow trapezoidal-shaped slot recess 9306 having outlet 9306a.

[2151] Figure 93A shows a corresponding top view of the plate of Figure 93. Figure 93B shows a corresponding side view of the plate of Figure 93

[2152] Figures 93 and 93B also show holes 9307 that are present in the side surface of the plate. These holes may be used to physically secure the plate to a manifold or other fluid source utilizing a bolt or another structure.

[2153] Figures 93-93B further shows projections 9308 extending from the end surface 9302. These projections are configured to engage with corresponding openings present in the second plate, thereby allowing aligned mating of the plates in order to define the sprayer.

[2154] Specifically, Figure 94 is a perspective view of an embodiment of the second plate that is configured to mate with the first plate. Figure 94 shows the surface 9402 of plate 9400 defining the half cylinder-shaped recess 9404 defining a planar opening and forming the other half of the sprayer structure. End surface 9402 also includes the holes 9410 that are sized to receive the corresponding projections from the surface of the second plate. Holes 9407 in the side surface of the plate, may be used to physically secure the plate to a manifold or other fluid source utilizing a bolt or similar structure.

[2155] Figure 95 shows a view of an embodiment of an assembled sprayer structure taken from the perspective of a chamber that is configured to receive liquid from the sprayer. Figure 95 shows the plates 9300 and 9400 mated together, with only the opening of the trapezoidal-shaped slot portion visible as an elongated hole 9500.

[2156] Figure 96 shows a view of the embodiment of the assembled sprayer structure of Figure 95, taken from the perspective of a pressurized source of liquid to the sprayer such as a manifold. Figure 96 shows the plates 9300 and 9400 mated together, with the planar opening to the cylindrical-shaped recess visible as a circle 9600.

[2157] Nozzles according to certain embodiments of the present invention may offer a benefit by producing a fan-shaped spray. For example in certain embodiments the liquid may be injected into a chamber to efficiently perform heat exchange with a gas. Such liquid-gas heat exchange may be useful in achieving compression of a gas, or expansion of a compressed gas, under thermodynamically efficient conditions.

[2158] In particular, the amount of heat exchange depends upon a surface area of the liquid that is exposed to the gas. Providing a given volume of injected liquid over a fan-shaped area, produces a sheet of liquid that thins as the liquid flows, eventually breaking up into individual droplets. It may be desirable to produce small sized droplets distributed evenly over a large volume. Smaller sized droplets in turn exhibit larger surface area and enhanced heat exchange properties.

[2159] Using conventional spray nozzle designs, the liquid that is present at the edges of a spray may tend to remain coalesced in droplets of larger size relative to droplets in the center of the fan spray. The presence of such larger droplets at the edge may undesirably lower a surface area of the liquid that is available for heat exchange with the gas. This would reduce the efficiency of liquid-gas heat exchange.

[2160] Use of spray nozzle designs according to embodiments of the present invention as described above, however, may result in fewer large droplets at the edge of the fan spray. Specifically, Figure 97 shows that liquid emerging from the edge of the direction changing region (hemispherical region), must traverse a longer distance within the limited volume of the narrow slot. This longer flow path X' through the narrow slot, as compared with the shorter flow path X through the slot taken by liquid emerging from the center of the direction changing region, should cause liquid at the edges of the fan spray to experience lower flow rates, reducing the volume of liquid present at the edge of the spray relative to the volume of

liquid at the center of the spray. This lower flow rate effect should in turn reduce the relative thickness of the liquid sheet before breakup, and hence the size and number of the droplets at the edge of the spray, as shown in Figure 98.

[2161] One potential benefit offered by some embodiments of spray structures according to the present invention, is relative ease of manufacturing. Specifically, the recesses forming the sprayer are defined between opposing surfaces that are mated together. Prior to mating of the plates, their respective surfaces are exposed and hence readily accessible to the designer and to machine tools, facilitating fabrication of recesses having the desired shape.

[2162] The multi-piece construction of certain embodiments in accordance with the present invention, also facilitates fabrication of more complex apparatuses utilizing multiple sprayers. Specifically, access to the surface of the plate(s) prior to their assembly, allows multiple recesses to be formed adjacent to each other in the same surface. Subsequent mating of the plate with one or more plates also having multiple such recesses, allows formation of a structure having multiple sprayers.

[2163] Furthermore, the shapes of the recesses in the surfaces of the plate may be relatively simple and easy to create with the appropriate precision. For example, certain milling tools may allow fabrication of shapes with features of 100 microns, 50 microns, or even 25 microns or less. The manufacture of nozzles with such precise small dimensions permits careful regulation of the flows of liquid through the device.

[2164] In certain embodiments such as are shown in Figures 93-93B, one plate may have a surface with a planar opening defining one-half of a cylindrical shaped recess with a hemispherical end. Such a shape may readily be formed with high precision and low dimensional tolerances, utilizing a machining tool having the appropriate profile.

[2165] The shape of the recess formed in the opposing surface of the other plate may be somewhat more complex, also including the shallow trapezoidal slot portion that is in contact with the spherical or other-shaped direction changing portion. However, even such more complex combinations of shapes may readily be formed with high precision and low dimensional tolerances, utilizing conventional milling techniques.

[2166] Figures 89-96 show only particular embodiments of spray structures, and should not be viewed as limiting the invention. Alternative embodiments could employ specific relative dimensions different from those shown in the figures, and remain within the scope of the present invention.

[2167] Still other embodiments of sprayers according to the present invention, may be formed from recesses shaped differently from those of the particular embodiments shown and described above. For example, the relative angle between the sides of the trapezoidal-shaped recess is not limited to 120°, and could be larger or smaller depending upon the particular application, resulting in a fan spray of liquid having a different angle. Increasing the angle may shorten the breakup length and affect droplet size.

[2168] In accordance with alternative embodiments, other configurations of recesses are possible. For example, while the above embodiments show a slot feature that is oriented to eject liquid either at an angle perpendicular or parallel to an inlet bore axis, this is not required by the present invention.

[2169] Figures 99A-D show an alternative embodiment a nozzle structure 9900 according to the present invention, wherein the slot portion 9902 having outlet 9902a is oriented at an angle of only 15° relative to the plane defined by the side faces 9904a and 9906a of the mated plates 9904 and 9906. This is accomplished by forming the plates or portions thereof in shapes other than rectangles, such that their opposed mating end faces 9904b and 9906b are not perpendicular to the respective side faces 9904a, 9904b of the plates.

[2170] Thus in the particular embodiment shown in Figures 99A-D, the partially-spherical recess 9908 defining a planar opening 9910 is formed in triangle-shaped plate 9906, and the recess 9912 defining the non-planar opening 9914 is formed in the plate 9904 having a surface that fits with that triangle-shaped plate.

[2171] Figures 99A-D also show the liquid inlet opening 9915, as well as the openings to the bores 9916 that may receive screws or bolts that can be used to secure the plates together.

[2172] The particular embodiment of Figures 99A-D differs from prior multi-piece embodiments, in that the shapes of the recesses in the respective plates are not substantially symmetrical relative to one another. That is, recess 9908 in the plate 9906 defines the partially spherical portion, while the recess 9912 in the plate 9904 defines a cylindrical shaped channel leading from the inlet opening 9915 to a non-planar opening and the slot. Again, however, these recesses are relatively simply shaped and readily formed in the separate plates by milling techniques prior to assembly.

[2173] While the nozzle embodiments described above are defined between opposing faces of two plates fitted against each other, the present invention is not limited to this particular approach. Alternative embodiments in accordance with the present invention could be created by inserting a first piece into a second piece, such that the corresponding faces of the inserted pieces define the nozzle.

[2174] For example, Figures 100A-J show various views of an alternative embodiment of a nozzle design 10000, which is formed by the insertion of a first piece 10002 within an opening 10003 present in a second piece 10004. The two pieces 10002 and 10004 are secured together utilizing a bolt 10006 fitted through hole 10008 in the first piece and hole 10010 in the second piece. The bolt 10006 includes an end piece 10006a. Washer 10005 is seated on surface 10004b of the second piece 10004, and the first piece 10002 is seated on the washer.

[2175] As shown in the cross-sectional view of Figure 100H, the flow of liquid to be sprayed is indicated with the arrows as shown. This liquid flows through orifice(s) 10021 (here twelve in number) that are present in the second piece 10004.

[2176] The flowing liquid then changes direction in region 10007, as shown by the arrow. Region 10007 thus corresponds to the direction changing portion of this embodiment of a nozzle design.

[2177] This liquid then flows through the passageway 10009 defined between opposing surfaces 10002a and 10004a offered by the first and second respective pieces. Because passageway 10009 offers a smaller cross-sectional area to the incoming liquid than passageway 10021, velocity of the liquid is enhanced.

[2178] In addition, the respective surfaces 10002a and 10004a are inclined at different angles relative one another (surface 10002a is inclined at an angle of 15°, while surface 10004a is inclined at an angle of 30°). As shown in Figure 100J, this geometry is arranged to offer substantially the same cross-sectional area as the liquid flows through passageway 10009. In particular, the cross-sectional area A of the inlet 10009a to the passageway 10009 forming the velocity enhancement portion, is substantially equal to (or even somewhat larger than) the cross-sectional area A' of the gap 10020 forming the outlet of that passageway.

[2179] Based upon the relative cross-sectional areas of the inlet and outlet to the velocity enhancement portion of the nozzle, the configuration of the embodiment of Figures 100A-J can lower the magnitude of the pressure drop experienced by the liquid. In this manner, the configuration of the embodiment of Figures 100A-J can desirably reduce incidence of cavitation, while inducing the velocity vector profile to create a hollow conical sheet of the liquid emerging from the nozzle.

[2180] The pressurized flowing liquid then ultimately exits from passageway 10009 and the nozzle through narrow gap 10020. Figure 100H is not drawn to scale here, and the width of the gap 10020 is exaggerated for purposes of illustration.

[2181] One potential benefit of the performance of the embodiment of a nozzle design shown in Figures 100A-J is that it produces a spray in a hollow cone pattern. The lack of an edge offered by such a pattern may produce a more uniform distribution of droplet sizes than a fan spray. Additionally, a hollow cone spray pattern distributes liquid over a larger volume.

[2182] The nozzle shown in Figures 100A-J exhibits a geometry that is favorable to the creation of droplets of desired size for heat exchange. Specifically, the gap 10020 of the nozzle is 25 μm in this embodiment. This gap 10020 may be determined at least in part by a thickness of the washer 10005.

[2183] In the design of Figures 100A-J, the surface of the second piece 10004 adjacent to the outlet side of the gap 10020, is recessed. This recess may be helpful in avoiding deviation of the liquid spray attributable to the Coanda effect. According to certain embodiments, the side of the first (insert) piece may be recessed or beveled in order to avoid the Coanda effect. In other embodiments, the Coanda effect may be relied upon to divert or alter the flow direction.

[2184] A volume flow rate of 0.41 Gal/Minute 25.93 (ml/s) was measured from a stop watch and a graduated cylinder at a water pressure of 50 psig: 0.41 Gal/Minute; 25.93 (ml/s). The following table presents a brief summary of results of flowing liquid through the nozzle of Figure 100A-J at two different pressures.

Water Pressure (PSIG)		100	50
Run #		1, 4, & 12	2, 3 & 20
Average velocity in run 1 & 2 (m/s)		22.60	15.06
Droplet Size in 1.94" FOV (runs 4 & 3)	D32 (μm)	161.4	167.9
	DV50 (μm)	160.5	174.9
Droplet Size in 0.63" FOV (runs 12 & 20)	D32 (μm)	116.8	127.9
	DV50 (μm)	134.2	151.8
Breakup length from one instantaneous		1.15"	1.4"

image (inch)		
Sheet Angle	30°	
Thickness Water sheet at y= 3"	Greater than 20 mm	Maybe same as 100 psi

[2185] This table includes two measures of droplet size. The quantity D32 (also known as Sauter Mean Diameter or SMD), quantifies a spray with a fictitious droplet whose diameter represents the average ratio of volume to surface area for the droplets measured.

[2186] The quantity DV50 gives the droplet diameter which 50% of the droplets are smaller than. The quantity DV90 gives the droplet diameter which 90% of the droplets are smaller than.

[2187] For measurements taken with the 1.94" field of view (including runs 4 & 3), small droplets were not recognized. Thus, the droplet size statistics may not reflect all droplets.

[2188] An experimental setup for evaluating nozzle performance was created, as shown in Figures 101A-C. Water pressures of 50 and 100 PSIG were tested.

[2189] Because the nozzle of Figure 100A-J exhibits a high flow rate, a drop in the water pressure of between about 8 to 10 PSI occurs when the nozzle is spraying. So the actual water pressure experienced by the nozzle may be about 42-50 PSIG and 90-100 PSIG.

[2190] Because the two internal surfaces of the nozzle exhibit different angles (30° and 15°), the angle of the water sheet at the exit was not know before the test. As shown in Figure 101C, the average angle of 22.5° relative to the nozzle surface is used in the installation.

[2191] The angle between the water sheet and the nozzle surface calculated from the measurement is 30°. This indicates that the water sheet follows the 30° surface.

[2192] Figure 101A shows the Field of View (FOV) coordinates. In addition to the typical measurement plane (z=0), more runs had been conducted at different z locations, as shown in Figure 101B. This was to determine the thickness of the spray layer and the spray angle.

[2193] Figures 102-112B show results of spraying through the nozzle of Figure 100A-J, at 100 PSIG water pressure. Figure 102 shows the global flow structure from two instantaneous shadowgraphy images. The two images were not taken at the same time. The white lines indicate the break up length of 1.15".

[2194] The following table shows the mean velocity from runs 1 and 4 with 300 instantaneous velocity fields.

Run #		Min (m/s)	Max (m/s)	Average (m/s)	RMS (m/s)
1	Vx	-31.52	1.81	-20.43	4.77
	Vy	-23.25	25.29	0.53	9.69
	|V|	0.07	32.36	22.60	4.85
4	Vx	-19.37	-2.19	-9.01	4.33
	Vy	-5.57	6.13	0.28	1.78
	|V|	2.19	19.93	9.15	4.42

[2195] Figure 103 shows mean velocity vectors from run 1 and run 4. Figure 104 shows RMS velocity vectors from run 1 and run 4.

[2196] The droplet sizes resulting from run 1 are now discussed. The break up length is 1.15", and the field of view is 1.94". Since the spray does not break up until 2/3 of the FOV of run 1, the droplets size analysis is conducted only from x = -1.64" to -2.24".

[2197] Figure 105 shows one instantaneous image with recognized droplets from run 1. Only some of the droplets are shown. The rest of the droplets are either too small to be recognized or are out of focus.

[2198] Because small droplets are not recognized, the droplet size statistics are not completely accurate. However, these droplet size statistics are shown in the following table to give an idea of the big droplets distribution

Number of droplets	100630
D10 (μm)	119.2
D32 (μm)	155.2
DV10 (μm)	96.7
DV50 (μm)	164.3
DV90 (μm)	281.4
RMS (μm)	42.6

Figure 106 shows the histogram of the droplet size of run 1.

[2199] The droplet sizes resulting from run 4 are now discussed. Figure 107 shows one instantaneous image with recognized droplets from run 4. Only some of the droplets are recognized, with the rest either being too small to be recognized or out of focus.

[2200] The lack of recognition of small droplets again affects the overall accuracy of the droplet size statistics. However, the purpose of showing these droplet size statistics in the following table is provide a sense of the distribution of large droplets.

Number of droplets	244616
D10 (μm)	110.8
D32 (μm)	161.4
DV10 (μm)	91.1
DV50 (μm)	160.5
DV90 (μm)	497.0
RMS (μm)	40.3

Figure 108 shows the corresponding histogram of droplet size.

[2201] The droplet sizes resulting from runs 5-15 and 25-27 are now discussed. Figure 109A shows one instantaneous image with recognized droplets of run 12 (z = 7 mm) and Figure 109B shows one instantaneous image with recognized droplets of run 14 (z = 9 mm). Only certain droplets are recognized, with the rest of the droplets being either too small to be recognized, or out of focus.

[2202] Figure 110A shows the histogram of the droplet size of run 12. Figure 110B shows the histogram of run 14.

[2203] The following table shows the statistics of droplet size of runs 5-15 and 25-27.

Run	Z (mm)	Sheet Angle	# of droplets	D10 (μm)	D32 (μm)	DV10 (μm)	DV50 (μm)	DV90 (μm)	RMS (μm)

5	0	22.5	59884	55.4	93.1	47.6	113.3	189.3	29.0
6	1	23.3	65301	55.5	95.0	48.5	115.0	196.4	29.8
7	2	24.0	70230	56.5	99.5	50.9	121.8	203.9	31.5
8	3	24.8	70469	57.0	100.4	52.4	121.0	201.9	32.0
9	4	25.5	73430	57.9	102.9	54.3	124.4	205.2	33.0
10	5	26.3	73169	58.8	104.4	56.5	124.9	204.3	33.9
11	6	27.0	72683	59.5	105.0	57.8	125.0	201.5	34.3
12	7	27.7	70776	61.1	116.8	63.1	134.2	263.6	36.3
13	8	28.5	69952	60.9	107.8	60.9	127.8	204.3	35.6
14	9	29.2	68666	61.4	108.6	61.3	128.5	205.0	35.8
15	10	30.0	68069	61.4	109.8	61.5	130.5	212.8	36.1
25	4	25.5	56900	58.7	103.4	53.1	127.2	202.9	32.9
26	8	28.5	67633	60.3	108.1	58.9	130.2	210.5	35.3
27	10	30.0	66282	60.0	106.7	58.7	127.9	203.2	34.9

[2204] Figure 111A shows the droplet size distribution along z axis of runs 5 to 15 and runs 25 to 27. Figure 111B shows the same data in terms of sheet angle.

[2205] Figure 112A shows the number of droplets recognized at each z location of runs 5 to 15 and runs 25 to 27. Figure 112B shows the same data in terms of sheet angle.

[2206] Figures 112A-B show that the D32 line keeps increasing until z = 7 mm (sheet angle 27.7°), and is then stabilized for z = 8 to 10 mm (sheet angle from 28.5° to 30°). So the sheet thickness defined by the droplet size is more than 20 mm.

[2207] Figures 112A-B also show that the number of droplets recognized peak at 4 mm (sheet angle 25.5°), and the resulting sheet thickness defined would be more than 10 mm. Even though the number of droplets is growing smaller from z = 4 to 10 mm, this layer may be important owing to the large droplet size containing more water.

[2208] Figures 113-123B show results of spraying through the nozzle of Figure 100A-J, at 50 PSIG water pressure. Figure 113 shows the global flow structure from two instantaneous shadowgraphy images. The two images were not taken at the same time. The white lines indicate the break up length of 1.4".

[2209] The following table shows the mean velocity from runs 2 and 3 with 300 instantaneous velocity fields.

Run #		Min (m/s)	Max (m/s)	Average (m/s)	RMS (m/s)
2	Vx	-22.27	1.84	-13.56	3.57
	Vy	-18.06	19.2	0.42	6.79
	|V|	0.16	23.09	15.06	3.99
3	Vx	-12.14	-2.17	-5.96	2.31
	Vy	-3.32	3.54	0.07	1.14
	|V|	2.22	12.22	6.05	2.36

[2210] The velocity field for run 2 may lack accuracy because the flow is too smooth and not ideal for PIV analysis. The mean and RMS velocity vector fields from runs 2 and 3 are shown respectively in Figures 114 and 115.

[2211] The field of view of run 2 is 1.94", and the break up length is 1.4". Since the spray of run 2 does not break up until 2/3 of its field of view, the droplets size analysis is conducted only from x= -1.64" to -2.24".

[2212] Figure 116 shows one instantaneous image with recognized droplets from run 2. As indicated before, only certain droplets are recognized. The rest of the droplets are either too small to be recognized, or are out of focus.

[2213] Lack of recognition of the small droplets may affect accuracy of the droplet size statistics. However, the purpose of showing these statistics is to provide some idea of the distribution of big droplets.

[2214] The following table shows the statistics for droplet size from run 2:

Number of droplets	84843
D10 (μm)	128.6
D32 (μm)	180.9
DV10 (μm)	106.4
DV50 (μm)	195.8
DV90 (μm)	358.0
RMS (μm)	52.8

Figure 117 shows the corresponding histogram of the droplet size.

[2215] Figure 118 shows one instantaneous image with recognized droplets from run 3. Again, only certain droplets are recognized droplets, with the rest being either too small to be recognized, or out of focus. While this affects the droplet size statistics, these are indicated in the following table to provide an idea of the distribution of big droplets.

Number of droplets	219604
D10 (μm)	117.2
D32 (μm)	167.9
DV10 (μm)	96.5
DV50 (μm)	174.9
DV90 (μm)	495.5
RMS (μm)	45.2

Figure 119 shows a corresponding histogram of the droplet size from run 3.

[2216] Figure 120 shows one instantaneous image with recognized droplets of run 20, with only some of the droplets recognized. The rest of the droplets are either too small to be recognized, or are out of focus.

[2217] The following table shows the statistics of droplet size of runs 16 to 24.

Run	Z (mm)	Sheet Angle	# of droplets	D10 (μm)	D32 (μm)	DV10 (μm)	DV50 (μm)	DV90 (μm)	RMS (μm)
16	0	22.5	30990	64.7	123.1	62.6	154.6	248.9	39.3
17	2	24.0	45744	62.1	120.8	63.3	151.1	243.8	38.9
18	4	25.5	50251	64.3	126.5	69.6	155.1	251.1	41.4
19	6	27.0	50169	66.1	127.2	72.9	153.6	241.6	42.5
20	8	28.5	51067	66.8	127.9	74.7	151.8	241.3	43.1
21	10	30.0	49241	67.5	129.4	75.9	153.7	241.3	43.6

22	10	30.0	50406	65.5	123.5	71.4	148.4	228.6	41.5
23	8	28.5	49721	65.6	123.5	69.6	149.3	229.6	41.1
24	4	25.5	44984	62.9	118.3	61.8	146.9	232.0	38.3

Figure 121 shows a histogram of the corresponding droplet size from run 20.

[2218] Figure 122A plots droplet size distribution along the z axis for runs 16-21 and 22-24 in terms of mm. Figure 122B plots this droplet size distribution data in terms of sheet angle.

[2219] Figure 123A shows the number of droplets recognized at each z location of runs 16 to 24. Figure 123B shows the same data in terms of sheet angle.

[2220] Both lines of the D32 and the number of droplets recognized reach flat asymptote lines at z = 4 mm (sheet angle 25.5). So the sheet thickness is also more than 20 mm.

[2221] In contrast with the results observed with a water pressure of 100 psig, the last three runs that were shifted in the x direction are different with those without shift. This suggests that the lower water pressure (50 psig) case may result in one or more of a smaller cone angle, a relatively more uniform droplet size distribution in space, and a bigger droplet size.

[2222] One possible benefit offered by the nozzle structure shown in Figures 100A-J, is the lack of features projecting into the cylinder. In particular, because the opening of the slot is flush with the wall of the chamber, the nozzle will not require providing additional dead volume within the cylinder to accommodate it. Lower dead volume is favorable to creating a high compression or expansion ratios.

[2223] Another possible advantage of the nozzle structure shown in Figure 100A-J is ease of fabrication. In particular the paired recesses defining the nozzle that are present in the opposing surfaces of the plates, are readily machined with precision even in complex shapes, prior to mating of the plates.

[2224] As mentioned above, embodiments of sprayers according to the present invention may be particularly suited for use in injecting liquid droplets into a pressurized gas. In some embodiments, this pressurized gas may be experiencing compression, or may be undergoing expansion. In certain embodiments, the sprayer may be configured to inject liquid into the pressurized gas for purposes of performing heat exchange.

[2225] Embodiments of the present invention may be suited to the injection of droplets of liquid water into a pressurized gas. In some embodiments the gas may be air.

[2226] Embodiments of sprayers according to the present invention may be suited to injecting liquid into compressed gas that is present within a chamber in which compression and/or expansion is taking place. One example of such a chamber is a cylinder housing a reciprocating member such as a solid piston. Another example is a chamber housing a moveable member such as a screw. Other examples of apparatuses with which embodiments of a sprayer according to the present invention could possibly be used, include but are not limited to turbines, multi-lobe blowers, vane compressors, gerotors, and quasi-turbines.

[2227] Embodiments of sprayer structures according to the present invention may be configured to receive the pressurized flow of liquid through a liquid valve structure. Examples of such liquid valve structures that are suited for flowing pressurized liquid to a sprayer structure, include but are not limited

to solenoid-actuated valves, spool valves, poppet valves, or needle valves. The liquid flow valves may be actuated by mechanical, magnetic, electromagnetic, pneumatic, or hydraulic forces.

[2228] In certain embodiments, the sprayer structure may be configured to receive the pressurized flow of liquid through a manifold structure. In some embodiments, a sprayer structure may be configured to receive the pressurized flow of liquid from a valve through a separate conduit, a portion of which may be shared with other sprayers.

[2229] In certain embodiments, the conduit connecting the sprayer structure to a liquid flow valve, may be made as short as possible. Such a configuration could be useful to reduce potential problems associated with bubbles forming in the conduit, due to outgassing when the valve is closed. Such outgassing could occur due to the liquid being supplied to the valve in pressurized form, with a lower pressure existing in the chamber that is receiving the liquid flowed through the sprayer.

[2230] In certain embodiments, a sprayer structure according to an embodiment of the present invention may be positioned relative to a second sprayer that is also in fluid communication with the same chamber. In some embodiments, the dimensions of the sprayers may be the same, but they could be oriented relative to one another in a particular manner.

[2231] For example, in the embodiment of Figures 100A-J, the insert includes a surface angled at 15° relative to the plane of the top of the insert, which may be the same as a wall of a compression and/or expansion chamber. In certain embodiments, two or more sprayers may have their outlet slots oriented in a consistent manner relative to a particular direction. According to certain embodiments, this direction may be influenced by factors such as a position of a gas inlet valve relative to the sprayer, and/or a direction of movement of the moveable member within the chamber.

[2232] Embodiments of the present invention as have been described so far, relate to a sprayer structure for use in injecting liquid spray to perform heat exchange with a compressed gas. However, it will be appreciated that the sprayer structure is not limited to use in any particular application, and could be employed where liquid is to be introduced into a gas.

[2233] The following claims relate to embodiments of nozzles.

[2234] 1. A liquid spray nozzle comprising:

a first piece;

a second piece; and

a securing member configured to secure the first piece to the second piece to define between them a space comprising,

a direction changing portion configured to change a direction of liquid received from a liquid source, and to flow the liquid to an outlet of the direction changing portion having a first cross-sectional area;

a velocity elevating portion configured to receive liquid from the outlet of the direction changing portion through an inlet having a second cross-sectional area, the velocity elevating portion configured to accelerate a velocity of liquid flowed from the inlet of the velocity elevating portion, and

an outlet in fluid communication with the velocity elevating portion and having a third cross-sectional area,

wherein the second cross-sectional area is significantly smaller than the first cross-sectional area and is approximately the same size or slightly larger than the third cross-sectional area.

[2235] 2. A liquid spray nozzle according to claim 1 wherein the first piece is configured to be inserted within an opening of the second piece.

[2236] 3. A liquid spray nozzle according to claim 2 wherein a periphery of the opening is substantially circular.

[2237] 4. A liquid spray nozzle according to claim 2 wherein the securing member comprises a threaded bolt.

[2238] 5. A liquid spray nozzle according to claim 4 wherein the threaded bolt is received by threads in a jam nut.

[2239] 6. A liquid spray nozzle according to claim 4 wherein the threaded bolt is received by threads in the first piece.

[2240] 7. A liquid spray nozzle according to claim 2 further comprising a spacer positioned between the first piece and the second piece.

[2241] 8. A liquid spray nozzle according to claim 7 wherein the securing member comprises a threaded bolt and the spacer comprises a washer.

[2242] 9. A liquid spray nozzle according to claim 2 wherein a first region of top surface of the second piece proximate to the outlet, defines a recess.

[2243] 10. A liquid spray nozzle according to claim 9 wherein upon insertion of the first piece into the second piece, a top surface of the first piece is flush with a second region the top surface of the second piece lying outside of the first region.

[2244] 11. A liquid spray nozzle according to claim 1 wherein the liquid flowed out of the outlet exhibits a Sauter mean diameter of between about 10-50 um.

[2245] 12. A liquid spray nozzle according to claim 1 wherein the liquid flowed out of the outlet exhibits a flow rate of between about 20 and 0.01 liters per second.

[2246] 13. A liquid spray nozzle according to claim 1 wherein an axis of the velocity enhancing portion is inclined at other than normal to a top surface of the first piece and a top surface of the second piece.

[2247] 1. A method comprising:

flowing a liquid from a liquid source to a chamber housing a moveable member, through a space defined between a first piece and a second piece, the space comprising,

a direction changing portion configured to change a direction of liquid received from a liquid source, and to flow the liquid to an outlet of the direction changing portion having a first cross-sectional area;

a velocity elevating portion configured to receive liquid from the outlet of the direction changing portion through an inlet having a second cross-sectional area, the velocity elevating

portion configured to accelerate a velocity of liquid flowed from the inlet of the velocity elevating portion, and

an outlet in fluid communication with the velocity elevating portion and with the chamber, the outlet having a third cross-sectional area,

wherein the second cross-sectional area is significantly smaller than the first cross-sectional area and is approximately the same size or slightly larger than the third cross-sectional area.

[2248] 2. A method according to claim 1 wherein the liquid is flowed through the space to the chamber during expansion of compressed gas within the chamber.

[2249] 3. A method according to claim 1 wherein the liquid is flowed through the space to the chamber during compression of gas within the chamber by the moveable member.

[2250] 4. A method according to claim 1 wherein the liquid is flowed through the space to the chamber during inflow of gas into the chamber.

[2251] 5. A liquid spray nozzle according to claim 1 wherein the first piece is inserted within an opening of the second piece.

[2252] 6. A liquid spray nozzle according to claim 5 wherein the direction changing portion, the velocity acceleration portion, and the outlet comprise a toroidal shapes.

[2253] Embodiments in accordance with the present invention are not limited to injection of liquids in any particular direction relative to a direction of motion of a moveable member, or to a direction of an inlet flow of gas. For example, the particular embodiments of Figures 50A-B feature liquid sprayers are positioned on opposite end walls of a cylinder, with valve structures positioned on side walls of the cylinder.

[2254] In the configuration of these embodiments, owing to the location of the sprayers, liquid may be injected into the chamber in a direction parallel to the movement of the piston. Such an orientation may promote interaction between the gas and the injected liquid to form a liquid-gas mixture having the desired properties.

[2255] In these embodiments, the direction of liquid injection is not necessarily substantially coincident with the direction of inlet of gases through gas flow valves located on the side walls of the chamber. Such an orientation may promote interaction between the gas and the injected liquid to form a liquid-gas mixture having the desired properties.

[2256] The particular embodiment of Figure 51 shows sprayers are positioned on opposite side walls of the chamber, with the valve structures positioned on other side walls. Accordingly, a direction of liquid injection may not necessarily be substantially parallel to either a direction of gas flowed into the chamber (in compression or expansion mode), or to a direction of movement of the piston within the chamber. Such lack of coincidence between the direction of liquid injection and directions of inlet gas flow or piston movement, may promote gas-liquid mixing and the formation of a liquid-gas mixture having the desired properties.

[2257] In other embodiments, however, liquid may be injected into the chamber in a direction substantially corresponding to a direction of inlet gas flow to the chamber. Such directionality of liquid injection may promote formation of a liquid-gas mixture having the desired properties.

[2258] For example, while the embodiments of Figures 50A-B and Figure 51 show the low pressure side and high pressure side valves as being disposed on walls of the chamber different from the location of the liquid sprayers, this is not required by the present invention. Figure 124 shows an alternative embodiment wherein sprayers 12438 and valves 12412 and 12422 are located on the same side walls 12408b of the chamber 12408.

[2259] In the embodiment of Figure 124, a three-way valve 12436 is provided between the pump 12434 and the sprayers 12438 to selectively direct the flow of liquid to the particular sprayers located on the chamber side wall adjacent to low pressure side valve 12412, or to the sprayers located on the chamber side wall adjacent to the high pressure side valve 12422, depending upon the operational mode. Such a valve may also be configurable to block flow through the valve in any direction, thereby isolating the liquid circulation system from pressure changes in the chamber when liquid is not being introduced.

[2260] The embodiment of Figure 124 may offer an advantage in that the sprayers can be oriented to inject liquid droplets in a direction substantially corresponding to a direction of gas flow into the chamber, in either compression mode or in expansion mode. Such coincidence between the directions of liquid injection and gas flow may promote formation of a liquid-gas mixture having the desired properties.

[2261] The embodiment of Figure 124 may offer an advantage in that the sprayers may be oriented to inject liquid droplets in a direction that is not substantially parallel to a direction of movement of the moveable element within the chamber during compression or expansion. Such lack of coincidence between the directions of liquid injection and piston movement may promote formation of a liquid-gas mixture having the desired properties.

[2262] While the embodiment of Figure 124 shows sprayers positioned on the chamber side wall above the respective valves, this specific configuration is not required by the present invention and variations are possible. For example, Figure 124A shows a view of a side wall 12450 from inside a chamber, showing valve 12452 including valve plate 12454. Figure 124A shows a plurality of sprayers 12456 surrounding the valve and configured to inject liquid in a plurality of trajectories into the inlet gas flow.

[2263] In certain embodiments, the sprayers may be configured to inject liquid in a direction substantially parallel to a direction of flow of gas through the valve. In other embodiments, one or more of the sprayers may be configured to inject liquid in a direction not substantially parallel to a direction of flow through the valve. In such embodiments, the outlets of the sprayers may be aligned in a uniform or non-uniform manner relative to each other.

[2264] While the above embodiments show sprayers positioned on a single wall or on opposing walls of a compression or expansion chamber, the present invention is not limited to such configurations. For example, Figure 125 shows an alternative embodiment wherein sprayers are located both on the end wall

and on adjacent side walls of the chamber. In certain embodiments, such a configuration may be facilitated by providing a liquid manifold 12570 that extends around various sides of the chamber 12508, with the sprayers in common liquid communication with that manifold. The view of Figure 125 depicts only a cross-section, and thus in certain embodiments the liquid manifold could also extend out of the plane of the paper to allow fluid communication with sprayers located on other chamber walls.

[2265] Figure 126 shows yet another embodiment, wherein the sprayers 12638 and each of the valves 12612 and 12622 are located on the same (end) wall 12608a of the chamber 12608. Such orientation of the sprayers relative to the valves, potentially allows use of the same sprayers to introduce liquid during both compression and expansion. This could avoid the need for design and placement of separate sprayers for compression and expansion, and would also avoid the additional valve and conduit complexity for routing liquid to respective sets of sprayers exclusive to compression or expansion.

[2266] While the particular embodiment of Figure 126 shows the sprayers located between the valves, this is not required. In alternative embodiments, the sprayers could surround the valves in a manner similar to that shown in Figure 124A.

[2267] As shown in Figure 126, a valve 12636 may be positioned between the sprayer and the pump to isolate the fluid circulation system from pressure changes occurring in the chamber when liquid is not being introduced.

[2268] The embodiment of Figure 126 may offer an advantage in that the sprayers are oriented to inject liquid droplets in a direction substantially corresponding to a direction of gas flow into the chamber. Such coincidence between the directions of liquid injection and gas flow may promote formation of a liquid-gas mixture having the desired properties.

[2269] The embodiment of Figure 126 may also offer an advantage in that the sprayers are oriented to inject liquid droplets in a direction substantially corresponding to a direction of movement of the moveable element within the chamber during compression or expansion. Such coincidence between the directions of liquid injection and piston movement may also promote formation of a liquid-gas mixture having the desired properties.

[2270] While the embodiment of Figure 126 may offer certain potential benefits, it positions a number of elements (valves, valve actuators, multiple sprayers and liquid conduits) within a relatively small region at the end wall of the chamber. Such a clustering of elements within a small space may affect design, construction, inspection, and/or maintenance of the apparatus.

[2271] However, it is typically the orientation of the sprayers relative to a gas inlet valve, that is important in determining the character of the liquid-gas mixture. In particular the liquid is injected into the inlet gas for heat exchange during compression/expansion processes. Because compression or expansion may be concurrent with inlet gas flow, it may be desirable to position the sprayers in a manner promoting rapid interaction between incoming gas and the liquid spray.

[2272] By contrast, the orientation of the liquid sprayers relative to the outlet valve may be less important. This is because the outlet valve is utilized simply to exhaust the liquid-gas mixture once an exchange of thermal energy during compression or expansion has already taken place.

[2273] Accordingly, certain embodiments of the present invention may introduce liquid through sprayers oriented relative to a single valve dedicated to regulating a flow of gases into the chamber in compression and/or expansion modes. Figure 127 shows a simplified schematic view of one such embodiment, wherein inlet valve 12712 is positioned on end wall 12708a of chamber 12708.

[2274] In the embodiment of Figure 127, a plurality of sprayers 12738 are also positioned on the end wall 12708a around inlet valve 12712. These sprayers are in fluid communication with a common liquid manifold 12770 that is configured to receive liquid from pump 12734. Outlet valve 12722 is provided in side wall 12708b of the chamber.

[2275] By careful design of the sprayers and their position relative to the inlet valve, liquid may be introduced to the chamber to result in a liquid-gas mixture possessing the desired characteristics (such as droplet size, uniformity of droplet distribution, liquid volume fraction, temperature, and pressure). And because the same valve is used to admit gas in both the compression and expansion modes, a liquid-gas mixture having desired properties may be produced in each case.

[2276] The conditions under which liquid is introduced, may different in the compression case versus the expansion case. For example during compression, the liquid will be introduced into a gas flow having a lower pressure. During expansion, the liquid will be introduced into a compressed gas flow having a higher pressure.

[2277] Accordingly, in the embodiment of Figure 127 the operational parameters of certain elements may be controlled to produce a liquid-gas mixture having the desired properties. One example of a parameter which may be varied is the velocity at which the liquid is introduced into the chamber. Such a velocity parameter may be affected by variables such as the speed of the pump, and/or the dimensions of the sprayer, and/or characteristics of the conduit leading to the sprayer, such as bore, length, and number/degree of turns. In certain embodiments, the sprayer may comprise a nozzle having an orifice with dimensions adjustable to control a velocity of the liquid. In certain embodiments, the characteristics of the conduit leading to the sprayer may be changed (for example by actuation of a valving changing a path of liquid flow).

[2278] In certain embodiments, a pressure of the liquid may be changed. This may be done, for example, by altering a characteristic of operation of the pump (for example pump speed). In certain embodiments, liquid pressure may be changed by manipulation of a valve to give rise to pressure accumulation that is periodically relieved by bursts of liquid flows at high velocities.

[2279] The size of the liquid droplet may also affect its interaction with gas flows of different pressures. For example, a liquid droplet of a greater size may be able to penetrate more deeply into a compressed volume of gas. Thus in certain embodiments, the sprayer may be designed to produce droplet size that is different for the compression versus the expansion case.

[2280] The embodiment of Figure 127 may offer an advantage in that the sprayers may be oriented to inject liquid droplets in a direction substantially corresponding to a direction of gas flow into the chamber. These sprayers are also oriented to inject liquid droplets in a direction substantially

corresponding to a direction of movement of the moveable element within the chamber during compression or expansion.

[2281] Such coincidence between the directions of liquid injection and gas flow and piston, movement may promote formation of a liquid-gas mixture having the desired properties. However, embodiments of the present invention are not limited to flows of liquid in any particular direction relative to gas flows or piston movement.

[2282] Figure 128 accordingly shows an alternative embodiment, wherein the inlet valve 12812 is located on a side wall 12808a of the chamber 12808, and the sprayers 12838 are positioned on the end wall 12808b of the chamber. In this embodiment, a trajectory of the liquid injection does not substantially correspond to a direction of gas inlet into the chamber. Such an embodiment may promote formation of a liquid-gas mixture having the desired properties.

[2283] Figure 129 shows still another embodiment, wherein the sprayers 12938 are positioned on a plurality of chamber walls that are orientated differently relative to a direction of inlet gas flow and a direction of piston movement. Such a configuration may be facilitated by use of a liquid manifold 12970 extending around multiple sides of the compression or expansion chamber. The view of Figure 129 depicts only a cross-section, and thus in certain embodiments the liquid manifold could also extend out of the plane of the paper to allow fluid communication with sprayers located on other walls of the chamber.

[2284] Embodiments of the present invention are not limited to the particular liquid nozzle injection design shown in Figures 100A-J. For example, Figure 80 shows the spray profile of yet another type of nozzle where the insert has a square pyramidal shape, although the present invention is not limited to an insert having this or any particular number of sides.

[2285] Figures 133A-G show an alternative embodiment of still another embodiment of a nozzle design. In this nozzle design, a first piece 13302 is inserted within opening 13303 of the second piece 13304. The pieces are secured utilizing a bolt 13310 threaded into opening 13308 of the second piece. The back of bolt 13310 is secured to the back of the second piece 13304 utilizing a jam nut 13306.

[2286] Washer 13305 is seated on surface 13304b of the second piece 13304. The first piece 13302 is seated on the washer.

[2287] As shown in the cross-sectional view of Figure 133F, the flow of liquid to be sprayed is indicated with the arrows as shown. This liquid flows through orifice(s) 13321 (here twelve in number) that are present in the second piece 13304.

[2288] The liquid then flows through the passageway 13309 defined between opposing surfaces 13302a and 13304a offered by the first and second respective pieces. Because passageway 13309 offers a smaller cross-sectional area to the incoming liquid, velocity of the liquid is enhanced.

[2289] In addition, the respective surfaces 13302a and 13304a are inclined at different angles relative one another (surface 13302a is inclined at an angle of 15°, while surface 13304a is inclined at an angle of 30°). Similar to the nozzle embodiment of Figures 100A-J, this geometry is arranged to have substantially the same cross-sectional area as the liquid flows through passageway 13309, thereby

reducing the incidence of cavitation while inducing the velocity vector profile to create a hollow conical sheet of liquid emerging from the nozzle.

[2290] The pressurized flowing liquid then ultimately exits from passageway 13309 and the nozzle through narrow gap 13320. Figure 133F is not drawn to scale here, and the width of the gap 13320 is exaggerated for purposes of illustration.

[2291] The nozzle shown in Figures 133A-G exhibits a geometry that is favorable to the creation of droplets of desired size for heat exchange. Specifically, the gap 13320 of the nozzle is 25 μm in this embodiment. This gap 13320 may be determined at least in part by a thickness of the washer 13305.

[2292] In the design of Figures 133A-G, the surface of the second piece 13304 adjacent to the outlet side of the gap 13320, bears a first recess 13330, and a second recess 13340. These recesses may be helpful in avoiding deviation in the path of the liquid spray attributable to the Coanda effect.

[2293] The nozzle design embodiment of Figures 133A-G may offer certain possible benefits. For example, the careful use of recesses in the second piece and thicknesses of material in constructing the first piece, allows the top surface of the first piece to be flush with the top surface of the second piece. This prevents the first piece from projecting into the chamber, reducing dead volume.

[2294] Another possible benefit of the embodiment of the nozzle of Figures 133A-G, is the ability to fix the first and second pieces together under conditions of vibration and liquid flow. In particular, these two pieces are secured together by bolt, which is in turn secured against the second piece by a jam nut, which resists loosening of the bolt under operational conditions of the nozzle.

[2295] Nozzle designs according to the present invention are not limited to the particular embodiments described above. For example, while Figures 100A-J and Figures 133A-G show a nozzle having a second piece with an array of (twelve) bores with axes oriented perpendicular to the surface of the second piece, this is not required by the present invention.

[2296] According to alternative embodiments, the axes of the bores could be oriented differently, for example offset at a consistent angle relative to the surface normal. Such a configuration could impart a swirl to the liquid flowed out of the nozzle. Such a swirled flow of liquid could exhibit beneficial properties, including but not limited to a reduced break-up length.

[2297] Moreover, the operational characteristics of a particular nozzle can be determined by differences in relative dimensions between elements. For example, Figure 134A shows an enlarged view of the gap region 13400 formed between two pieces 13402 and 13204 of a nozzle 13406.

[2298] Liquid flows out of the nozzle at an angle approximately normal to the plane formed between the ends of the pieces 13402 and 13404. Accordingly, changing the relative lengths of these pieces can affect the spray angle.

[2299] Figure 134B shows an alternative embodiment with the length L of the first piece 13402 shortened relative to the embodiment of Figure 134A. This dimensional change results in a corresponding increase in the flow angle A relative to the plane of the surface of the nozzle, as compared with the embodiment of Figure 134.

[2300] Figure 134C shows an alternative embodiment with the length L of the first piece 13402 lengthened relative to the embodiment of Figure 134A. This dimensional change results in a corresponding decrease in the flow angle A relative to the plane of the surface of the nozzle, as compared with the embodiment of Figure 134.

[2301] Embodiments of spray nozzles according to the present invention may exhibit particular performance characteristics. One performance characteristic is droplet size.

[2302] Droplet size may be measured using DV50, Sauter mean diameter (also called SMD, D32, d_{32} or D[3, 2]), or other measures. Embodiments of nozzles according to the present invention may produce liquid droplets having SMD's within a range of between about 10-200 um. Examples of droplet sizes produced by embodiments of nozzles according to the present invention include but are not limited to those having a SMD of about 200 microns, 150 microns, 100 microns, 50 microns, 25 microns, and 10 microns.

[2303] Another performance characteristic of liquid spray nozzles according to embodiments of the present invention, is flow rate. Embodiments according to the present invention may produce a flow rate of between about 20 and 0.01 liters per second. Examples of flow rates of embodiments of nozzles according to the present invention are 20, 10, 5, 2, 1, 0.5, 0.25, 0.1, 0.05, 0.02, and 0.01 liters per second. , breakup length, spray pattern, spray cone angle, fan angle, angle to surface (for fan sprays), droplet spatial distribution

[2304] Another performance characteristic of liquid spray nozzles according to embodiments of the present invention, is breakup length. Liquid output by embodiments of nozzles according to the present invention may exhibit a breakup length of between about 1-100 mm. Examples of breakup lengths of sprays of liquid from nozzles according to the present invention include 100, 50, 25, 10, 5, 2, and 1 mm.

[2305] Embodiments of nozzles according to the present invention may produce different types of spray patterns. Examples of spray patterns which may be produced by nozzle embodiments according to the present invention include but are not limited to, hollow cone, solid cone, stream, single fan, and multiple fans.

[2306] Embodiments of nozzles according to the present invention may produce spray cone angles of between about 20-180 degrees. Examples of such spray cone angles include but are not limited to 20°, 22.5°, 25°, 30°, 45°, 60°, 90°, 120°, 150°, and 180°.

[2307] Embodiments of nozzles according to the present invention may produce spray fan angles of between about 20-360 degrees. Examples of such fan angles include but are not limited to 20°, 22.5°, 25°, 30°, 45°, 60°, 90°, 120°, 150°, 180°, 225°, 270°, 300°, 330°, or 360°. Examples of fan spray angles to surface possibly produced by embodiments of the present invention, include but are not limited to 90°, 80°, 60°, 45°, 30°, 22.5°, 20°, 15°, 10°, 5°, or 0°.

[2308] Droplet spatial distribution represents another performance characteristic of liquid spray nozzles according to embodiments of the present invention. One way to measure droplet spatial distribution is to measure the angle of a sheet or cone cross-section that includes most of the droplets that deviate from the sheet. In nozzle designs according to embodiments of the present invention, this angle

may be between 0-90 degrees. Examples of such angles possibly produced by embodiments of the present invention include but are not limited to 0°, 1°, 2°, 5°, 7.5°, 10°, 15°, 20°, 25°, 30°, 45°, 60°, 75°, or 90°.

[2309] According to certain embodiments of the present invention, it may be important to control the amount of liquid introduced into the chamber to effect heat exchange. The ideal amount may depends on a number of factors, including the heat capacities of the gas and of the liquid, and the desired change in temperature during compression or expansion.

[2310] The amount of liquid to be introduced may also depend on the size of droplets formed by the spray nozzle. One measure of the amount of liquid to be introduced, is a ratio of the total surface area of all the droplets, to the number of moles of gas in the chamber. This ratio, in square meters per mole, could range from about 1 to 250 or more. Examples of this ratio which may be suitable for use in embodiments of the present invention include 1, 2, 5, 10, 15, 25, 30, 50, 100, 125, 150, 200, or 250.

[2311] Certain nozzle designs may facilitate the fabrication of individual nozzles. Certain nozzle designs may also permit the placement of a plurality of nozzles in a given surface proximate to one another, which can enhance performance.

[2312] For example, Figure 130A shows the spray trajectories of a number of nozzles 13010 that are present on the same wall of a cylinder. In certain regions 13012, sprays of liquid from two or even more of the nozzles overlap with each other. This overlap creates the potential that the liquid spray droplets will collide with each other, thereby further breaking them up into smaller sizes for heat exchange.

[2313] The flexibility in fabrication and placement of a plurality of spray nozzles, may offer additional enhancements to performance. For example, in certain embodiments the orientation of the dimensional axis of spray structures relative to a direction of piston movement and/or a direction of gas inflow, may be uniform or non-uniform relative to other spray structures.

[2314] Thus in certain embodiments, the dimensional axis of the spray structures could each be offset from a gas flow direction in a consistent manner, such that they combine to give rise to a bulk effect such as swirling. In other embodiments, the dimensional axis of the spray structures could be oriented in a non-uniform relative to certain direction, in a manner that is calculated to promote interaction between the gas and the liquid droplets. Such interaction could enhance homogeneity of the resulting mixture, and the resulting properties of the heat exchange between the gas and liquid of the mixture.

[2315] In certain embodiments, one or more spray nozzles may be intentionally oriented to direct a portion of the spray to impinge against the chamber wall. Such impingement may serve to additionally break up the spray into smaller droplets over a short distance.

[2316] Figure 130B shows still another approach that is designed to enhance breakup of liquid sprays into droplets of smaller sizes. In this embodiment, the nozzle 13020 is designed to produce a fan spray which impinges against the chamber walls. Sonic or ultrasonic energy 13022 from transducers 13024 also impinges the chamber walls, causing them to vibrate.

[2317] This vibration alters the effective position or angle of liquid impingement, and hence the position or angle of reflection of the liquid off of the vibrating walls. Such reflection in turn serves to

further distribute a given volume of liquid spray over a larger area, thereby breaking it up into smaller droplets to effectively perform heat exchange.

[2318] The present invention is not limited to the particular embodiment shown in Figure 130B. In particular, while this figure shows the ultrasonic transducers as being positioned outside of the chamber, alternatively or in conjunction with such external placement, the sonic transducers could be positioned within the chamber.

[2319] Also, while this embodiment describes liquid impinging on a surface indirectly energized by a sonic or ultrasonic transducer, this is not required. According to certain embodiments, liquid may directly interact with a surface of a sonic or ultrasonic transducer. Some types of transducers are piezoelectric, electromagnetic, and magnetostrictive.

[2320] The direction at which a sprayer is configured to introduce liquid, is not necessarily normal to the chamber wall in which the nozzle is formed. For example in the embodiment of Figs. 100A-J the outlet slot is inclined at a large angle relative to normal of the chamber wall.

[2321] A dimensional axis of a sprayer could lie angled toward or away from a direction in which inlet gas flows into the chamber (in compression or expansion). This direction of liquid introduction could also be angled toward or away from a direction of movement of the piston during introduction of the liquid in compression or expansion.

[2322] Such inclination of the spray can serve to effectively increase the path of the injected liquid, before it encounters the piston head or some other solid surface. Such a longer path affords more time for the liquid to break up into individual droplets having the desired small size (and hence large surface area) favorable for efficient heat exchange. This can be significant in designs where the overall length of the piston stroke is short relative to a the break-up length of the sprayed liquid.

[2323] The previous embodiments have depicted the chamber as a simplified interior space defined within walls. In certain embodiments, however, an interior of the chamber may exhibit a more complex profile.

[2324] For example, Figure 131 shows a simplified cross-sectional view of an embodiment of a compression or expansion chamber housing a double-acting piston comprising a piston head 13106a and a piston shaft 13106b. The piston head defines two chambers 13108 and 13109, which are in fluid communication with external conduits through valve openings 13111 and 13123, and valve openings 13112 and 13122 respectively.

[2325] Figure 131 shows in dashed lines the position of the piston head at the two extreme positions 13130 and 13132. At these positions, the piston head covers a portion of the valve opening through which gases are expected to flow.

[2326] Figure 131 also shows that the end walls 13108a and 13109a of the chambers include respective recessed portions 13108b and 13109b proximate to the valve openings. The interior spaces 13108c and 13109c offered by these recesses can accommodate flows of gas through the valve openings when they are partially obstructed by the piston at positions 13130 and 13132.

[2327] Accordingly, in certain embodiments the liquid sprayers may be specifically oriented relative to interior chamber spaces, in order to promote formation of a liquid-gas mixture having the desired properties. For example, in the embodiment of Figure 131 the sprayers 13138 may be specifically oriented in the end walls to introduce liquid droplets into the spaces 13108c and 13109c that are in the expected path of gas flows inlet through the valve openings.

[2328] While the specific embodiment of Figure 131 shows a chamber having a particular interior profile, the present invention is not limited to the injection of liquid into this or any other type of chamber. For example, Figure 132 shows a cross-sectional view of another chamber housing a double-acting piston.

[2329] In the embodiment of Figure 132, the piston head 13206a exhibits a convex shape, with the corresponding end walls of the chamber exhibiting a concave shape. Figure 132 thus shows the sprayers 13238 positioned in the end walls to inject liquid into the space defined between the convex piston head and the concave wall shape.

[2330] The particular embodiments of Figures 131 and 132 show the injection of liquids into chamber having a moveable member that is moveable in the horizontal direction. Thus embodiments of the present invention are not limited to the injection of liquids along any particular axis, and liquid can be injected into a chamber having a direction of piston movement in the horizontal or vertical direction.

[2331] In certain embodiments, direct injection of liquids may take into account changing conditions occurring during gas compression or expansion processes. One example of such a changing condition is temperature.

[2332] Specifically, gas heating does not take place at a constant rate over a compression stroke. Instead, heating intensifies at the end of the stroke as pressure builds to a higher level. Thus, in order to achieve compression under near-isothermal conditions, a greater amount of heat exchange may be required near an end of a compression stroke to maintain temperatures within a certain range. This greater amount of heat exchange may in turn require the introduction of additional volumes of liquid near an end of the stroke, which can be accomplished utilizing particular arrangements of liquid introduction apparatuses.

[2333] The effective volume of liquid introduced may be controlled in a variety of ways, taken alone or in combination. For example, the sprayers may be smaller or larger in size and/or fewer or larger in number, thereby reducing the amount of liquid injected. Alternatively or in conjunction with these factors, the sprayers may receive liquid that is flowed at small or large velocities, such that liquid is injected at a relatively low or high flow rate.

[2334] Further alternatively or in combination with the above factors, the sprayers may be configured to generate droplets of a different size. Such different sized-droplets may offer less or more surface area for heat exchange, and hence represent a smaller effective volume.

[2335] While the above description has focused on changes in temperature occurring over a compression stroke, other conditions may also change. For example, another example of a changing condition is pressure. Specifically, during initial stages of the compression process, the pressure of the

gas is lower, allowing penetration and mixing of water droplets in the gas. By contrast, at the end of the compression stroke the pressure of the gas is much higher. This changed pressure condition may serve to exclude liquid, inhibiting interaction between the droplets and the gas because the gas pressure and/or density resists the impetus of the injected liquid.

[2336] The design of a particular apparatus could take into account this effect. For example, air being compressed at a BDC position of the chamber would be expected to be at a lowest pressure, encouraging interaction and mixing between the gas and the injected liquid. Accordingly, in this embodiment the sprayers at this position may be configured to inject a largest effective volume of liquid, utilizing one or more of the approaches described above.

[2337] While the above examples have focused upon changes in temperature and pressure occurring during a compression stroke, volume represents still another example of a changing condition. Specifically, during initial stages of the compression process, the gas is distributed over a large volume, offering more space for the positioning of sprayers to interact with the gas. By contrast, at the end of the compression stroke the gas is confined to a much smaller volume, reducing the space available for the sprayers to inject the liquid. Again, one or more of the liquid introduction factors described above may be employed to provide an effective liquid volume for heat exchange at the appropriate location in the chamber.

[2338] Designs of apparatuses utilizing the introduction of liquid according to embodiments of the present invention, should take into account the timing of liquid injection. For example, while liquid injection may take place at the beginning of the compression stroke, according to certain embodiments liquid injection may also occur as air is being flowed into the chamber during the immediately preceding stroke of the piston.

[2339] Such an approach could change the desirable configuration for the liquid injection system. For example, a consideration could be the orientation of the sprayers relative to the incoming gas, rather than various locations along the direction of the piston stroke. Such positioning of sprayers configured to inject large effective volumes close to the inlet valve, could promote gas-liquid mixing as the droplets interact with the gas flowing in to fill the chamber prior to compression. Of course, in certain embodiments liquid could continue to be directly injected even after the chamber is filled with gas, and as the piston moves toward TDC in compression.

[2340] Other configurations of liquid injection systems may be appropriate for the expansion case. There, while the relationship between the position of the piston in the stroke, and temperature and pressure is the same as that shown in connection with compression, these conditions vary in the opposite direction in time. Also, the particular values for pressure and temperature may be different during expansion and compression. Accordingly, the relative configuration of injection systems may be different in order to achieve optimal heat exchange between gas and injected liquid in the context of expansion.

[2341] The specific embodiments depicted so far have been provided for purposes of illustration only, and the present invention should not be limited to them. For example, while many of the chambers

described above utilize two or more ports to flow gases into and out of a chamber, this is not required by the present invention.

[2342] According to alternative embodiments, a compression and/or expansion chamber could have a single port which is used to flow gases into and out of the chamber, in the compression and/or expansion mode. Such gas flows through the port may be regulated by a single valve, which is opened to admit gas, closed, and then opened to flow (compressed or expanded) gas out of the chamber.

[2343] This single port could be in communication with appropriate conduits on high- or low-pressure sides through a three way valve or a valve network, in order to allow appropriate routing of the compressed or expanded gases. Use of such a configuration having only a single port and corresponding gas flow valve, could simplify the structure of the device and substantially reduce costs.

[2344] And while certain of the embodiments described above utilize liquid inject through walls of a chamber, this is also not required by the present invention. In alternative embodiments, liquid could be introduced through the moveable member, for example utilizing orifices in a solid piston head, a piston rod, and/or a membrane.

[2345] The following claims relate to expansion.

[2346] 1. A method comprising:

providing a chamber having a moveable member disposed therein;

flowing a compressed gas into the chamber through a port;

introducing a liquid into the chamber;

allowing expansion of the compressed gas in a presence of the liquid in an absence of combustion of the liquid to move the moveable member; and

generating power from a linkage in physical communication with the moveable member.

[2347] 2. A method according to claim 1 wherein introducing the liquid comprises spraying droplets of the liquid.

[2348] 2a. A method according to claim 2 wherein a ratio of the total surface area of the droplets, to the number of moles of gas in the chamber, is between about 1-250 m^2/mol.

[2349] 3. A method according to claim 1 wherein introducing the liquid comprises bubbling the compressed gas through the liquid.

[2350] 4. A method according to claim 1 wherein the power is generated from rotation of a shaft turned by movement of the moveable member.

[2351] 5. A method according to claim 1 wherein the physical communication does not include hydraulic or pneumatic communication.

[2352] 6. A method according to claim 1 wherein the physical communication includes mechanical communication, magnetic communication, electromagnetic communication, and/or electrostatic communication.

[2353] 7. A method according to claim 1 wherein the moveable member comprises a solid piston or a screw.

[2354] 8. A method according to claim 1 wherein the linkage comprises a crankshaft.

[2355] 9. A method according to claim 1 wherein the liquid is introduced in a direction other than substantially parallel to a direction of flow of the compressed gas into the chamber.

[2356] 10. A method according to claim 1 wherein the liquid is introduced in a direction other than substantially parallel to a direction of movement of the moveable member.

[2357] 11. A method according to claim 1 wherein the liquid is introduced through a wall of the chamber that defines the port.

[2358] 12. A method according to claim 1 wherein the liquid is introduced through a manifold.

[2359] 13. A method according to claim 1 wherein the liquid is introduced through a valve.

[2360] 14. A method according to claim 1 further comprising:

flowing a gas-liquid mixture from the chamber; and

separating at least a portion of the liquid from the gas-liquid mixture.

[2361] 15. A method according to claim 14 wherein the gas-liquid mixture is flowed from the chamber other than through the port.

[2362] 16. A method according to claim 1 wherein the liquid is introduced during flow of the compressed gas into the chamber.

[2363] 17. A method according to claim 1 wherein the liquid is introduced during expansion of the compressed gas.

[2364] 18. A method according to claim 1 wherein generating power comprises generating electricity.

[2365] 19. A method according to claim 1 wherein generating power comprises generating mechanical power.

[2366] 20. A method according to claim 1 further comprising cooling an end user through a thermal linkage with the chamber.

[2367] The following claims relate to compression.

[2368] 1. A method comprising:

providing a chamber having a moveable member disposed therein;

flowing a gas into the chamber through a port;

introducing a liquid into the chamber;

compressing the gas in a presence of the liquid by movement of moveable member in physical communication with a linkage; and

flowing the compressed gas from the chamber.

[2369] 2. A method according to claim 1 wherein introducing the liquid comprises spraying droplets of the liquid.

[2370] 2a. A method according to claim 2 wherein a ratio of the total surface area of the droplets, to the number of moles of gas in the chamber, is between about 1-250 m^2/mol.

[2371] 3. A method according to claim 1 wherein introducing the liquid comprises bubbling the gas through the liquid.

[2372] 4. A method according to claim 1 wherein the moveable member is moved by rotation of a shaft.

[2373] 5. A method according to claim 1 wherein the physical communication does not include hydraulic or pneumatic communication.

[2374] 6. A method according to claim 1 wherein the physical communication includes mechanical communication, magnetic communication, electromagnetic communication, and/or electrostatic communication.

[2375] 7. A method according to claim 1 wherein the moveable member comprises a solid piston or a screw.

[2376] 8. A method according to claim 1 wherein the linkage comprises a crankshaft.

[2377] 9. A method according to claim 1 wherein the liquid is introduced in a direction other than substantially parallel to a direction of flow of the gas into the chamber.

[2378] 10. A method according to claim 1 wherein the liquid is introduced in a direction other than substantially parallel to a direction of movement of the moveable member.

[2379] 11. A method according to claim 1 wherein the liquid is introduced through a wall of the chamber that defines the port.

[2380] 12. A method according to claim 1 wherein the liquid is introduced through a manifold.

[2381] 13. A method according to claim 1 wherein the liquid is introduced through a valve.

[2382] 14. A method according to claim 1 further comprising:
flowing a gas-liquid mixture from the chamber; and
separating at least a portion of the liquid from the gas-liquid mixture.

[2383] 15. A method according to claim 14 wherein the gas-liquid mixture is flowed from the chamber other than through the port.

[2384] 16. A method according to claim 1 wherein the liquid is introduced during flow of the gas into the chamber.

[2385] 17. A method according to claim 1 wherein the liquid is introduced during compression of the gas.

[2386] 18. A method according to claim 1 wherein the liquid is introduced during flow of the gas into the chamber, and during compression of the gas.

[2387] 19. A method according to claim 1 further comprising heating an end user through a thermal linkage with the chamber.

[2388] The following are apparatus claims.

[2389] 1. An apparatus comprising:

a first chamber having a first member moveably disposed therein;

a first element configured to introduce liquid into the first chamber;

a linkage in physical communication with the first member to compress gas within the first chamber;

a second chamber having a second member moveably disposed therein;

a second element configured to introduce liquid into the second chamber;

a counterflow heat exchanger configured to receive,

a flow of gas compressed in the first chamber by the first moveable member, and

a flow of gas expanded in the second chamber; and

a thermal conduit between the second chamber and an end user.

[2390] 2. An apparatus according to claim 1 further comprising a compressed gas storage unit configured to receive the flow of compressed gas from the counterflow heat exchanger, and configured to flow stored compressed gas to the second chamber.

[2391] 3. An apparatus according to claim 1 wherein the second moveable member is in physical communication with the linkage.

[2392] 4. An apparatus according to claim 3 wherein the second chamber is in thermal communication with a heat source.

[2393] 5. An apparatus according to claim 4 wherein the second moveable member is in physical communication with an electrical generator.

[2394] 6. An apparatus according to claim 1 wherein the second moveable member is in physical communication with an electrical generator.

[2395] 7. An apparatus according to claim 6 wherein the second moveable member is in physical communication with the electrical generator through the linkage.

[2396] 8. An apparatus according to claim 7 wherein the linkage comprises a rotating shaft.

[2397] 9. An apparatus according to claim 7 wherein the linkage comprises a multi-node gearing system.

[2398] 10. An apparatus according to claim 7 wherein the first element and/or the second element are selected from a sprayer or a sparger.

[2399] 1. A method of controlling a flow of fluid into a chamber, the method comprising:

providing a cylinder having a port in gaseous communication with a gas source;

providing first piston moveable within the cylinder; and

providing a second piston moveable within the cylinder to selectively block the port.

[2400] 2. A method of controlling a flow of fluid into a chamber according to claim 1 wherein movement of the second piston is synchronized with movement of the first piston.

[2401] 3. A method of controlling a flow of fluid into a chamber according to claim 2 wherein movement of the second piston is synchronized with movement of the first piston utilizing a common linkage.

[2402] 4. A method of controlling a flow of fluid into a chamber according to claim 3 wherein the common linkage comprises a common mechanical linkage.

[2403] 5. A method of controlling a flow of fluid into a chamber according to claim 4 wherein the common mechanical linkage comprises a crankshaft.

[2404] 6. A method of controlling a flow of fluid into a chamber according to claim 1 further comprising providing liquid to the cylinder during movement of the first piston.

[2405] 7. A method of controlling a flow of fluid into a chamber according to claim 6 wherein movement of the first piston compresses gas within the cylinder.

[2406] 8. A method of controlling a flow of fluid into a chamber according to claim 6 wherein movement of the first piston is in response to expansion of compressed gas within the cylinder.

[2407] 9. An apparatus for compression or expansion of gas, the apparatus comprising:

a chamber having a port and configured to contain a gas;

a moveable member disposed within the chamber; and

a conduit in fluid communication with the port and having a feature tuned to a resonant characteristic of a gas flow through the port to enhance a volumetric efficiency of the gas flow.

[2408] 10. An apparatus for compression or expansion of gas according to claim 9 wherein the feature comprises a length of the conduit between the port and an inlet of the gas flow.

[2409] 11. An apparatus for compression or expansion of gas according to claim 9 wherein the feature comprises a length of the conduit between the port and an outlet of the gas flow.

[2410] 12. An apparatus for compression or expansion of gas according to claim 9 wherein the feature comprises a cross-sectional area of the conduit.

[2411] 13. An apparatus for compression or expansion of gas according to claim 1 wherein the feature comprises length of a path of the conduit between the port and a gas source.

[2412] 14. An apparatus for compression or expansion of gas according to claim 9 wherein the gas flow comprises gas compressed by the moveable member in the chamber.

[2413] 15. An apparatus for compression or expansion of gas according to claim 14 wherein the resonant characteristic is determined from a timing of actuation of an outlet flow valve from the chamber, and/or a timing of actuation of an outlet flow valve from the conduit.

[2414] 16. An apparatus for compression or expansion of gas according to claim 9 wherein the gas flow comprises compressed gas.

[2415] 17. An apparatus for compression or expansion of gas according to claim 16 wherein the resonant characteristic is determined from a timing of actuation of a chamber flow valve located at a first end of the conduit proximate to the port, and/or a timing of actuation of a flow valve located at a second end of the conduit opposite to the first end.

[2416] 18. A liquid spray nozzle comprising:

a first piece;

a second piece; and

a securing member configured to secure the first piece to the second piece to define between them a space comprising,

a direction changing portion configured to change a direction of liquid received from a liquid source, and to flow the liquid to an outlet of the direction changing portion having a first cross-sectional area;

a velocity elevating portion configured to receive liquid from the outlet of the direction changing portion through an inlet having a second cross-sectional area, the velocity elevating portion configured to accelerate a velocity of liquid flowed from the inlet of the velocity elevating portion, and

an outlet in fluid communication with the velocity elevating portion and having a third cross-sectional area,

wherein the second cross-sectional area is significantly smaller than the first cross-sectional area and is approximately the same size or slightly larger than the third cross-sectional area.

[2417] 19. A liquid spray nozzle according to claim 18 wherein the first piece is configured to be inserted within an opening of the second piece.

[2418] 20. A liquid spray nozzle according to claim 18 configured to produce a spray of droplets wherein a ratio of the total surface area of the droplets, to the number of moles of gas in the chamber, is between about 1-250 m2/mol.

[2419] A compressed gas energy storage system incorporated within a generation layer of a power supply network, may be used to supply stable electricity over the short term to cover a ramp-up period of a power generation asset such as a natural gas turbine. The compressed gas energy storage system may be physically co-situated with the generation asset, and may be in electrical communication with the power supply network through a common busbar. Alternatively, the generation asset and the energy storage system may be in electrical communication with the power supply network through a common transmission line.

[2420] Figure 142 presents a generic description of an embodiment of a network for the generation, transmission, distribution, and consumption of electrical power. The embodiment shown in Figure 142 represents a substantial simplification of an actual power network, and should not be understood as limiting the present invention.

[2421] Power distribution network 14201 comprises a generation layer 14202 that is in electrical communication with a transmission layer 14204. Power from the transmission layer is flowed through distribution layer 14205 to reach the individual end users 14206 of the consumption layer 14208. Each of these layers of the power distribution network are now described in turn.

[2422] Generation layer 14202 comprises a plurality of individual generation assets 14210a, 14210b that are responsible for producing electrical power in bulk quantities onto the network. Examples of such generation assets 14210a, 14210b can include conventional power plants that burn fossil fuels, such as

coal-, natural gas-, or oil-fired power plants. Other examples of conventional power plants include hydroelectric and nuclear power plants that do not consume fossil fuels. Still other examples of generation assets include sources of alternative energy, for example wind turbines or solar energy harvesting installations such as photovoltaic (PV) arrays and thermal solar plants.

[2423] The assets of the generation layer generally deliver electrical power in the form of alternating current at relatively low voltages (<50kV) compared to the transmission layer. This electrical power is then fed to the transmission layer for routing. Specifically, the interface between a generation asset and the transmission layer is hereafter referred to as a busbar 14212.

[2424] The transmission layer comprises respective transformer elements 14220a and 14220b that are positioned at various points along a transmission line 14222. The step-up transformer 14220a is located proximate to the generation assets and corresponding busbars, and serves to increase the voltage of the electricity for efficient communication over the transmission line. Examples of voltages present in the transmission layer may be on the order of hundreds of kV.

[2425] At the other end of the transmission line, a step-down transformer 14220b serves to reduce the voltage for distribution, ultimately to individual end users. Power output by the step-down transformers of the transmission layer may lie in the voltage range of the low tens of kV.

[2426] Figure 142 presents the transmission layer in a highly simplified form. In practice, transmission of power may actually take place utilizing several stages at different voltages, with the stages demarcated by transmission substations.

[2427] The distribution layer 14205 receives the power from the transmission layer, and then delivers this power to the end users. Some end users 6a receive relatively high voltages directly from primary substation 14230a. The primary substation serves to further reduce the voltage to a primary distribution voltage, for example 12,000 V.

[2428] Other end users receive lower voltages from the secondary substations 14230b. Feeder lines 14232 connect the primary substation with the secondary substation, which further reduces the primary distribution voltage to the final voltage delivered to end users at a meter 14234. An example of such a final voltage is 120 V.

[2429] Figure 142 provides a general description of the physical elements of a power network which may be used in the generation, transmission, distribution, and consumption of electric power. Because it forms a vital part of the public infrastructure, and requires cooperation from a multitude of distinct geographic and political entities, such power networks are highly regulated at many levels (local, national, international).

[2430] Figure 142 thus also provides a framework for classifying the regulation of various network elements by different regulatory agencies. For example, an element of the power network may be regulated based upon its classification as an asset of the generation layer, transmission layer, distribution layer, or consumption layer, of the power network. Such regulatory classification can play an important role in determining properties of an energy storage system that is integrated within a power network.

[2431] The various assets of the generation layer of the power network of Figure 142, may be categorized in terms of the types of power that are to be produced. For example, baseload generation assets typically comprise apparatuses that are configured to produce energy at the cheapest price. Such baseload power generation assets are generally operated continuously at full power in order to afford a highest efficiency and economy. Examples of typical baseload generation assets include large power plants, such as nuclear, coal, or oil-fired plants.

[2432] Load following generation assets generally comprise apparatuses that are more capable of responding to changes in demand over time, for example by being turned on/off or operating at enhanced or diminished capacities. Examples of such load following generation assets include but are not limited to combustion turbines, steam turbines, diesel, and hydroelectric power plants.

[2433] A load following generation asset may be called upon to provide additional power or reduce power output to meet shifting demand continuously, with time intervals of changing power demand in 1 second to 5 seconds. In general, the efficiency of operation of load following generation assets may be optimized for full capacity. However, because load following generation assets typically do not operate continuously at full capacity, they may function less efficiently and their power may be more expensive than that available from baseline generation assets.

[2434] A third type of generation asset are the peak generation assets. Peak generation assets are utilized on an intermittent basis to meet the highest levels of demand. Peak generation assets are capable of operating on relatively short notice, but with reduced efficiency and correspondingly greater expense. A natural gas turbine is one example of an apparatus that is typically employed as a peak generation asset. A diesel generator is another example of a peak generation asset.

[2435] While they are capable of providing power on relatively short notice, even peak generation assets require some lead time before they are able to produce power of the quantity and quality necessary to meet the requirements of the power network. Examples of such power quality requirements include stability of voltage and frequency within a given tolerance range, and the necessity of synchronizing frequency of output with the frequency that is already extant on the network.

[2436] The ramp-up time necessary for generation assets to reach requirements of the network, can limit their use in peak demand or load following applications. For example, certain energy markets may provide advance notice of only a few minutes or even less, for the need to supply additional power. A generation asset having a ramp-up time exceeding this notice period may not be able to sell energy onto such an energy market, limiting its profitability.

[2437] Embodiments of compressed gas energy storage systems have previously been described in U.S. Patent Application Nos. 61/221,487 and 12/695,922, which are incorporated by reference in their entireties herein for all purposes.

[2438] One potential feature of such compressed gas energy storage systems, is their availability on short notice, to provide energy stored in relatively stable form. Specifically, the compressed gas may be maintained at an elevated pressure within a storage unit having a large volume. Examples of such storage structures include but are not limited to man-made structures such as tanks or abandoned mines

or oil wells, or naturally-occurring geological formations such as caverns, salt domes, or other porous features.

[2439] Upon demand, the energy stored in the form of compressed gas may be accessed by actuating a gas flow valve to provide fluid communication between the storage unit and an expander apparatus. This simple valve actuation allows rapid conversion of the energy in the compressed gas into mechanical or electrical form.

[2440] For example, as described below expansion of the compressed gas within a chamber may serve to drive a piston also disposed therein. The piston may be in mechanical communication with a generator to create the electricity. Such a configuration allows for stable power to be rapidly generated because no warm-up period characteristic of a combustion engine is required. The energy in the air is available immediately, and need only overcome the system's inertia in order to deliver full power. A few seconds is sufficient.

[2441] Such ready availability of energy stored in the form of compressed gas, stands in marked contrast to combustion-type apparatuses, where stable power output may only be achieved upon regulation of multiple flows of material, and power ramp rates which may be necessary to limit the thermal stress and fatigue on the generator. For example, stable operation of a natural gas turbine may only occur by exercising precise control over flows of air and natural gas, the mixing of these flows, and the ignition of the mixture under substantially unvarying conditions, and carefully controlling the thermal stress on the unit. Operation of a gas turbine to produce stable, reliable output also requires careful management of the heat resulting from the combustion, to produce expanding gas that is converted to mechanical energy in the form of spinning turbine blades.

[2442] Accordingly, certain embodiments compressed gas energy storage and recovery systems may be utilized to provide stable electrical power over a short term period, thereby covering the time period required to ramp-up a power generation asset. In a particular embodiment, a compressed gas energy storage and recovery system may supply stable power with advance notice of ten minutes or less, to cover a ramp-up period of one hour to two hours or less of a gas turbine peak generation asset.

[2443] The following provides a listing the characteristic time constants in which a generation asset is required to act under various circumstances. These times, in reality are a function of the desired service required, as well as the characteristics of the specific generator, and thus should be considered as guidelines rather than binding limitations. The capacities and outputs are situational, and can vary from hundreds of kw to tens of Mw with time durations ranging from minutes to hours.

- Peak

  Time to Ramp – 1+ hour

  Output – Situational 1- 100 Mw

  Capacity – 2-200 Mwh

- Load Following

  Time to ramp – continuous in steps of 1-5 seconds

  Output – 1 to 100 Mw

Capacity – 0.5 to 50 Mwh

- Spinning Reserve

  Time to ramp – 1 to 10 minutes

  Output – 10 to 100 Mw

  Capacity – 20 to 500 Mwh

- Standby Non-Spinning Reserve

  Time to ramp – 1 hour

  Output - 10 to 100 Mw

  Capacity – 20 to 500 Mwh

[2444] Figure 142 shows incorporation of compressed gas storage systems into a power network according to embodiments of the present invention. In certain embodiments, a compressed gas energy storage and recovery system 14240b may be incorporated in the generation layer located along the same transmission line as a power generation asset 14210a or 14210b. In other embodiments, a compressed gas energy storage and recovery system 14240a according to the present invention may be physically co-situated with the power generation asset, possibly behind the same busbar.

[2445] Locating a compressed gas energy storage and recovery system with a power generation asset, may confer certain benefits. One possible benefit which may be realized by co-situation of the energy storage system with a power generation asset, is the ability to leverage off of existing equipment. For example, a compressed gas energy storage and recovery system could utilize a power generation asset's existing interface with the network (busbar), in order to communicate power to the network.

[2446] Co-situation of the energy storage system with a power generation asset, may further enhance coordinated action between the two elements. In particular, a communication link 14250 between the compressed gas energy storage system 14240a and the co-situated generation asset may be local in nature, and hence potentially faster and more reliable than a larger area network.

[2447] According to certain embodiments, electricity recovered from the storage of compressed gas, may be used to supply stable electrical power to cover the period required for a generation asset to ramp-up. Accordingly, close proximity between the energy storage system and the generation asset may help to facilitate a seamless transition from electricity being output onto the network from the storage system, to electricity being output onto the network from the generation asset.

[2448] While desirable under certain circumstances, it is not required that the compressed gas energy storage system according to the present invention be physically co-situated with a power generation asset. In particular, the increased reliability of communication over wide area networks such as the internet, or utility Supervisory Control and Acquisition (SCADA) systems, has reduced the need for close proximity between different elements of the network.

[2449] Accordingly, Figure 142 also shows an embodiment of a compressed gas energy storage and recovery system 14240b that is located along the same transmission line as a power generation asset 14210a. System 14240b and power generation asset 14210a may effectively communicate over wired or wireless network link 14257.

[2450] Such positioning of the energy storage system in a location different from the generation asset, may be beneficial under certain circumstances. For example, positioning a compressed gas energy storage system in a different location than a generation asset, may endow it with greater flexibility.

[2451] Specifically, operation of such a remotely located energy storage system would not necessarily be tied to any particular generation asset. Thus, the compressed gas energy storage and recovery system 14240b of Figure 142 could readily supply power onto the network in order to provide coverage over the ramp-up period for generation asset 14210a, generation asset 14210b, or both of these.

[2452] Figure 143 shows a simplified block diagram of one embodiment of a compressed gas storage system according to the present invention. In particular, compressed gas storage and recovery system 14301 comprises compressor/expander (C/E) 14302 in fluid communication with gas inlet 14305, and in fluid communication with compressed gas storage unit 14303.

[2453] In certain embodiments, the compressed gas storage unit 14303 may comprise a steel tank having a length of about 1.6 meters, that is capable of storing air at 200 atmospheres and which is equipped with a valve. Some embodiments may utilize a much larger steel tank having a length of about 16 meters long, which could reduce a cost of spinning the tank closed and to a neck, also reduce the cost of the valves. Embodiments of the present invention may alternatively utilize larger man-made or geological features for storage.

[2454] Figure 143 shows that compressor/expander 14302 is in selective physical communication with motor/generator (M/G) 14304 through linkage 14307. Linkage 14307 may be of several types, including mechanical, hydraulic, pneumatic, magnetic, or electro-magnetic.

[2455] In a first mode of operation, motor/generator 14304 operates as a motor to allow energy to be stored in the form of a compressed gas (for example air). Motor/generator 14304 receives power from an external source, and communicates that power to cause compressor/expander 14302 to function as a compressor.

[2456] Once possible source of power for the motor/generator 14304 is the meter 14380 that is in electrical communication through line 14381 with substation 14382 of the distribution layer of the power grid 14314. In certain embodiments the power grid 14314 may be a smart grid containing information in addition to power.

[2457] In a compression mode of operation, motor/generator 14304 in turn communicates power to compressor/expander 14302 through linkage 14307, allowing compressor/expander 14302 to function as a compressor. Compressor/expander 14302 receives the gas from inlet 14305, compresses the gas, and flows the compressed gas to the storage unit 14303.

[2458] In an expansion mode, compressed gas is flowed from storage unit 14303 to compressor/expander 14302 that is operating as an expander. Expansion of the compressed gas causes actuation of linkage 14307, which drives motor/generator 14304 to function as a generator. Electricity output from motor/generator 14304 operating as a generator, is flowed to the power grid 14314 through busbar 14372 and transmission line 14312.

[2459] Gas undergoing compression or expansion within compressor/expander 14302 will tend to experience some temperature change. In particular, gas will tend to increase in temperature as it is compressed, and gas will tend to decrease in temperature as it expands.

[2460] The processes of compressing and decompressing the gas as described above, may experience some thermal and mechanical losses. However, these processes will occur with reduced thermal loss if they proceed at near-isothermal conditions with a minimum change in temperature.

[2461] Accordingly, the compressor/expander apparatus 14302 of the system 14301 is in fluid communication with one or more heat exchanger(s) 14360 that may be selectively in thermal communication with a heat sink or a heat source 14362. In a compression mode of operation, the heat exchanger is placed into thermal communication with a heat sink, for example a fan that blows air to cool the heat exchanger. In an expansion mode of operation, the heat exchanger is placed into thermal communication with a heat source, for example an environmental air temperature or a source of waste heat.

[2462] Figure 143 further shows that the compressed gas energy storage system 14301 may be co-situated with a generation asset 14364, for example a natural gas turbine or diesel generator. This co-situated generation asset may draw upon a dispatchable energy source 14350 such as a pipeline of oil or natural gas.

[2463] In particular, energy from the dispatchable source 14350 may be consumed by a generation asset 14364 such as a natural gas turbine or diesel generator, to produce electricity to the power grid. This electricity may be flowed onto the power grid for consumption, through busbar 14372 and transmission line 14312 as shown.

[2464] The various elements of the system 14301 are in communication with a central controller or processor 14396, that is in turn in electronic communication with a computer-readable storage medium 14394. The central controller or processor 14396 may also be in communication with the power grid 14314 (for example a smart grid) through a wired connection 14316 and or a wireless link between nodes 14318 and 14328. The central controller or processor 14396 may also be communication with other sources of information, for example the internet 14322.

[2465] Based upon instructions in the form of computer code stored on computer-readable storage medium 14394, the controller or processor 14396 may operate to control various elements of the system 14301. This control may be based upon data received from various sensors in the system, values calculated from that data, and/or information received by the controller or processor 14396 from various sources, including co-situated sources or external sources.

[2466] In certain embodiments, the controller of the compressed gas energy storage system may be configured to commence operation based upon an instruction received from a generation asset. For example, where the generation asset has received instructions to begin ramping up, it may in turn communicate a signal to the controller indicating the need for the compressed gas energy storage system to provide the necessary electrical power to cover the ramp-up period.

[2467] In certain embodiments, the compressed gas energy storage system may transmit signals to a generation asset. For example, upon detection of an event (such as meteorological conditions requiring the contribution of additional power), the system controller could be configured to transmit a signal instructing ramp-up of the generation asset to provide sufficient power coverage over longer time frame, with the compressed gas energy storage system providing necessary coverage over the ramp-up period.

[2468] While Figure 143 has shown an embodiment of a compressed gas storage and recovery system having a combined compressor/expander (C/E) and a combined motor/generator (M/G), this is not required by the present invention. Alternative embodiments may utilize separate, dedicated compressor and expander elements in communication with separate, dedicated motor and generator elements respectively. In certain embodiments these elements may be in physical communication through a single common linkage. In other embodiments, these elements may be in physical communication through a plurality of linkages.

[2469] Incorporation of compressed gas energy storage and recovery systems into the generation layer of a power network, may allow existing generation assets to be utilized in roles from which they might otherwise be precluded by virtue of their ramp-up times. For example, a potential role for generation assets may be to sell power onto energy markets.

[2470] One such market is for the sale of energy to balance supply with demand over time frames of greater than one hour. Such an embodiment may dispatch power from storage systems in near-real time in order to allow an existing generation asset to meet short-term fluctuation in demand. These fluctuations can result from natural causes, for example a change in an amount of power supplied by a variable renewable energy source (such as a wind farm). Fluctuations can also be of an artificial origin, for example changes in rate scheduling by energy markets.

[2471] Certain embodiments of compressed gas energy storage and recovery systems may be configured to facilitate the ramp-up of generation assets to sell power onto wholesale energy markets over longer time frames, for example within a day. Thus another potential role for energy storage systems of the present invention, may be to facilitate bulk intraday arbitrage by a generation asset.

[2472] In such a role, a generation asset would function to ramp-up and provide energy for sale when wholesale power is expensive. The presence of a compressed gas energy storage system would allow a generation asset to respond on short notice to opportunities for such bulk intraday arbitrage.

[2473] Power from the storage system (and later replaced by power from the generation asset after ramp-up), could be sold onto the wholesale energy market. Such a compressed gas energy storage and recovery system could be owned and operated by an Independent Power Producer (IPP), a generation utility, or some other Load Serving Entity (LSE).

[2474] Another potential role for generation assets whose ramp-up is covered by compressed gas energy storage and recovery systems, may be to perform diurnal renewable levelizing. Specifically, the fast response time of such a generation asset would allow demand to quickly be shifted as necessary to meet demand.

[2475] While the above description has related to systems classified as belonging to the generation layer whose recovered power is sold onto wholesale energy markets, the present invention is not limited to performing such roles. In accordance with alternative embodiments, energy storage and recovery systems could sell energy to other types of markets and remain within the scope of the present invention.

[2476] An example of such an alternative market for selling power recovered from compressed gas, is the ancillary services (A/S) market. Broadly speaking, the ancillary services market generally represents the sale of electrical power to the network for purposes other than consumption by end users. Such purposes include maintaining integrity and stability of the network, and the quality of the power provided thereon.

[2477] The ability (capacity) to provide energy to the ancillary services market, is usually sold for periods of less than one day, at a market price. The Independent System Operator (ISO) pays the capacity cost for reserving such capacity.

[2478] The actual energy itself, is sold in response to a call from the network to provide the power for a duration. When this happens, the owner of the system would be paid the market value of the energy sold.

[2479] One ancillary market exists for maintaining the capacity to provide necessary reserves needed to operate the network. That is, the operator of the network is required to be able to supply an amount of power above and beyond an existing demand, in order to ensure that the network is able to meet future demand. Such reserves are typically calculated as a percentage in excess of a supply.

[2480] One form of reserves are contingency reserves. Contingency reserves are summoned by the power network at relatively short notice in response to certain events (contingencies) that are unexpected but need to be planned for. Examples of such contingencies include the failure of an element of the transmission layer (such as a transmission line), an unanticipated surge in demand, or the need to shut down or reduce output of a generation element on short notice.

[2481] One form of contingency reserves are spinning reserves. Such spinning reserves are typically available on extremely short notice. Spinning reserves have traditionally taken the form of an increase in output from generating units that are operating at less than capacity, or by interruption of service to certain customers. Such reserve is referred to as "spinning" because in order to satisfy the demand on short notice, the generation asset may already be on-line and operating in a synchronous manner ("spinning") with the rest of the network.

[2482] Another form of contingency reserves are standing reserves. Standing reserves are available with a longer lead time than spinning reserves, as the generation element is not yet synchronously on-line (spinning). Standing reserves may also take the form of an interruption of service to certain customers, with a correspondingly longer notice period.

[2483] In certain embodiments, existing generation assets whose ramp-up times are covered by compressed gas energy storage and recovery systems according to the present invention, may be able to function to provide contingency reserves. Such assets would have the capacity to provide the necessary

amount of contingency power for a duration required by the service provider. The various roles for ramp-up coverage are summarized above.

[2484] 1. A method comprising:

allowing compressed gas to expand to drive a moveable member positioned within a chamber;

generating electricity from movement of the moveable member; and

supplying the electricity to a power network over a ramp-up period of a generation asset of the power network.

[2485] 2. The method of claim 1 wherein the electricity is supplied to the power network through a busbar, and the generation asset is in electrical communication with the network through the busbar.

[2486] 3. The method of claim 2 wherein the electricity is supplied to the power network through a generator, and the generation asset is in physical communication with the generator.

[2487] 4. The method of claim 1 wherein the electricity is supplied to a transmission line of the power network, and the generation asset is in electrical communication with the transmission line.

[2488] 5. The method of claim 1 wherein the generation asset comprises a gas turbine or a diesel generator.

[2489] 6. The method of claim 1 further comprising placing the moveable member in electronic communication with the generation asset.

[2490] 7. An apparatus comprising:

a chamber having disposed therein a member moveable in response to expansion of gas within the chamber;

a generator in physical communication with the moveable member and in electrical communication with a transmission layer of a power network; and

a compressed gas storage unit configured to be in selective fluid communication with the chamber such that the generator supplies electricity to the power network during a ramp-up period of a generation asset.

[2491] 8. The apparatus of claim 7 wherein the generator and the generation asset are in electrical communication with the transmission layer through a common busbar.

[2492] 9. The apparatus of claim 7 wherein the generator and the generation asset are in electrical communication with the transmission layer through a common transmission line.

[2493] 10. The apparatus of claim 7 wherein the generation asset comprises a natural gas turbine or a diesel generator.

[2494] 11. The apparatus of claim 7 further comprising a controller in electronic communication with the moveable member and in electronic communication with the generation asset.

[2495] Operation of an embodiment of a system according to the present invention with a power grid could be coordinated by a central processor receiving inputs and producing outputs based upon a control algorithm. An example of such operation is now described in connection with Figures 147-147A.

[2496] Figure 147 plots power output over time, of various elements of a power supply network. A first element is a renewable energy source (such as wind farm), whose output is variable depending upon natural forces. A second element is a system according to an embodiment of the present invention.

[2497] A third element whose power output is shown in Figure 147, is a short-term generation asset. Such a short-term generation asset may be configured to provide power on short notice, but at low efficiency and/or relatively high cost. An example of such a short-term generation asset is a diesel generator, or even another energy storage apparatus.

[2498] A fourth element whose power output is shown in Figure 147, is a longer-term generation asset. Such a longer-term generation asset may be configured to provide efficient power at relatively low cost, but requiring longer term notice. An example of such a longer-term generation asset is a natural gas turbine.

[2499] Operation of these various elements may be coordinated by a central processor, in order to maintain a stable supply of power on the network while ensuring efficient utilization of available resources. Figure 147A shows a simplified view of an example of a system 14700 comprising a processor 14702 in electronic communication with a power supply network and with an energy storage apparatus, the system further comprising a computer-readable storage medium 14704 in electronic communication with the processor and having stored thereon code configured to cause the processor to:

- receive an input 14706 relating to a predicted change in a load of the power supply network, or a change in generation capacity available to the power supply network,
- process the input according to a control algorithm,
- communicate a first signal 14708 either automatically causing the energy storage apparatus to operate to output electrical power, or recommending a human operator to instruct the energy storage apparatus to operate to output electrical power, and
- communicate a second signal 14710 either automatically causing ramp-up of a generation asset of the power supply network, or recommending the human operator to instruct ramp-up of a generation asset of the power supply network.

[2500] According to certain embodiments, the input may originate from the power supply network, for example a demand response command). In some embodiments, the input may originate from the meter, for example indicating consumption approaching or exceeding a historic peak.

[2501] In certain embodiments, the input may be a predicted change in wind or solar energy at a renewable generation asset of the power supply network. The input may comprise an environmental temperature change indicative of the changed load, or may comprise a weather disturbance predictive of disruption of the power supply network.

[2502] In certain embodiments, the energy storage apparatus may be configured to output the electrical power directly to a consumer located behind a meter of the power supply network. According to particular embodiments, the energy storage apparatus may be configured to output the electrical power onto the power supply network, for example to a distribution or transmission layer through a transformer, or to a generation layer through a busbar.

[2503] In certain embodiments the energy storage system may store energy in electrical form, for example a battery or capacitor bank. In some embodiments, the energy storage apparatus is configured to generate the electrical power from expansion of compressed gas in a presence of a liquid to drive a physical linkage such as a crankshaft. Particular embodiments may introduce the liquid by spraying with a rotational motion followed by impingement upon a deflection surface.

[2504] According to some embodiments, the computer readable storage medium may further include code stored thereon to cause the processor to communicate a signal 14712 either automatically halting operation of the energy storage apparatus, or recommending the human operator to instruct halting of operation of the energy storage apparatus, in response to a signal 14714 indicating completion of the ramp-up of the generation asset.

[2505] A system according to particular embodiments may have the computer readable storage medium further including code stored thereon to communicate a signal 14716 either automatically causing replenishment of the energy storage apparatus, or recommending the human operator to instruct replenishment of the energy storage apparatus.

[2506] Returning to the particular example shown in Figure 147, over the time interval A the renewable energy source provides a power output that varies within an expected range R. Over this same time interval A, the system according to an embodiment provides sufficient power to compensate for this variable power output and thereby maintain power at a level Z. Here, Z may represent the total power on the grid, or a portion of that total power (for example a power commitment from the wind farm established by contract). Accordingly, over the time period A neither the short-term nor the long-term generation assets are required to be used.

[2507] At a time B, the central processor receives information indicative of a long term loss of power from the renewable generation asset. For example, the renewable generation asset may communicate information indicating a pattern of changed wind velocity conforming to historical trends of substantial wind loss. Such historical trends may also be influenced by other factors, such as the time of year, the time of day, the particular geographic location of the wind turbine, and meteorological models of current and future weather activity. One possible source of predictive wind modeling is True Wind Solutions LLC of Albany, New York.

[2508] Accordingly, at time B the processor sends a signal to the short-term generation asset, instructing its ramp-up to begin to supply power replacing that of the renewable generation asset. As such ramp-up is not instantaneous, the processor also notifies the compressed gas storage system to expect to maintain or even increase its output in order to cover the ramp-up period of the short-term generation asset.

[2509] As predicted at time C the wind velocity drops below a threshold T, below which no power is generated from the wind turbine. At this point C the compressed gas energy storage system assumes the entire load Z.

[2510] The ability of the system according to an embodiment of the present invention to provide power, may ultimately be limited by one or more factors, including the size of its generator, the size of its

storage capacity, and the current state of its existing storage capacity. In addition, the system may provide power at a certain cost that may be higher than that available from the long-term generation asset. These pieces of information are available as inputs to the processor. In response, at time C the central processor notifies the longer-term generation asset to prepare to come on-line to meet the load over the longer term.

[2511] At time D the short-term generation asset has warmed up and comes on-line, and rapidly begins to generate power to meet the full demand by time E. Over the period from D to E, the compressed gas storage system correspondingly ramps down its output.

[2512] By time F, the prolonged ramp-up period for the long-term generation asset has been reached, and that asset also now comes on-line and begins to provide increasing power to meet the load. Over the period from F to G, the short-term generation asset correspondingly ramps down its output.

[2513] The transition of Figure 147 (from the grid receiving power primarily from the renewable energy source, to its receiving power from a longer-term generation asset), is coordinated by the central processor based upon information received from various sources. This transition is accomplished with desirable efficiency from available resources, without imperiling the stability of power on the network.

[2514] The particular transition shown in Figure 147, represents a highly simplified case. For example, at any given time multiple generation assets of different types (i.e. variable (renewable), baseline, peak, load following) would be contributing power to meet demand. Moreover, multiple storage apparatuses would be deployed at different points in the network, with more than one storage apparatus being used to satisfy demand at any given point in time.

[2515] The specific scenario shown in Figure 147 is also simplified in that it shows only the activation of resources to meet demand. In a variant of these events, the wind speed could unexpectedly pick back up in a manner indicating continued dependable supply. In such a scenario, based upon this newly received information the processor could instruct/recommend suspension of ramp-up of generation assets, or other steps accommodating the now-available dependable supply of renewable energy.

[2516] The scenario shown in Figure 147 is simplified in that the overall load is shown as unchanging. In reality, the load on the grid will experience changes over time in ways that are both predictable (e.g. daily patterns, scheduled maintenance) and unpredictable (storm damage, unscheduled maintenance). The ability of the processor to rapidly respond to such changing conditions (in the form of varying inputs), can aid a human operator in the decision-making process.

[2517] The scenario of Figure 147 is simplified in that it presents only one particular chain of events (loss of generation capacity available from a renewable resource). A myriad of other events is of course possible, influenced by factors including but not limited to:

- weather patterns;
- demand patterns;
- energy pricing structures/agreements;
- availability of transmission and/or distribution assets;
- conditions of other interconnected power grids.

[2518] Of course, the present invention is not limited to use with renewable energy sources, or with particular energy storage systems. Rather, embodiments of the present invention could employ a central processor to control (or recommend control decisions to a human user) various assets of a power supply network to coordinate activity with different types of energy storage, of which compressed gas is only one example. Thus according to alternative embodiments, a central processor could execute a control algorithm to integrate a storage system comprising a battery, with non-renewable generation assets of a grid, for example to meet changing demands.

[2519] Examples of inputs to such a control algorithm executed by a central processor, include but are not limited to:

- existing/expected future load;
- price of power from generation asset;
- ramp-up time of generation asset;
- available storage capacity;
- storage recharge requirements;
- status of generation asset (i.e. spinning, stand-by);
- market (wholesale, A/S) price for power;
- status of renewable power sources (i.e. current/future meteorological conditions);
- transmission capacity.

[2520] Examples of decisions made or recommended to a human operator based upon inputs to a control algorithm, include but are not limited to:

- activating/de-activating generation assets;
- discharging/charging storage apparatuses;
- altering transmission/distribution pathways; and
- purchasing power from wholesale or ancillary services markets.
- reducing/shifting demand;

[2521] In connection with reducing/shifting of demand, an energy storage apparatus could perform this function without actually outputting electricity onto the network through a busbar or transformer. Specifically, an energy storage apparatus positioned behind a meter with an end user, could output power (in electrical or other forms) directly to that end user. Such power output from the storage device would effectively replace the electricity drawn by the consumer from the grid, thereby reducing the load on the power supply network.

[2522] 1. A system comprising:

a host computer comprising,

a processor in electronic communication with a power supply network and with an energy storage apparatus, and

a computer-readable storage medium in electronic communication with the processor, the computer readable storage medium having stored thereon code configured to cause the processor to,

receive an input based upon a meteorological condition,

process the input according to a control algorithm, and

based upon the processing, send a signal either automatically causing the energy storage apparatus to operate to output power, or recommending a human operator to instruct the energy storage apparatus operate to output power.

[2523] 2. A system of claim 1 wherein the input comprises a predicted change in wind profile at a renewable generation asset of the power supply network.

[2524] 3. A system of claim 1 wherein the input comprises a predicted change in solar energy profile at a renewable generation asset of the power supply network.

[2525] 4. A system of claim 1 wherein the input comprises an environmental temperature change predictive of an increased load on the power supply network.

[2526] 5. A system of claim 1 wherein the input comprises a weather disturbance predictive of disruption of the power supply network.

[2527] 6. A system of claim 1 wherein the computer readable storage medium further includes code stored thereon to communicate a second signal either automatically causing ramp-up of an other generation asset of the power network, or recommending the human operator to instruct ramp-up of the other generation asset.

[2528] 7. A system of claim 6 wherein the computer readable storage medium further includes code stored thereon to cause the processor to communicate a third signal either automatically halting operation of the energy storage apparatus, or recommending the human operator to instruct halting of operation of the energy storage apparatus, in response to a fourth signal indicating completion of ramp-up of the other generation asset.

[2529] 8. A system of claim 1 wherein the computer readable storage medium further includes code stored thereon to communicate a second signal either automatically causing replenishment of the energy storage apparatus, or recommending the human operator to instruct replenishment of the energy storage apparatus.

[2530] 9. A system of claim 1 wherein the energy storage apparatus is configured to output power to the power supply network.

[2531] 10. A system of claim 9 wherein the energy storage apparatus is configured to output power to the power supply network through a busbar.

[2532] 11. A system of claim 9 wherein the energy storage apparatus is configured to output power to the power supply network through a transformer.

[2533] 12. A system of claim 1 wherein the energy storage apparatus is configured to output power directly to a consumer located behind a meter of the power supply network.

[2534] Embodiments of apparatuses, methods, and systems according to the present invention may allow the conversion between different forms of energy. For example, Figures 144A-C show views of an embodiment of a system. Figure 144A shows the input 14400 of different energy types to an system 14402 having one or more characteristics as described herein. Figure 144A also shows the corresponding

output 14404 of energy in various forms, from the system. Figure 144A further shows the optional storage of compressed gas in storage unit 14405, between the input and the output.

[2535] Particular embodiments of compression/expansion systems according to the present invention, have previously been shown and described in connection at least with Figures 1, 10, 22, 24, 42, and 50. Figure 144B shows a generalized depiction of such a system 14402 (including the optional compressed gas storage 14405), in communication with an energy source 14410 and with an energy destination 14412.

[2536] Specifically, energy source 14410, system 14402, and energy destination 14412 are in thermal communication with thermal network 14450. Such a network transmits thermal energy, and may comprise elements such as liquid flow conduits, gas flow conduits, heat pipes, insulated vessels, heat exchangers (including counterflow heat exchangers), loop heat pipes, thermosiphons, heat sources, and heat sinks. Figure 144B particularly shows the thermal network as including heat source 14452 and heat sink 14454, which comprise a source of low grade heat and the external environment, respectively.

[2537] FIG. 144B also shows energy source 14410, system 14402, and energy destination 14412, as being in communication with fluidic network 14460. Such a network transmits fluids including gases, liquid, and/or mixtures thereof, and may comprise elements such as tanks or reservoirs, liquid flow conduits, gas flow conduits, pumps, vents, liquid flow valves, gas flow valves, switches, liquid sprayers, gas spargers, mixers, accumulators, and separators.

[2538] Various types of separators have been mentioned above. Gas-liquid separators and/or liquid-liquid separators may be employed, depending upon the particular embodiments. Examples of gas-liquid separator designs include vertical type, horizontal type, and spherical type. A liquid collector section of a separator may include elements such as inlet diverters including diverter baffles, tangential baffles, centrifugal, elbows, wave breakers, vortex breakers, defoaming plates, stilling wells, and mist extractors.

[2539] FIG. 144B further shows energy source 14410, system 14402, and energy destination 14412 as being in communication with physical network 14470. Such a network transmits physical energy, and may comprise mechanical elements configured to convert linear motion to/from rotational motion, such as shafts (including crankshafts). Other examples of mechanical components of physical networks include screws, pistons, gears (including multi-node gearing systems such as planetary gears), and motors.

[2540] Physical networks may also comprise hydraulic or pneumatic elements, including pistons, accumulators, gas chambers liquid chambers, gas conduits, liquid conduits, hydraulic motors, hydraulic transformers, pneumatic motors, and others known in the art.

[2541] FIG. 144B finally shows energy source 14410, system 14402, and energy destination 14412 as being in communication with electrical network 14480. Such a network transmits electrical energy, and may comprise elements such as resistors, transistors, capacitors, inductors, transformers, batteries, insulators, diodes, amplifiers, power sources, bus lines, meters, busbars, filters, power conditioning equipment, and any of the other myriad of electrical components as are known in the art.

[2542] Figure 145A shows a simplified schematic diagram of an embodiment of an apparatus in accordance with the present invention, that may be arranged in various configurations to provide different functions. In particular, Figure 145A shows a system 14500 comprising two cylinders 14502, 14504 having the rods 14564, 14566 of respective pistons 14580, 14582 connected to a common crankshaft 14562 coupled to a motor/generator 14560.

[2543] Figure 145A shows each cylinder having respective inlet valves 14570, 14574, that receive gas flowed through gas-gas heat exchangers 14514, 14518, respectively. Each cylinder also includes respective outlet valves 14572, 14576 that are in communication with gas-liquid separators 14556, 14558. These gas-liquid separators are in gas communication with respective gas-gas heat exchangers 14516, 14520.

The gas-liquid separators are in liquid communication with respective gas-liquid heat exchangers 14522, 14524, and then with the respective cylinders 14502, 14504 through respective nozzles 14554, 14552 (and optionally liquid pumps and/or liquid flow valves), as has been recounted at length above.

[2544] Figure 145A further shows the cylinders as being in selective fluid communication with each other, with the storage tank, and with various ports to the system, through a network of gas conduits and multi-way valves 14506, 14508, 14510, and 14512. Operation of such multi-way valves, in addition to operation of the cylinder inlet and outlet valves, may be coordinated by a central processor 14590 based upon code present in computer-readable storage medium 14592.

[2545] For example, Figure 145BA is a table showing different configurations of the apparatus of Figure 145A. The table of Figure 145BA further indicates the interaction between system elements and various thermal nodes 14625, 14528, 14530, 14532, 14534, 14536, and 14540, in the different configurations. Such thermal nodes can comprise one or more external heat sources, or one or more external heat sinks, as indicated more fully in that table. Examples of such possible such external heat sources include but are not limited to, thermal solar configurations, geothermal phenomena, and proximate heat-emitting industrial processes. Examples of such possible such external heat sinks include but are not limited to, the environment (particularly at high altitudes and/or latitudes), and geothermal phenomena (such as snow or water depth thermal gradients).

[2546] Figures 145BB-BG are highly simplified depictions of the flow of gases through the apparatus of Figure 145A in various configurations. For example, in configuration 1, (Figure 145BB) both cylinders act as compressors. Gas is sucked in from ambient, a tank, or another, lower pressure stage. Gas is then compressed near-isothermally by spraying a liquid into the air during or before compression. An amount of liquid introduced into the cylinders controls the discharge temperature of compressed gas. Heat can be extracted from the heated compressed gas before or after it enters the tank or a second stage.

[2547] In configuration 2 (Figure 145BC), both cylinders act as expanders. Compressed gas is fed into the cylinders from a tank and/or another source of compressed gas (such as a higher-pressure stage). Pressure of the compressed gas drives the physical linkages and/or electrical generator in communication therewith. This process produces cold gas and cool liquid that can be used, directly or indirectly, for air-conditioning, refrigeration, or cooling.

[2548] In configuration 3 (Figure 145BD), one cylinder acts as a compressor and the other acts as an expander. The working gas is in a closed loop. Gas is compressed in the compressor, producing hot gas and hot liquid. The compressed gas is then fed into the expander. The liquid sprayed into the expander, or the compressed gas, can be preheated by external heat sources to generate a net deliverable mechanical energy. Expander produces the power required to derive the compressor, and to generate energy in various forms (e.g. electrical/mechanical/hydraulic/pneumatic energy).

[2549] In configuration 3, gas may be flowed through a counter flow heat exchanger. The counter flow heat exchanger may be used to preheat the compressed gas and cool down the expanded gas.

[2550] In configuration 4 (Figure 145BE), one cylinder acts as a compressor and the other acts as an expander. Gas is sucked in from ambient, a tank, or another stage. The gas is then compressed near-isothermally. Heat may be extracted from the heated compressed gas, or additional heat may be added to the gas stream before it is fed into the expander. The liquid sprayed into the expander may be preheated with an external heat source. The expander produces the power required to derive the compressor, and to generate output energy in one or more forms (e.g. electrical/mechanical/hydraulic/ pneumatic energy).

[2551] Certain embodiments of the present invention may operate in any of the above configurations continuously, or may switch between configurations intermittently. For example, such intermittent operation between configurations could entail electronic control over the states of the multi-way valves, for example such that gas is flowed to and/or from the storage unit at particular times.

[2552] Moreover, systems according to embodiments of the present invention could be operated in a combination of the above configurations. For example, Figure 145BF shows a simplified view of the flow of gases through the system of Figure 145A, in an alternative configuration combining compressor and heat engine functions.

[2553] In certain such combined configurations, the multi-way valves may be configured to combine multiple inputs, or to provide multiple outputs. In the combined configuration of Figure 145BF, one of the multi-way valves outputs compressed gas not only to the (right-hand) cylinder acting as an expander, but also to the storage tank.

[2554] Figure 145BG shows a simplified view of the flow of gases through the system of Figure 145A, in an alternative configuration combining expander and heat engine functions. In this configuration, one of the multi-way valves receives compressed gas not only from the (left-hand) cylinder acting as a compressor, but also from the storage tank. The right hand cylinder serves to recover energy from expansion of this combined amount of compressed gas.

[2555] While Figures 145BF-BG show combinations of configurations where the gas flow path is open, embodiments of the present invention are not limited to this approach. Alternative embodiments could employ the flow of compressed gas to/from storage, in combination with gas flow within a closed circuit, as in the manner of Figure 145BC.

[2556] In certain embodiments of configurations, a starter may be used to initiate the action of the compressor.

[2557] Embodiments of the present invention are not limited to expansion of compressed gas to atmospheric pressure, and under certain circumstances the gas may be expanded to below atmospheric. Moreover embodiments of the present invention are not limited to compressing gas from ambient temperature, and under some circumstances the inlet gas for compression may be below ambient temperature.

[2558] Furthermore, the present invention is not limited to the particular apparatus shown in Figure 145A, and variations are possible. For example, in some embodiments a system could be operated with additional heat exchanger(s), or without heat exchanger(s). In particular embodiments, the system could be operated in parallel or series with one or more similar systems.

[2559] And while the particular embodiment of Figure 145A shows the two cylinders as operating out-of-phase, this is not required. According to alternative embodiments, the cylinders could be operated in-phase with one another and/or with other stages.

[2560] Connection of embodiments of a system to one or more of the various different networks, allows flows of energy between various sources and destinations to be converted into different forms. The tables of FIGS. 145C-EB show examples of the processes and pathways of such energy conversion.

[2561] Embodiments of the present invention operating as heat engines and receiving input in the form of thermal energy, may be used to substitute or supplement conventional regimes relying upon the Rankine cycle. For example, an embodiment according to the present invention may be incorporated within a combustion- or nuclear-based power plant in lieu of, or in supplement to, a Rankine cycle steam turbine.

[2562] The system is not limited to receiving or outputting energy in any single form. Instead, the system may include an ability to combine different forms of input energy, and/or to apportion output energy into a multitude of different forms. Such apportioning is depicted in simplified form in FIG. 146.

[2563] Specifically, inputs in the form of compressed gas, heated gas/liquid, cooled gas/liquid, physical energy, and/or electrical energy, may be combined as shown to ultimately produce energy in the form of compressed gas. Optionally, this compressed gas may be stored for later recovery.

[2564] Upon expansion of the compressed gas (whether immediately or following storage for some period of time), the energy released therefrom may be apportioned between multiple forms of output. For example, apportioning may occur between energy released in thermal form versus non-thermal form. Such apportioning may be determined by controlling the magnitude of the temperature change experienced by the expanding gas, for example by an amount of liquid that is injected.

[2565] Under certain circumstances (such as a heat wave), a large amount of energy in thermal form may be desirable. Compressed gas could thus be expanded in a substantially non-isothermal manner, with the resulting cooled gas being used to absorb heat from a user. Such non-isothermal expansion could be realized by controlling an amount of liquid that is introduced into the expansion chamber for heat exchange.

[2566] Conversely, where a large amount of non-thermal output is desired, expansion could take place under isothermal or near-isothermal conditions. Such energy recovery would result in energy recovery at

high efficiency. The transfer of heat between gas and injected liquid, would allow thermal energy to be output in the form of the liquid.

[2567] Still another apportioning is of the non-thermal energy. As shown in Figure 146, the non-thermal energy may be apportioned between output in electrical form and in mechanical/hydraulic/pneumatic form. For example, a rotating shaft or other physical linkage may be in communication with a gearing system (for example a multi-node gearing system such as a planetary gear system) allowing some of the non-thermal output energy to drive an electrical generator to produce electricity.

[2568] Figure 146 shows still another apportioning, here of the thermal energy. In particular, this thermal energy from the expanding gas may be apportioned between heated gas and/or liquid and/or cooled gas and/or liquid. Apportioning of energy resulting from gas expansion between different outputs, may be accomplished with reference to the various pathways presented in connection with Figures 145BA-EB.

[2569] While certain aspects of the above description have emphasized the storage, generation, and conversion of power, the primary emphasis of a system according to embodiments of the present invention could be on temperature control, with the added benefit of reduced consumption of power from the grid. Such savings could be achieved by 1) harnessing the cooling/heating power of the gas and/or separated liquid, and/or 2) time-shifting the storage and expansion of the gas to leverage economic factors such as price and demand.

[2570] 1. A method comprising:

receiving energy of a first type; and

utilizing expansion of a compressed gas in the presence of an injected liquid to convert the energy of the first type to energy of a second type.

[2571] 2. The method of claim 1 wherein the energy of the first type comprises energy used to create the compressed gas, and the energy of the second type comprises cooling in the form of the expanded gas.

[2572] 3. The method of claim 1 wherein the energy of the first type comprises energy used to create the compressed gas, and the energy of the second type comprises cooling in the form of the injected liquid cooled by the expanding gas.

[2573] 4. The method of claims 1 or 2 wherein the energy of the first type is selected from mechanical energy, hydraulic energy, or electrical energy.

[2574] 5. The method of claim 1 wherein the energy of the first type comprises heat applied to the expanding gas, and the energy of the second type comprises cooling in the form of the injected liquid cooled by the expanding gas.

[2575] 6. The method of claim 1 wherein the energy of the first type comprises heat applied to the expanding gas, and the energy of the second type comprises cooling in the form of the expanded gas.

[2576] 7. The method of claim 1 wherein the energy of the first type comprises heat applied to the expanding gas, and the energy of the second type is physical energy.

[2577] 8. The method of claims 5, 6, or 7 wherein the heat is applied to the expanding gas by raising a temperature of the injected liquid.

[2578] 9. The method of claim 7 further comprising converting at least a portion of the physical energy to electrical energy.

[2579] 10. An apparatus comprising:

a first cylinder having a first piston moveably disposed therein;

a second cylinder having a second piston moveably disposed therein;

a gas flow network comprising a counterflow heat exchanger between the first cylinder and the second cylinder, the gas flow network further comprising a plurality of multi-way valves actuable in one of the following configurations:

a compression configuration wherein gas is compressed by first piston and by the second piston;

an expansion configuration wherein compressed gas is expanded to drive the first piston and to drive the second piston;

a combination configuration wherein gas is compressed by one of the first piston or the second piston, and expanding gas drives the other of the first piston or the second piston.

[2580] 11. The apparatus of claim 10 wherein in the compression configuration the gas flow network is configured to flow compressed gas to a storage unit.

[2581] 12. The apparatus of claim 10 wherein in the expansion configuration the gas flow network is configured to flow compressed gas from a storage unit.

[2582] 13. The apparatus of claim 10 wherein in the combination configuration the gas flow network is configured to flow compressed gas to a storage unit.

[2583] 14. The apparatus of claim 10 wherein in the combination configuration the gas flow network is configured to flow compressed gas from a storage unit.

[2584] 15. The apparatus of claim 10 wherein in the combination configuration the gas flow network is configured to flow expanded gas to an outlet.

[2585] 16. The apparatus of claim 10 wherein in the combination configuration the gas flow network is configured to flow gas expanded in one of the first cylinder or the second cylinder, to the other of the first cylinder or the second cylinder for compression.

[2586] 17. The apparatus of claim 10 wherein in the combination configuration the gas flow network is configured to flow gases through the counterflow heat exchanger.

[2587] 18. The apparatus of claim 10 wherein the first piston and the second piston are in mechanical communication with a common crankshaft.

[2588] 19. The apparatus of claim 18 further comprising an electrical generator in communication with the common crankshaft.

[2589] 20. The apparatus of claim 18 further comprising a motor in communication with the common crankshaft.

[2590] As discussed above, one or more embodiments of the present invention may utilize heat exchanger structure(s). Such heat exchangers may perform heat exchange between materials in the same

state (e.g. gas-gas heat exchangers). Some heat exchangers may perform heat exchange between materials in different states (e.g. gas-liquid heat exchangers).

[2591] Figure 181 shows a view of one exemplary type of heat exchanger which may be integrated with an energy system according to the present invention. For example, the heat exchanger of Figure 181 may be employed as one or more of the gas-gas or gas-liquid heat exchangers shown in Figure 145A.

[2592] Figure 181 shows a simplified schematic view of an embodiment of an apparatus 18100 according to the present invention that may serve as a heat exchanger/thermal node. The embodiment of Figure 181 provides for effective heat exchange between two gases (which may be at different pressures), or between one or two liquid streams and one/two gas streams. The embodiment of Figure 181 also allows for effective heat exchange with external heat sources (e.g. thermal solar, geothermal, fuel burners) or heat sinks (e.g. ice/snow).

[2593] Operation of the apparatus 18100 may proceed as follows. Liquid is sprayed into chamber 18120 using one or multiple nozzles 18101. It forms spray shower 18114. The liquid exits the chamber from drain 18103.

[2594] Liquid is sprayed into chamber 18121 using one or multiple nozzles 18102. It forms spray shower 18115. The liquid exits the chamber from drain 18104.

[2595] In chamber 18120, gas enters from gas port 18106, exchanges heat with the spray shower 18114, and exits through gas port 18105. Such counter flow motion of gas with respect to liquid-drops (e.g. gas flow from port 18106 to port 18105) enhances heat exchange, and introduces pressure-drop for the gas flow. Moreover, in this configuration gravity, as well as momentum of the spray drops, enhances the discharge of liquid from the chamber.

[2596] In alternative configurations, gas may be fed into the chamber from port 18105 and exhausted from port 18106. Such co-flow motion of gas and liquid (e.g. gas flow from port 18105 to port 18106) may increase pressure of the gas, enhancing the gas flow.

[2597] In the instant configuration, gas enters chamber 18121 from gas port 18107, exchanges heat with the spray shower 18115, and exits through gas port 18108. Such counter flow motion of gas with respect to liquid-drops (e.g. gas flow from port 18107 to port 18108) enhances heat exchange, and introduces pressure-drop for the gas flow. Moreover, in this configuration gravity, as well as momentum of the spray drops, enhances the discharge of liquid from chambers.

[2598] In alternative configurations, gas may be fed into the chamber from port 18108 and exhausted from port 18107. Such co-flow motion of gas and liquid (e.g. gas flow from port 18108 to port 18107) may increase pressure of the gas, enhancing the gas flow.

[2599] In the instant configuration, the direction of heat flow is as follows. Gas fed into chamber 18120 is heated/cooled by the liquid spray drops, while the hot/cold spray drops are cooled/heated by the gas. Cooled/heated liquid is drained through port 18103, and sprayed into chamber 18121. The sprayed liquid then cools/heats the gas fed into chamber 18121. The liquid drops are heated/cooled in this process and are fed back into chamber 18120.

[2600] Additional heat energy may be fed into or rejected from the liquid through thermal nodes 18131 and 18132. An example of this is an external heater (e.g. fuel burner, thermal solar, geothermal) that heats the liquid prior to being sprayed into the chambers. Another example is an external cooler (e.g. deep sea low-temperature heat-sink, heat exchange with ice/snow) that cools the liquid prior to being sprayed into the system.

[2601] The liquid cycle may be a closed cycle if the gas streams are saturated. Additional / replenishing liquid can be fed into the system through fluid linkages 18141 and 18142 to compensate for liquid that is evaporated, leaked, or carried-over.

[2602] The liquid cycle may be partially/fully open. In a fully open cycle, liquid enters from liquid linkage 18141 / 18142, is sprayed into chamber 18120 / 18121, drained through ports 18103 / 18104, and then dumped through liquid linkage 18132 / 18131.

[2603] In a partially open cycle, external fluid is combined with cycling liquid. Such mixing may allow the introduction of additional thermal energy, may allow heat to be rejected from the cycling liquid, and/or may pressurize the cycling liquid.

[2604] The liquid cycles of the two chambers may be separated. Such separation may allow for different liquids to be sprayed into the chambers. The use of different liquids may effectively accommodate a range of operating temperatures.

[2605] The thermal nodes/fluid linkages may exchange heat/fluid with one another. For example, fluid linkage 18143 allows thermal communication between the thermal nodes 18131 and 18132.

[2606] There may be no direct mixing between the two gasses. The pressure of the gasses in chambers 18120 and 18121 may be different. In order to achieve sufficient interaction between the gas and the liquid, the pump/turbine may need to change the liquid pressure appropriately.

[2607] Hydraulic pumps 18111 and 18112 can be positive displacement or centrifugal. The pumps may have two separate motors, may share one motor 18150 (as shown here).

[2608] When pressure in one chamber (e.g. chamber 18120) is much higher than that in the other chamber (e.g. chamber 18121), power may be needed to pressurize the liquid from low pressure of chamber to high pressure chamber. However, energy can be recovered from the pressurized liquid before feeding it into the low pressure chamber.

[2609] A turbine (e.g. pump/turbine 18112) may generate mechanical / electrical energy. This turbine may be mechanically linked to pump/turbine 18111 via linkage 18113, to reduce load on the pump motor, or can be used to generate electrical energy, for example where the motor 18150 comprises a motor/generator.

[2610] Certain embodiments according to the present invention may recover the liquid that is sprayed. Accordingly, the apparatus of Figure 181 includes gas-liquid separators 18151-18154 with liquid conduits as shown.

[2611] Various possible modes of operation are described in the table of Figure 181A. In certain embodiments this apparatus may also be used as a gas cleaner / filter. The sprayed liquid shower may

remove dust / solid particulates / suspended or dissolved liquid drops from gas. For example, dust particles may be dissolved in the sprayed liquid shower, and drained through ports 18103 and 18104.

[2612] Embodiments of apparatuses according to the present invention may also be used to transfer mass between materials in liquid and gas states, and/or induce or enhance a chemical reaction between such materials. For example, this embodiment can be used to humidify air or dehumidify air (e.g. by adding salt to the water). Another possible application is to transfer oxygen to water, or to add chemicals to air/water for chemical processing.

[2613] Apparatuses according to embodiments of the present invention may be subject to degradation due to physical wear conditions, and also to due to chemical corrosion such as by exposure to water. In certain embodiments, such degradation may be reduced or avoided by the fabrication of components from particular materials, through the use of coatings, and/or through the use of anti-corrosion additives.

[2614] Various types of anti-corrosion materials may be added to liquids utilized in embodiments of the present invention. Examples include but are not limited to anodic inhibitors and cathodic inhibitors. A list of specific corrosion inhibitors includes but is not limited to alkyldimethylbenzylammonium chloride (ADBAC), hexamine, benzotriazole, phenylenediamine, dimethylethanolamine, polyaniline, nitrites including sodium nitrite, cinnamaldehyde, metal oxides including zinc oxide, condensation products of aldehydes and amines (imines), volatile amines, chromates, nitrites, phosphates, hydrazine, ascorbic acid, fungicides, and biocides.

[2615] Moreover, a number of different types of materials may offer resistance to physical wear and/or chemical corrosion. One or more components of the apparatus may be fabricated in whole or in part, from such materials. Examples include stainless steel (either as a component material or a coating), diamond-like carbon (DLC) coatings, and composite materials.

[2616] In general, composite materials include a continuous phase (typically called a matrix), and a reinforcing phase. Composites having ceramic materials as the matrix, are known as ceramic matrix composites (CMCs). Composites having metal materials as the matrix, are known as metal matrix composites (MMCs). Composites having polymers as the matrix, are known as polymer matrix composites (PMCs).

[2617] PMCs can comprise thermoplastic materials, examples of which include but are not limited to poly(ether-ether-ketone) (PEEK), polypropylene, and poly(ethylene terephthalate) (PET). PMCs can also comprise thermoset materials, examples of which include but are not limited to polyester, epoxy, and phenolics.

[2618] The reinforcing phase of composite materials can comprise particles and/or fibers. Examples of fibers are given below, and can come in a variety of lengths. Such fibers can be arranged unidirectionally relative to length, as a textile, or randomly relative to the length direction. The reinforcing phase can function to improve strength/stiffness of the resulting composite, and/or to improve creep resistance of the material.

[2619] Various components of the composite can impart desirable characteristics to the material, including but not limited to reducing corrosion, improving wear resistance, changing thermal

conductivity, and/or enhancing internal lubrication by lowering frictional coefficient and/or by forming a transfer film.

[2620] Specific examples of possible candidates for composite material coatings that may be useful in embodiments of the present invention, may include one or more of the following as a component, as part of a matrix, for reinforcement, for lubrication, and/or for other purposes such as corrosion resistance:

- carbon-containing materials, including graphite and/or silicon carbide (SiC);
- nickel, boron, and/or nickel borides, including but not limited to, NiB, Ni_2B, Ni_3B, Ni_4B_3, Ni_3B_2, NiB2, NiB_{12}, Ni_2B_3, NiB.
- polymers, including but not limited to polytetrauoroethylene (PTFE); polypropylene; polyethylene, including high density polyethylene (HDPE), poly(ethylene terephthalate) (PET); poly(ether-ether-ketone) (PEEK); poly(phenylene sulphide) (PPS); polyamide (PA); Polymethylmethacrylate (PMMA); aliphatic polyketone (APK); polyester; polyoxymethylene (POM);
- copper containing materials, for example copper compounds including but not limited to bronze, CuO, CuS, and/or CuF_2;
- metal oxides including but not limited to TiO_2, ZrO_2, and/or Al_2O_3;
- fibers of various lengths, including but not limited to aramid fibers (AFs), carbon fibers (CFs), basalt fibers (BFs), and glass fibers (GFs) including glass fiber reinforced (GFR) materials;
- molybdenum containing materials, including but not limited to MoS_2.

[2621] In addition to imparting wear/corrosion resistance, composite materials can find other uses in embodiments according to the present invention. For example, in certain embodiments the gas storage vessel may comprise a composite material. One example of such a composite material could include a reinforcing phase in the form of a metal wire or basalt fiber. Such a composite material could reduce the weight and cost of the storage tank, while preserving its ability to store gas at high pressure.

[2622] Other techniques can also be applied to improve performance of the storage unit. For example, certain embodiments may employ energy from gas expansion to drive flows of liquid into the storage tank, thereby maintaining a substantially constant pressure in the storage tank as gas is flowed therein.

[2623] Conventionally, during expansion a stored gas starts off at a given pressure, which diminishes over time as the system runs and the gas supply is depleted. However the efficiency of the system declines as the gas pressure drops.

[2624] By contrast, Figure 141 shows a simplified view of an embodiment of a system which may be used to avoid this inefficiency. Specifically, in the system 14100 efficiency is improved by pumping liquid into the tank to replace the volume of air that is released during expansion. In this manner, the pressure in the tank remains roughly constant as the gas supply is depleted.

[2625] In certain embodiments the pump 14104 can be driven by the same linkage 20306 (here a crankshaft) being actuated by the motion of a moveable member 14108 (here a reciprocating piston) that is driven by the expanding gas. In certain embodiments, this pump can feature components (e.g. cylinder, piston, valve) similar to the gas expansion/compression apparatus 14110.

[2626] During gas compression, the opposite mechanism is used. That is, liquid is removed from the gas storage tank 14102 as compressed gas is added from the expander/compressor 14110. The liquid removed from the tank will be at high pressure and can be used to drive the piston 14112 and the linkage which then acts as a hydraulic motor, reducing the amount of power required to compress the incoming gas.

[2627] Certain embodiments according to the present invention could feature a pump/motor element that operates according to pneumatic principles to flow a gas stabilizing a pressure within the storage unit. The storage unit could includes a moveable barrier defining two compartments.

[2628] 1. A system comprising:

a chamber in selective fluid communication with a gas storage unit, the chamber having disposed therein a member moveable in response to gas from the gas storage unit expanding within the chamber;

a pump in selective pressure communication with the gas storage unit; and

a linkage between the member and the pump, wherein gas expanding within the chamber drives the pump to stabilize a pressure within the gas storage unit.

[2629] 2. The system of claim 1 wherein the member comprises a piston and the linkage is configured to convert reciprocating piston motion into shaft torque.

[2630] 3. The system of claim 2 wherein the linkage comprises a crankshaft.

[2631] 4. The system of claim 2 further comprising an element configured to inject a liquid into gas expanding within the chamber.

[2632] 5. The system of claim 1 wherein the linkage is in communication with an electrical generator.

[2633] 6. The system of claim 1 wherein the pump is configured to flow a liquid into the gas storage unit.

[2634] Some embodiments of the present invention may utilize certain devices that can convert inlet thermal energy in the form of heat, into outlet thermal energy in the form of coolness. One example of such a device is an absorption chiller, wherein moisture taken in by a liquid sorbent (for example ammonia or aqueous LiBr solution) results in a lowering of temperature (cooling). Desorption is the converse process, wherein application of the inlet thermal energy in the form of heat liberates the moisture from the liquid sorbent, thereby regenerating the liquid sorbent to allow the next cooling cycle. The liquid sorbent may, but need not be, the same liquid that is injected for heat exchange. Alternative embodiments may use the process of adsorption, wherein the sorbent is a solid material (e.g. silica) rather than a liquid.

[2635] According to certain embodiments of the present invention, small liquid droplets exhibiting a large surface area desirable for effective heat exchange, may be introduced into gas undergoing compression or expansion, utilizing nozzle designs that combine a swirling liquid flow with impingement upon a deflection plate. Figures 148AA-B depict various views schematically illustrating the effect of such a configuration upon droplet formation.

[2636] Specifically, particular embodiments of the present invention impart a swirling motion to flowing water utilizing helical channels 14802 present in a first (swirl) structure 14804. This swirling motion creates a streamlined water flow 14806 around an axial rod, here a neck 14808 of a second (deflector) structure 14810.

[2637] The number of such helical channels may differ between particular embodiments. For example while the embodiment of Figure 148AA shows a structure having four such helical channels, this is not required. An alternative embodiment such as is shown in Figures 148AB-AE, may feature a different number (two) of helical channels.

[2638] Figures 148AB-AE show various views illustrating exemplary flow paths of liquid through a swirl nozzle according to embodiments of the present invention. In particular, the liquid flow path first enters the recesses 14801 present in the back surface 14804a of the insert (points A and A' in Figs. 148AD-AE). The liquid flow path then follows the helical channel 14802 at a fixed radius around the perimeter of the insert to emerge from the helical channel (at points B and B' in Figs. 148AD-AE). Over this distance the flowing liquid acquires an angular momentum.

[2639] Thereafter, the liquid flow path moves to the toroidal-shaped outlet opening 14820 defined between the neck of the deflector plate and the surrounding material of the body (points C and C' in Figs. 148AD-AE). Over segments (B-C, B'-C') of the respective flow paths the liquid acquires an angular velocity component, owing to the decreased radial distance of the toroidal-shaped outlet opening, relative to radial distance of the outlets of the spiral channels.

[2640] Moreover, owing to conservation of the existing angular momentum previously imparted by the spiral channels, over the segments (B-C, B'-C') the angular velocity component increases as the radius of the flow path declines. This increasing tangential velocity component serves to streamline the fluid flow to swirl around the neck of the deflector and exit through the outlet opening.

[2641] Upon exiting the toroidal-shaped outlet opening, the liquid travels in a linear direction until reaching the surface 14810a of the deflection plate 14810. Upon impinging this deflection surface (points D and D' respectively in Figures 148AD-AE), the liquid flow continues to travel over the surface of the deflector.

[2642] In particular, Figure 148B shows that impingement by the swirling liquid flow upon the surface 14812 of the deflector structure, spreads a thin sheet of water 14814 over that surface 14812 (between solid boundary and air). The sheet grows even thinner as it reaches the edge of the deflector plate. Ultimately the sheet exits the deflector plate, and breaks up into small droplets 14816.

[2643] Figures 148CA-CB show assembled and exploded views respectively, of the first (swirl) structure 14804 and the second (deflector) structure 14910 as positioned within a corresponding cavity 14950 of a nozzle body 14952.

[2644] One potential benefit offered by nozzle designs exhibiting a swirling flow in the manner of Figures 148A-B, is a reduction in the amount of energy required to drive the liquid through the nozzle. In particular, rather than impinging the deflection surface at a near orthogonal angle (as is the case with the nozzle embodiment of Figures 100A-J), the swirling liquid flow instead impinges the deflection

surface at a larger angle. This reduces the magnitude of momentum change imparted to the flowing liquid, hence the corresponding energy loss.

[2645] The short break-up length resulting from rotational motion of the liquid in combination with impingement upon the deflector plate, may convey a number of beneficial effects. One such effect is to lengthen an amount of time that a resulting small liquid droplet is exposed to compressing or expanding gas, prior to encountering a solid surface such as a piston head or cylinder wall. Such prolonged exposure provides an opportunity for greater heat exchange with the compressing or expanding gas.

[2646] Another potential benefit of a short break-up length is a reduction in local pressure differentials within the cylinder, that can undesirably interfere with uniform mixing of droplets and gas. For example, liquid in the form of a continuous sheet can serve as a barrier to the free circulation of gas, preventing the rapid equilibration of local pressure differences.

[2647] In some cases, the presence of a continuous liquid sheet can promote formation of low pressure pockets proximate to the cylinder head. These low pressure pockets can in turn draw the liquid toward the cylinder wall, preventing further break-up and even causing re-coalescence of droplets along the wall. Both effects are undesirable from the standpoint of promoting gas-liquid heat exchange.

[2648] By contrast, embodiments of the present invention seek to disrupt the stability of a continuous liquid sheet, both by imparting rotational motion to the liquid flow and by its impingement upon a deflection surface. The resulting small liquid droplets do not form a barrier to the free flow of gases, promoting equilibration to resolve local pressure differences.

[2649] Embodiments of nozzles according to the present invention may offer certain benefits over conventional atomizers. For example, such conventional designs typically form a very thin sheet of liquid between the solid walls of the nozzle. However, creating such a thin sheet between two solid walls may introduce certain difficulties, for example in terms of machining, nozzle clogging, and/or pressure-drop. Additionally, sheet thickness and droplet sizes of such conventional nozzles may be sensitive to the geometric dimensions and machining tolerance.

[2650] Moreover, embodiments of nozzles according to the present invention may also offer certain benefits over conventional swirl atomizer designs. For example, in conventional swirl atomizers the swirling motion causes the liquid to attach to inner walls. The liquid is then spread thin between the solid boundary at the exit orifice and the air.

[2651] Once the sheet exits the orifice of such a conventional swirl atomizer, it forms a hollow cone of thin liquid sheet, which breaks up into small droplets. However, the cone angle for conventional swirl nozzles is typically small (less than 100 degrees). By contrast, incorporation of a deflection plate in the embodiments described above, can increase the cone angle.

[2652] A number of swirl nozzle designs were created, and their performance tested. Figures 149A-DB show various views of a generic swirl nozzle. In particular, the swirl nozzle comprises a body 14902 including an interior angled surface 14903, and defining a cavity 14904 having a first larger inlet opening 14906, and a defining a second smaller outlet opening 14908. Swirl insert 14910 featuring back surface

14909 having indentations 14912 in fluid communication with helical channels 14914, is positioned within the cavity 14904.

[2653] Figures 149DA-DB show different views of the front surface 14911 of the swirl insert. In particular, Figures 149DA-DB show this front surface 14911 as comprising outlet openings 14913 in fluid communication with the spiral channels. The front surface 14911 further comprises a recess 14915 whose angled surface 14917 in combination with the opposing angled internal surface 14903 of the body 14902, defines a velocity enhancing portion 14960.

[2654] Specifically, the liquid flows through the passageway 14960 defined between opposing surfaces 14917 and 14903 offered by the insert and the body. Because passageway 14960 offers a smaller cross-sectional area to the incoming liquid than the spiral channel(s) 14914, the velocity of the liquid is enhanced.

[2655] Additionally, the spiral channels have a larger radial distance from the axis than the outlet opening 14908. Therefore, based on the conservation of tangential momentum, the liquid's tangential velocity increases at it moves towards the outlet opening 14908.

[2656] In addition, the respective surfaces 14917 and 14903 are inclined at different angles relative one another. Specifically, in this particular embodiment, the surface 14903 is inclined at an angle of 15°, while surface 14917 is inclined at an angle of 30°.

[2657] This geometry is arranged to offer smaller cross-sectional area as the liquid flows through passageway 14960. In particular, the cross-sectional area of the inlet to the velocity enhancement portion, is substantially smaller than the cross-sectional area of the gap forming the outlet of the velocity enhancement portion.

[2658] Based upon the relative cross-sectional areas of the inlet and outlet to the velocity enhancement portion of the nozzle, the configuration of the embodiment of Figures 149A-DB can lower the magnitude of the pressure drop experienced by the liquid. Such a reduced pressure drop can desirably lower the amount of energy required to force the liquid through the nozzle. In addition, this configuration can desirably reduce an incidence of cavitation while inducing the velocity vector profile to create a hollow conical sheet of the liquid emerging from the nozzle.

[2659] Experiments conducted on embodiments 1-8 show that performance of various embodiments of the nozzle is not strongly sensitive to geometric dimensions and machining tolerance. Flow rate through the nozzles at a fixed pressure does depend on the number of helical channels.

[2660] Deflection insert 14916 comprising neck 14918 supporting deflector plate 14920 having inclined surface 14922, is positioned through opening 14924 in the swirl insert 14910. The flow of liquid through body 14902 and these two inserts 14910, 14916 to produce spray droplets, proceeds generally as described above in connection with Figures 148AA-CB.

[2661] Figures 149A-B show the inserts 14910, 14916 as being secured within the cavity utilizing a number of components. In particular, the swirl insert 14910 is fixed to the body 14902 utilizing bracket 14930 and corresponding pins 14932. The swirl insert 14910 may be prevented from rotating by a raised

or recessed backside feature (not shown here) configured to mate with a complementary frontside feature of the bracket.

[2662] Deflection insert 14916 is secured by threaded engagement with swirl insert , and is fixed in place using lock nut 14940. Relative spacing between the deflection insert 14916 and the body 14902 may be controlled by this threaded engagement. Such relative spacing can determine, for example, the size of the gap through which the liquid exits.

[2663] Moreover, the nozzle design provides for a second mechanism for controlling the spacing between the body and the insert deflection insert 14916. In particular, shims 14942 (here four washers) having a fixed thickness. may be used to control the position relative to the body, of the assembly comprising the deflection insert 14916 and the swirl insert 14910.

[2664] Body 14902 having the inserts 14910, 14916 secured therein, may receive a liquid flow from manifold 14950. This manifold may be secured to holes 14952 in body 14902 utilizing screws 14954.

[2665] Embodiments of spray nozzles according to the present invention may exhibit particular performance characteristics. One performance characteristic is droplet size.

[2666] Droplet size may be measured using DV50, Sauter mean diameter (also called SMD, D32, d32 or D[3, 2]), or other measures. Embodiments of nozzles according to the present invention may produce liquid droplets having SMD's within a range of between about 10-300 microns. Examples of droplet sizes produced by embodiments of nozzles according to the present invention include but are not limited to those having a SMD of about 300 microns, 250 microns, 200 microns, 150 microns, 100 microns, 50 microns, 25 microns, and 10 microns.

[2667] Another performance characteristic of liquid spray nozzles according to embodiments of the present invention, is flow rate. Embodiments according to the present invention may produce a flow rate of between about 20 and 0.01 liters per second. Examples of flow rates of embodiments of nozzles according to the present invention are 20, 10, 5, 2, 1, 0.5, 0.25, 0.1, 0.05, 0.02, and 0.01 liters per second.

[2668] Another performance characteristic of liquid spray nozzles according to embodiments of the present invention, is breakup length. Liquid output by embodiments of nozzles according to the present invention may exhibit a breakup length of between about 1-100 mm. Examples of breakup lengths of sprays of liquid from nozzles according to the present invention include 100, 50, 25, 10, 5, 2, and 1 mm.

[2669] Embodiments of nozzles according to the present invention may produce different types of spray patterns. Examples of spray patterns which may be produced by nozzle embodiments according to the present invention include but are not limited to, hollow cone, solid cone, stream, single fan, and multiple fans.

[2670] Embodiments of nozzles according to the present invention may produce spray cone angles of between about 20-180 degrees. Examples of such spray cone angles include but are not limited to 20°, 50°, 90°, 120°, 140°, 150°, 155°, 160°, 165°, 170°, 175° , and 180°.

[2671] Droplet spatial distribution represents another performance characteristic of liquid spray nozzles according to embodiments of the present invention. One way to measure droplet spatial distribution is to measure the angle of a sheet or cone cross-section that includes most of the droplets that deviate from the

sheet. In nozzle designs according to embodiments of the present invention, this angle may be between 0-90 degrees. Examples of such angles possibly produced by embodiments of the present invention include but are not limited to 0°, 1°, 2°, 3°, 4°, 5°, 7.5°, 10°, 15°, 20°, 25°, 30°, 45°, 60°, 75°, or 90°.

[2672] According to certain embodiments of the present invention, it may be important to control the amount of liquid introduced into the chamber to effect heat exchange. The ideal amount may depends on a number of factors, including the heat capacities of the gas and of the liquid, and the desired change in temperature during compression or expansion.

[2673] The amount of liquid to be introduced may also depend on the size of droplets formed by the spray nozzle. One measure of the amount of liquid to be introduced, is a ratio of the total surface area of all the droplets, to the number of moles of gas in the chamber. This ratio, in square meters per mole, could range from about 1 to 250 or more. Examples of this ratio which may be suitable for use in embodiments of the present invention include 1, 2, 5, 10, 15, 25, 30, 50, 100, 125, 150, 200, or 250.

[2674] Figures 149CA-CB show generic representations of the nozzle design, including particular dimensions. Specific swirl nozzle designs represent variations in those dimensions as referenced in the following table.

For swirl nozzle embodiments 1-8:
D4 = 12.7 mm; A1 = 15°; A2 = 30°;
L6 = 4.57 mm; A7 = 9.1E-7 m^2;
Helix pitch = 20 mm/turn

Nozzle embodiment #	D1	D2	D3	L4	L5	A3	R1	L7	# of helices
	[mm]				[μm]	[deg]	[mm]		
1	5.0	2.5	8.8	0.78	270	15	--	N/A	4
2	3.0	1.43	8.84	1.06	290				
3		1.55	5.01*	0.63	357	12			2
4		1.43	8.84	0.965	201	15			
5			~4*	0.53	390	12			
6			~7*	0.75	320	12			
7		1.54	4.97	N/A	360	15	1.11	1.626	
8					485			1.746	

[2675] In the nozzle design of Embodiments 3 and 5-8, the deflector plate tapers at an angle after the widest point represented by the dimension D3, as shown in the dotted line of Figure 149CA. This taper is made to reduce dripping as well as water bending attributable to the Coanda effect.

[2676] The methodology for testing certain of these embodiments is now described in detail below. In evaluating performance of the embodiment 1, the flow rate was correlated to pressure by measuring accumulated volume using a stop watch and a graduated cylinder. The results were: pressure = 132.5 psig, flow rate = 75.94 ml/s; pressure = 180 psig, flow rate = 89.2 ml/s.

[2677] An experiment setup to evaluate nozzle performance was created as shown in Figures 150A-B. Figure 150C shows a simplified sketch of the coordinate system and the field of view, and is not drawn to scale.

[2678] Various runs took place with water pressures of 105 and 205 PSIG being tested. The angle between the nozzle surface and x-y plane is 13.2 degree in the test. The following table summarizes the testing conditions for different runs.

Run	z [mm]	Mean P [PSI]	FOV size [inch]
1	0	85	1.9
2	0	180	1.9
3	0	205	1.9
4	0	105	1.9
5	0	105	1.9
6	0	205	1.9
7	0	205	0.638
8	1	205	0.638
9	2	205	0.638
10	3	205	0.638
11	0	105	0.638
12	1	105	0.638
13	2	105	0.638
14	3	105	0.638
15	4	105	0.638
16	5	105	0.638
17	6	105	0.638
18	7	105	0.638
19	8	105	0.638

[2679] The following table summarizes performance of the nozzle embodiment 1:

		205 PSIG (runs 3 & 7)	105 PSIG (runs 4 & 15)
Average velocity in run 3 & 4 [m/s]		34.27	23.56
Droplet Size in 1.9" FOV; run 3 & 4	D32 [μm]	241.9	283.8
	DV50 [μm]	276.7	326.1
Droplet Size in 0.638" FOV; run 7 & 15	D32 [μm]	231.1	264.0
	DV50 [μm]	278.8	311.6
Breakup length from one instantaneous image [inch]		Shorter than 0.455"	About 0.455" or less
Sheet Angle		13.2	16.2
Thickness Water sheet at x= 3" [mm]		5.6	8.3

For runs 3 and 4, a lack of recognition of small droplets may reduce the reliability of the droplet size statistics.

[2680] Figure 151 shows a structure of the spray from the embodiment 1 at a pressure of 205 PSIG. In particular, Figure 151 shows global flow structure from two instantaneous shadowgraphy images that were not taken at the same time.

[2681] The velocity field of the embodiment 1 at a pressure of 205 PSIG is described in the following table, which shows the mean velocity from runs 3 and 6 with 300 instantaneous velocity fields.

Run		Min [m/s]	Max [m/s]	Max from profile FIG. 153 [m/s]	Average [m/s]	RMS [m/s]
3	Vx	-46.02	-19.63	N/A	-31.84	2.84

	Vy	-28.61	29.65	N/A	-0.72	12.50
	|V|	28.72	47.20	37.9	34.27	2.02
6	Vx	-33.00	-18.99	N/A	-27.62	2.45
	Vy	-11.64	10.02	N/A	-0.66	4.60
	|V|	19.09	33.00	N/A	28.00	2.55

[2682] Figure 152A shows mean velocity vectors of 205 PSIG from run 3 and run 6. The line shows the location of velocity profile in Figure 153 that is x = -3.1 mm. Figure 152B shows RMS velocity vectors of 205 PSIG from run 3 and run 6.

[2683] Figure 153 shows profiles of velocity magnitude along x=-3.1 mm line in run 3. Y position (mm) is plotted along the horizontal axis. Velocity magnitude (m/s) is plotted along the vertical axis. The red line is mean velocity, and the green line is RMS velocity.

[2684] Droplet sizes were analyzed at pressures of 205 PSIG in embodiment 1, as follows. For run 3, the droplets size analysis was conducted only from the lower 1/2 of the FOV.

[2685] Figure 154A shows one instantaneous image with recognized droplets from run 3. The blue circles/dots show the recognized droplets. The rest of the droplets are either too small to be recognized or out of focus. Figure 154B shows the histogram of droplet size.

[2686] The following table shows droplet size statistics.

Number of droplets	745365
D10 [μm]	158.9
D32 [μm]	241.9
DV10 [μm]	142.7
DV50 [μm]	276.7
DV90 [μm]	474.8
RMS [μm]	75.2

While the small droplets are not recognized, this does give some idea of the distribution of big droplets.

[2687] Figure 155A shows one instantaneous image with recognized droplets from run 6. The blue circles/dots show the recognized droplets. The rest of the droplets are either too small to be recognized or out of focus.

[2688] Figure 155B shows the histogram of the droplet size. The following table shows droplet size statistics.

Number of droplets	860219
D10 [μm]	153.9
D32 [μm]	230.4
DV10 [μm]	139.0
DV50 [μm]	263.4
DV90 [μm]	426.6
RMS [μm]	72.4

Again, while the small droplets are not recognized, this does give some idea of the distribution of big droplets.

[2689] The droplet sizes in runs 7-10 were also analyzed. Figure 156A shows one instantaneous image with recognized droplets of run 7 (z = 0 mm; sheet angle = 13.2 degree). The blue circles/dots show the

recognized droplets. The rest of the droplets are either too small to be recognized or out of focus. Figure 156B shows the histogram of the droplet size of run 7.

[2690] The following table shows the statistics of droplet size of runs 7-10.

Run	Z [mm]	Sheet Angle	# of droplets	D10 [μm]	D32 [μm]	DV10 [μm]	DV50 [μm]	DV90 [μm]	RMS [μm]
7	0	13.2	71891	108.4	231.1	140.1	278.8	443.2	79.7
8	1	14.0	60498	105.4	231.1	137.3	280.3	456.4	78.5
9	2	14.7	44229	103.7	228.2	132.8	280.7	456.9	76.3
10	3	15.5	33241	93.0	220.9	121.7	276.9	519.4	70.1

[2691] Figure 157 shows droplets size distribution along z axis (in terms of sheet angle) of runs 7 to 10. The D32 line and number of droplet line reach maximum at z = 0 mm (sheet angle 13.2 degree). The sheet thickness defined by Full-Width Half-Maximum (FWHM) from the number of droplets line is about 5.6 mm.

[2692] As indicated above, the nozzle embodiment 1 was also run at a lower pressure of 105 psig. Figure 158 shows the flow structure from two instantaneous shadowgraphy images that were not taken at the same time.

[2693] The velocity field for the lower pressure runs 4 and 5 of the embodiment 1 nozzle design, is shown in the following table.

Run		Min [m/s]	Max [m/s]	Max from profile in FIG. 160 [m/s]	Average [m/s]	RMS [m/s]
4	Vx	-35.40	-11.84	N/A	-21.90	2.22
	Vy	-20.09	20.49	N/A	-0.46	8.56
	|V|	11.93	36.38	26.7	23.56	1.80
5	Vx	-22.04	-13.70	N/A	-17.64	1.77
	Vy	-7.21	6.84	N/A	-0.42	2.91
	|V|	13.80	22.05	N/A	17.88	1.81

[2694] The mean and RMS velocity fields from runs 4-5 are shown in Figure 159A. The red line shows the location of velocity profile in figure Q at x = -3.1 mm. Figure 159B shows the RMS velocity vectors from runs 4-5.

[2695] Figure 160 plots profiles of velocity magnitude along x = -3.1 mm line in run 4. The y position (mm) is plotted along the horizontal axis. The velocity magnitude (m/s) is plotted along the vertical axis. The red line is mean velocity, and the green line is RMS velocity.

[2696] Droplet sizes were analyzed at lower pressures of 105 PSIG in embodiment 1, as follows. For run 4, the droplets size analysis was conducted only from the lower 1/2 of the FOV.

[2697] Figure 161A shows one instantaneous image with recognized droplets from run 4. The blue circles/dots show the recognized droplets. The rest of the droplets are either too small to be recognized or out of focus. Figure 161B shows a histogram of droplet size.

[2698] The following table shows statistical results from run 4.

Number of droplets	384952
D10 [μm]	180.7
D32 [μm]	283.8

DV10 [μm]	173.7
DV50 [μm]	326.1
DV90 [μm]	525.8
RMS [μm]	92.4

Again, while the small droplets are not recognized, this does give some idea of the distribution of big droplets.

[2699] Figure 162A shows one instantaneous image with recognized droplets from run 5. The blue circles/dots show the recognized droplets. The rest of the droplets are either too small to be recognized or out of focus. Figure 162B shows a histogram of droplet size.

[2700] The following table shows statistical results from run 5.

Number of droplets	427711
D10 [μm]	171.4
D32 [μm]	265.5
DV10 [μm]	164.5
DV50 [μm]	306.0
DV90 [μm]	474.1
RMS [μm]	86.7

Again, while the small droplets are not recognized, this does give some idea of the distribution of big droplets.

[2701] The droplet sizes in runs 11-19 were also analyzed. Figure 163A shows one instantaneous image with recognized droplets of run 15 (z = 4 mm; sheet angle = 16.2 degree). The blue circles/dots show the recognized droplets. The rest of the droplets are either too small to be recognized or out of focus. Figure 163B shows the histogram of the droplet size of run 15.

[2702] The following table shows the statistics of droplet size of runs 11 to 19.

Run	Z [mm]	Sheet Angle	# of droplets	D10 [μm]	D32 [μm]	DV10 [μm]	DV50 [μm]	DV90 [μm]	RMS [μm]
11	0	13.2	25938	110.2	249.2	145.5	305.4	519.4	83.6
12	1	14.0	33321	117.2	251.4	153.3	302.5	473.4	87.8
13	2	14.7	41542	123.2	258.4	160.2	305.8	478.6	91.5
14	3	15.5	47037	126.7	261.9	163.8	308.6	478.9	93.6
15	4	16.2	49550	127.8	264.0	165.0	311.6	479.1	94.6
16	5	17.0	48237	126.7	261.2	163.9	308.4	465.4	93.6
17	6	17.7	44849	121.3	259.5	162.0	310.2	471.3	92.3
18	7	18.4	36947	115.1	257.4	156.7	309.9	489.5	89.3
19	8	19.2	28838	106.7	248.7	147.6	307.9	480.8	84.3

[2703] Figure 164 shows droplets size distribution along the z axis (in terms of sheet angle) of runs 11 to 19. The D32 line and number of droplet line reach maximum at z = 4 mm (sheet angle 16.2). The sheet thickness defined by Full-Width Half-Maximum (FWHM) from the number of droplets line is 8.3 mm.

[2704] Exit velocity versus water pressure for the embodiment 1 nozzle, is plotted in Figure 165. The following table lists exit velocity versus water pressure.

Run	1	4	2	3
Pressure [PSIG]	85	105	180	205
Max velocity at x = -3.1 mm [m/s]	24	26.7	35.78	37.9

[2705] As indicated above, a second embodiment (embodiment 2) of the nozzle design had features similar to embodiment 1, but with certain dimension different. In evaluating performance of this embodiment 2, the flow rate was correlated to pressure by measuring accumulated volume using a stop watch and a graduated cylinder. The results were: pressure = 61 psig, flow rate = 33.05 ml/s; pressure = 105 psig, flow rate = 43.87 ml/s; pressure = 200 psig, flow rate = 60.43 ml/s.

[2706] An experiment setup to evaluate nozzle performance was created as shown in Figures 166A-B. Figure 166C shows a simplified sketch of the coordinate system and the field of view, and is not drawn to scale.

[2707] Various runs took place with water pressures of 100 and 200 PSIG being tested. The angle between the nozzle surface and x-y plane is 16 degree in the test. The following table summarizes the testing conditions for different runs.

Run	z [mm]	Mean P [PSI]	FOV size [inch]
1	0	100	2.1
2	0	196	2.1
3	4	196	2.1
4	4	100	2.1
5	0	200	0.6
6	1	200	0.6
7	2	200	0.6
8	3	200	0.6
9	4	200	0.6
10	5	200	0.6
11	6	200	0.6
12	7	200	0.6
13	8	200	0.6
14	9	200	0.6
15	10	200	0.6
16	0	100	0.6
17	2	100	0.6
18	3.5	100	0.6
19	5	100	0.6
20	6.5	100	0.6
21	8	100	0.6
22	9.5	100	0.6
23	11	100	0.6
24	12.5	100	0.6
25	14	100	0.6
26	15.5	100	0.6

[2708] The following table summarizes performance of the nozzle embodiment 2:

		200 PSIG (run 2 & 11)	100 PSIG (run 1 & 22)
Average velocity in run 1 & 2 [m/s]		30.2	20.5
Droplet Size in 0.638" FOV; run 11 & 22	D32 [μm]	146.9	176.6
	DV50 [μm]	179.0	214.3
Breakup length from one instantaneous image [inch]		Less than 0.445"	About 0.445"

Sheet Angle	18.3 | (20.5)	20.9 | (22.5)
Thickness Water sheet at x= 3" [mm]	10.2	13.8

Quantities in parentheses indicate alternative values.

[2709] Figure 167 shows a structure of the spray from the embodiment 2 at a pressure of 200 PSIG. In particular, Figure 167 shows global flow structure from two instantaneous shadowgraphy images that were not taken at the same time.

[2710] The velocity field of the embodiment 2 at a pressure of 200 PSIG is described in the following table, which shows the mean velocity from runs 2 and 3 with 300 instantaneous velocity fields.

Run		Min [m/s]	Max [m/s]	Max from profile in FIG. 169 [m/s]	Average [m/s]	RMS [m/s]
2	Vx	-35.3	-15.1	N/A	-27.5	3.3
	Vy	-30.5	26.0	N/A	-4.4	11.7
	|V|	20.0	38.0	37.5	30.2	3.6
3	Vx	-27.1	-9.6	N/A	-19.5	3.6
	Vy	-11.4	5.3	N/A	-1.4	3.4
	|V|	9.8	27.7	N/A	19.8	3.7

[2711] Figure 168A shows the mean velocity vectors from runs 2 and 3. The line shows the location at x = -3.1 mm of the velocity profile in Figure 169. Figure 168B shows the RMS velocity vectors from runs 2 and 3.

[2712] Figure 169 shows profiles of velocity magnitude along x = - 3.1 mm line in run 2. Y position (mm) is plotted along the horizontal axis. Velocity magnitude (m/s) is plotted along the vertical axis. The red line is mean velocity, and the green line is RMS velocity.

[2713] Droplet sizes were analyzed at the pressure of 200 PSIG in embodiment 2, as follows. For runs 2-3, the large FOV measurements are not suitable for droplet size analysis, so they are not reported.

[2714] Figure 170A shows one instantaneous image with recognized droplets of run 8 (z = 3 mm; sheet angle = 18.3 degree). The blue circles/dots show the recognized droplets. The rest of the droplets are either too small to be recognized or out of focus. Figure 170B shows the histogram of the droplet size of run 8.

[2715] Figure 171A shows one instantaneous image with recognized droplets of run 11 (z = 6 mm; sheet angle = 20.5 degree). The blue circles/dots show the recognized droplets. The rest of the droplets are either too small to be recognized or out of focus. Figure 171B shows the histogram of the droplet size of run 11.

[2716] The following table shows the statistics of droplet size of runs 5 to 15.

Run	Z [mm]	Sheet Angle	# of droplets	D10 [μm]	D32 [μm]	DV10 [μm]	DV50 [μm]	DV90 [μm]	RMS [μm]
5	0	16.0	54835	62.2	113.0	65.0	133.4	236.2	36.9
6	1	16.8	65263	64.7	118.7	68.8	140.5	243.8	39.0
7	2	17.5	76078	68.0	127.2	73.4	152.4	260.0	42.0
8	3	18.3	79048	71.1	133.0	77.0	160.5	267.7	44.2
9	4	19.0	74532	73.7	138.4	80.0	167.5	271.8	46.1
10	5	19.8	67217	75.8	144.5	83.4	175.6	283.5	48.2
11	6	20.5	58155	77.7	146.9	84.4	179.0	289.4	49.0

12	7	21.2	49095	77.5	146.2	83.8	177.5	293.1	48.6
13	8	22.0	36850	77.2	143.4	81.4	174.0	285.3	47.5
14	9	22.7	31440	75.3	141.2	79.3	172.2	286.0	46.4
15	10	23.5	24374	73.0	134.5	74.8	164.4	280.3	43.8

[2717] Figure 172 shows droplets size distribution along z axis (in terms of sheet angle) of runs 5 to 15. The number of droplets line reaches maximum at z = 3 mm (sheet angle 18.3 degree). The sheet thickness defined by Full-Width Half-Maximum (FWHM) from the number of droplets line, is about 10.2 mm. The sheet angle and FWHM from D32 lines are 20.5 degree and 18 mm.

[2718] The accuracy of the sheet thickness determination from the D32 lines may be reduced, because the profile needs to be extended far away from measurement data. The sheet thickness determined from the D32 lines may not be useful, since there may be not many droplets far away from the sheet center.

[2719] As indicated above, the nozzle embodiment 2 was also run at a lower pressure of 100 psig. Figure 173 shows the flow structure from two instantaneous shadowgraphy images that were not taken at the same time.

[2720] The following table shows the mean velocity from runs 1 and 4 with 300 instantaneous velocity fields.

Run		Min [m/s]	Max [m/s]	Max from profile in FIG. 175 [m/s]	Average [m/s]	RMS [m/s]
1	Vx	-25.6	-9.7	N/A	-18.6	2.8
	Vy	-20.7	18.8	N/A	-2.9	8.1
	|V|	11.0	26.9	25.6	20.5	3.0
4	Vx	-18.4	-3.5	N/A	-11.5	3.0
	Vy	-7.2	4.3	N/A	-1.0	2.1
	|V|	3.7	18.6	N/A	11.7	3.1

[2721] Figure 174A shows mean velocity vectors of 100 PSIG from runs 1 and 4. The red line shows the location of velocity profile at x = -3.1 mm in Figure 175. Figure 174B shows the RMS velocity vectors of 100 PSIG from runs 1 and 4.

[2722] Figure 175 shows profiles of velocity magnitude along x = -3.1 mm lines in run 1. Velocity magnitude (m/s) is plotted along the vertical axis. The red line is mean velocity, and the green line is RMS velocity.

[2723] Droplet sizes were analyzed at the pressure of 100 PSIG in embodiment 2, as follows. For runs 1 and 4, the large FOV measurements are not suitable for droplet size analysis, so they are not reported.

[2724] Figure 176A shows one instantaneous image with recognized droplets of run 20 (z = 6.5 mm; sheet angle = 20.9 degree). The blue circles/dots show the recognized droplets. The rest of the droplets are either too small to be recognized or out of focus. Figure 176B shows the histogram of the droplet size of run 20.

[2725] Figure 177A shows one instantaneous image with recognized droplets of run 22 (z = 9.5 mm; sheet angle = 23.1 degree). The blue circles/dots show the recognized droplets. The rest of the droplets are either too small to be recognized or out of focus. Figure 177B shows the histogram of the droplet size of run 22.

[2726] The following table shows the statistics of droplet size of runs 16 to 26.

Run	Z [mm]	Sheet Angle	Num of droplets	D10 [μm]	D32 [μm]	DV10 [μm]	DV50 [μm]	DV90 [μm]	RMS [μm]
16	0	16.0	16157	75.0	145.3	85.7	176.8	271.0	48.9
17	2	17.5	22503	78.6	156.7	94.4	190.5	297.4	53.1
18	3.5	18.6	27922	82.0	166.2	100.8	202.1	298.4	56.7
19	5	19.8	34045	82.5	171.3	103.9	209.1	298.5	58.7
20	6.5	20.9	36466	81.9	173.3	105.8	211.7	298.7	59.4
21	8	22.0	34979	80.5	174.5	106.8	212.3	298.8	59.4
22	9.5	23.1	31309	79.9	176.6	108.2	214.3	298.9	60.1
23	11	24.2	27585	76.7	169.0	102.3	207.3	298.8	57.0
24	12.5	25.3	21124	75.7	161.8	97.2	197.3	298.5	54.4
25	14	26.4	18964	72.4	153.5	90.2	189.1	298.4	50.8
26	15.5	27.5	16706	69.0	141.3	79.8	173.2	294.5	46.0

[2727] Figure 178 shows droplets size distribution along z axis (in terms of sheet angle) of runs 16 to 26. The number of droplet line reaches maximum at z = 6.5 mm (sheet angle 20.9). The sheet thickness defined by Full-Width Half-Maximum (FWHM) from the number of droplets line is 13.8 mm. The sheet angle and sheet thickness from D32 lines are about 22 to 23 degrees and 26 mm.

[2728] Again, the accuracy of the sheet thickness determination from D32 lines may be reduced, because the profile needs to be extended far away from measurement data. The determination of sheet thickness from D32 lines may not be useful since there may be not many droplets far away from the sheet center.

[2729] As indicated previously, embodiments of other nozzle designs were tested. Figures 179A-179C show the experimental setup to test the embodiment 3 nozzle design. Figures 179D-E plot droplet size distribution along the z axis (in terms of sheet angle), of runs of the embodiment 3 nozzle design of Figures 179A-C. The following table shows performance characteristics of the embodiment 3 nozzle.

		195 PSIG (runs 2, 6)		100 PSIG (runs 1, 17)	
Average velocity in run 1 & 2 [m/s]		26.5		17.1	
Droplet Size in 0.604" FOV; run 6 & 17	D32 [μm] from Max_D | Max_Q	181.8	181.8	197.7	195.8
	DV50 [μm] from Max_D | Max_Q	219.0	219	238.6	237.4
Breakup length from one instantaneous image [inch]		Less than 0.49"		Less than 0.49"	
Sheet Angle from (Max_D|Max_num)		10.3	8.1	11.1	8.8
Thickness Water sheet at x= 3" [mm]		12		15	

[2730] Figure 179F are results of modeling showing contours of velocity magnitude of a spray from nozzle embodiment 3.

[2731] Figures 180A-180C show the experimental setup to test the embodiment 4 nozzle design. Figures 180D-E plot droplet size distribution along the z axis (in terms of sheet angle), of runs of the embodiment 4 nozzle design of Figures 180A-C. The following table shows performance characteristics of the embodiment 4 nozzle.

		200 PSIG (run 1)		100 PSIG (run 2)	
Average velocity in run 1 & 2 [m/s]		24.7		16.2	
Droplet Size in 0.604" FOV	D32 [μm] from Max_D | Max_Q	140.4	132.5	207.4	196.6
	DV50 [μm] from Max_D | Max_Q	167.3	158.0	252.1	238.7
Breakup length from one instantaneous image [inch]		Less than 0.46"		Less than 0.46"	
Sheet Angle from (Max_D |Max_num)		18.3	15.3	22.7	18.3
Thickness Water sheet at x= 3" [mm]		11		13.5	

[2732] Figures 182A-182C show an experimental setup to test the embodiment 5 swirl nozzle design. Figures 183A-B plot droplet size distribution along the z axis (in terms of sheet angle), of runs of the nozzle design of Figures 182A-C. The following table shows performance characteristics of the embodiment 5 nozzle.

		200 PSIG (run 1, 21, 22)		100 PSIG (run 2, 5, 6)	
Average velocity in run 1 & 2 [m/s]		27.8		18.6	
Droplet Size in 0.604" FOV; run 21, 22, 5, 6	D32 [μm] from Max_D | Max_Q	179.8	178.4	244.7	241.6
	DV50 [μm] from Max_D | Max_Q	223.5	224.0	296.9	289.6
Breakup length from one instantaneous image [inch]		<0.57"		~ 0.57	
Sheet Angle from (Max_D | Max_num)		10	9.3	13.1	10.8
Thickness Water sheet at x= 3" [mm] (Max_num | Max_Q)		15.1	10.9	13.6	10.5

[2733] Figures 184A-184C show an experimental setup to test the embodiment 6 swirl nozzle design. Figures 185A-B plot droplet size distribution along the z axis (in terms of sheet angle), of runs of the nozzle design of Figures 184A-C. The following table shows performance characteristics of the embodiment 6 nozzle.

		200 PSIG (run 1, 25, 27)		100 PSIG (run 2, 14, 12)	
Average velocity in run 1 & 2 [m/s]		27.7		18.3	
Droplet Size in 0.600" FOV; run 27 and 12	D32 [μm] from Max_D | Max_Q	219.0	219.0	246.2	246.2
	DV50 [μm] from Max_D | Max_Q	263.7	263.7	294.4	294.4
Breakup length from one instantaneous image [inch]		< 0.52		~0.52	
Sheet Angle from (Max_D | Max_num)		8.5	7.1	10	8.5
Thickness Water sheet at x= 3" [mm] (Max_num | Max_Q)		10.1	7.8	13.9	10.1

[2734] Figures 186A-186C show an experimental setup to test the embodiment 7 swirl nozzle design. Figure 187 plots droplet size distribution along the z axis (in terms of sheet angle), of runs of the nozzle

design of Figures 186A-C. The following table shows performance characteristics of the embodiment 7 nozzle.

		200 PSIG	
Droplet Size in 0.600" FOV; run 1 and 3	D32 [μm] from Max_D | Max_Q	194.1	194.1
	DV50 [μm] from Max_D | Max_Q	236.0	236.0
Sheet Angle from (Max_D | Max_num)		10.8	9.3
Thickness Water sheet at x= 3" [mm] Max_num | Max_Q		10	12

[2735] Figures 188A-188C show an experimental setup to test the embodiment 8 swirl nozzle design. In evaluating performance of the embodiment 8, the flow rate was correlated to pressure by measuring accumulated volume using a stop watch and a graduated cylinder. The results were: pressure = 102 psig, flow rate = 28.36 ml/s; pressure = 200 psig, flow rate = 42.33 ml/s.

[2736] Figure 189A plots droplet size distribution along the z axis (in terms of sheet angle), of high pressure runs of the nozzle design of Figures 188A-C. Figure 189B plots droplet size distribution along the z axis (in terms of sheet angle), of lower pressure runs of the nozzle design of Figures 188A-C. The following table shows performance characteristics of the embodiment 8 nozzle.

		200 PSIG		100 PSIG	
Average velocity in run 51 & 52 [m/s]		28.4		18.6	
Droplet Size in 0.574" FOV	D32 [μm] from Max_D | Max_Q	199.1	195.5	237.2	231.3
	DV50 [μm] from Max_D | Max_Q	240.4	235.2	282.6	276.5
Breakup length from one instantaneous image [inch]		<0.55		~0.55	
Sheet Angle from (Max_D | Max_num)		13.8	10.8	15.3	13.1
Thickness Water sheet at x= 3" [mm] (Max_num | Max_Q)		12	13.1	12	8.4

[2737] The following table lists the performance characteristics of the embodiments of swirl nozzles that were tested ("#" = nozzle embodiment).

200 psig (nominal)								
#	Flow rate [ml/s]	D32 [μm] From Max_D	D32 [μm] From Max_Q	DV50 [μm] From Max_D	DV50 [μm] From Max_Q	Breakup Length [inch]	Sheet Angle [deg]	Sheet thickness at x=3" [mm]
1	89.2*	231.1	231.1	278.8	278.8	< 0.46"	13.2	5.6
2	60.43	146.9	144.5	179	175.6	<0.45"	18.3	10.2
3	41.11	181.8	181.8	219	219	<0.49"	8.1-10.3	12
4	37.72	140.4	132.5	167.3	158.0	<0.46"	15.3-18.3	11
5	N/A	179.8	178.4	223.5	224.0	<0.57"	9.3-10.0	10.9-15.1
6	42.72	219.0	219.0	263.7	263.7	<0.52"	7.1-8.5	7.8-10.1
7	42.26	194.1	194.1	236.0	236.0	N/A	9.3-10.8	10-12
8	42.23	199.1	195.5	240.4	235.2	<0.55"	10.8-13.8	7.2-12
100 psig (nominal)								

#	Flow rate [ml/s]	D32 [μm]		DV50 [μm]		Breakup Length [inch]	Sheet Angle [deg]	Sheet thickness at x=3" [mm]
		From Max_D	From Max_Q	From Max_D	From Max_Q			
1	75.94*	264	264	311.6	311.6	~0.46"	16.2	8.3
2	43.87	176.6	173.3	214.3	211.7	~0.45"	20.9	13.8
3	29.09	197.7	195.8	238.6	237.4	<0.49"	8.8 - 11.1	15
4	26.61	207.4	196.6	252.1	238.7	<0.46"	18.3-22.7	13.5
5	33.97	244.7	241.6	296.9	289.6	~0.57"	10.8-13.1	10.5-13.6
6	29.46	246.2	246.2	294.4	294.4	~0.52"	8.5-10	10.1-13.9
8	28.36	237.2	231.3	282.6	276.5	~0.55"	13.1-15.3	8.4-12

* Embodiment 1 was measured at 180 psig (89.2 ml/s) and 132.5 psig (75.94 ml/s)

[2738] The performance exhibited by the swirl nozzle designs of the various embodiments 1-8 differed in certain respects. For example, in the embodiment 2 nozzle design, the sheet width and sheet angle as determined from the number of droplets and the D32 lines are slightly different. In the embodiment 1 design, the number of droplets and the D32 lines are almost overlapping.

[2739] FIGS. 190A-C plot three measures of liquid droplet character (D32, num, and Q) versus sheet angle, for the embodiment 7 and 8 nozzle designs.

[2740] Swirl nozzles according to particular embodiments of the present invention may differ in certain respects from the nozzle designs of Figures 100A-J. For example, the swirl nozzle designs may utilize smallest dimensions that are substantially larger than those of the non-swirl nozzles. For example, the narrowest gap in the nozzle design of Figures 100A-J is 25 um, while the narrowest gap in a nozzle of the swirl design may be an order of a magnitude larger.

[2741] Such dimensions of swirl nozzle designs according to embodiments of the present invention may offer a number of potential benefits. One such potential benefit is more reliable operation, as the wider dimension of the nozzle renders it less susceptible to clogging by materials dissolved in the liquid. Also, since the smallest geometric dimension is relatively large, the manufacturing is less sensitive to machining tolerance.

[2742] Another potential benefit offered by certain embodiments of the present invention, is to produce a shorter breakup length, which is valuable in the confined spaces of a cylinder head. Still another potential benefit of certain embodiments is to prevent circulation of air behind a traveling liquid sheet.

[2743] Still another possible benefit offered by embodiments of the present invention is the relatively large size (about 160 degrees) of the cone angle produced. This is larger than the conventional swirl nozzles (up to/about 100 degrees).

[2744] For the case of non-swirl nozzles, the cone angle may be determined/limited by the machining capability. For the case of conventional swirl nozzles, the cone angle is primarily dependent on the ratio

of tangential velocity at exit to axial velocity at exit. In some regimes, surface tension may decrease cone angle.

[2745] Larger minimum dimensions may be available to the swirl nozzle design, in part because flow velocity is enhanced utilizing angular momentum rather than a large pressure difference. Specifically, as the flow is moved by the helical channels towards the central axis defined by the deflector neck, the radial distance of the flow becomes smaller. Conservation of angular momentum in turn dictates that the angular velocity be increased with decreasing radial distance.

[2746] Certain relative dimensions in the swirl nozzle design may be controlled to achieve desired performance characteristics. For example, Figure 148D shows an enlarged cross-section of a velocity enhancing portion of the swirl nozzle.

[2747] As shown in Figure 148D, the area A" of the helical flow channel is smaller than the area A defined in the inlet velocity enhancing region between the swirl insert and the body cavity. This area difference does not result in substantial cavitation, as both of the areas A" and A are relatively large and velocity magnitudes are relatively small as compared with the nozzle design of Figures 100A-J. Since the flow swirls multiple times in the velocity enhancing region, the area A is designed to be large in order to reduce friction losses.

[2748] Figure 148D also shows that the area A' of the outlet of the velocity enhancing region is also smaller than the area A of the inlet to the velocity enhancing region. This increases the magnitude of the radial velocity, making the flow more streamlined, as the radial and tangential components of velocity will be of same order of magnitude.

[2749] As mentioned above, embodiments of the present invention are not limited to the use of liquid water to perform heat exchange. In alternative embodiments, other materials could be used.

[2750] For example, one potentially desirable property for an alternative heat exchange material is the extension of freezing point below that of water. By allowing the heat exchange material to remain in a liquid state at lower temperatures, embodiments would allow the transfer of heat to gas expanding over a wider range of temperatures.

[2751] One candidate for such a liquid is a propylene glycol/water mixture. The freezing points of various such mixtures is given below in the following table:

% propylene glycol by volume	% propylene glycol by mass	°C	°F
0	0	0	32
10	10	-3	26
19	20	-8	18
29	30	-14	7
40	40	-22	-8
50	50	-34	-29
60	60	-48	-55

[2752] Figures 191A-191C show an experimental setup to test the embodiment 8 swirl nozzle design used to flow at 200 psig a liquid comprising one of: water, a 5% (by weight) propylene/water mixture, a

10% (by weight) propylene/water mixture, a 20% (by weight) propylene/water mixture, or a 40% (by weight) propylene/water mixture.

[2753] The following table shows performance characteristics of the embodiment 8 nozzle used to spray different liquids:

WAT = tap water (@200 psig)
WAT3 = repeat tap water (@200 psig)
WAT3-1 = repeat tap water (@100 psig)
WAT3-3 = repeat tap water (@300 psig)
P05 = 5% propylene glycol / 95% water by weight (@200 psig)
P10 = 10% propylene glycol / 90% water by weight (@200 psig)
P20 = 20% propylene glycol / 80% water by weight (@200 psig)
P20-1 = 20% propylene glycol / 80% water by weight (@100 psig)
P20 -3= 20% propylene glycol / 80% water by weight (@300 psig)
P40 = 40% propylene glycol / 60% water by weight (@200 psig)
P20T05 = 20% propylene glycol / 5% TritonX / 75% water by weight (@200 psig)

Liquid	Flow rate [ml/s]	**D32 [µm]**		**DV50 [µm]**		Sheet Angle [deg]	Sheet thickness at x=3" [mm]
		From Max_D	From Max_Q	From Max_D	From Max_Q		
WAT		194.8	194.8	233.1	233.1	10.8 - 12.3	7 - 9.9
WAT3	42.33	194.3	191.1	233.2	228.8	11.55-12.3	6.8-7.7
WAT3-1	28.36	232	228.2	279.2	271.7	13.05-15.3	9.6-9.9
WAT3-3	50.3	173.6	171.9	206.7	209.1	10.8-11.5	5.9-7.1
P05	N/A	222.9	215.2	272.2	263.3	9.3-11.55	8.7-10.8
P10	41.9	221.7	221.7	271.3	271.3	8.6-10.8	9.6-13.8
P20	42.3	225.0	220.5	276.3	270.4	9.3 - 10.8	7.8 - 11.5
P20-1	30.7	257.2	257.2	321.3	321.3	7.8-11.55	10.3-17.7
P20-3	51.7	218.2	207.1	263.3	255.1	7.8-9.3	6.5-10.5
P20T05	N/A	200-240		265-280		N/A	N/A
P40	43.4	229.5	225.7	282.2	278.9	9.3 - 10.8	7.4 -9.9

[2754] Figures 192A-C plot three measures of droplet size distribution of each different polypropylene glycol liquids. Figures 193A-C plot droplet size distribution along the z axis (in terms of sheet angle) of runs of water at different pressures. Figures 194A-C plot droplet size distribution along the z axis (in terms of sheet angle) of runs of different liquids at different pressures. Figures 195A-B plots droplet size for liquids including a surfactant (TRITONX100).

[2755] Figure 200 plots nozzle flow rate versus pressure, for different liquids. These results agree substantially with shadowgraphy results presented in Figure 192B.

[2756] The spray characteristics of the swirl nozzle designs described above, may be compared with a swirl nozzle lacking a separate deflector plate element. The following Figures 201A-LB describe such an embodiment. In particular, an embodiment lacking a deflector plate exhibited dimensions as summarized below, where the region on the front surface previously designated to receive the deflector plate stem, was solid and planar:

D1 = 1.97 mm; D4 = 12.7 mm;
A1 = 15°; A2 = 30°; L6 = 4.57 mm; A7 = 9.1E-7 m^2;
Helix pitch = 20 mm/turn; # of helices =4

[2757] Figure 201A shows a simplified view of an experimental set up to test this nozzle. The volume flow rate measured from stop watch and graduated cylinder under this configuration at 95 psig, was 0.454 Gal/Minute 28.62 (ml/s). The following table summarizes the results.

Maximum velocity in run 1 (m/s)		28.5
From one instantaneous image	Breakup length	0.74"
	Cone angle	72.7
Run	D32 (μm)	DV50 (μm)
Droplet Size in 2.05" FOV; run 1	225.9	257.8
Droplet Size in 2.05" FOV; run 2	229.1	252.2
Droplet Size in 0.63" FOV; run 3	226.7	281
Droplet Size in 0.63" FOV; run 4	178.8	216.4
Droplet Size in 0.63" FOV; run 5	165.7	196.4

[2758] The following table presents the testing conditions for various runs:

Run	P start [psi]	P end [psi]	Mean P [PSI]	FOV size [inch]
1	95	92	93.5	2.05
2	102	92	97	2.05
3	100	95	97.5	0.631
4	100	95	97.5	0.631
5	102	95	98.5	0.631

[2759] Figures 201B-C each show global flow structures from two instantaneous shadowgraphy images that were not taken at the same time. The red lines indicate the break up length of 0.74" (average of 0.69" and 0.78"). The spray is a cone with cone angle of 72.7 degree. Figure 201B shows a spray structure comprising a straight cone edge, while Figure 201C shows a spray structure comprising a wavy cone edge.

[2760] The following table shows the mean velocity from runs 1 and 2 with 300 instantaneous velocity fields.

Run		Min (m/s)	Max (m/s)	Average (m/s)	RMS (m/s)
1	Vx	-22.89	3.75	-13.97	6.89
	Vy	-18.36	20.47	-1.037	8.84
	|V|	0.09	29.18	16.25	7.58
2	Vx	-21.13	-1.06	-10.92	4.89
	Vy	-1.19	15.79	4.99	5.19
	|V|	2.65	25.36	12.52	6.19

Figure 201D shows mean velocity vectors from run 1 and run 2. Figure 201E shows RMS velocity vectors of 100PSIG from run 1 and run 2.

[2761] Figures 201FA-201FD show profiles of velocity magnitude along several lines in run 1. In particular, Figure 201FA shows the definition of these lines. Figure 201FB shows velocity magnitude over an average of x= -5 mm to x = -8 mm, with the horizontal axis representing the value of "y" in Figure 19XFA. Figure 201FC shows velocity magnitude over an average of x= 10 mm to x = 15 mm, with the horizontal axis representing the value of "y" in Figure 201FA. Figure

201FD plots velocity magnitude along a line through two points (x, y) [mm]: (-3, 0) and (-33, -25), where the horizontal axis is the value of "x" in Figure 201FA, and where the bottom line is the RMS velocity and the top line is the mean velocity.

[2762] Droplet sizes in various runs were analyzed as follows. The droplet size analysis is conducted only from 1/4 of the FOV in run 1. Figure 201GA shows one instantaneous image with recognized droplets. The blue circles/dots show the recognized droplets. The rest of the droplets are either too small to be recognized or out of focus, which may affect the accuracy of the droplet size statistics. However, these statistics are included to provide an idea of the big droplets distribution. Specifically, Figure 201GB shows the histogram of the droplet size, and the following table shows the statistics of droplet size.

Number of droplets	35681
D10 (μm)	140.9
D32 (μm)	225.9
DV10 (μm)	124.2
DV50 (μm)	257.8
DV90 (μm)	498.5
RMS (μm)	67.3

[2763] Figure 201HA shows one instantaneous image with recognized droplets from run 2. Note that small droplets are not recognized, but the droplet size statistics are included to provide an idea of the big droplets distribution. Figure 201HB shows the histogram of the droplet size. The following table shows the statistics of droplet size.

Number of droplets	191420
D10 (μm)	145.1
D32 (μm)	229.1
DV10 (μm)	127.6
DV50 (μm)	252.2
DV90 (μm)	498.7
RMS (μm)	66.7

[2764] Runs 6-12 are affected by fog on the imaging window. Accordingly, the results of these runs are not included.

[2765] Figures 201IA-KB show instantaneous images with recognized droplets, together with their respective histograms, of the droplet size of runs 3-5. The following table provides statistical results for these runs.

Run	X (inch)	Number of droplets	D10 (μm)	D32 (μm)	DV10 (μm)	DV50 (μm)	DV90 (μm)	RMS (μm)
3	-0.39	75421	87.2	226.7	117.7	281.0	499.1	66.5

4	-1	56529	86.5	178.8	103.9	216.4	373.5	59.6
5	-2	25660	92.7	165.7	97.8	196.4	321.4	55.2

[2766] 1. A liquid spray nozzle comprising:

a first piece configured to impart an angular momentum to a flow of water; and

a second piece having a planar surface configured to deflect the flow of water including the angular momentum.

[2767] 2. A liquid spray nozzle according to claim 1 wherein the first piece comprises an inlet in fluid communication with a helical channel.

[2768] 3. A liquid spray nozzle according to claim 2 wherein the inlet further comprises an indentation in fluid communication with the helical channel.

[2769] 4. A liquid spray nozzle according to claim 3 wherein the indentation exhibits a profile corresponding to a portion of a sphere.

[2770] 5. A liquid spray nozzle according to claim 2 wherein first piece is positioned within a cavity of a third piece, and the helical channel is defined between a recess in a side of the first piece and a first wall region of the cavity.

[2771] 6. A liquid spray nozzle according to claim 5 wherein:

the helical channel is in fluid communication with an outlet; and

a second wall region of the cavity defines a velocity enhancement portion having an inlet cross-sectional area larger than a cross-sectional area of the outlet.

[2772] 7. A liquid spray nozzle according to claim 6 wherein the outlet comprises a toroid.

[2773] 8. A liquid spray nozzle according to claim 2 wherein the second piece comprises a neck inserted through a bore in the first piece.

[2774] 9. A liquid spray nozzle according to claim 8 wherein a decreased radial distance between the helical channel and the toroid results in an increasing angular velocity component of the liquid flow.

[2775] 10. A liquid spray nozzle according to claim 8 wherein the increasing angular velocity component streamlines the liquid flow to swirl around the neck and exit through the outlet.

[2776] 11. A liquid spray nozzle according to claim 8 wherein the first and second piece are in threaded engagement.

[2777] 12. A method of spraying a liquid, the method comprising:

imparting an angular momentum to a liquid flow; and

deflecting the liquid flow including the angular momentum, by impingement upon a surface.

[2778] 13. A method according to claim 12 wherein the angular momentum is imparted by causing the liquid flow to move through a helical channel.

[2779] 14. A method according to claim 12 further comprising increasing an angular velocity component of the liquid flow prior to the deflecting.

[2780] 15. A method according to claim 14 wherein the increasing tangential velocity component streamlines the liquid flow to swirl around a neck supporting the surface.

[2781] 16. A method according to claim 14 wherein the liquid flow is caused to move through a passage having a narrowing cross-sectional area.

[2782] 17. A method according to claim 16 wherein the narrowed cross-sectional area is defined between a wall of a cavity and an insert within the cavity.

[2783] 18. A method according to claim 16 wherein an inlet to the passage has a cross-sectional area larger than a cross-sectional area of an outlet of the passage.

[2784] According to certain embodiments, the energy present in a flow of liquid injected into a cylinder (whether through a swirl nozzle or not), may be harnessed to reduce energy losses associated with gas flows. For example, Figure 196 shows an embodiment of a cylinder 19600 according to the present invention, in a gas intake stage.

Specifically, liquid flowing through conduits 19602 is sprayed through nozzles 19604 at high velocity to enter the cylinder. Displacement of the gas by the force of this sprayed liquid, in turn creates a low pressure region 19606 in a vicinity of the nozzle.

[2785] Figure 196 shows the location of gas flow valve 19608 in the cylinder head with the nozzles. By virtue of the proximity of gas flow valve 19608 to the low pressure region 19606 created by the injected liquid, incoming gas is encouraged to enter the cylinder with reduced energy consumption, thereby enhancing efficiency of the system.

[2786] As previously discussed, embodiments of systems according to the present invention may be co-sited with other sources of electrical power. Examples of such other electrical power sources include but are not limited to photovoltaic cells, fuel cells, and batteries (including vehicle batteries such as plug-in hybrid vehicle batteries).

[2787] Embodiments of the present invention may employ appropriate power conditioning in conjunction with the generation of electrical power. Examples of such power conditioning electronics include, but are not limited to, Variable Frequency Drives (VFDs), capacitor banks, and a reactive power compensators.

[2788] Figure 197 shows one embodiment of a system 19700 of the present invention comprising expander 19701 and generator 19703, which is configured to interact with power

conditioning electronics in the form of a VFD 19702. In particular, end user 19704 and system 19700 are in communication with meter 19706 through VFD 19702.

[2789] As is well known, a VFD may comprise a first part in which incoming 3 phase AC is rectified to a high DC voltage (the DC bus), and a second part in which that DC voltage is converted to 3 phase AC at variable frequency and power. In the latter process, that 3 phase AC is applied to a motor/generator. If the motor is driving a load, it draws its power from the DC bus. If the motor is being driven as a generator, it feeds power back to the DC bus.)

[0378] The presence of the VFD may serve to improve the power factor behind the meter. Moreover, this higher power factor electricity afforded by the VFD, may be flowed back through the meter (for example in distributed generation applications) to improve the stability of the grid itself.

[0378] In certain embodiments, the VFD could include an active front end filter component. Such an active front end filter component could serve to further enhance the quality of the power behind the meter, as well as any power that is flowed back through the meter to the grid. In particular, the front end filter component could reduce harmonics associated with the consumption of energy by the system or by the end user.

[0378] In certain embodiments, a VFD of the present invention may include a regenerative power component. Such a VFD with regenerative capability further includes a regeneration unit, which can take power from the DC bus and convert it to 3 phase AC at the line frequency and feed it back out to the grid. This makes the VFD a regenerative drive.

[0378] Because the system can convert power from the grid to mechanical power in a motor/generator, and later convert mechanical power back to AC power on the grid, it has the capability to act as an energy storage system if the mechanical system has some inherent storage, such as a flywheel. Additionally, there could be some storage on the DC bus (such as capactors or batteries).

[0378] Since this system is interposed between the grid and an electrical load, it isolates any harmonics generated by the load (typically a motor) from the grid. It may, however, generate its own harmonics, but these are typically at a high frequency and are fairly easily filtered out.

[0378] Apart from improved power quality, such embodiments employing a regenerative VFD could offer the additional benefit of enhanced efficiency. For example, the end user and/or the energy system may have one or more applications where the energy demand is cyclical. In such applications, power may be consumed from the grid for a few seconds/minutes in half the cycle, with extra energy present in the remainder of the cycle in the form of kinetic or inertia energy.

[2790] Conventionally this extra energy is wasted, thereby reducing efficiency. According to an embodiments of the present invention however, a regenerative VFD could be installed to store the energy (kinetic/inertia) and deliver it back to reduce demand cost rather than just reducing consumption cost. Embodiments of systems according to the present invention can be designed to match with this cyclical power demand, in order to reduce the overall energy consumption and demand.

[2791] As described above, the use of systems according to the present invention in conjunction with power conditioning electronics (such as a VFD), offers potential benefit in the form of enhanced power quality. For example, most end-user facilities consume the power, causing low power factor and high harmonics which result in extra heating and hence over-sizing of the utility feeder. In addition, the periods associated with commencing or halting operation of a system according to the present invention, may be associated with generation of less stable, lower quality power.

[2792] Locating power conditioning electronics such as a VFD with a system of the present invention, can address both issues and result in high quality power with near-unity power factor and low harmonics for consumption by an end user. Such high quality power may be necessary for efficient operation of the various applications that are located within the end user.

[2793] Moreover, the high quality power afforded by a VFD is desirable from the standpoint of grid stability. In distributed generation (DG) applications, the high quality power can be fed back through the meter to the grid, helping to stabilize the grid. In other applications, use of a VFD with a system according to the present invention can help to stabilize other grid layers, for example by providing high quality power to the generation layer through a busbar, or by providing high quality power to the transmission or distribution layers through a transformer.

[2794] While the particular embodiment shown in Figure 197 shows the system and the power conditioning electronics as being located behind the meter, this is not required by the present invention. According to alternative embodiments, a system and associated power conditioning equipment could be positioned at other grid locations and remain within the scope of the present invention.

[2795] One example of this is where the system is located behind a transformer of a distribution substation. Such an embodiment could advantageously leverage off of power conditioning electronics (such as a capacitor bank) already present at the substation. Moreover, such an embodiment of a system could provide power to the grid on very short notice, by virtue of the rapid availability of power stored in the capacitor bank.

[2796] Certain embodiments according to the present invention may call for multiple systems to be connected in parallel, in order to meet the demand load (from kW to MW). Such embodiments may call for the individual units to be switched on and off as required.

[2797] Rather than incurring the expense of a separate VFD for each unit, however, embodiments of the present invention may employ a switching mechanism to allow maximum utilization of VFD resource(s). This is shown the embodiment of Figure 198, where a plurality of systems 19800a-c are positioned behind an interface 19802 (meter, busbar, or transformer) with a power grid.

[2798] Each of the systems are in selective communication with the interface directly or with the interface through the VFD 19803, through switch 19804. As each system is called upon in succession, it initially provides power to the interface through the VFD to enhance power quality. Upon reaching a stabilized output of higher quality power, the switch is reconfigured to route that power to the interface directly, thereby freeing up the VFD to receive the output of another unit being activated. The reverse process occurs as the load falls, with the switch successively routing the output of the units through the VFD as they fall below steady-state output.

[2799] While the above discussion has focused upon the use of a VFD for power conditioning, the present invention is not limited to this approach. Alternative embodiments could employ other approaches to power conditioning that do not require a VFD, and remain within the scope of the present invention. For example certain embodiments could utilize the features of the energy storage/recovery/conversion system itself, to achieve power conditioning.

[2800] Figure 199 shows one such embodiment, comprising a system 19900 that is positioned behind a meter 19902 with an end user 19903. Figure 199 shows various linkages 19904, 19906 present between the system 19900 and the end user 19903. These linkages may be fluidic, mechanical, and/or thermal in nature as has been previously discussed.

[2801] Figure 199 also shows electrical linkages between the end user, the system, and the meter, in the form of a three-phase wiring system 19910. As is well known, each wire 19910a, 19910b, 19910c in this linkage is configured to carry an electrical power signal of phase differing by 120 degrees relative to the other wires. Where the load is evenly distributed between the wires (as reflected by the three signals having the same amplitude), the load is said to be "balanced".

[2802] The manner of consumption of power by the end user, may however, unbalance the load. This can be attributable, for example, to operation of a single load motor in the end user. Maintaining load balance becomes more challenging with the diversity of applications run by an end user, for example an office building or factory.

[2803] In certain applications, an energy system according to an embodiment of the present invention is located behind the meter to provide power solely to an end user. In some such embodiments, the energy system may be expected produce a corresponding load to match that being consumed by the end user.

[2804] In certain applications, however, an energy system according to an embodiment of the present invention may be expected to both supply the end user and provide power back to the power supply network across the interface. In such cases, the meter "expects" to see a balanced load, with deviation from this balanced state serving to degrade the power quality of the overall grid. This effect becomes even more important where power is being provided back to the grid from behind the meter (as in the case of distributed generation).

[2805] Thus according to embodiments of the present invention, the load behind the meter could be re-balanced by effect of the energy storage/recovery/conversion system. For example, a load could be drawn from the power supply to power one or more functions of the system, including but not limited to water heating, compression, and/or liquid pumping.

[2806] 1. A system comprising:

an interface with a power supply network;

a system comprising gas expansion cylinder having a piston disposed therein and a liquid introduction element, the piston in physical communication with an electrical generator; and

power conditioning electronics in communication with the interface and with the electrical generator.

[2807] 2. The system of claim 1 wherein the power conditioning electronics comprises a variable frequency drive (VFD).

[2808] 3. The system of claim 2 wherein the VFD comprises a regenerative component.

[2809] 4. The system of claim 2 wherein the VFD comprises an active front end filter.

[2810] 5. The system of claim 2 wherein the interface comprises a meter.

[2811] 6. The system of claim 1 wherein the power conditioning electronics comprises a capacitor bank.

[2812] 7. The system of claim 6 wherein the interface comprises a transformer of a distribution subsystem.

[2813] 8. The system of claim 1 wherein the power conditioning electronics comprises a reactive power compensator.

[2814] 9. The system of claim 1 wherein the piston is in physical communication with the electrical generator through a crankshaft.

[2815] 10. The system of claim 1 wherein the piston is in physical communication with the electrical generator through a hydraulic linkage.

[2816] 11. The system of claim 1 further comprising a switch selectively allowing either communication between the electrical generator and the power conditioning electronics, or communication between the electrical generator and the interface directly.

[2817] 1. A method comprising:

allowing gas to expand within a cylinder in a presence of a liquid spray to move a piston disposed within the cylinder;

causing the moving piston to drive an electrical generator through a physical linkage; and

flowing output of the electrical generator through power conditioning electronics to an interface with a power supply network.

[2818] 2. The method of claim 1 wherein the power conditioning electronics comprises a variable frequency drive (VFD) configured to improve a power factor.

[2819] 3. The method of claim 2 wherein the VFD includes an active front end configured to reduce harmonics.

[2820] 4. The method of claim 2 wherein the VFD includes a regenerative component configured to reduce energy losses attributable to cyclic output.

[2821] 5. The method of claim 1 wherein the power conditioning electronics comprises a capacitor bank.

[2822] 6. The method of claim 5 wherein the capacitor bank is configured to improve power quality of a distribution substation.

[2823] 7. The method of claim 1 wherein the power conditioning electronics comprises a reactive power compensator.

[2824] 8. The method of claim 1 wherein the moving piston drives the electrical generator through a crankshaft.

[2825] 9. The method of claim 1 wherein the moving piston drives the electrical generator through a hydraulic linkage.

[2826] 10. The method of claim 1 wherein the output is selectively flowed from the generator to the power conditioning electronics through a switch.

[2827] While certain embodiments of the present invention have focused upon apparatuses employing reciprocating pistons to transfer of energy to/from compressed gas, the present invention is not limited to this or any particular structure. Alternative embodiments could employ other types of moveable structures for this purpose, including but not limited to screws, turbines,

quasi-turbines, multi-lobe blowers, gerotors, vane compressors, and centrifugal/axial compressors.

[2828] As described throughout the instant patent application, embodiments of the present invention may introduce liquid (e.g. by bubbling or spraying) into compressed or expanding gas. However in an open system taking air from the atmosphere during compression and exhausting it to the atmosphere during expansion, introduced liquid may gradually leave as saturated air is outlet.

[2829] According to certain embodiments of the present invention, if the introduced liquid is water, that liquid can be replenished from the atmosphere by condensation. Some embodiments of the present invention may thus include one or more condensing elements positioned at various locations within the system. Typically, condensation would occur at the lowest-pressure stage in a multi-stage system, because the water condensed is at atmospheric pressure.

[2830] Figure 14002 shows an embodiment of such a system 14000 that is configured to collect water from the atmosphere. The system is operated under conditions resulting in some delta-T existing during expansion in expander 14002. While the system may operate less efficiently where this delta-T is greater (and therefore, the spray water is cooled more than usual during expansion), this reduced efficiency may be offset by the need to generate additional liquid as described below.

[2831] As has been previously described, water cooled by expansion is separated, collected, and routed into a condenser 14004. This condenser exposes the flowed liquid to the atmosphere which serves as a heat source to warm up the water. The cold water flowing through the condenser coils 14006 will cause atmospheric water vapor to condense on the coils and drip down into a collector 14008.

[2832] The water collected via the condenser can then be added by valve 14010 to the reservoir 14012 that holds the water to be introduced by spraying or bubbling, until the reservoir is filled to the desired level. This will likely only need to be done periodically.

[2833] While the particular embodiment shown in Figure 140 flows cooled liquid through the condenser, this is not required by the present invention. According to alternative embodiments, the gas cooled by expansion may be flowed through a condenser instead of (or in addition to) the recovered cooled water, in order to result in condensation of water from the atmosphere.

[2834] And while the particular embodiment shown in Figure 140 shows the condenser as the sole heat exchanger for the liquid, this is also not required. Alternative embodiments according to the present invention could include additional heat exchanger structures that are optimized for that function, rather than for generation of liquid water by condensation from the atmosphere.

[2835] Moreover, while the specific embodiment of Figure 140 shows a condenser as being an element separate from the gas-liquid separator, the present invention is also not limited to such a configuration. According to alternative embodiments, the gas-liquid separator could itself act as a condenser, with the inflowing air-water mixture driving condensation.

[2836] While the above description has focused upon condensation resulting from gas expansion, the present invention is not limited to these approaches. According to alternative embodiments, condensation could be achieved by other mechanisms, including but not limited to isothermal gas compression, or bringing a gas stream into contact with a hygroscopic material.

[2837] Embodiments of the present invention may allow the system to be sited in locations lacking an abundant water supply, for example deserts or other arid regions. Subsequent recovery of the liquid by gas-liquid separation would allow the liquid supply to be preserved. The transfer of recovered liquid to different locations in the system, can be accomplished actively (for example by pumping), and/or by intrinsic operation of the system (for example by shifting modes of operation between compression and expansion.

[2838] Moreover, the use of condensation as a source for injected liquid is not limited to systems employing solid pistons or mechanical linkages. Liquid generation by condensation could apply to other types of compressed gas energy storage technology utilizing the introduction of liquids.

[2839] 1. A system comprising:

a chamber having disposed therein a member moveable in response to gas expanding within the chamber;

an element for injecting liquid into the gas expanding within the chamber; and

a condenser in fluid communication with an outlet of the chamber and in thermal communication with the atmosphere to condense liquid water from the atmosphere linkage based upon a temperature difference, the condenser in liquid communication with the element.

[2840] 2. The system of claim 1 wherein the member comprises a piston and the system further comprises a linkage configured to convert reciprocating piston motion into shaft torque.

[2841] 3. The system of claim 2 wherein the linkage comprises a crankshaft.

[2842] 4. The system of claim 1 wherein the condenser comprises a gas-liquid separator.

[2843] 5. The system of claim 1 wherein the condenser is in fluid communication with the outlet through a gas-liquid separator.

[2844] 6. The system of claim 5 wherein the condenser is in liquid communication with the gas-liquid separator.

[2845] 7. The system of claim 1 wherein the element comprises a sprayer or a bubbler.

[2846] 1. A system comprising:

a host computer comprising a processor in electronic communication with a power supply network and with an energy storage apparatus, the host computer further comprising a computer-readable storage medium in electronic communication with the processor and having stored thereon code configured to cause the processor to,

receive an input relating to a predicted change in a load of the power supply network, or a change in generation capacity available to the power supply network,

process the input according to a control algorithm,

communicate a first signal either automatically causing the energy storage apparatus to operate to output electrical power, or recommending a human operator to instruct the energy storage apparatus to operate to output electrical power, and

communicate a second signal either automatically causing ramp-up of a generation asset of the power supply network, or recommending the human operator to instruct ramp-up of a generation asset of the power supply network.

[2847] 2. A system of claim 1 wherein the input is selected from a predicted change in wind or solar energy at a renewable generation asset of the power supply network, an environmental temperature change indicative of the changed load, or a weather disturbance predictive of disruption of the power supply network.

[2848] 3. A system of claim 1 wherein the computer readable storage medium further includes code stored thereon to cause the processor to communicate a third signal either automatically halting operation of the energy storage apparatus, or recommending the human operator to instruct halting of operation of the energy storage apparatus, in response to a fourth signal indicating completion of the ramp-up of the generation asset.

[2849] 4. A system of claim 1 wherein the computer readable storage medium further includes code stored thereon to communicate a third signal either automatically causing replenishment of the energy storage apparatus, or recommending the human operator to instruct replenishment of the energy storage apparatus.

[2850] 5. A system of claim 1 wherein the energy storage apparatus is configured to output the electrical power onto the power supply network.

[2851] 6. A system of claim 5 wherein the energy storage apparatus is configured to output the electrical power onto a transmission layer of the power supply network.

[2852] 7. A system of claim 5 wherein the energy storage apparatus is configured to output the electrical power onto a distribution layer of the power supply network.

[2853] 8. A system of claim 1 wherein the energy storage apparatus is configured to store energy in electrical form.

[2854] 9. A system of claim 1 wherein the energy storage apparatus is configured to generate the electrical power from expansion of compressed gas.

[2855] 10. A system of claim 9 wherein the energy storage apparatus is configured to generate the electrical power from a generator in communication with a mechanical linkage driven by expansion of the compressed gas.

[2856] 11. A system of claim 10 wherein mechanical linkage comprises a crankshaft.

[2857] 12. A system of claim 10 wherein the expansion of the compressed gas occurs in the presence of a liquid.

[2858] 13. A system of claim 12 wherein the liquid is sprayed with a rotational motion followed by impingement upon a deflection surface.

[2859] 14. A system of claim 1 wherein the input originates from the power supply network.

[2860] 15. A system of claim 14 wherein the input comprises a demand response command.

[2861] 16. A system of claim 1 wherein the energy storage apparatus is configured to output the electrical power directly to a consumer located behind a meter of the power supply network.

[2862] 17. A system of claim 16 wherein the input indicates consumer consumption from the power supply network approaching or exceeding a historic peak.

[2863] 18. A system of claim 17 wherein the input originates from the power supply network.

[2864] 19. A system of claim 18 wherein the input originates from the meter.

WHAT IS CLAIMED IS:

1. A method comprising:

providing a first reversible gas compressor/expander configured to effect gas-liquid heat exchange with gas being compressed or expanding within a first chamber;

providing a second reversible gas compressor/expander configured to effect gas-liquid heat exchange with gas being compressed or expanding within a second chamber; and

providing a network of gas conduits and valves allowing selective fluid communication between the first reversible gas compressor/expander, the second reversible gas compressor/expander, a compressed gas storage unit, and a counter-flow heat exchanger, the network of gas conduits and valves selectively operable in one of the following modes:

an energy storage mode wherein the first reversible gas compressor/expander operates as a compressor to flow compressed gas to the compressed gas storage unit, and the second reversible compressor/expander operates as a compressor to flow compressed gas to the compressed gas storage unit, such that an input energy is converted into pneumatic form,

an energy recovery mode wherein the first reversible gas compressor/expander operates as an expander to receive compressed gas from the compressed gas storage unit, and the second reversible compressor/expander operates as an expander to receive compressed gas from the compressed gas storage unit, such that an input pneumatic energy is converted into another form of energy, and

a heat engine mode wherein the first reversible gas compressor/expander operates as a compressor to flow compressed gas through the counter-flow heat exchanger to the second reversible gas compressor/expander operating as an expander, such that an input thermal energy is converted into a different form of energy.

2. A method as in claim 1 wherein gas-liquid heat exchange is effected by injecting liquid droplets into the first chamber and/or the second chamber.

3. A method as in claim 1 wherein gas-liquid heat exchange is effected by injecting liquid droplets into an upstream mixing chamber.

4. A method as in claim 1 wherein gas is compressed in the first reversible compressor/expander by reciprocating motion.

5. A method as in claim 4 wherein the first reversible compressor/expander comprises a reciprocating solid piston.

6. A method as in claim 4 wherein the first reversible compressor/expander further comprises a reciprocating hydraulic fluid.

7. A method as in claim 1 wherein gas is compressed in the first reversible compressor/expander by rotational motion.

8. A method as in claim 7 wherein the first reversible compressor/expander comprises a turbine.

9. A method as in claim 1 wherein in the heat engine mode, the network of gas conduits and valves is selectively operable to flow a quantity of compressed gas from the first reversible compressor/expander to the compressed gas storage unit.

10. A method as in claim 1 wherein in the heat engine mode, the network of gas conduits and valves is selectively operable to flow a quantity of compressed gas from the compressed gas storage unit to the second reversible compressor/expander.

11. A method as in claim 1 wherein the first reversible compressor/expander and the second reversible compressor/expander are in communication with a mechanical linkage.

12. A method as in claim 11 wherein the mechanical linkage comprises a rotating shaft.

13. A method as in claim 12 wherein the rotating shaft comprises a crankshaft.

14. A method as in claim 1 further comprising in the energy recovery mode or the heat engine mode, applying thermal energy to enhance a power of the expanding gas.

15. A method as in claim 1 further comprising in the energy recovery mode or the heat engine mode, flowing liquid that has exchanged heat with the expanding gas, to an HVAC system.

16. A method as in claim 1 further comprising:

in the energy storage mode or in the heat engine mode, separating liquid from compressed gas flowed from the first reversible compressor/expander.

17. A method as in claim 16 further comprising storing the separated liquid in an insulated vessel.

18. A method as in claim 1 further comprising:

in the energy storage mode or in the heat engine mode, communicating energy from a turbine to cause the first reversible compressor/expander to compress gas.

19. A method as in claim 18 wherein the turbine comprises a wind turbine.

20. A method as in claim 18 wherein the turbine comprises a combustion turbine.

21. An apparatus comprising:

a first reversible gas compressor/expander configured to effect gas-liquid heat exchange with gas being compressed or expanding within a first chamber;

a second reversible gas compressor/expander configured to effect gas-liquid heat exchange with gas being compressed or expanding within a second chamber; and

a network of gas conduits and valves allowing selective fluid communication between the first reversible gas compressor/expander, the second reversible gas compressor/expander, a compressed gas storage unit, and a counter-flow heat exchanger, the network of gas conduits and valves selectively operable in one of the following modes:

an energy storage mode wherein the first reversible gas compressor/expander operates as a compressor to flow compressed gas to the compressed gas storage unit, and the second reversible compressor/expander operates as a compressor to flow compressed gas to the compressed gas storage unit, such that an input energy is converted into pneumatic form,

an energy recovery mode wherein the first reversible gas compressor/expander operates as an expander to receive compressed gas from the compressed gas storage unit, and the second reversible compressor/expander operates as an expander to receive compressed gas from the compressed gas storage unit, such that an input pneumatic energy is converted into another form of energy, and

a heat engine mode wherein the first reversible gas compressor/expander operates as a compressor to flow compressed gas through the counter-flow heat exchanger to the second reversible gas compressor/expander operating as an expander, such that an input thermal energy is converted into a different form of energy.

22. An apparatus as in claim 21 further comprising a nozzle to effect gas-liquid heat exchange by injecting liquid droplets into the first chamber.

23. An apparatus as in claim 21 further comprising a nozzle to effect gas-liquid heat exchange by injecting liquid droplets into an upstream mixing chamber.

24. An apparatus as in claim 21 further comprising a reciprocating member to compress gas within the first chamber.

25. An apparatus as in claim 24 wherein the reciprocating member comprises a solid piston.

26. An apparatus as in claim 24 wherein the reciprocating member comprises a hydraulic fluid.

27. An apparatus as in claim 21 further comprising a rotating member to compress gas within the first chamber.

28. An apparatus as in claim 27 wherein the rotating member comprises a turbine.

29. An apparatus as in claim 21 wherein in the heat engine mode, the network of gas conduits and valves is selectively operable to flow a quantity of compressed gas from the first reversible compressor/expander to the compressed gas storage unit.

30. An apparatus as in claim 21 wherein in the heat engine mode, the network of gas conduits and valves is selectively operable to flow a quantity of compressed gas from the compressed gas storage unit to the second reversible compressor/expander.

31. An apparatus as in claim 21 wherein the first reversible compressor/expander and the second reversible compressor/expander are in communication with a mechanical linkage.

32. An apparatus as in claim 31 wherein the mechanical linkage comprises a rotating shaft.

33. An apparatus as in claim 32 wherein the rotating shaft comprises a crankshaft.

34. An apparatus as in claim 21 further comprising a thermal node in thermal communication with a heat source to receive thermal energy to enhance a power of the expanding gas in the energy recovery mode or the heat engine mode.

35. An apparatus as in claim 21 further a thermal node to communicate thermal energy from liquid that has exchanged heat with the expanding gas, to an HVAC system.

36. An apparatus as in claim 21 further comprising a gas-liquid separator configured to receive a compressed gas-liquid mixture from the first reversible compressor/expander, in the energy storage mode or the heat engine mode.

37. An apparatus as in claim 36 further comprising an insulated vessel to receive separated liquid from the gas-liquid separator.

38. An apparatus as in claim 21 further comprising a linkage configured to receive energy from turbine to cause the first reversible compressor/expander to compress gas.

39. An apparatus as in claim 38 wherein the linkage comprises a mechanical linkage.

40. An apparatus as in claim 38 wherein the linkage comprises a rotating shaft.


Controller
1004
Memory
1002
Air Tank
32
1024
1026
33
34
41
40
53
54
Pressure Cell
49f
1016
1014
1018
11
39
51
52
25
24
55
47
48
1020
44
1008
1010
1012
49e
23
38
37
36
35
Cylinder
22
30
42
43
19
21
26
Air filler
Air-liquid separator
31
1022
Liquid Tank
46
20
1006
10
27
28
49d

FIG. 1


Air Tank
32
Final Stage
24c
33
Second Stage
24b
First Stage (Lowest Pressure)
24a
20
30
31
43
42
26
Air filter
Air-liquid separator
Liquid Tank
46
10
27
28

FIG. 2


Controller
3006
Memory
3008
Air filter
13e
Liquid Trap Reservoir
46
26e
3038
3040
Air Tank
32
20
Heat Exchanger
12
3034
139e
3024
52e
3026
Pressure Cell 2
25e
11e
137
135
136
134
3030
142
3022
3020
49e
54
53
3032
139d
132
3018
3016
Pressure Cell 1
25d
11d
133
131
3028
141
3014
52d
3012
130
49d
24
140
138
3010
10
Air filter
26d
3036
Liquid Trap Reservoir
13d
Hydraulic Motor (57)
3002
3004

FIG. 3


92b
93b
41b
25b
40b
54b
52b
Pressure Cell
53b
45b
39b
47b
24b
44b
38b
37b
36b
35b
Cylinder
22b
49b
23b
19b
21b
90b
91b

FIG. 4


Controller
5002
Memory
5004
41b
40b
92b
93b
54b
52b
Pressure Cell
53b
45b
25b
47b
55b
39b1
23b
39b2
24b
51b
44b1
49b1
44b2
38b2
38b1
37b1
Cylinder
22b1
36b1
35b1
22b2
37b2
36b2
19b
90b
21b
35b2
91b

FIG. 5


Controller
6002
Memory
6004
92c
95c
93c
41c
49c2
52c
6018
25c
40c
54c
116c
Pressure Cell
PT
6016
6014
53c
115c
114c
6006
112c
24c
21c
Cylinder
22c
49c1
109c
111c
113c
19c
23c
6010
6012
108c
6008
110c
106c
107c
90c
105c
91c
94c

FIG. 6

FIG. 7


92b
93b
41b
25b
40b
Pressure Cell
55b
49b
45b
47b
90b
91b
35b1
35b2
35b3
39b1
39b2
39b3
39b4
23b1
23b2
23h
23b4
21b1
21b2
21b3
21b4
19b1
19b2
19b3
19b4
44b1
44b2
44b3
44b4
38b1
38b2
38b3
38b4
37b1
37b2
37b3
37b4
36b1
36b2
36b3
36b4
Cylinder


W. Direct Air-Liquid Hydraulic
X. Single-Acting Piston
Y. Double-Acting Piston
Z. Air-Liquid Hydraulic with Diaphragm
22w
22x
22y
22z
121w
121x
121y
121z
122w
122x
122y
122z
123w
123x
123y
123z
124w
124y
124z
125
19x
19y
21w
21x
21y
21z
23x
23y
49w
49x
49y1
49y2
49z

FIG. 8


Hydraulic motor(57)
138
20
24a
24b
24c
21a2
21b1
21b2
21c1
21c2
23a1
23a2
23b1
23b2
23c1
23c2
19a1
19a2
19b1
19b2
19c1
19c2
60a1
60a2
60b1
60b2
60c1
60c2
61a1
61a2
61b1
61b2
61c1
61c2
58
59

FIG. 9


Controller
10002
Memory
10004
Heat Exchanger
10026
Heat Exchanger
10030
10034
10038
10044
10042
10010
10064
Cylinder
10046
10048
10050
10040
10060
10018
10020
10022
10054
10058
10052
Stage 2
Heat Exchanger
10024
Heat Exchanger
55
10032
10036
10028
48
44
Cylinder
22
49e
23
10008
37
10012
10014
10016
30
36
19
35
42
43
26
Air filter
Air-liquid separator
31
10063
Liquid Tank
46
10006
10
27
28
49d
20
Stage 1

FIG. 10



FIG. 11A



FIG. 11B



FIG. 11C



FIG. 11D



FIG. 11E



FIG. 11F

Figure 12A


Air Tank
32
33
34
Pressure Cell
49f
52
53
54
40
41
55
51
39
11
25
24
Compression Step 1
47
1020
44
48
38
23
49e
37
19
30
36
42
43
35
31
22
21
Air filter
Air–liquid separator
26
10
27
Liquid Tank
46
28
49d
20

Figure 12B


Air Tank
Pressure Cell
Liquid Tank
Air filter
Air-liquid separator
Compression Step 2
10
11
19
20
21
22
23
24
25
26
27
28
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
46
47
48
49d
49e
49f
51
52
53
54
55
1020

Figure 12C


Air Tank
Pressure Cell
Air filter
Air–liquid separator
Liquid Tank
Compression Step 3
10
11
19
20
21
22
23
24
25
26
27
28
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
46
47
48
49d
49e
49f
51
52
53
54
55
1020

Figure 13A


Air Tank
Pressure Cell
Liquid Tank
Air filter
Air–liquid separator
Expansion Step 1
32
33
34
40
53
54
41
49f
52
55
51
39
11
25
24
47
1020
44
48
38
23
49e
37
30
42
43
36
19
21
26
35
31
22
46
10
27
28
20
49a

Figure 13B


Air Tank
Pressure Cell
Liquid Tank
Air filter
Air—liquid separator
Expansion Step 2
32
33
34
40
53
54
41
49f
52
55
51
39
11
25
24
47
1020
44
48
38
23
49e
37
19
30
43
42
36
35
31
21
22
26
46
10
27
28
20
49a

Figure 13C


Air Tank
Pressure Cell
Liquid Tank
Air filter
Air—liquid separator
Expansion Step 3
32
33
34
40
53
54
41
49f
52
51
55
39
11
25
24
47
1020
44
48
38
37
23
49e
30
43
42
36
35
31
22
21
19
26
46
10
27
28
49d
20


92c
93c
95c
41c
49c2
52c
25c
40c
116c
54c
Pressure Cell
115c
53c
114c
24c
Compression Step 1
22c
49c1
112c
21c
113c
109c
111c
110c
108c
19c
23c
107c
106c
105c
90c
91c
94c

Figure 14A


92c
93c
95c
41c
49c2
52c
25c
40c
116c
54c
Pressure Cell
115c
53c
114c
Compression Step 2
24c
22c
49c1
112c
21c
113c
109c
111c
110c
108c
106c
107c
19c
23c
105c
90c
91c
94c

Figure 14B


92c
93c
95c
41c
49c2
52c
25c
40c
116c
54c
Pressure Cell
115c
53c
114c
Compression Step 3
24c
22c
49c1
112c
21c
113c
109c
111c
110c
108c
106c
107c
19c
23c
105c
90c
91c
94c

Figure 14C


92c
93c
95c
41c
49c2
52c
25c
40c
116c
54c
Pressure Cell
115c
53c
114c
Expansion Step 1
24c
22c
49c1
112c
21c
113c
109c
111c
110c
108c
106c
19c
23c
107c
105c
90c
91c
94c

Figure 15A


92c
93c
95c
41c
49c2
52c
25c
40c
116c
54c
Pressure Cell
115c
53c
114c
Expansion Step 2
24c
22c
49c1
112c
21c
113c
109c
111c
110c
108c
106c
107c
19c
23c
105c
90c
91c
94c

Figure 15B


92c
93c
95c
41c
49c2
52c
25c
40c
116c
54c
Pressure Cell
115c
53c
114c
Expansion Step 3
24c
22c
49c1
112c
21c
113c
109c
111c
110c
108c
106c
107c
19c
23c
105c
90c
91c
94c

Figure 15C



Figure 16A Compression step 1



Figure 16B Compression step 2



Figure 16C Compression step 3



Figure 16D Compression step 4



Figure 17A Expansion step 1



Figure 17B Expansion step 2



Figure 17C Expansion step 3



Figure 17D Expansion step 4


Air filter
Liquid Trap Reservoir
46
32
Air Tank
20
26e
13e
142
49e
52e
139e
135
136
Pressure Cell 2
25e
134
11e
137
Heat Exchanger
54
53
139d
132
141
Pressure Cell 1
25d
131
11d
133
138
12
24
52d
49d
140
130
Compression Step 1
Hydraulic Motor (57)
10
Air filter
Liquid Trap Reservoir
26d
13d

Figure 18A


Air filter
Liquid Trap Reservoir
46
32
Air Tank
20
26e
13e
142
49e
52e
139e
135
136
134
Pressure Cell 2
25e
11e
137
Heat Exchanger
54
53
139d
132
141
Pressure Cell 1
25d
12
131
11d
133
138
24
52d
49d
140
130
Hydraulic Motor (57)
Compression Step 2
10
Air filter
Liquid Trap Reservoir
26d
13d

Figure 18B


Air filter
Liquid Trap Reservoir
46
32
Air Tank
20
26e
13e
142
49e
52e
139e
135
136
134
Pressure Cell 2
25e
11e
137
Heat Exchanger
54
53
139d
132
141
Pressure Cell 1
25d
131
11d
133
138
12
24
52d
49d
140
130
Compression Step 3
Hydraulic Motor (57)
10
Air filter
Liquid Trap Reservoir
26d
13d

Figure 18C


Air filter
Liquid Trap Reservoir
46
32
Air Tank
20
26e
13e
142
49e
52e
139e
135
136
134
Pressure Cell 2
25e
11e
137
Heat Exchanger
54
53
139d
132
141
131
Pressure Cell 1
25d
11d
133
138
12
24
140
130
52d
49d
Compression Step 4
Hydraulic Motor (57)
10
Air filter
Liquid Trap Reservoir
26d
13d

Figure 18D


Air filter
Liquid Trap Reservoir
46
32
Air Tank
20
26e
13e
142
49e
52e
139e
135
136
Pressure Cell 2
25e
134
11e
137
Heat Exchanger
54
53
139d
132
141
Pressure Cell 1
25d
131
11d
133
138
12
24
52d
49d
140
130
Hydraulic Motor (57)
Expansion Step 1
10
Air filter
Liquid Trap Reservoir
26d
13d

Figure 19A


Air filter
Liquid Trap Reservoir
46
32
Air Tank
20
26e
13e
142
49e
52e
139e
135
136
Pressure Cell 2
25e
134
11e
137
Heat Exchanger
54
53
139d
132
141
Pressure Cell 1
25d
131
11d
133
138
12
24
52d
49d
140
130
Hydraulic Motor (57)
Expansion Step 2
10
Air filter
Liquid Trap Reservoir
26d
13d

Figure 19B


Air filter
Liquid Trap Reservoir
46
32
Air Tank
20
26e
13e
142
49e
52e
139e
Heat Exchanger
135
136
134
Pressure Cell 2
25e
11e
137
54
53
139d
132
141
131
Pressure Cell 1
25d
11d
133
138
12
24
140
130
52d
49d
Expansion Step 3
Hydraulic Motor (57)
10
26d
13d
Air filter
Liquid Trap Reservoir

Figure 19C


Air filter
Liquid Trap Reservoir
Air Tank
Heat Exchanger
Pressure Cell 2
Pressure Cell 1
Expansion Step 4
Hydraulic Motor (57)
Air filter
Liquid Trap Reservoir
20
12
24
10
26e
13e
46
32
142
49e
52e
139e
135
136
134
25e
11e
137
54
53
139d
132
141
131
25d
11d
133
138
52d
49d
140
130
26d
13d

Figure 19D



FIG. 20



FIG. 20A


INPUT(S)
Pressure
-chamber
-ambient
-pressure cell
-conduits
-output
Temperature
-chamber
-liquid
-input
-output
Speed of Output Shaft
Torque of Output Shaft
Humidity of Output
Volume
-liquid in chamber
-liquid in pressure cell
-gas in chamber
-gas in pressure cell
Pump Speed
Fan Speed
Flow Rate
IN
from
system
PROCESSOR
- calculate efficiency
- calculate power input/output
- calculate ΔT across heat exchanger
- calculate maximum T in chamber
- calculate minimum T in chamber
- calculate water generated
OUT
to
system
STORAGE MEDIUM
OUTPUT(S)
Valve Timing
Power to Motor
Frequency of Motor
Power Fed Back to System
Waste Heat Back to System
Pump Speed
Fan Speed

FIG. 21


2250
HEAT SOURCE 2290
HEAT SINK 2292
2288
2286
Grid 2298
2284
M/G 2294
2296
C/E 2282

FIG. 22A


2280
HEAT SOURCE
2290
HEAT SINK
2292
2288
2286
2298
2284
M/G
2294
2296
C/E
2282

FIG. 22B



FIG. 23



FIG. 24A



FIG. 24B



FIG. 24C


CO_2 STORAGE
CO_2
30°C
150 ATM
COMP-RESSOR
30°C
20°C
AIR COOLED HEAT EXCH.
15°C
SHIFT
20°C
7ATM
EXPANDER
115°C
20 ATM
20°C
115°C
25°C
CO_2 120°C 1ATM
120°C
115°C
145°C
EXPANDER
116°C
20 ATM
FLUE GAS OUT 40°C, 1ATM
FLUE GAS 150°C 1ATM
RE-GENERATOR
110°C
50 ATM
30°C
50 ATM
35°C 20ATM
30°C
20°C
AIR COOLED HEAT EXCH.
15°C
COM-PRESSOR
20°C 7ATM HELIUM

FIG. 24D


Controller
2594
Memory
2592
Air Tank
2532
2584
2586
2533
2554
2562
2512
2560
2564
2553
2551
2541
2576
2574
Pressure Cell
2549f
2553
2554
2540
2534
2552
2578
2511
2539
2525
2524
2555
2547
2548
2544
2538
2598
2570
2572
2549e
2523
2580
2537
2536
2535
Cylinder
2522
2530
2542
2543
2526
2531
2519
2521
Air filter
Air-liquid separator
2582
Liquid Tank
2546
2596
2510
2527
2528
2549d
2520

FIG. 25


Air Tank
2632
2633
Final Stage
2624c
Second Stage
2624b
First Stage (Lowest Pressure)
2624a
2620
2650
2652
2654
2630
2631
2642
2643
2626
Air filter
Air-liquid separator
2610
2627
Liquid Tank
2628
2646

FIG. 26


Air Tank
2632
2662
Final Stage
2624c
2633
Second Stage
2624b
2652
2654
2650
First Stage (Lowest Pressure)
2624a
2670
2664
2666
2631
2630
2643
2642
2626
Air filter
Air-liquid separator
Liquid Tank
2646
2660
2610
2627
2628

FIG. 26A


Air Tank
2632
2633
2685
2686
Final Stage
2624c
2624
Second Stage
2624b
2683
2682
2680
First Stage (Lowest Pressure)
2624a
2630
2631
2643
2642
2626
Air filter
Air-liquid separator
Liquid Tank
2646
2610
2627
2628

FIG. 26B


GAS INLET
LIQUID SPRAY
PULSATION DAMPER BOTTLE
VALVES
DOUBLE-ACTING PISTON
SEPARATOR
GAS OUTLET
LIQUID RESERVOIR
PUMP

FIG. 27


~55° F
55° F
Cool side Heat Exchanger
Intake: 75° F
45° F
Pump
Air
Water
Air/Water Mix
45° F
A
55° F
45° F
Air/Water Seperator
Counter Flow Heat Exchanger
115° F
105° F
Compressor/Expander
Pump
115° F
115° F
105° F
Warm side Heat Exchanger
Intake: 95° F
~105° F
Electric Motor

FIG. 28


55° F
65° F
Cool side Heat Exchanger
Intake: 75° F
Pump
Gas
Liquid
Gas/Liquid Mix
40° F
50° F
40° F
Gas/Liquid Separators
Counter Flow Heat Exchanger
Compressor/Expander
130° F
120° F
130° F
Pump
105° F
Warm side Heat Exchanger
Intake: 95° F
115° F
Electric Motor

FIG. 28A

FIG. 29

FIG. 30



FIG. 31



FIG. 32


COP: 4.37, Carnot COP: 17.4, T_{intake}: 75 F, $T_{exhaust}$: 55, T_h: 95 F
Grid
Drive
Motor
Motor Shaft
Compressor
Expander
Building Thermal Reservoir (Tc)
Hot Reservoir (T_h)
η_{grid}: 100%, Electric: 1 kw
η_{drive}: 97.%, Electric: 0.97 kw
η_{motor}: 95.%, Work: 0.922 kw
η_{shaft}: 99.5%, Work: 4.81 kw
$\eta_{exp,thermal}$: 92.7%, Heat: 4.37 kw
$\eta_{exp,total}$: 87.6%, $\eta_{exp,thermal}$: 92.7%, $\eta_{exp,mech/valve/leakage}$: 95.5%, $\eta_{exp,spray}$: 99.%, Work: 3.91 kw
$\eta_{comp,total}$: 92.7%, $\eta_{comp,thermal}$: 98.%, $\eta_{comp,mech/valve/leakage}$: 95.6%, $\eta_{comp,spray}$: 99.%, Work: 4.46 kw
$\eta_{comp,thermal}$: 97.%, Heat: 4.71 kw

FIG. 32A


3300
3304
3308
3301
3305
3312
M/G
T
3303
3302
C/E
3316
3314
3307
3311
3309
3320
3306
3313
3306a
3318
to grid

FIG. 33



FIG. 33A



FIG. 33AA


3404
3400
3402
3401
T
3405
3411
3406a
3406
3418
3412
C/E
3416
3414
to grid
M/G

FIG. 34


3500
3504
3508
3305
3501
3512
G
T
3503
3502
E
3516
3514
3507
3511
3574
3509
3506
3513
3506a
3518
3570
3572
C
M
to grid
3550
3554

FIG. 35


3580
3581
T
3582
3583
C
3586
3591
3589
3596
3596a
3598
3593
3592
3588
E
-or-
E/C
G
-or-
G/M
3584
to grid

FIG. 35A



FIG. 37



FIG. 36


3800
3802
liquid
3805
3807
3802a
3802b
gas/liquid mixture
gas
3804
3801

FIG. 38


3904
3902
3900
3910
3910
3911
3911
3910
3910
3906
3902
3908
LIQUID SPRAY
3916
3938
PULSATION DAMPER BOTTLE
3914
W
3918
3950
3996
3920b
3920a
INLET VALVES
3912
3924
DOUBLE-ACTING PISTON
3994
3913a
3913
3913b
3922b
3922a
3952
3933
SEPARATOR 3930
GAS OUTLET
3932
LIQUID RESERVOIR 3934
3936 PUMP

FIG. 39


3902
3900
3910
3910
3911
3911
3910
3910
3906
3914
3938
3996
3920b
3920a
INLET
VALVES
3912
3924
DOUBLE-ACTING
PISTON
3913a
3913
3922b
3913b
3922a
3994
SEPARATOR
3930
GAS
OUTLET
3933
3932
LIQUID
RESERVOIR
3934
3936
PUMP

FIG. 39A


3902
3900
3910
3910
3911
3911
3910
3910
3906
3914
3938
3996
3906
3920a
INLET
VALVES
3912
3924
DOUBLE-ACTING
PISTON
3913a
3913
3922b
3913b
3922a
3994
SEPARATOR
3930
GAS
OUTLET
3933
3932
LIQUID
RESERVOIR
3934
3936
PUMP

FIG. 39B



FIG. 39CB



FIG. 39CA


4004
4032
4002
4010
4010
4011
4011
4010
4010
4006
4002
4008
LIQUID
SPRAY
PULSATION
DAMPER
BOTTLE
4014
W
4038
4096
4020b
4020a
INLET
VALVES
4012
4013a
4013
4022b
4024
DOUBLE-ACTING
PISTON
4013b
4022a
4094
SEPARATOR
4030
GAS
OUTLET
LIQUID
RESERVOIR
4034
4036
PUMP

FIG. 40


4032
4002
4010
4010
4011
4011
4010
4010
4006
4002
4014
4038
4096
4020b
4020a
INLET
VALVES
4012
4013a
4013
4022b
4024
DOUBLE-ACTING
PISTON
4013b
4022a
4094
SEPARATOR
4030
GAS
OUTLET
LIQUID
RESERVOIR
4034
4036
PUMP

FIG. 40A


4032
4002
4010
4010
4011
4011
4010
4010
4006
4002
4038
4014
4096
4020b
4020a
INLET
VALVES
4012
4024
DOUBLE-ACTING
PISTON
4094
4013a
4013
4013b
4022b
4022a
SEPARATOR
4030
GAS
OUTLET
LIQUID
RESERVOIR
4034
4036
PUMP

FIG. 40B


4100
4150
AIR FILTER
4152
4182
H.E.1
4190
4164
4174
4172
4134
4136
4102
4104
4108
4113a
4120
4121
4113b
4112
4122
4123
4124
LOW PRESSURE SIDE
HIGH PRESSURE SIDE
4196
4194
H.E.2
4192
4183
4166
4165
TANK 4132
4170
4135
4176

FIG. 41



FIG. 41B



FIG. 41A



FIG. 41D

FIG. 41C



FIG. 41EA



FIG. 41EB



FIG. 41EC



FIG. 41ED



FIG. 41EE



FIG. 41FC



FIG. 41FB



FIG. 41FA



FIG. 41G



FIG. 41H


Tank
4232
Final Stage
4224c
4233
Second Stage
4224b
First Stage (Lowest Pressure)
4224a
4220
gas in
H

FIG. 42A



FIG. 42B



FIG. 42BA



FIG. 42BB



FIG. 42BC


AIR FILTER
H.E.
4262
4264
4266
H.E.
4260
AIR TANK
4268
WATER TANK
WATER TANK

FIG. 42C



FIG. 43



FIG. 43A


4360
AIR TANK
WATER TANK
H.E.
4302
4304
H.E.
4306
4306
4308
WATER TANK

FIG. 43B


4400
4450
AIR FILTER
4402
H.E.1
4404
4434
LEAVE WATER TANK
4436
4405
4406
d
H.E.2
4404
4404
4404
4402
H.E.3
4404
4435
LEAVE WATER TANK
TANK 4432
4404

FIG. 44



FIG. 45



FIG. 46B



FIG. 46A


INPUT(S)
* Pressure
-chamber
-ambient
-mixing chamber
-conduits
-output
* Temperature
-chamber
-liquid
-input
-output
* Speed of Output Shaft
* Torque of Output Shaft
* Humidity of Output
* Volume
-liquid in chamber
-liquid in reservoir
-gas in chamber
-gas in mixing chamber
* Pump Speed
* Fan Speed
* Flow Rate
IN from system
PROCESSOR
- calculate efficiency
- calculate power input/output
- calculate ΔT across heat exchanger
- calculate maximum T in chamber
- calculate minimum T in chamber
- calculate water generated
STORAGE MEDIUM
OUT to system
OUTPUT(S)
* Valve Configuration
* Valve Timing
* Power to Motor
* Frequency of Motor
* Power Fed Back to System
* Waste Heat Back to System
* Pump Speed
* Fan Speed
* Volume of condensed H_2O
* Volume of other deliverable

FIG. 47



FIG. 48A



FIG. 48B



FIG. 48C



FIG. 49A



FIG. 49B



FIG. 49C


AIR CLEANER
5020
5010
SUCTION BOTTLE
5013b
CYLINDER
5008
5008a
5008b
DISCHARGE BOTTLE
5023
5022
5022a
5022b
5012
5012a
5012b
5060
5033
SOLENOID VALVE
5034
5061
5013
5013a
5027b
5027
5027a
5006
5036
LOW PRESSURE SIDE
HIGH PRESSURE SIDE
5098
5099
CYCLONE SEPARATOR
5028
BAFFLE SEPARATOR
5027
5024
5026
5054 PRESSURE REGULATOR
AIR STORAGE TANK
300 GAL. (PVC)
5032
MUFFLER
5052
ACCUMULATOR
5039
MULTI-STAGE WATER PUMP
5031
SPRAY NOZZLE 5035
CITY WATER
FILTER
5050
VACUUM RELIEF VALVE
SUPPLY WATER TANK
300 GAL. (PVC)
5046
DRAIN
RELIEF VALVE
PRESSURIZED WATER TANK
300 GAL. (PVC)
DRAIN
5030
5088
5042
TRANSFER PUMP
5047
5048
5044
HEAT EXCHANGER
5002
5096
5094
= FLOAT VALVE

FIG. 50A


ACCUMULATOR
SEPARATOR(S)
SOLENOID VALVE
linkage
LOW PRESSURE SIDE
HIGH PRESSURE SIDE
generator
SPRAY NOZZLE
AIR STORAGE TANK 300 GAL.
PRESSURE REGULATOR
BOTTLE
CYLINDER
BOTTLE
MUFFLER
SOLENOID VALVE
SPRAY NOZZLE
CITY WATER
FILTER
PRESSURIZED WATER TANK 300 GAL.
DRAIN
RELIEF VALVE
MULTI-STAGE WATER PUMP
VACUUM RELIEF VALVE
SUPPLY WATER TANK 300 GAL.
DRAIN
HEAT EXCHANGER
TRANSFER PUMP
= FLOAT VALVE

FIG. 50B


5100
5102
5106
5108
5110
5112
5112a
5112b
5112c
5114
5115
5120
5122
5122a
5122b
5122c
5124
5125
5126
5130
5132
5134
5136
5138
5140
5142
5150
5152
5154
5194
5196
HIGH PRESSURE SIDE
LOW PRESSURE SIDE
P
V
T
S
H

FIG. 51


INPUT(S)
* Pressure
-chamber
-ambient
-storage tank
-conduits
-output
-mixing chamber
* Temperature
-chamber
-liquid
-input
-output
-heat exchanger
* Speed of Output Shaft
* Torque of Output Shaft
* Humidity of Output
* Volume
-liquid in chamber
-liquid in reservoir
-gas in chamber
-gas in storage tank
* Pump Speed
* Fan Speed
* Flow Rate
* Valve state
IN from system
INPUT(S)
* current power price
* expected future power price
* current power demand
* expected future power demand
* contact terms
* weather information
* state of alt. power source
* commodity prices
* amount of deliverable needed
* state of end user
* meter information
IN from external
PROCESSOR
- calculate efficiency
- per stage
- calculate power input/output
- per stage
- calculate ΔT across heat exchanger
- per stage
- calculate maximum T in chamber
- per stage
- calculate minimum T in chamber
- per stage
- calculate water generated
STORAGE MEDIUM
OUT to system
OUTPUT(S)
* Valve Configuration
* Valve Timing
* Power to Motor
* Frequency of Motor
* Power Fed Back to System
* Waste Heat Back to System
* Pump Speed
* Fan Speed
* Volume of condensed H_2O
* Volume of other deliverable

FIG. 52


Air Tank
5332
Final Stage
5324c
5333
Second Stage
5324b
First Stage (Lowest Pressure)
5324a
5320
5330
5331
5343
5342
5326
Air filter
Air-liquid separator
Liquid Tank
5346
5328
5310
5327

FIG. 53A



FIG. 53B



FIG. 53BA



FIG. 53BB



FIG. 53BC


5360
AIR FILTER
BOTTLE
5362
H.E.
WATER TANK
5364
5366
BOTTLE
H.E.
AIR TANK
5368
WATER TANK

FIG. 53C



FIG. 54



FIG. 54A


AIR TANK
WATER TANK
BOTTLE
H.E.
5500
5502
5504
BOTTLE
H.E.
5506
5508
5507
WATER TANK

FIG. 55


5600
5650
AIR FILTER
BOTTLE
5604
H.E.
5636
WATER TANK
5634
5606
d
5605
5696
5694
5632
TANK
5635

FIG. 56


TANK
5796
5794
5700
BOTTLE
5702
H.E.1
5704
5702
5704
H.E.2
5702
BOTTLE
AIR FILTER

FIG. 57



FIG. 58



FIG. 58A


5880
VALVE NETWORK
5888
5882a
5882b
5882c
P_{in}
P_{out}
$+\Delta T_1$
$-\Delta T_6$
$+\Delta T_2$
$-\Delta T_5$
$+\Delta T_3$
$-\Delta T_4$
P_{St}
P_{St}
W_{in1}
W_{out1}
W_{in2}
W_{out2}
W_{in3}
W_{out3}
M/G

FIG. 58B


P_{OUT}
P_{IN}
P_{St}
VALVE NETWORK
-ΔT
-ΔT
-ΔT
+ΔT
+ΔT
+ΔT
W_{out}
W_{out}
W_{out}
W_{in}
W_{in}
W_{in}
G
M

FIG. 58C



FIG. 59B



FIG. 59A



FIG. 59

Temperature Control Role	End Use Examples	Air Conditioned Square Footage	Expected Duration (hrs)	Output (BTU/h)	System Capacity (Tons)[1]	Energy Use (kWh)[2]
Cooling	Small home	200 - 4,000	4 - 8	6,000 - 60,000	1 - 5	1 - 40
	Medium home, small office	2,000 - 20,000	4 - 8	60,000 - 300,000	5 - 25	10 - 220
	Large home, small warehouse	8,000 - 48,000	4 - 8	240,000 - 720,000	20 - 60	60 - 520
	Small office building	16,000 - 50,000	4 - 8	720,000 - 1,500,000	60 - 125	170 - 1,090
	Medium office building	27,000 - 200,000	4 - 8	1,200,000 - 6,000,000	100 - 500	280 - 4,360
	Large office building	27,000 - 400,000	4 - 8	1,200,000 - 12,000,000	100 - 1,000	280 - 8,730
	Medium warehouse	40,000 - 400,000	8 - 12	1,200,000 - 6,000,000	100 - 500	560 - 6,550
	Large warehouse	100,000 - 800,000	8 - 12	3,000,000 - 12,000,000	250 - 1,000	1,410 - 13,090
	Refrigerated Warehouse	40,000 - 160,000	24 - 24	1,800,000 - 4,800,000	150 - 400	2,540 - 10,470
	Supermarket, food service facility	27,000 - 100,000	24 - 24	1,200,000 - 3,000,000	100 - 250	1,690 - 6,550
Heating	Small home	200 - 3,000	4 - 8	6,000 - 60,000	1 - 5	1 - 40
	Medium home, small office	2,000 - 15,000	4 - 8	60,000 - 300,000	5 - 25	10 - 220
	Large home, small warehouse	8,000 - 36,000	4 - 8	240,000 - 720,000	20 - 60	60 - 520
	Small office building	18,000 - 50,000	4 - 8	720,000 - 1,500,000	60 - 125	170 - 1,090
	Medium office building	30,000 - 200,000	4 - 8	1,200,000 - 6,000,000	100 - 500	280 - 4,360
	Large office building	30,000 - 400,000	4 - 8	1,200,000 - 12,000,000	100 - 1,000	280 - 8,730
	Medium warehouse	40,000 - 300,000	8 - 12	1,200,000 - 6,000,000	100 - 500	560 - 6,550
	Large warehouse	100,000 - 600,000	8 - 12	3,000,000 - 12,000,000	250 - 1,000	1,410 - 13,090
	Automotive assembly plant, storage facility	8,000 - 200,000	24 - 24	300,000 - 6,000,000	25 - 500	420 - 13,090

Notes:
1) 1 Ton = cooling power of one short ton (2000 pounds or 907 kilograms) of ice melting in a 24-hour period. Equals 12,000 BTU per hour, or 3517 watts.
2) Assume SEER (Seasonal Energy Efficiency Rating) range of 11 to 17.

FIG. 60



FIG. 61C



FIG. 61B



FIG. 61A

	Discharge Duration*		
Power Supply Role	**Low**	**High**	**Notes**
Electric Energy Time-shift	2	8	Depends on energy price differential, storage efficiency, and storage variable operating cost.
Electric Supply Capacity	4	6	Peak demand hours.
Load Following	2	4	Assume: 1 hour of discharge duration provides approximately 2 hours of load following.
Area Regulation	15 min.	30 min.	Based on demonstration of Beacon Flywheel.
Electric Supply Reserve Capacity	1	2	Allow time for generation-based reserves to come on-line.
Voltage Support	15 min.	1	Time needed for a) system stabilization or b) orderly load shedding.
Transmission Support	2 sec.	5 sec.	Per EPRI-DOE Handbook of Energy Storage for Transmission and Distribution Applications.
Transmission Congestion Relief	3	6	Peak demand hours. Low value is for "peaky" loads, high value is for "flatter" load profiles.
T&D Upgrade Deferral - 50th Percentile	3	6	Same as above.
T&D Upgrade Deferral - 90th Percentile	3	6	Same as above.
Substation On-site Power	8	16	Per EPRI/DOE Substation Battery Survey.
Time-of-use Energy Cost Management	4	6	Peak demand hours.
Demand Charge Management	5	11	Maximum daily demand charge hours, per utility tariff.
Electric Service Reliability	5 min.	1	Time needed for a) shorter duration outages or b) orderly load shutdown.
Electric Service Power Quality	10 sec.	1 min.	Time needed for events ridethrough depends on the type of PQ challenges addressed.
Renewables Energy Timeshift	3	5	Depends on energy cost/price differential and storage efficiency and variable operating cost.
Renewables Capacity Firming	2	4	Low & high values for Renewable Gen./Peak Load correlation (>6 hours) of 85% & 50%.
Wind Generation Grid Integration, Short Duration	10 sec.	15 min.	For a) Power Quality (depends on type of challenge addressed) and b) Wind Intermittency.
Wind Generation Grid Integration, Long Duration	1	6	Backup, Time Shift, Congestion Relief.

Notes:
**Hours unless indicated otherwise. min. = minutes. sec. = seconds.*
Source: United States. Dept. of Energy. Sandia National Laboratories. Energy Storage for the Electricity Grid: Benefits and Market Potential Assessment Guide. By Jim Eyer and Garth Corey. Springfield, VA: National Technical Information Service, 2010

FIG. 62

Capacity (Power: kW,		
Low	High	Notes
1MW	500MW	Low per ISO transaction min. (Can aggregate smaller capacity). High = combined cycle gen.
1MW	500MW	Same as above.
1MW	500MW	Same as above.
1MW	40MW	Low per ISO transaction min. Max is 50% of estimate CA technical potential of 80MW.
1MW	500MW	Low per ISO transaction min. (Can aggregate smaller capacity). High = combined cycle gen.
1MW	10MW	Assume distributed deployment, to serve Voltage support needs locally.
10MW	100MW	Low value is for subtransmission.
1MW	100MW	Low per ISO transaction min. (Can aggregate smaller capacity). High = 20% of high capacity
250kW	5MW	Low = smallest likely; High = high end for distribution and subtransmission.
250kW	2MW	Same as above.
1.5kW	5kW	Per EPRI/DOE Substation Battery Survey.
1kW	5MW	Residential to medium sized commercial/industrial users.
50kW	10MW	Small commercial to large commercial/industrial users.
0.2kW	10MW	Low = under desk UPS. High = facility wide for commercial industrial users.
0.2kW	10MW	Same as above.
1kW	500MW	Low = small residential PV. High = "bulk" renewable energy fueled generation.
1kW	500MW	Same as above.
0.2kW	500MW	Low = small residential turbine. High = large wind farm boundary.
0.2kW	500MW	Same as above.

FIG. 62 (Cont.)



FIG. 63A

FIG. 63B

FIG. 63C



FIG. 64A



FIG. 64B



FIG. 65


6601
GENERATION LAYER 6602
TRANSMISSION LAYER 6604
DISTRIBUTION LAYER 6606
CONSUMPTION LAYER 6608
6610a
6612
6620a
6622
6630a
6630b
6632
6634
6634a
6634b
6640a
6640b
6641
6642
6644
6650
6655
6657
6661
6663
6665
6667
6669
6680a
6680b
6690
6606
6606a
6606b

FIG. 66


Total (Storage & Generation Asset)
Generation Asset only
Storage only
Z
A
Power
Time
B

FIG. 67


6828
6814
6825
POWER GRID
6822
6823
6816
6882
DIST. SUBST.
6812
6801
6818
6896
6894
6878
6876
6872
6862
6881
6870
6880
METER
6874
C/E
6802
6807
M/G
6804
6865
6864
6885
6883
6822
6860
6805
6806
6820
6821
6810
6850

FIG. 68



FIG. 68A



FIG. 68B


TO: •Combustion generation asset
FROM:
•generation asset
6803
6896
6894
6886
C
E
6888
6899
O
FROM:
•generation asset
FROM:
•meter
M
G
TO: •busbar
•co-located facility
6887
6889
FROM:
•generation asset

FIG. 68C


6950
6992
METER
6990
6994
6996
6980
6987
Out
6986
SOURCE
6988
6964
6981
S
6905
E
6973
V
T
P
6907
6949
6928
6932
6911
6909
STORAGE
6924
6923
6904
M/C
6922
6921
6902
C
6947
6903
6985
6961
6984
6963
Out
6901
H
SINK
6962
6982

FIG. 69



FIG. 69A



FIG. 69B



FIG. 69C



FIG. 69D


7094
7096
7050
METER
7074
7070
7082
7005
Out
7072
7003
SOURCE
E
G
7080
STORAGE
O
7002
7099
7004
C
M
Out
7001
SINK

FIG. 70

DG = distributed generation; NM = net metering

MODE	DESCRIPTION
Compression	• Electricity from meter powers motor to drive compressor to compress gas that is flowed to storage unit. • Thermal energy from separated liquid is communicated from compressor to end user where heating is desired. Otherwise, thermal energy from the heated separated liquid is routed out of the system.
Expansion	• Expansion of compressed gas in expander cools liquid that is separated and flowed to end user where cooling is desired. If cooling is not desired, thermal energy from the cooled separated liquid is routed out of the system. • Expansion of compressed gas in expander also drives the generator through the shaft to flow electricity to the end user, to the meter (DG/NM), or to both.
Compression and Expansion	• Electricity from meter powers motor to drive compressor to compress gas, and flow the compressed gas to storage unit. Thermal energy from separated liquid is communicated from compressor to end user where heating is desired. Otherwise, the heated separated liquid is routed out of the system. • Compressed gas from the storage unit is expanded in expander, which cools liquid that is separated and flowed to end user where cooling is desired. If cooling is not desired, the cooled separated liquid is routed out of the system. • Expansion of compressed gas in expander drives the generator through the shaft to flow electricity to the end user, to the meter (DG/NM), or to both.

FIG. 71

PV = photovoltaic; TS = thermal solar; WT = wind turbine; MT = microturbine; DG = distributed generation; NM = net metering

MODE	DESCRIPTION
Compression	• Electricity from meter powers motor to drive compressor to compress gas that is flowed to the storage unit. • Electricity from local source (PV) powers motor to drive compressor, alone or in conjunction with electricity from meter. • Physical energy from local source (WT/MT) drives compressor through gearing. • Gearing allows physical energy from local source (WT/MT) to be combined with physical energy from motor to drive compressor. • Thermal energy from separated liquid is communicated from compressor to end user where heating is desired. Otherwise, thermal energy from the heated separated liquid is routed out of the system.
Expansion	• Expansion of compressed gas in expander cools liquid that is separated and flowed to end user where cooling is desired. If cooling is not desired, thermal energy from the cooled separated liquid is routed out of the system. • Expansion of compressed gas in expander also drives the generator through the gearing to flow electricity to the end user, to the meter (DG/NM), or to both. • Thermal energy from the local source (TS/MT/or facility) is communicated to enhance efficiency of, and/or augment the power output from, recovery of energy from expansion of compressed gas in the expander.
Compression and Expansion	• Electricity from meter powers motor to drive compressor to compress gas that is flowed to the storage unit. • Electricity from local source (PV) may also power motor to drive compressor. • Physical energy from local source (WT/MT) drives compressor through gearing. • Gearing may allow physical energy from local source (WT/MT) to be combined with energy from motor to drive compressor. • Thermal energy from separated liquid is communicated from compressor to end user where heating is desired. Otherwise, the heated separated liquid is routed out of the system. • Compressed gas from the storage unit is expanded in expander, which cools liquid that is separated and flowed to end user where cooling is desired. If cooling is not desired, the cooled separated liquid is routed out of the system. • Expansion of compressed gas in expander drives the generator through the gearing to flow electricity to the end user, to the meter (DG/NM), or to both. • Thermal energy from the local source (TS/MT/or facility) is communicated to enhance efficiency of, and/or augment the power output from, recovery of energy from expansion of compressed gas in the expander.

FIG. 72


7314
45°F
7303
7313
7315
Expansion
7307
55°F
7309
7305
Counter-flow heat exchanger
7316
Cold side heat exchanger
7304
Hot side heat exchanger
7310
7308
7311
Compression
105°F
7306
7312
115°F
7302
M
7301

FIG. 73


No Water Injection
With Water Injection
Temperature (K)
1400
1200
1000
800
600
400
200
0
0
0.1
0.2
0.3
0.4
0.5
0.6
Time (Seconds)

FIG. 74



FIG. 74A



FIG. 75


Lower Bound on η thermal, rt
100%
90%
80%
70%
60%
50%
0.1%
0.5%
1%
5%
10%
50%
Initial Water Volume Fraction
1 µm
50 µm
100 µm
200 µm

FIG. 76A


Upperbound on ΔT_{eq} (K)
1000
100
10
1
0.1%
0.5%
1%
5%
10%
50%
Initial Water Volume Fraction
200 µm
100 µm
50 µm
1 µm

FIG. 76B



FIG. 77


No Water Spray
With Water Spray
Temperature (K)
600
550
500
450
400
350
300
0
60
120
180
240
300
360
Crank Angle (Degrees)

FIG. 78


Sheet Breakup
Formation and Growth of Instability
Droplet Breakup and Coalescence

FIG. 79



FIG. 80



FIG. 81a



FIG. 81b


8200
gas
liquid
8204
Hot
8210
8216
gas + liquid
liquid
Hot
SINK
8220
8214
8206
C
8208
8212
8230
8232
TV
Hot
8202
gas
gas + liquid

FIG. 82


No Water Spray (Adiabatic)
With Splash Model
Without Splash Model
Temperature (K)
600
550
500
450
400
350
300
250
200
0
60
120
180
240
300
360
Crank Angle (Degrees)

FIG. 83


8500
8502
8512
8506
8504
8508
8509
8514
8510
8509

FIG. 85


OUTLET
8404
8402
INLET
8400

FIG. 84

FIG. 86A	FIG. 86B	FIG. 86C

FIG. 86


ACCUMULATOR
Controller
8602
Memory
8604
2 INCH
3 INCH
FILTER 2
PRESSURE
RELIEF VALVE
P17
500 PSI
BALL VALVE
BV3
2 INCH
VFD
SW11
P16
MULTI-STAGE
WATER PUMP
3 INCH
MV4
CITY
SEWER
MOTOR OPERATED
3 WAY BALL VALVE
BV1
ATMOSPHERIC VENT
1 INCH
FILTER 1
MAIN
WATER TANK
260 GAL.
3
2
1
P4
HEAT
EXCHANGER 1
2 INCH
MV3
P3
PID
CV1
8602
TRANSFER PUMP
SW9
3 INCH
BALL VALVE
BV4
P12
P15

FIG. 86A


P2
T1
P1
F1
T13
P18
LFE
1 INCH
6 INCH
T15
P22
SOLENOID VALVE SV5-12(NC)
1 INCH
SUCTION BOTTLE
P19
T3
V1
T4
P5
P6
P7
CYLINDER
SPRAY NOZZLE
P8
SPRAY NOZZLE
P9
P10
FLOAT SWITCH
T5
T6
FLOAT SWITCH
CITY WATER
L4
T7
P11
L8
MV1
FLOAT SWITCH
L6
DISCHARGE BOTTLE
300 PSI
4 INCH
LEVEL SENSOR L1
FLOAT SWITCH
L5
FLOAT SWITCH
L7
RELIEF VALVE
SOLENOID VALVE SV1(NC)
2 INCH
2 INCH
T11
RELIEF VALVE
GV1
MV6
MUFFLER
3 INCH
LEVEL SENSOR L2
SUMP WATER TANK 240 GAL.
2 INCH
MV7
DRAIN
MV2

FIG. 86B


140/326
AIR CLEANER
H1
P20
SOLENOID VALVE
SV13-20(NC)
T8 P12
BAFFLE
SEPARATOR
4 INCH
CYCLONE
SEPARATOR
T9 P13
4 INCH
FLOAT VALVE
SOLENOID VALVE
SV3(NC)
SOLENOID VALVE
SV2(NC)
MV5
RELIEF VALVE
2 INCH
FLOAT SWITCH L9
TO
ATMOSPHERE
AIR STORAGE
TANK
240 GAL.
1
2
MOTOR
OPERATED
3 WAY BALL
VALVE
BV2
T10
P14
4 INCH
2 INCH

FIG. 86C


GAS FLOW VALVE NETWORK
LIQUID FLOW VALVE NETWORK
8700
8702
8704
8706
8708
8710
8712
8714

FIG. 87


GAS FLOW VALVE NETWORK
gas liquid separator 8802
LIQUID FLOW VALVE
AND SEPARATION NETWORK
8800

FIG. 88


120°
OUTLET
8910
8912a
8908
8912
8902
8904b
8904
8904a
8906
INLET

FIG. 89



FIG. 90C



FIG. 90B



FIG. 90A



FIG. 91C



FIG. 91A



FIG. 91E



FIG. 91D



FIG. 91B



FIG. 92C

FIG. 92A



FIG. 92E



FIG. 92D



FIG. 92B



FIG. 93



FIG. 93A



FIG. 93B



FIG. 94



FIG. 95



FIG. 96



FIG. 97



FIG. 98


9904
9904b
9906
9906b
9916
9915
9914
9912
9910
9908
9906a
9904a
9902
9900
CHAMBER SIDE

FIG. 99A



FIG. 99B



FIG. 99C



FIG. 99D



FIG. 100A



FIG. 100B



FIG. 100C



FIG. 100D



FIG. 100E



FIG. 100F



FIG. 100G


10006
10004b
10004
10021
10005
10007
10004a
10002a
10020
A
10009a
10000
A'
10009
10002

FIG. 100H



FIG. 100I



FIG. 100J



FIG. 101A



FIG. 101B



FIG. 101C



FIG. 102


Avg V m/s
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
position mm
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
-2.5
-5.0
-7.5
-10.0
-12.5
-15.0
-17.5
-20.0
-22.5
-32 m/s
-32 m/s
-5
-10
-15
-20
-25
-30
-35
-40
-45
position mm
position mm

FIG. 103


RMS V m/s
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
position mm
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
-2.5
-5.0
-7.5
-10.0
-12.5
-15.0
-17.5
-20.0
-22.5
-32 m/s
-32 m/s
-5
-10
-15
-20
-25
-30
-35
-40
-45
position mm
-5
-10
-15
-20
-25
-30
-35
-40
-45

FIG. 104


Particle segmentation
This side not used
24
20
16
12
8
4
0
-4
-8
-12
-16
-20
-24
position mm
-45
-40
-35
-30
-25
-20
-15
-10
-5
position mm

FIG. 105


100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
% of max
0.05
0.10
0.15
0.20
0.25
0.30
0.35
0.40
0.45
0.50
Diameter mm

FIG. 106


Particle segmentation
24
20
16
12
8
4
0
-4
-8
-12
-16
-20
-24
position mm
-45
-40
-35
-30
-25
-20
-15
-10
-5
position mm

FIG. 107


% of max
100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
0.05
0.10
0.15
0.20
0.25
0.30
0.35
0.40
0.45
0.50
Diameter mm

FIG. 108


Particle segmentation
7
6
5
4
3
2
1
0
-1
-2
-3
-4
-5
-6
-7
position mm
-14
-12
-10
-8
-6
-4
-2
position mm

FIG. 109A


Particle segmentation
7
6
5
4
3
2
1
0
-1
-2
-3
-4
-5
-6
-7
position mm
-14
-12
-10
-8
-6
-4
-2
position mm

FIG. 109B


100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
% of max
0.025 0.050 0.075 0.100 0.125 0.150 0.175 0.200 0.225 0.250 0.275 0.300
Diameter mm

FIG. 110A


% of max
100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
0.025 0.050 0.075 0.100 0.125 0.150 0.175 0.200 0.225 0.250 0.275 0.300
Diameter mm

FIG. 110B



FIG. 111A



FIG. 111B



FIG. 112A



FIG. 112B



FIG. 113


Avg V m/s
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
position mm
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
-2.5
-5.0
-7.5
-10.0
-12.5
-15.0
-17.5
-20.0
-22.5
-32 m/s
-32 m/s
position mm
-5
-10
-15
-20
-25
-30
-35
-40
-45
position mm
-5
-10
-15
-20
-25
-30
-35
-40
-45

FIG. 114


RMS V m/s
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
position mm
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
-2.5
-5.0
-7.5
-10.0
-12.5
-15.0
-17.5
-20.0
-22.5
-32 m/s
-32 m/s
position mm
-5
-10
-15
-20
-25
-30
-35
-40
-45
position mm
-5
-10
-15
-20
-25
-30
-35
-40
-45

FIG. 115


Particle segmentation
This side not used
24
20
16
12
8
4
0
0-4
-8
-12
-16
-20
-24
position mm
-45
-40
-35
-30
-25
-20
-15
-10
-5
position mm

FIG. 116


% of max
100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
0.05
0.10
0.15
0.20
0.25
0.30
0.35
0.40
0.45
0.50
Diameter mm

FIG. 117


Particle segmentation
24
20
16
12
8
4
0
-4
-8
-12
-16
-20
-24
position mm
-45
-40
-35
-30
-25
-20
-15
-10
-5
position mm

FIG. 118


100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
% of max
0.05
0.10
0.15
0.20
0.25
0.30
0.35
0.40
0.45
0.50
Diameter mm

FIG. 119


Particle segmentation
7
6
5
4
3
2
1
0
-1
-2
-3
-4
-5
-6
-7
position mm
-14
-12
-10
-8
-6
-4
-2
position mm

FIG. 120


100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
% of max
0.025 0.050 0.075 0.100 0.125 0.150 0.175 0.200 0.225 0.250 0.275 0.300
Diameter mm

FIG. 121



FIG. 122A



FIG. 122B



FIG. 123A



FIG. 123B



FIG. 124



FIG. 124A



FIG. 125


12636
12612
12622
12638
12608a
12608
LOW
PRESSURE
SIDE
HIGH
PRESSURE
SIDE

FIG. 126



FIG. 127



FIG. 128



FIG. 129



FIG. 130A



FIG. 130B



FIG. 131



FIG. 132



FIG. 133A



FIG. 133B



FIG. 133C



FIG. 133D



FIG. 133E


13306
13305
13321
13304
13320
13309
13304a
13330
13302a
13340
13310
13302

FIG. 133F



FIG. 133G



FIG. 134A



FIG. 134B



FIG. 134C



FIG. 135A



FIG. 135B



FIG. 135C



FIG. 135D



FIG. 135E


13600
13613
PUMP
13614
HEAT
EXCHANGER
13612
GAS - LIQUID
SEPARATOR
SPRAY
NOZZLE
13607
HIGH - PRESSURE
GAS IN
LOW - PRESSURE
GAS OUT
INTAKE
VALVE
13610 EXHAUST VALVE
13608 CYLINDER
13602
PISTON
GENERATOR
13606
13604
CRANKSHAFT

FIG. 136


13700
HIGH - PRESSURE GAS
LOW - PRESSURE GAS
VALVE
VALVE
13712 COMPRESSIBLE MEMBER (EG. SPRING)
13710 VALVE
13706 NOZZLE PLATE
13708 LIQUID INLET
13702 LIQUID
13704 PISTON
13720 CYLINDER

FIG. 137


13800
OPTIONAL VARIABLE FLOW VALVE 13806
GAS - LIQUID SEPARATOR 13802
13810 HIGH - PRESSURE GAS
VALVE
13804 SPRAY NOZZLE
VALVE
PISTON
LOW - PRESSURE GAS

FIG. 138



FIG. 139


20200
High Pressure Gas In
Inlet Valve
20202
Piston
Spray Nozzle
Outlet Valve
Gas - Liquid Separator
Expanded Gas Exhaust
Condenser 20204
Valve
20206
20208
20210
20212 Water Reservoir
Pump

FIG. 140


20302
Gas Storage
20308
Piston
20310
To Atmosphere or to next Lower-Pressure Stage
20304
20312
20306
Crankshaft
Piston
20300
Liquid Reservoir
Motor/Generator

FIG. 141


14201
GENERATION LAYER 14202
TRANSMISSION LAYER 14204
DISTRIBUTION LAYER 14206
CONSUMPTION LAYER 14208
14210a
14212
14257
14220a
14222
14220b
14265
14230a
14230b
14232
14234
14234a
14234b
14240a
14240b
14250
14206
14206a

FIG. 142


14328
14314
POWER GRID
14322
14316
14382
DIST. SUBST.
14312
14303
14301
14318
14396
14394
14372
BUSBAR
14362
14381
14380
METER
C/E
14302
14307
M/G
14304
14364
14360
14305
14306
14350

FIG. 143


GAS STORAGE
14405
COMPRESSION/ EXPANSION SYSTEM
14402
IN
ELECTRICAL ENERGY
MECHANICAL ENERGY
HYDRAULIC PNEUMATIC ENERGY
HOT GAS/ LIQUID
COLD GAS/ LIQUID
14400
PHYS. ENERGY
THERMAL ENERGY
OUT
ELECTRICAL ENERGY
MECHANICAL ENERGY
HYDRAULIC PNEUMATIC ENERGY
HOT GAS/LIQUID
COLD GAS/ LIQUID
COMPRESSED GAS
POTABLE WATER
HUMIDITY
14404
PHYS. ENERGY
THERMAL ENERGY

FIG. 144A


ENERGY SOURCE
14410
SINK
14454
SOURCE
14452
THERMAL
14450
FLUIDIC
14460
PHYSICAL
14470
ELECT.
14480
COMPRESSION/ EXPANSION SYSTEM
14402
GAS 14405
STORAGE
14412
ENERGY DESTINATION

FIG. 144B


Gas Tank
14578
Ext. Thermal
14536
14520
14558
14576
14512
S+P
HE
14534
14502
14566
14582
14510
14524
14518
14504
14574
14540
Side2
14538
14532
14590
14592
14516
Side1
14530
14556
14502
14562
14572
14564
14528
14554
14580
14570
14522
14514
14506
14508
14526
14560

FIG. 145A

- Combinations of Configurations are Possible Per Figure 146
- (Parenthesis) indicate optional functionality or optional presence of element

Configuration	ID	1	2	3	4
	Description	Energy Storage	Energy Delivery	Heat Engine	Heat Engine
	Storage		from storage	No storage	No storage
	Gas Flow	Open System; Fig. 145BB; upward to storage	Open System; Fig. 145BC; downward from storage	Closed Circuit; Fig. 145BD; counter-clock-wise/clockwise	Open System; Fig. 145BE; Left→Right/ Right→Left
Cylinder No.	14502	Compressor	Expander	Compressor/ Expander	Compressor/ expander
	14504	Compressor	Expander	Expander/ Compressor	Expander/ compressor
Valve No. Connection: Port a - port _	14506	b	c	d	b
	14508	c	b	d	d
	14510	b	c	d	d
	14512	c	b	d	b
Counterflow Heat Exchanger 14538	Side 1	N/A	N/A	Cold/Hot	N/A
	Side 2			Hot/Cold	
Gas-Gas Heat Exchanger	14514	--	--	--	--
	14516	(act as heater)	(act as cooler)	(act as heater/ act as cooler)	(act as heater/ act as cooler)
	14518	--	--	--	--
	14520	(act as heater)	(act as cooler)	(act as cooler/ act as heater)	(act as cooler/ act as heater)
Liquid-Gas Heat Exchanger	14522	(act as heater)	(act as cooler)	(act as heater/ act as cooler)	(act as heater/ act as cooler)
	14524	(act as heater)	(act as cooler)	(act as cooler/ act as heater)	(act as cooler/ act as heater)
External Thermal Node	14526	(Heat Sink)	(Heat Source)	(Heat Sink/ Heat Source)	(Heat Sink/ Heat Source)
	14528	(Heat Sink)	(Heat Source)	Heat Sink/ Heat Source	Heat Sink/ Heat Source
	14530	(Heat Sink)	(Heat Source)	(Heat Sink/ Heat Source)	(Heat Sink/ Heat Source)
	14532	(Heat Sink)	(Heat Source)	(Heat Source/ Heat Sink)	(Heat Source/ Heat Sink)
	14534	(Heat Sink)	(Heat Source)	Heat Source/ Heat Sink	(Heat Source/ Heat Sink)
	14536	(Heat Sink)	(Heat Source)	(Heat Source/ Heat Sink)	(Heat Source/ Heat Sink)
	14540	N/A	N/A	Heat Sink or Heat Source	Heat Sink or Heat Source

FIG. 145BA



FIG. 145BD



FIG. 145BE



FIG. 145BB



FIG. 145BC



Heat engine + Compressor (storage)

FIG. 145BF



Heat engine + expander (energy delivery)

FIG. 145BG

INPUT	OUTPUT (DELIVERABLE)	● PROCESS ○ PATHWAY (ELEMENT) = OPTIONAL
Configuration #1: Electrical Energy, Mechanical Energy, Hydraulic or Pneumatic Energy drive compressor to compress gas	Compressed Gas	● Gas compression yields compressed gas directly to be stored; ○ INPUT ENERGY→PHYS. LINKAGE→COMPRESSOR→COMPRESSED GAS STORAGE
		● Some amount of compressed gas not apportioned to storage or expansion, may be routed out of the system (for example to a co-situated user such as a combustion turbine) ○ INPUT ENERGY→PHYS. LINKAGE→COMPRESSOR→FLUIDIC LINKAGE
	Thermal Energy (hot gas)	● Gas compression yields hot gas directly or indirectly via heat exchange with separated fluids ○ INPUT ENERGY→PHYS. LINKAGE→COMPRESSOR→GAS-LIQUID SEPARATOR→FLUIDIC LINKAGE (if hot gas is used directly) or THERMAL LINKAGE (if gas absorbs heat from the hot liquid via a heat exchanger)
	Thermal Energy (hot liquid)	● Gas compression yields hot liquid directly through heat exchange with hot gas or indirectly via heat exchange with separated fluids ○ INPUT ENERGY→PHYS. LINKAGE→COMPRESSOR→GAS-LIQID SEPARATOR→ FLUIDIC LINKAGE (if hot liquid is used directly) or THERMAL LINKAGE (if liquid absorbs heat from the hot gas via a heat exchanger)

FIG. 145C

INPUT	OUTPUT (DELIVERABLE)	● PROCESS ○ PATHWAY (ELEMENT) = OPTIONAL
Configuration #2: Compressed Gas (Storage Tank) (Thermal energy source in the form of hot medium or radiation)	Electrical Energy*	● Expansion of compressed gas drives generator ○ COMPRESSED GAS (directly or from TANK)→EXPANDER→ LINKAGE→ GENERATOR
	Mechanical Energy*	● Expansion of compressed gas drives mechanical linkage; ○ COMPRESSED GAS (directly or from TANK)→EXPANDER→MECH. LINKAGE
	Pneumatic / Hydraulic Energy*	● Expansion of compressed gas creates pressure differential driving pneumatic or hydraulic linkage; ○ COMPRESSED GAS (directly or from TANK)→EXPANDER→ HYDRAUL./PNEUMAT. LINKAGE
	Thermal Energy (cool gas)	● Expansion of compressed gas yields cooled gas directly or via heat exchange with separated fluids ○ COMPRESSED GAS (directly or from TANK)→EXPANDER→GAS-LIQUID SEPARATOR→FLUIDIC LINKAGE (if cool gas is used directly) or THERMAL LINKAGE (if gas transfers heat to the cool liquid via a heat exchanger)
	Thermal Energy (cool liquid)	● Expansion of compressed gas yields cooled liquid directly through heat exchange with cool gas, or indirectly via heat exchange with separate fluids ○ COMPRESSED GAS (directly or from TANK)→EXPANDER→ GAS-LIQUID SEPARATOR→FLUIDIC LINKAGE (if cool liquid is used directly) or THERMAL LINKAGE (if liquid transfers heat to the cool gas via a heat exchanger)
	Potable Water	● Expansion of compressed gas yields cooled gas or liquid for use in condensing moisture out of air; ○ COMPRESSED GAS (directly or from TANK)→EXPANDER→THERMAL LINKAGE→CONDENSOR
	Humidified Gas	● Expansion of compressed gas yields humidified air; ○ COMPRESSED GAS (directly or from TANK)→EXPANDER→GAS SEPARATOR→ HUMIDIFIED AIR
	Dehumidified Gas	● Expansion of compressed gas yields cooled gas or liquid for use in condensing moisture out of air; ○ COMPRESSED GAS (directly or from TANK)→EXPANDER→THERMAL LINKAGE→CONDENSOR→DEHUMIDIFIED AIR

* External heat sources can be employed to heat the working fluids (liquid and gas), and to deliver more electrical, mechanical, pneumatic, or hydraulic energy.

FIG. 145D

INPUT	OUTPUT (DELIVERABLE)	● PROCESS PATHWAY (ELEMENT) = OPTIONAL
Configuration #3 or **Configuration #4:** Thermal energy source in the form of hot medium or radiation (Compressed gas) (Compressed gas storage tank) (Electrical, Mechanical, Hydraulic or Pneumatic Energy)	Electrical Energy	● Hot gas or liquid is either 1) input directly into expander, or 2) exchanges heat through heat exchanger with working fluids. Expansion of compressed gas drives compressor cylinder and generator. ○ PHYS. LINKAGE→COMPRESSOR→COMPRESSED GAS (directly or from TANK)→HEAT EXCHANGE→EXPANDER→LINKAGE→GENERATOR
	Mechanical Energy	● Hot gas or liquid is either 1) input directly into expander, or 2) exchanges heat through heat exchanger with working fluids.Expansion of compressed gas drives mechanical linkage. ○ PHYS. LINKAGE→COMPRESSOR→COMPRESSED GAS (directly or from TANK)→HEAT EXCHANGE→EXPANDER→MECH. LINKAGE
	Pneumatic / Hydraulic Energy	● Hot gas or liquid is either 1) input directly into expander, or 2) exchanges heat through heat exchanger with working fluids. Expansion of compressed gas creates pressure differential driving pneumatic or hydraulic linkage. ○ PHYS. LINKAGE→COMPRESSOR→COMPRESSED GAS (directly or from TANK)→HEAT EXCHANGE→EXPANDER→HYDRAUL./PNEUMAT. LINKAGE
	Thermal Energy (cool gas)	● Expansion of compressed gas yields cooled gas directly or via heat exchange with separated fluids ○ PHYS. LINKAGE→COMPRESSOR→COMPRESSED GAS (directly or from TANK)→HEAT EXCHANGE→EXPANDER→GAS-LIQUID SEPARATOR→FLUIDIC LINKAGE (if cool gas is used directly) or THERMAL LINKAGE (if gas transfers heat to the cool liquid via a heat exchanger)
	Thermal Energy (cool liquid)	● Expansion of compressed gas yields cooled liquid directly through heat exchange with cool gas, or indirectly via heat exchange with separate fluids ○ PHYS. LINKAGE→COMPRESSOR→COMPRESSED GAS (directly or from TANK)→HEAT EXCHANGE→EXPANDER→GAS-LIQUID SEPARATOR→FLUIDIC LINKAGE (if cool liquid is used directly) or THERMAL LINKAGE (if liquid transfers heat to the cool gas via a heat exchanger)
	Thermal Energy (hot gas)	● Gas compression yields hot gas directly or indirectly via heat exchange with separated fluids ○ INPUT ENERGY→PHYS. LINKAGE→COMPRESSOR→GAS-LIQUID SEPARATOR→FLUIDIC LINKAGE (if hot gas is used directly) or THERMAL LINKAGE (if gas absorbs heat from the hot liquid via a heat exchanger)→EXPANDER→GAS-LIQUID SEPARATOR→THERMAL/PHYS. LINKAGE

FIG. 145EA

INPUT	OUTPUT (DELIVERABLE)	• PROCESS ○ PATHWAY (ELEMENT) = OPTIONAL
Configuration #3 or **Configuration #4:** Thermal energy source in the form of hot medium or radiation (Compressed gas) (Compressed gas storage tank) (Electrical, Mechanical, Hydraulic or Pneumatic Energy)	Thermal Energy (hot gas)	• Gas compression yields hot liquid directly through heat exchange with hot gas or *indirectly* via heat exchange with separated fluids ○ INPUT ENERGY→PHYS. LINKAGE→COMPRESSOR→GAS-LIQUID SEPARATOR→ FLUIDIC LINKAGE (if hot liquid is used directly) or THERMAL LINKAGE (if liquid absorbs heat from the hot gas via a heat exchanger)→ EXPANDER→ GAS-LIQUID SEPARATOR→THERMAL/PHYS. LINKAGE
	Potable Water	• Expansion of compressed gas yields cooled gas or liquid for use in condensing moisture out of air; ○ COMPRESSED GAS (directly or from TANK)→EXPANDER→THERMAL LINKAGE→CONDENSOR
	Humidified Gas	• Expansion of compressed air yields humidified air; ○ PHYS. LINKAGE→COMPRESSOR→COMPRESSED GAS (directly or from TANK)→HEAT EXCHANGE→EXPANDER →GAS-LIQUID SEPARATOR→ HUMIDIFIED AIR
	Dehumidified Gas	• Expansion of compressed air yields cooled gas or liquid for use in condensing moisture out of air; ○ PHYS. LINKAGE→COMPRESSOR→COMPRESSED GAS (directly or from TANK)→HEAT EXCHANGE→EXPANDER→THERMAL LINKAGE→ CONDENSOR→ DEHUMIDIFIED AIR

FIG. 145EB


IN
①
②
③
④
⑤
Compressed Gas
Heated Gas/Liquid
Cooled Gas/Liquid
Mechanical-/ Hydraulic-/ Pneumatic-in
Electrical-in
(Heat Exchange)
Physical Linkage
Electric Motor
Fluidic or Thermal Linkage
Thermal Energy in
NonThermal Energy in
Compressor
(Gas Storage)
Expander
NonThermal Energy out
Thermal Energy out
Fluidic or Thermal Linkage
Physical Linkage
Electrical Generator
(Heat Exchange)
Electrical - out
Mechanical -/ Hydraulic -/ Pneumatic - out
Heated Gas/Liquid
Cooled Gas/Liquid
Compressed Gas
⑤
④
②
③
①
OUT

FIG. 146


Total
Renewable Generation Asset
Energy Storage Apparatus
Short-Term Generation Asset
Longer-Term Generation Asset
Power
Time
Z
A
B
C
D
E
F
G
R
T

FIG. 147



FIG. 147A



FIG. 148AA



FIG. 148AB



FIG. 148AC



FIG. 148AD



FIG. 148B



FIG. 148CA

230/326



FIG. 148CB



FIG. 148D


14940
14902
14930
14942
14932
14910
14916
14924
14960
14903
14942

FIG. 149A


14950
14940
14932
14912
14930
14942
14942
14924
14910
14914
14952
14952
14902
14906
14903
14904
14908
14954
14918
14916
14954
14922
14920

FIG. 149B



FIG. 149CA



FIG. 149CB


14914
14912
14913
14914
14910
14911
14913
14914
14913
14917
14915
14914
14913

FIG. 149DA



FIG. 149DB



FIG. 150A



FIG. 150B


X
Z
Nozzle
Thickness
of the spray
13.2
Deg
Sheet Angle
(between sheet &
nozzle surface)

FIG. 150C



FIG. 151


Avg V m/s
40.0
37.5
35.0
32.5
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
position mm
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
-2.5
-5.0
-7.5
-10.0
-12.5
-15.0
-17.5
-20.0
-22.5
+32 m/s
-32 m/s
-5
-10
-15
-20
-25
-30
-35
-40
-45
position mm
-5
-10
-15
-20
-25
-30
-35
-40
-45

FIG. 152A


Avg V m/s
40.0
37.5
35.0
32.5
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
position mm
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
-2.5
-5.0
-7.5
-10.0
-12.5
-15.0
-17.5
-20.0
-22.5
-32 m/s
-5
-10
-15
-20
-25
-30
-35
-40
-45
position mm
-32 m/s

FIG. 152B


37.5
35.0
32.5
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
Length m/s
20
15
10
5
0
-5
-10
-15
-20
position mm

FIG. 153


Particle segmentation
24
20
16
12
8
4
0
-4
-8
-12
-16
-20
position mm
-45
-40
-35
-30
-25
-20
-15
-10
-5
position mm

FIG. 154A


% of max
100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
0.05 0.10 0.15 0.20 0.25 0.30 0.35 0.40 0.45 0.50 0.55 0.60 0.65 0.70
Diameter mm

FIG. 154B


Particle segmentation
24
20
16
12
8
4
0
-4
-8
-12
-16
-20
position mm
-45
-40
-35
-30
-25
-20
-15
-10
-5
position mm

FIG. 155A


% of max
100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
0.05 0.10 0.15 0.20 0.25 0.30 0.35 0.40 0.45 0.50 0.55 0.60 0.65 0.70
Diameter mm

FIG. 155B


Particle segmentation
8
7
6
5
4
3
2
1
0
-1
-2
-3
-4
-5
-6
-7
-8
position mm
-16
-14
-12
-10
-8
-6
-4
-2
position mm

FIG. 156A


100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
% of max
0.05 0.10 0.15 0.20 0.25 0.30 0.35 0.40 0.45 0.50 0.55 0.60 0.65 0.70
Diameter mm

FIG. 156B


232
230
228
226
224
222
220
D32
8
7
6
5
4
3
2
1
0
Num of Droplets x 10000
d32 µm
Num
13.0
13.5
14.0
14.5
15.0
15.5
16.0
Sheet Angle

FIG. 157



FIG. 158


Avg V m/s
40.0
37.5
35.0
32.5
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
6.0
2.5
0.0
position mm
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
-2.5
-5.0
-7.5
-10.0
-12.5
-15.0
-17.5
-20.0
-22.5
-32 m/s
-32 m/s
position mm
-5
-10
-15
-20
-25
-30
-35
-40
-45
-5
-10
-15
-20
-25
-30
-35
-40
-45

FIG. 159A


Avg V m/s
40.0
37.5
35.0
32.5
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
position mm
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
-2.5
-5.0
-7.5
-10.0
-12.5
-15.0
-17.5
-20.0
-22.5
-32 m/s
-32 m/s
-5
-10
-15
-20
-25
-30
-35
-40
-45
position mm

FIG. 159B


Length m/s
27
26
25
24
23
22
21
20
19
18
17
16
15
14
13
12
11
10
9
8
7
6
5
4
3
2
1
20
15
10
5
0
-5
-10
-15
-20
position mm

FIG. 160


Particle segmentation
24
20
16
12
8
4
0
-4
-8
-12
-16
-20
position mm
-45
-40
-35
-30
-25
-20
-15
-10
-5
position mm

FIG. 161A


% of max
100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
0.05 0.10 0.15 0.20 0.25 0.30 0.35 0.40 0.45 0.50 0.55 0.60 0.65 0.70
Diameter mm

FIG. 161B


Particle segmentation
24
20
16
12
8
4
0
-4
-8
-12
-16
-20
position mm
-45
-40
-35
-30
-25
-20
-15
-10
-5
position mm

FIG. 162A


100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
% of max
0.05 0.10 0.15 0.20 0.25 0.30 0.35 0.40 0.45 0.50 0.55 0.60 0.65 0.70
Diameter mm

FIG. 162B


Particle segmentation
8
7
6
5
4
3
2
1
0
-1
-2
-3
-4
-5
-6
-7
-8
position mm
-16
-14
-12
-10
-8
-6
-4
-2
position mm

FIG. 163A


% of max
100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
0.05 0.10 0.15 0.20 0.25 0.30 0.35 0.40 0.45 0.50 0.55 0.60 0.65 0.70
Diameter mm

FIG. 163B


d32 µm
Num
D32
Num of Droplets x 10000
Sheet Angle
266
264
262
260
258
256
254
252
250
248
246
6
5
4
3
2
1
0
12.0
14.0
16.0
18.0
20.0

FIG. 164


Max velocity at x = - 3.1 mm
Velocity [m/s]
40
38
36
34
32
30
28
26
24
22
80
100
120
140
160
180
200
220
Pressure [PSIG]
Max velocity at x = -3.1 mm
Power (Max velocity at x = -3.1 mm)
y = 2.3179x^0.5258

FIG. 165



FIG. 166A



FIG. 166B


X
Z
Nozzle
Thickness
of the spray
16
Deg
Sheet Angle
(between sheet &
nozzle surface)

FIG. 166C



FIG. 167


Avg V m/s
40.0
37.5
35.0
32.5
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
position mm
-24
-20
-16
-12
-8
-4
0
4
8
12
16
20
24
-32 m/s
-32 m/s
position mm
-5
-10
-15
-20
-25
-30
-35
-40
-45
-50
-5
-10
-15
-20
-25
-30
-35
-40
-45
-50

FIG. 168A


position mm
40.0 37.5 35.0 32.5 30.0 27.5 25.0 22.5 20.0 17.5 15.0 12.5 10.0 7.5 5.0 2.5 0.0
position mm
24 20 16 12 8 4 0 -4 -8 -12 -16 -20 -24
-32 m/s
-32 m/s
position mm
-5 -10 -15 -20 -25 -30 -35 -40 -45 -50
position mm
-5 -10 -15 -20 -25 -30 -35 -40 -45 -50

FIG. 168B


37.5
35.0
32.5
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
Length mis
25
20
15
10
5
0
-5
-10
-15
-20
-25
position mm

FIG. 169


Particle segmentation
7
6
5
4
3
2
1
0
-1
-2
-3
-4
-5
-6
-7
position mm
-14
-12
-10
-8
-6
-4
-2
position mm

FIG. 170A


% of max
100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
0.025 0.050 0.075 0.100 0.125 0.150 0.175 0.200 0.225 0.250 0.275 0.300
Diameter mm

FIG. 170B


Particle segmentation
7
6
5
4
3
2
1
0
-1
-2
-3
-4
-5
-6
-7
position mm
-14
-12
-10
-8
-6
-4
-2
position mm

FIG. 171A


% of max
100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
0.025 0.050 0.075 0.100 0.125 0.150 0.175 0.200 0.225 0.250 0.275 0.300
Diameter mm

FIG. 171B


200 PSIG
D32
Num of Droplets x 10000
D32 µm
Num
Sheet Angle
150
145
140
135
130
125
120
115
110
9
8
7
6
5
4
3
2
15.0
17.0
19.0
21.0
23.0
25.0

FIG. 172



FIG. 173


Avg V m/s
40.0
37.5
35.0
32.5
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
position mm
24
20
16
12
8
4
0
-4
-8
-12
-16
-20
-24
32 m/s
32 m/s
position mm
-5
-10
-15
-20
-25
-30
-35
-40
-45
-50
-5
-10
-15
-20
-25
-30
-35
-40
-45
-50

FIG. 174A


Avg V m/s
40.0
37.5
35.0
32.5
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
0.0
position mm
24
20
16
12
8
4
0
-4
-8
-12
-16
-20
-24
>32 m/s
>32 m/s
position mm
-5
-10
-15
-20
-25
-30
-35
-40
-45
-50

FIG. 174B


Length m/s
27
26
25
24
23
22
21
20
19
18
17
16
15
14
13
12
11
10
9
8
7
6
5
4
3
2
1
25
20
15
10
5
0
-5
-10
-15
-20
-25
position mm

FIG. 175


Particle segmentation
7
6
5
4
3
2
1
0
-1
-2
-3
-4
-5
-6
-7
position mm
-14
-12
-10
-8
-6
-4
-2
position mm

FIG. 176A


% of max
100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
0.025 0.050 0.075 0.100 0.125 0.150 0.175 0.200 0.225 0.250 0.275 0.300
Diameter mm

FIG. 176B


Particle segmentation
7
6
5
4
3
2
1
0
-1
-2
-3
-4
-5
-6
-7
position mm
-14
-12
-10
-8
-6
-4
-2
position mm

FIG. 177A


% of max
100
95
90
85
80
75
70
65
60
55
50
45
40
35
30
25
20
15
10
5
0
-5
0.025 0.050 0.075 0.100 0.125 0.150 0.175 0.200 0.225 0.250 0.275 0.300
Diameter mm

FIG. 177B


100 PSIG
D32
Num of Droplets x 10000
Sheet Angle
D32 µm
Num
185
180
175
170
165
160
155
150
145
140
135
4
3.5
3
2.5
2
1.5
15
20
25
30

FIG. 178



FIG. 179A



FIG. 179B


X
Z
Nozzle
Thickness
of the spray
12.6
Deg
Sheet Angle
(between sheet &
nozzle surface)

FIG. 179C



FIG. 179D



FIG. 179E


Contours of Velocity Magnitude (mixture) (m/s) (Time=3.4855e-03)
24
19
15
9.7
4.9
0
Y
X
Z

FIG. 179F



FIG. 180A



FIG. 180B


X
Z
Nozzle
Thickness
of the spray
12.3
Deg
Sheet Angle
(between sheet &
nozzle surface)

FIG. 180C



FIG. 180D



FIG. 180E


18100
18101
18102
18103
18104
18105
18106
18107
18108
18111
18112
18113
18114
18115
18120
18121
18131
18132
18141
18142
18143
18150
18151
18152
18153
18154
Gas out/in
Gas in/out
liquid flow
pump / turbine
motor
pump / turbine
Thermal Node / Fluid Linkage

FIG. 181

Element	Ref. No.	High Pressure Differential Gas Heat Exchanger	Solar Gas Heater (e.g. pre-heater for multi-stage gas expander)	Water Heater / Gas Cooler (e.g. pre-cooler for a 2-stage gas compressor)	Industrial Air Cooler / Air Cleaner
Chamber	18120	High pressure gas heater	High pressure gas heater	High pressure gas cooler	Atmospheric gas cooler
Chamber	18121	Low pressure gas cooler	Mid pressure gas heater	Mid pressure gas cooler	Atmospheric gas cooler
Port	18106	High pressure gas in	High pressure gas in	High pressure gas in (discharged from 2nd stage compressor)	Dusty and hot air in (from factory / assembly line)
Port	18105	Heated high pressure gas out	Heated high pressure gas out (towards 1st stage expander)	Cooled high-pressure gas out (towards storage tank)	Slightly cooler / cleaner air out (towards chamber 18121 / port 18107 to be further cooled)
Port	18107	Low pressure gas in	Mid pressure gas in (discharged from 1st stage expander)	Mid pressure gas in (discharged from 1st stage compressor)	Slightly cooler / cleaner air in (discharged from chamber 18120 / port 18105)
Port	18108	Cooled low pressure gas out	Heated mid pressure gas out (towards 2nd stage expander)	Cooled mid-pressure gas out (towards 2nd compression stage)	Cooled / Cleaned air out (fed back to the factory / assembly line)
Thermal Node/ Fluid Linkage	18131/ 18141	N/A	Solar thermal liquid heater	Liquid heat exchanger that cools cycling water and heats residential water suppiy line	No thermal linkage. Drains liquid from port 3. Sucks in liquid separated from gas-liquid separator of an expander (e.g. separator 14522 in Fig. 145A)
Thermal Node/ Fluid Linkage	18132/ 18142	N/A	Solar thermal liquid heater	Liquid heat exchanger that melts driveway snow	No thermal linkage. Drains liquid from port 4. Sucks in liquid separated from gas-liquid separator of an expander (e.g. separator 14558 in Fig. 145A)
Nozzle	18101	Sprays hot liquid	Sprays hot liquid	Sprays cooled liquid	Sprays cooled liquid (e.g. liquid coming from gas-liquid separator 14522 of expander 14502 in Fig. 145A)
Nozzle	18102	Sprays cold liquid	Sprays hot liquid	Sprays cooled liquid	Sprays cooled liquid (e.g. liquid coming from gas-liquid separator 14558 of expander 14504 in Fig. 145A)
Port	18103	Drains cooled liquid	Drains cooled liquid	Drains heated liquid	Drains heated / contaminated liquid
Port	18104	Drains heated liquid	Drains cooled liquid	Drains heated liquid	Drains heated / contaminated liquid
Pump/ Turbine	18111	Pumps liquid to high pressure of chamber 18120 + pressure drop across nozzle18101	Pumps liquid to pressure of chamber 18120 + pressure drop across nozzle 18101	Pumps liquid to pressure of chamber 18120 + pressure drop across nozzle 18101	Pumps liquid
Pump/ Turbine	18112	Acts as turbine. Recovers energy from pressurized liquid and reduces load on pump motor 18150 (via mechanical linkage 18113)	Pumps liquid to pressure of chamber 18121 + pressure drop across nozzle 18102	Pumps liquid to pressure of chamber 18121 + pressure drop across nozzle 18102	Pumps liquid

FIG. 181A



FIG. 182A



FIG. 182B


X
Z
Nozzle
Thickness
of the spray
12.3
Deg
Sheet Angle
(between sheet
& nozzle surface)

FIG. 182C



FIG. 183A



FIG. 183B



FIG. 184A



FIG. 184B


X
Z
Nozzle
Thickness
of the spray
12.3
Deg
Sheet Angle
(between sheet
& nozzle surface)

FIG. 184C



FIG. 185A



FIG. 185B



FIG. 186A



FIG. 186B


X
Z
Nozzle
Thickness
of the spray
12.3
Deg
Sheet Angle
(between sheet
& nozzle surface)

FIG. 186C


200 PSIG
D32
Num of Droplets
x 10000
Sheet Angle
D32 µm
Num
Q_Normalized
200
190
180
170
160
150
140
130
6
5.5
5
4.5
4
3.5
3
2.5
2
1.5
6.0
8.0
10.0
12.0
14.0

FIG. 187



FIG. 188A



FIG. 188B


X
Z
Nozzle
Thickness
of the spray
12.3
Deg
Sheet Angle
(between sheet
& nozzle surface)

FIG. 188C



FIG. 189A



FIG. 189B



FIG. 190A



FIG. 190B



FIG. 190C



FIG. 191A



FIG. 191B



FIG. 191C



FIG. 192A



FIG. 192B



FIG. 192C



FIG. 193A



FIG. 193B



FIG. 193C



FIG. 194A



FIG. 194B



FIG. 194C



FIG. 195A



FIG. 195B



FIG. 196



FIG. 197



FIG. 198


19903
END USER
19903
19910a
METER
19910
19906
19904
19910c
19910b
19902
ENERGY SYSTEM
19900

FIG. 199


Volume flow rate of LSI18I
Water Q (ml/s)
P10 Q (ml/s)
P20 Q (ml/s)
P40 Q (ml/s)
Q [ml/s]
Pressure [PSIG]
54
52
50
48
46
44
42
40
38
36
34
32
30
28
0
50
100
150
200
250
300
350

FIG. 200


Run 3 - 12
Size: 0.63"
Runs Center
3 (-0.39,-0.5)
4 (-1,-0.79)
5 (-2,-1.6)
6 (-3,-1.8)
7 (-3,-1.8)
8 (-3,-2.4)
9 (-3,-3)
10 (-4,-3.4)
11 (-4,-2.8)
12 (-4,-2.2)
Nozzle exit
X
Y
Run 1
Center (-1.02", -0.07")
Size (2.05")
Run 2
Center (-2.02", -1.07")
Size (2.05")
3
4
5
6,7
8
9
10
11
12

FIG. 201A



FIG. 201B


Some instantaneous images have significantly wavy cone edges

FIG. 201C


Avg V m/s
30.0
27.5
25.0
22.5
20.0
17.5
Position mm
24
20
16
12
8
4
0
-4
-8
-12
-16
-20
-24
-32 m/s
-32 m/s
-32 m/s
-5
-10
-15
-20
-25
-30
-35
-40
-45
-50
-30
-35
-40
-46
-50
Position mm

FIG. 201D


Avg V m/s
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
Position mm
24
20
16
12
8
4
0
-4
-8
-12
-16
-20
-24
-5
-10
-15
-20
-25
-30
-35
-40
-45
-50
Position mm
-32 m/s
-32 m/s
-32 m/s

FIG. 201E


~32 m/s
24
20
16
12
8
4
0
-4
-8
-12
-16
-20
-24
Position mm
30.0
27.5
25.0
22.5
20.0
17.5
15.0
12.5
10.0
7.5
5.0
2.5
Avg V m/s
-50
-45
-40
-35
-30
-25
-20
-15
-10
-5
Position mm

FIG. 201FA



FIG. 201FB



FIG. 201FC


Length m/s
28
26
24
22
20
18
16
14
12
10
8
6
4
2
-5.0 -7.5 -10.0 -12.5 -15.0 -17.5 -20.0 -22.5 -25.0 -27.5 -30.0 -32.5
Position mm

FIG. 201FD



FIG. 201GA



FIG. 201GB



FIG. 201HA



FIG. 201HB



FIG. 201IA



FIG. 201IB



FIG. 201JA



FIG. 201JB



FIG. 201KA



FIG. 201KB